
# MODERN INORGANIC CHEMISTRY

WILLIAM L. JOLLY





McGRAW-HILL INTERNATIONAL EDITIONS

**Chemistry Series** 

7		1
r	1	1
t	-	4
+	1	-
F		1
H	1	4
M	_	-
F	_	7
L	T	
-	1	7
A.		-
-	I	4
r	_	7
H	-	-
-	I	
F		
t		7
r	T	
-		
(		)
-		7
-	I Y	4
-		1
1	Y	1
Y	1	7
F		4
-		
(	4	)
1		7
1		1
100		101
100	-	100
トロくと	-	こうつこ
コンフロ	-	11001
コロントロロ	-	こつつこ
TUCTUL	-	コンコンフィ
TUCIULU		LUCINI
INCINIA	-	1 111001

Alkaline earths

Halogens

ses							_			-			-			-				
Noble gases	4.003	He	2	20.183	Ne	10	39.948	Ar	18	83.80	Kr	3%	131.30	Xe	54	(222)	Rn	86		
	1/4	+	VIIB	18.998	F	6	35.453	C	17	79.904	Br	35	126.904	I	53	(210)	At			
	Chalcogens	•	VIB	15.999	0	00	32.064	S	16	78.96	Se		09.7	Te	52	(210)	Po	84		
	0		VB	14.007	Z	7	30.974	Ь	15	74.922	As			Sb	51	208.980	<u>2</u>	83		
			IVB	12.011	0	9	28.086	Si	14	72.59	Ge	32	114.82 118.69 121.75	Sn	50	207.19	Pb	82		
			IIIB	10.811	B	5	26.982	Al	13	69.72	Ga	31	114.82	In		204.37	E	81		
						1	tals		IIB	65.37	Zn	30	112.40	PO		200.59	Hg	80		
							Coinage metals	-,	IB	63.546	Cu	29	107.868	50	_	196.961	Au	79		
							Coi		Г	58.71	Z	28	106.4	Pd	-	_	Pt	78	als	
					S		-	VIIII	-	58.933	°C		102.905	P	1		4	77	Platinum metals	
					Transition metals				L	55.847	Fe	26 27	101.07	Su.	1000	7.0.7	S	16	Platir	
					Transitio				VIIA	54.938	Mn		(66)	Tc	6 92	-	e	0		
									VIA	51.996	C		-	M0	85	AA.	4	(263)		106
									VA	50.942	>	_	97.900	QN F	0.948	É		260)	Ha	105
									IVA	47.90	=		77.16	40 40	178.49			(257)	Rf	104
			_[	2			7	-	HIIA		30	17		39	138.91	I	K7	(7227)	Ac	68
	8	-	IIA	9.01	Be	1	-	Mg	12	40.08	ي د	67.63	20.10	38	137.34	Ra	26	(226)	Ra	000
IA	1.00	H	1	6.939	r.	3	22.990	Na	111	39.102	N oi	85.47	Dh	37 TE	132.905	Č	55	(223)	FF	8/
				The same	7	-		21.5	-							180		-		1

	174.97	I m	Total	71	(257)	Tr	103
	173.04		7.0	70	(253)	Z	102
	168.934	Tm	A alla	69	(256)	Md	101
	167.26		1	99	(253)	Fm	100
	164.930	Ho		10	(254)	Es	66
	162.50	Dv		00	(249)	CC	86
1000	158.924	Tp	37	00	(247)	Bk	76
	157.25	P5	6.4	5	(247)	Cm	96
15100	151.96	Eu	63	200	(243)	Am	95
150.25	150.35	Sm	69	1000	(747)	Pu	94
(147)		Pa	19	10001	(757)	Z	93
14424		PN				n	92
140.907	6	-	59	(1331)	(107)	Pa	16
140.12	(	e e	58	237 038		Th	06
	Lonethoutil	Laminamide series				Actinide series	

Alkali metals

Price US # 195 US # 148.48

Acc no-16744

135 178 H

Table 1.7 Ionization potentials of the elements (in electronvolts)†‡ (continued)

Z	Element	I	II	III	IV	V	VI	VII	VIII
51	Sb	8.641	16.53	25.3	44.2	56	108	south Valor	1944 - 2012/0
52	Te	9.009	18.6	27.96	37.41	58.75	70.7	137	
53	I	10.451	19.131	33					
54	Xe	12.130	21.21	32.1					
55	Cs	3.894	25.1						
56	Ba	5.212	10.004						
57	La	5.577	11.06	19.175					
58	Ce	5.47	10.85	20.20	36.72				
59	Pr	5.42	10.55	21.62	38.95	57.45			
60	Nd	5.49	10.72						
61	Pm	5.55	10.90						
62	Sm	5.63	11.07						
63	Eu	5.67	11.25						
64	Gd	6.14	12.1						
65	Tb	5.85	11.52						
66	Dy	5.93	11.67						
67	Но	6.02	11.80						
68	Er	6.10	11.93						
69.	Tm	6.18	12.05	23.71					
70	Yb	6.254	12.17	25.2					
71	Lu	5.426	13.9						
72	Hf	7.0	14.9	23.3	33.3				
73	Ta	7.89	atoms	tency for	SECT TORK				
74	W	7.98							
75	Re	7.88							
76	Os	8.7							
77	Ir	9.1							
78	Pt	9.0	18.563						
79	Au	9.225	20.5						
80	Hg	10.437	18.756	34.2					
81	Tl	6.108	20.428	29.83					
82	Pb	7.416	15.032	31.937	42.32	68.8	88.3		
83	Bi	7.289	16.69	25.56	45.3	56.0	100.5		
84	Po	8.48	10.05	3 2 3 3 4 5 1 1	12000	STREET N			
85	At	0.40							
86	Rn	10.748							
87	Fr	10.740				SECTION STATE			
88	Ra	5.279	10.147						
89	Ac	6.9	12.1						
90	Th	0.9	11.5	20.0	28.8				
91	Pa		11.5	20.0	20.0				
91									
	U								
93	Np	5.0							
94	Pu	5.8							
95	Am	6.0							

<sup>†</sup> C. E. Moore, "Ionization Potentials and Ionization Limits Derived from the Analyses of Optical Spectra," NSRDS-NBS 34, National Bureau of Standards, Washington, D.C., 1970.

<sup>‡</sup> Italicized entries are estimates.

correctly predict that the effective nuclear charge (and hence the ionization potential) reaches a maximum at the noble gas argon. In the same way, we can account for the maxima in first ionization potentials observed for all the noble gases, which, except for helium, are characterized by valence shells containing complete sets of p electrons. Less pronounced maxima are observed for elements whose valence electrons consist of complete shells of d electrons, e.g., Zn and Cd. These maxima can also be rationalized by Slater's rules. However, Slater's rules are too simplified to account for the maxima at Be and Mg, corresponding to complete s shells, or the even less pronounced maxima at elements with half-filled valence p shells. The maxima at nitrogen and phosphorus occur because the next element in the periodic table has an np4 valence-shell configuration, in which two electrons are paired in the same atomic orbital, with consequent loss of exchange energy and a relatively great increase in electron repulsive energy.<sup>13</sup>

The stability of completely filled shells of p, d, and f electrons is very important in controlling the chemistry of most of the elements in the periodic table. As a general rule, atoms tend to acquire filled electron configurations of these types. For example, the  $2s^22p^6$  configuration is achieved in  $C^{4-}$ ,  $N^{3-}$ ,  $O^{2-}$ , F<sup>-</sup>, Ne, Na<sup>+</sup>, Mg<sup>2+</sup>, and Al<sup>3+</sup>. The  $3s^23p^63d^{10}$  configuration is achieved in Cu<sup>+</sup>,  $Zn^{2+}$ , and  $Ga^{3+}$ . The  $4s^24p^64d^{10}4f^{14}5s^25p^6$  configuration (with a just-completed 4f shell) is achieved in Yb2+, Lu3+, Hf4+, and Ta5+. Even the stability of a filled s shell is important in species such as Tl+, Pb2+, and Bi3+, which have the  $5s^25p^65d^{10}6s^2$  configuration. A lesser tendency for atoms to achieve half-filled shells is shown by Eu2+, Gd3+, and Tb4+, all of which have the

 $4s^24p^64d^{10}4f^75s^25p^6$  configuration (with a half-filled 4f shell).

It should be noted that the ionization potential of a negative species such as F is seldom referred to as such, but rather as the "electron affinity" of the corresponding neutral species F. Thus, the electron affinity of the fluorine atom is equivalent to the "zeroth" ionization potential of fluorine. The periodic-table trends of electron affinities are similar to those of ionization potentials. Tables of

electron affinities are given in Appendix C.

In conjunction with his scheme for estimating electron screening constants, Slater also proposed that a given electron should be assigned an "effective" quantum number  $n^*$ , which is the same as the true principal quantum number for  $n \le 3$ , but which has the values 3.7 when n = 4, 4.0 when n = 5, and 4.2 when n = 6. The total binding energy of an atom or ion (the energy required to remove all the electrons from the nucleus) is given approximately by the sum of the quantities

$$13.6 \left(\frac{Z-S}{n^*}\right)^2$$

calculated for all the electrons of the atom or ion.

As an example of the use of this relation, we shall estimate the first ionization potential of fluorine. This energy is equal to the difference between the total

<sup>13</sup> A. B. Blake, J. Chem. Educ., 58, 393 (1981)

binding energy of the normal atom and that of the ion. Because the 1s shell is complete in both the atom and the ion, and because the valence electrons are assumed not to contribute to the 1s shielding constant, the  $(Z - S)/n^*$  values for the 1s electrons will cancel when the difference is taken and hence can be ignored. For the 2s, 2p electrons of the atom, S = 2(0.85) + 6(0.35) = 3.8. For the 2s, 2p electrons of the ion, S = 2(0.85) + 5(0.35) = 3.45. The total 2s, 2p electron bonding energies are  $7(13.6)[9 - 3.8)/2]^2 = 643.6$  eV and  $6(13.6)[(9 - 3.8)/2]^2 = 643.6$ 3.45)/2]<sup>2</sup> = 628.4 eV, respectively, corresponding to an ionization potential of 643.6 - 628.4 = 15.2 eV. This value may be compared with the actual value. 17.4 eV.

As a second example, we shall estimate the first ionization potential of iron. Again, we can neglect the  $(Z - S)/n^*$  values for all the electrons but those in the outer shell. For the atom,  $(Z - S)/n^* = 3.75/3.7 = 1.014$ ; for the ion,  $(Z - S)/n^* = 3.75/3.7 = 1.014$ .  $n^* = 4.1/3.7 = 1.108$ . The ionization potential is given by  $13.6[2(1.014)^2 -$ (1.108)<sup>2</sup>] = 11.3 eV, which may be compared with the actual value, 7.9 eV. Obviously ionization potentials calculated by this method are only rough estimates whose principal value is in qualitatively predicting trends or changes in ionization potential.

#### ATOMIC-SIZE TRENDS

Another atomic property which varies systematically throughout the periodic table is atomic size. Unfortunately, atomic size, unlike ionization potential, is an ill-defined quantity. We shall later discuss several methods for defining and measuring effective radii for atoms and ions, but at this point it will suffice to discuss qualitative trends in atomic size. When the principal quantum number of the valence electrons is increased while the valence configuration is kept constant, atomic size increases. Thus the bromine atom is bigger than the chlorine atom. This effect is due to the fact that an increase in principal quantum number corresponds to a decrease in electron binding energy and an increased average distance from the nucleus. Thus atomic size increases as one descends any column of the periodic table. On the other hand, when we move from left to right in the periodic table, i.e., when an increase in atomic number is matched by an increase in the number of valence electrons in the valence shell, atomic size decreases. This effect is a consequence of the increase in the effective nuclear charge and the contraction of the electron cloud. Thus atomic size decreases from left to right in any row of the periodic table, as long as the n or l values of the. electrons added are not changed.

The contraction in size which occurs in the first series of transition metals (scandium through zinc) has interesting consequences in the succeeding elements, gallium, germanium, etc. The contraction causes gallium and germanium to be almost the same size as aluminum and silicon, respectively. Therefore, because chemical properties are highly dependent on atomic size, the chemical properties of aluminum and gallium are very similar, as are those of silicon and germanium. Similarly, the so-called lanthanide contraction which occurs from La to Lu, corresponding to the filling of the 4f shell, has important consequences in the series from Hf to Pt. The elements of the latter series are remarkably similar to the corresponding members of the second transition series, from Zr to Pd. Thus zirconium and hafnium are so similar that it is very difficult to separate these elements from each other. The block of six elements Ru, Rh, Pd, Os, Ir, and Pt have many chemical similarities and are called the "platinum metals." Beyond platinum, however, the effect of the lanthanide contraction markedly peters out; thus cadmium in some ways is more like zinc than like mercury, and tin in some ways is more like germanium than like lead.

#### PROBLEMS14

(Problems 1.1 to 1.12 should be answered without referring to the text or a periodic table.)

- 1.1 How many unpaired electrons do each of the following atoms or ions have in their ground states: Al, S, Sc<sup>3+</sup>, Cr<sup>3+</sup>, Ir<sup>3+</sup>, Dy<sup>3+</sup>?
- 1.2 What +2 ion has just six 4d electrons in its ground state?
- 1.3 Write out the electron configuration of arsenic.
- 1.4 On the basis of analogy with the lanthanides, which two actinides would you expect to show a stable +2 oxidation state?
- 1.5 List, in order of atomic numbers, the symbols of the elements between calcium and gallium.
- 1.6 Which element has the following electronic configuration:  $1s^22s^22p^63s^23p^63d^{10}4s^24p^64d^45s^{19}$ ?
- 1.7 Name the two elements whose chemical properties are very similar to those of chromium.
- 1.8 Which element has atomic number 25?
- 1.9 Which of the following gas-phase reactions can proceed spontaneously?

$$Kr + He^+ \rightarrow Kr^+ + He$$
  
 $Si + Cl^+ \rightarrow Si^+ + Cl$   
 $Cl^- + I \rightarrow I^- + Cl$ 

- 1.10 Why does potassium have a lower first ionization potential than lithium?
- 1.11 Why does copper have an outer electron configuration  $3d^{10}4s^1$  instead of  $3d^94s^2$ ?
- \*1.12 Arrange the ions of each group in order of increasing size:
  - (a) Y<sup>3+</sup>, Ba<sup>2+</sup>, Al<sup>3+</sup>, Co<sup>3+</sup>, Cs<sup>+</sup>, La<sup>3+</sup>, Ir<sup>3+</sup>, Fe<sup>3+</sup>
  - (b) Cl<sup>-</sup>, I<sup>-</sup>, Te<sup>2-</sup>, Ar<sup>+</sup>
- 1.13 Argue for the inclusion of B and Al in group IIIA, that is, in the same family with Sc, Y, La, and Ac.
- \*1.14 The probability of finding the electron of a hydrogen atom at a distance r from the proton is at a maximum for r = 0.529 Å. Does this statement contradict the fact that the electron density is greatest at the proton? Explain.
  - 1.15 Describe the nodal surfaces of a 3p orbital.
  - 1.16 Calculate the ninth ionization potential of fluorine.
- \*1.17 Using the angular parts of the hydrogen-atom wave function for p orbitals (see Tables 1.3 and

<sup>14</sup> In this and subsequent problem sections, asterisks indicate more difficult problems.

- 1.4), show that an atom with three equally occupied p orbitals, such as the nitrogen atom, is spherically symmetric.
- 1.18 Using Slater's rules, estimate the second ionization potentials of Na and Mg, and the 1s binding energy of Ne.
- 1.19 Using Slater's rules, estimate the first ionization potentials of S, Cl, Ar, K, and Ca. Show that the estimates are similar in magnitude and trend to the actual values.
- \*1.20 The +4 oxidation state of lead is much more strongly oxidizing than that of tin. Show that this fact can be explained by the first four ionization potentials of tin and lead. Rationalize the trends in these four ionization potentials in the series Ge, Sn, Pb.
- \*1.21 In the separation of nuclear fission products by elution from a column of ion-exchange resin, the following sequence of ions is observed: . . . ,  $Yb^{3+}$ ,  $Tm^{3+}$ ,  $Er^{3+}$ ,  $Ho^{3+}$ ,  $Y^{3+}$ ,  $Dy^{3+}$ ,  $Tb^{3+}$ ,  $Gd^{3+}$ , . . . . Explain the appearance of  $Y^{3+}$  in this series.
  - 1.22 What are the two common oxidation states of In, Sn, Sb, and Te?

## SYMMETRY AND THE ELEMENTS OF GROUP THEORY

Symmetry is one of the most pervasive concepts in the universe, and we almost subconsciously become familiar with the effects of symmetry through daily experience with symmetrical things. Even a beginner in chemistry recognizes that the structures of many compounds are "symmetric," and thus it should be no surprise that the principles of symmetry play an important part in chemistry. The simple, intuitive grasp of symmetry that most observant people naturally acquire is adequate for understanding chemistry up to a point. However, a systematic study of symmetry and the ways of specifying it with mathematical precision are important in the advanced study of inorganic chemistry because of the wide variety of symmetric structures encountered. The principles of symmetry and its close cousin, group theory, aid in the following (and many other) activities:

- Classifying molecular structures
- 2. Classifying molecular orbitals
- 3. Predicting splitting of electronic levels in electric fields of various symmetry
- 4. Constructing hybrid orbitals
- 5. Classifying electronic states of molecules
- 6. Classifying normal modes of vibration
- 7. Predicting allowed transitions in spectra

In this chapter, we shall briefly introduce the important concepts of symmetry and shall describe a few applications of group theory to chemical problems. In later

chapters we shall apply the methods of this chapter to the first four listed activities. If the material in this chapter whets your appetite for more extensive discussion, various texts can be consulted.<sup>1</sup>

You are encouraged to make structural models of the various compounds discussed in this chapter. The symmetry features of some molecules are difficult to visualize, and the discussions will be much more easily understood if you have the appropriate models in hand. Indeed, you will find that a simple set of molecular model-making equipment is valuable in studying all the discussions of structure found throughout this text.

### SYMMETRY OPERATIONS AND SYMMETRY ELEMENTS

If a molecule has two or more orientations in space that are indistinguishable, the molecule possesses symmetry. The process of going from one orientation to the other (a reflection, rotation, or a combination of these) is called a "symmetry operation," and the molecule possesses a corresponding "symmetry element." A symmetry element is a point, line, or plane about which the symmetry operation is carried out. For single molecules, there are five symmetry elements and corresponding symmetry operations.

- 1. *Identity, E.* The identity operation consists of doing nothing to the molecule. All molecules possess this symmetry element, inasmuch as the aspect of a molecule is unchanged after doing nothing to it. Although this may appear to be a trivial symmetry element, it is included because it is involved in group theoretical calculations.
- 2. Center of symmetry (inversion center), i. A molecule possesses a center of symmetry if every atom, when moved in a straight line through this center and an equal distance on the other side of the center, encounters a similar atom. Note that the square planar  $PtCl_4^{2-}$  ion (Fig. 2.1a) has a center of symmetry, whereas the tetrahedral  $SiF_4$  molecule (Fig. 2.1b) does not.
- 3. n-fold axis of symmetry (rotational axis),  $C_n$ . If rotation of a molecule by an angle of  $2\pi/n$  about an axis gives an indistinguishable configuration, the axis is an axis of symmetry. Thus the water molecule possesses one twofold axis of symmetry ( $C_2$ ), and the planar BF<sub>3</sub> molecule (Fig. 2.2) possesses one threefold axis ( $C_3$ ) and three twofold axes ( $C_2$ ). The highest-fold rotation axis of a molecule is conventionally taken as the vertical z axis:
- 4. Plane of symmetry (mirror plane),  $\sigma$ . If reflection of all parts of a molecule through a plane yields an indistinguishable orientation of the structure, the

<sup>&</sup>lt;sup>1</sup> F. A. Cotton, "Chemical Applications of Group Theory," 2d ed., Wiley-Interscience, New York, 1971; L. H. Hall, "Group Theory and Symmetry in Chemistry," McGraw-Hill, New York, 1969; H. H. Jaffe and M. Orchin, "Symmetry in Chemistry," Academic, New York, 1965; J. P. Fackler, Jr., "Symmetry in Coordination Chemistry," Academic, New York, 1971; D. S. Schonland, "Molecular Symmetry," Van Nostrand, Princeton, N.J., 1965.




Figure 2.1 The planar  $PtC1_4^{2-}$  ion (a) and the tetrahedral  $SiF_4$  molecule (b).




Figure 2.2 The BF<sub>3</sub> molecule, showing the four symmetry axes.

plane is a plane of symmetry. For example, the water molecule (Fig. 2.3) possesses two planes of symmetry: the plane in which the three atoms lie, and the plane perpendicular to that plane and bisecting the H—O—H angle.

Mirror planes containing the vertical axis are "vertical planes,"  $\sigma_v$ , and a mirror plane perpendicular to the vertical axis is the "horizontal plane,"  $\sigma_h$ . "Diagonal planes,"  $\sigma_d$ , are vertical planes that bisect the angles between successive twofold axes.




Figure 2.3 The water molecule, showing the symmetry elements.




Figure 2.4 The ethane molecule in a staggered configuration.




Figure 2.5 The  $SiF_4$  molecule, showing the changes in atomic positions accompanying an  $S_4$  rotation-reflection.

5. n-fold rotation-reflection axis (improper rotational axis),  $S_n$ . If rotation by an angle  $2\pi/n$  about an axis, followed by reflection through a plane perpendicular to the axis, yields an indistinguishable configuration, the axis is a rotation-reflection axis. For example, the staggered configuration of ethane has an  $S_6$  axis coincident with the  $C_3$  axis (Fig. 2.4), and SiF<sub>4</sub> has three  $S_4$  axes coincident with the three  $C_2$  axes which bisect the F—Si—F angles (Fig. 2.5). These symmetry elements are seen best with the aid of molecular models.

#### POINT GROUPS

The complete set of symmetry operations that can be carried out on a molecule constitutes a "point group." Although there are an infinite number of possible point groups, about 40 suffice to classify all known molecules. Point groups have labels, such as  $C_2$ ,  $C_{2\nu}$ ,  $D_{3h}$ ,  $O_h$ , and  $T_d$ . A yes-no system for determining the point group of a given molecule is outlined in Fig. 2.6. We shall demonstrate the use of this diagram with several examples.

1. HCl. The HCl molecule possesses an  $\infty$ -fold axis of rotation along the H—Cl bond, but it possesses no inversion center; therefore, the molecule belongs to the  $C_{\infty P}$  point group.




Figure 2.6 Procedure for determining the point group of a molecule.

2. BFClBr. This planar triangular molecule possesses only one symmetry element—the plane of symmetry in which the atoms lie. Consequently, the point group is  $C_s$ .

3. trans- $N_2O_2^{2-}$ , N=N. This planar ion possesses only one symmetry

axis, the twofold axis of symmetry perpendicular to the plane of the ion. There is no  $S_4$  axis, but there is a horizontal plane. Consequently, the point group is  $C_{2h}$ .

4. S<sub>8</sub>. The S<sub>8</sub> molecule consists of a zigzag closed chain of sulfur atoms, as pictured in Fig. 2.7. Notice that the molecule has one fourfold axis and four




Figure 2.7 Side view of an S<sub>8</sub> ring.

twofold axes perpendicular to the fourfold axis. It has no horizontal plane, but it has four vertical planes. Thus, the point group is  $D_{4d}$ .

5. NH<sub>3</sub>. The pyramidal ammonia molecule possesses a threefold rotational axis. It does not have a horizontal mirror plane, but it does have a set of three vertical planes. Hence the point group is  $C_{3\nu}$ .

6.  $CH_4$ . This regular tetrahedral molecule has four threefold axes, no center of symmetry, and six mirror planes, corresponding to the  $T_d$  point group.

Further examples are given in Table 2.1. The student should become adept at recognizing symmetry elements and at determining the point groups of molecules. A list of compounds and objects is given in the problems at the end of the chapter for practice.

Even if we pursued the subject of symmetry no further, you would find that familiarity with point groups is an asset. For example, consider how much structural information is condensed in the simple statement that the  $Ni(CN)_4^{2-}$  ion has  $D_{4h}$  symmetry. This statement implies that (1) the ion is completely planar, (2) the Ni-C-N bond angles are all 180°, (3) the C-Ni-C bond

Table 2.1 Examples of some common point groups and some a group through

Point group	Examples
Con listnovinos sano bas " to	SiFClBrI, SOFC1
Course turion said to mottate	ONCI, HOCI, SOCI <sub>2</sub>
	Nonplanar H <sub>2</sub> O <sub>2</sub>
Carried on their special states	Trans-planar H <sub>2</sub> O <sub>2</sub> , trans-C <sub>2</sub> H <sub>2</sub> Cl <sub>2</sub>
$C_{2}$	H <sub>2</sub> O, SO <sub>2</sub> F <sub>2</sub> , SCl <sub>2</sub> , ClO <sub>2</sub> -
C3, mass sd nan H andar sd	NH <sub>3</sub> , SiH <sub>3</sub> Cl, PF <sub>3</sub>
$C_{4\nu}$	
D <sub>2h</sub>	
P.	DCI DCI CO
D.,	PtCl.2-, Ni(CN),2-, trans-SF,Cl.
$D_{5h}$	Eclipsed Fe(C <sub>5</sub> H <sub>5</sub> ) <sub>2</sub>
$D_{6h}$	$Cr(C_6H_6)_2$
D <sub>2d</sub> and level than the bridge of the	Staggered B <sub>2</sub> Cl <sub>4</sub> , H <sub>2</sub> C=C=CH <sub>2</sub>
$D_{3d}$	Staggered Si <sub>2</sub> H <sub>6</sub>
$D_{4d}$	$Mn_2(CO)_{10}$
D	Staggered Fe(C <sub>5</sub> H <sub>5</sub> ) <sub>2</sub>
T	GeCl <sub>4</sub> , ClO <sub>4</sub>
O PART INVINCENTAL STATE OF THE PART IN TH	UF <sub>6</sub> , SF <sub>6</sub> , PF <sub>6</sub>
	H <sub>2</sub> , N <sub>3</sub> <sup>-</sup> , CO <sub>2</sub>
$D_{\infty v}$	HCI, CO, OCS
00 V	

angles are all 90°, (4) the four Ni—C bond lengths are all equal, and (5) the four C—N bond lengths are all equal. You will find that the inorganic chemical literature, in which point group symbols are commonly used to describe structures concisely, is much more easily understood when you are familiar with point groups.

### CHARACTER TABLES AND IRREDUCIBLE REPRESENTATIONS

For each point group there is a corresponding "character table." Some of the more important character tables are given in Table 2.2. At the top of each character table are listed horizontally the various classes of symmetry operations of the point group. These classes are indicated by the symbols for the operations of the point group. For example, the classes of symmetry operations of the  $C_{2p}$  point group are E,  $C_2$ ,  $\sigma_n(xz)$ , and  $\sigma_n'(yz)^2$ . In this case, there are four classes of symmetry operations, and there is one operation for each class. In some cases, a point group may possess more than one symmetry operation of a given class. For example, the  $C_{3v}$  point group has three different  $\sigma_v$  planes, and one finds  $3\sigma_v$  in the top row of the character table. For the same point group, there are two possible C<sub>3</sub> rotations (through 120 and 240°) other than rotation through 360° (the identity operation); thus, one finds  $2C_3$  in the table.<sup>3</sup> The number preceding the symmetry operator symbol is the number of distinct operations of that particular class and is represented by the general symbol  $g_R$ , where R refers to the Rth column in the table (absence of such a number implies that  $g_R = 1$ ). The "order" of the point group, g, is the total number of operations in the group, or simply the sum of the  $g_R$  terms,  $g = \sum_R g_R$ .

Below the listing of the symmetry operations, there is a matrix of terms (1, -1, 0, 2, 2), and so forth). Each term is a "character," and each horizontal row contains the characters of an "irreducible representation" of the point group. Each irreducible representation is labeled by a symbol  $(A_1, B_2, 3)$ , and so forth), which is the "symmetry species" of the irreducible representation. These symbols are presented in a column on the left side of the table. It can be seen, for example, that in the  $C_{2v}$  point group the irreducible representation 1, 1, -1, -1 corresponds to the symmetry species  $A_2$ . The symmetry species symbols are used for labeling normal vibrational modes, electronic states, molecular orbitals, etc. It will be noted from the character tables that the number of irreducible representations of a group is always equal to the number of classes of symmetry operations of the group. That is, each character table contains a square matrix of charac-

<sup>&</sup>lt;sup>2</sup> For planar  $C_{2\nu}$  molecules, the x axis is generally chosen perpendicular to the plane.

<sup>&</sup>lt;sup>3</sup> The effect of carrying out a rotation m times may be written  $C_n^m$ . Thus, the operation  $C_3$  or  $C_3^{-1}$  corresponds to rotation by 120°;  $C_3^{-2}$  corresponds to rotation by 240°; and  $C_3^{-3}$  corresponds to rotation by 360°  $(C_3^{-3} = E)$ . Often, there are equivalent ways of representing an operation—for example,  $C_6^{-3} = C_2$ ;  $C_6^{-2} = C_3^{-1}$ . Similar remarks apply to the other symmetry operations,  $\sigma$ , i, and S.

Table 2.2 Character tables for some important point group

Tab	le 2.2	2 Char	acter t	ables f	or so	me importa	nt poi	nt grou	ps	(Churc	966)	dde
$C_1$	E											
A	1											
	1											
$C_s$	E	$\sigma_h$										
A'	1	1	w 11 M	$^{2}$ , $y^{2}$ , $z^{2}$ ,	-							
A"	1	-1	z, y, x		xy							
			2, ,2,									
$C_2$	E	$C_2$	_22	1	18							
A	1	1	$z, x^2, y$	$z^2$ , $z^2$ , $xy$								
B	1	-1	x, y, y2									
	1											
$C_{2h}$	E	$C_2$	i	$\sigma_h$ -								
1	77.00	1-,0	1.76	1		2 -2 -1						
$A_g$ $B_g$	1	-1	1	$\begin{bmatrix} 1 \\ -1 \end{bmatrix}$		$z^{2}$ , $z^{2}$ , $xy$						
$A_u$	1	1	-1	-1	XZ, Y	THE LAND						
$B_u$	1	-1	-1	1	x, y							
11				* 1	7, 7							
$C_{2v}$	E	$C_2$	$\sigma_v(xz)$	$\sigma_{v}'($	yz)							
$A_1$	1	1	1	25 1		$z, x^2, y^2, z^2$						
$A_2$	1	1	-1	-1		xy						
$B_1$	1	-1	1	-1		x, xz						
$B_2$	1	-1	-1	1	1	y, yz						
			and of									
$C_{3v}$	E	$2C_3$	$3\sigma_v$									
$A_1$	1	1	1	z, x2 -	+ y2, z2	2						
$A_2$	1	1	-1									
E	2	-1	0	(x, y),	$(x^2 -$	$y^2$ , $xy$ ), $(xz, y)$	z)					
	ı i					120						
$C_{4v}$	E	2C <sub>4</sub>	$C_2$	$2\sigma_v$	$2\sigma_d$		9.50					
$A_1$	1	1	1	1	1	$z, x^2 + y^2,$	$Z^2$					
$A_2$	1	1	1	-1	-1							
$B_1$	1	-1	1	1	-1	$x^2-y^2$						
$B_2$	1	-1	1	-1	1	xy	io,					
E	2	0	-2	0	0	(x, y), (xz,	yz)					
$D_{2h}$	E	$C_2(z)$	$C_2(y)$	) C <sub>2</sub>	(x)	$i = \sigma(x)$	σ(	xz) o	$\sigma(yz)$			
$\overline{A_g}$		1	1		1		-			×2 ,2	-2 -2	
$B_{1g}$	1	1	-1	34_	1	$\begin{array}{cccccccccccccccccccccccccccccccccccc$	d w	1	1 1	$x^2, y^2,$	4	
$B_{2g}$	1	-1	1			1 -1			-1	xy xz		
$B_{3g}$	1	-1	-1		1	1 - 1	0 _		1	yz		
$A_u$	1	1	1		1	-1 $-1$	_		-1	To the		
$B_{1u}$	1	1	-1	-	1	-1 $-1$		1	1	Z		
$B_{2u}$	1	-1	1	-	1	-1 1	-	1	1	y		
$B_{3u}$	1	-1	-1		1	-1 1		1 -	-1	X		

Table 2.2 Character tables for some important point groups (continued)

								LGU!			Section 1
$D_{3h}$	E	$2C_3$	$3C_2$	$\sigma_h$	$2S_3$	$3\sigma_v$	LOCAL N	MALL A C			
$A_1'$	1	1	1	1	1	1	$x^2 + y^2$	$z^2$			
$A_2'$ $E'$	1 2	1 -1	$-1 \\ 0$	1 2	1 -1	$-1 \\ 0$	(x, y), (	$v^2 - v^2$	rv)		
A,"	1	1	1	-1	$-\hat{i}$	-1	(30, 37), (	o year	, ,,,		
$A_2^{\prime\prime}$	1	1	-1	-1	-1	1	Z				
E"	2	-1	0	-2	1	0	(xz, yz)				
$D_{4h}$	E	2C <sub>4</sub>	$C_2$	$2C_2'$	$2C_2''$	i	254	$\sigma_h$	$2\sigma_v$	$2\sigma_d$	
$A_{1g}$	1	legaci.	1	1 1	1	1	1	1	1	1	$x^2 + y^2, z^2$
$A_{2g}$	1	1	1	-1	-1	1	1	1	-1	-1	w - 12
$B_{1g}$ $B_{2g}$	1 1	$-1 \\ -1$	1		in Class	1	-1 -1	1	-1	-1 1	$x - y^2$
$E_g$	2	0	-2	0	0	2	0	-2	0	0	(xz, yz)
$A_{1u}$ $A_{2u}$	1	1	1	1	e lalon	-1	-1	-1	-1	-1	ELISTER ST
$B_{1u}$	1	-1	1	1	-1	- i		$=$ $\frac{1}{1}$	-1	1	Z
$B_{2u}$	1	-1	1	-1	1	-1		-1	1	-1	
$E_u$	2	0	-2	0	0	-2	2 0	2	0	0	(x, y)
$D_{5h}$	E	2C <sub>5</sub>	L ONE	$2C_{5}^{2}$	5C <sub>2</sub> σ	h	255	2	$S_5^3$	$5\sigma_v$	
$A_1'$	1	1		1	1	1	1	Maria I	1	1	$x^2 + y^2$ , $z^2$
$A'_2$ $E'_1$	1 2	1 2 cos 7	12° 2	1 cos 144°	$-\frac{1}{0}$	1	1		1	-1	
$E_2'$	2	2 cos 1		cos 72°		2 2	2 cos 72° 2 cos 144°	2 c	os 144° os 72°	0	$(x, y)$ $(x^2 - y^2, xy)$
A'' A'' 2	1	1		1	1 -	1	-1		-1	-1	
$E_1''$	1 2	2 cos 7		1 cos 144°	-1 - 0 - 0		-1		-1	1	Z ( 117)
$E_2^{\prime\prime}$	2	2 cos		cos 72°			2 cos 72° 2 cos 144°		os 144° os 72°	0	(xz, yz)
	1 2	duch								1010 1	
$\frac{D_{6h}}{}$	E	$2C_6$	$2C_3$	$C_2$ $3C_2$	$3C_2''$	i	$2S_3$ 2.	$S_6 \sigma_h$	$3\sigma_d$	$3\sigma_v$	
$A_{1g}$	1	1	1	1 1	1	1	100	1	1	1	$x^2 + y^2$ , $z^2$
$A_{2g}$ $B_{1g}$	1 1	-1	l le	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	-1	1	1	1 1	-1	-1	
$B_{2g}$	1	-1	1	-1 - 1	1	1 1	Eiro	1 -	1 -1	1	
$E_{1g}$	2	1	-1	-2   0	0	2	i -	-1 - 2	2 0	0	(xz, yz)
$E_{2g}$ $A_{1u}$	2	1		2 0	0	2 -1	-1 -	-1 2	2 0	0	$(x^2-y^2,xy)$
$A_{2\mu}$	1	MR-1	10	1 - 1	1 -10	-1	-1 -	1 -		-1	Z
$B_{1u}$	1	$-\frac{1}{2}$	1	-1 1	-1	-1	11 -	-1	1 -1	1	
$B_{2u}$ $E_{1u}$	2	1	-1	$ \begin{array}{cccc} -1 & -1 \\ -2 & 0 \end{array} $	1 0	$-1 \\ -2$	1 -		1 1	-1	(
$E_{2u}$	2	-1	-1	2 0	0	$-\frac{2}{2}$	1	1 -	2 0 0 0	0	(x, y)
-	200120	A PART OF					Tale NI	EPI-ATT	A Train	THE OWNER OF	NAME OF A DES

Table 2.2 Character tables for some important point groups (continued)

			W 150	1 242	1	a let rate 7	THE PARTY OF	N. Carlot	THE PERSON NAMED IN
$D_{2d}$	E	254	$C_2$ 2	$2C_2'$ 2	$\sigma_d$	the same land			
$A_1$	1	1	1	1	$1 \mid x$	$x^2 + y^2, z^2$			
$A_2$	1	1	1 -	-1 -	1				
$B_1$	1	-1	1	1 -	$1 \mid x$	$y^2 - y^2$			
$B_2$	1	-1	1 -	-1		xy			
E	2	0	-2	0	0   ()	(x, y), (xz, yz)			
	1								
$D_{3d}$	E	$2C_3$	$3C_2$	i 23	56 30	T <sub>d</sub>			
$A_{1g}$	1	1	1	-1	1	$1  x^2 + y^2$	72		
$A_{1g}$ $A_{2g}$	1	1	-1	1	1 -	the second secon	2		
$E_g$	2	LU LINES OF	0	2 -			$^{2}$ , $xy$ ), $(xz, yz)$		
$A_{1u}$	1	1	1	-1 -	1 -	1	1 - 2 /3 ( 2 - 7		
$A_{2u}$	1	1	-1	-1 -	1	1 z			
$E_u$	2	-1	0	-2	1	$0 \mid (x, y)$			
							table of the		
$D_{4d}$	E	$2S_8$	$2C_4$	$2S_8^3$	$C_2$	$4C_{2}'$ 40	d		
$A_1$	1		11/11/11	19/01		100	$1  x^2 + y^2$	72	
$A_2$	1	CITAL CON SI	thing th	1	uic <sub>1</sub>	i	The second secon		
$B_1$	1	-1	1	10-10	1	w <sub>1</sub> = =	I Die Sylla		
$B_2$	1	-1	3431	-10	1210	1-11-0	1 z		
$E_1$	2	$\sqrt{2}$	0	$-\sqrt{2}$	-2		$0 \mid (x, y)$		
$E_2$	2	0	-2	0	2		$0  (x^2 - y^2)$	xy)	
$E_3$	2	$-\sqrt{2}$	0	$\sqrt{2}$	-2	0	$0 \mid (xz, yz)$		
_ 0	lu.	17.4.65.3	and the same		owner.		or officers	and the	is constant b
$D_{5d}$	E	$2C_5$	2C <sub>5</sub>	5C	i	2530	2S <sub>10</sub>	$5\sigma_d$	<u> </u>
$A_{1g}$	1	- 1 L	157 I	vo 0001	1	1	ne that he	1	$x^2 + y^2$ , $z^2$
$A_{2g}$	1	1	12 20 12	-1	1	1	The day	-1	s and rouses
$E_{1g}$	2	2 cos 72°	2 cos 1		2	2 cos 72°	2 cos 144°	0	(xz, yz)
$E_{2g}$	2	2 cos 144	° 2 cos 7	72° 0	2	2 cos 144°	2 cos 72°	0	$(x^2-y^2,xy)$
$A_{1u}$	1	1	1	-1	-1	-1	-1	1	Z
$A_{2u}$ $E_{1u}$	2	2 cos 72°	2 cos 1	144° 0	-2	$-2\cos 72^{\circ}$	-2 cos 144°	0	(x, y)
$E_{2u}$	2	2 cos 144				$-2\cos 124^{\circ}$		0	(3, 1)
	1 -								
$T_d$	E	$8C_3$	$3C_2$ 6.	$S_4$ $6\sigma_a$	Dy DSI				
$A_1$	16	1	il possett	10.4564	v2	$+ y^2 + z^2$	of the walnet		
$A_1$ $A_2$	1	1		1 -1	A	1 9 1 2			
E	2	-1	2	0 0	(2z	$x^2 - x^2 - y^2$ , x	$(2-v^2)$		
$T_1$	3	0 -	-1	1 -1		mountain's	SERVICE STATE		
$T_2$	3	0 -	-1 -	1 1	(x,	y, z), (xy, xz,	yz)		
dr.	301	Vitton ni	e actions.	sh or si	diseas	21 li 26lime	lon oning	rays b	AND TEXT

Table 2.2 Character tables for some important point groups (continued)

O <sub>h</sub>	E	8C <sub>3</sub>	6C <sub>2</sub>	6C <sub>4</sub>	$3C_2 (= C_4$	<sup>2</sup> ) i	6S <sub>4</sub>	8 <i>S</i> <sub>6</sub>	$3\sigma_h$	$6\sigma_d$	70	ye 1	- <u>v</u> d
$A_{1g}$ $A_{2g}$	1	1	1	1 -1	1	1	1	1	. 1	1	x2 +	$y^2 + z^2$	
$E_g$ $T_{1g}$	2 3	-1	0 -1	0	2 -1	2 3	0	$-\frac{1}{0}$	2 -1	0 -1	(2z2 -	$-x^2-y^2, x^2$	$-y^{2}$ )
$T_{2g}$ $A_{1u}$	3	0	1	-1 1	-1	3 -1	-1 $-1$	0	-1	1	(xz, )	vz, xy)	
$A_{2u}$ $E_u$	1 2	1 -1	-1	-1	1 2	-1 $-1$ $-2$	1	-1	-1 $-1$ $-2$	-1 1 0	Dr.		
$T_{1u}$ $T_{2u}$	3	0	$-\frac{1}{1}$	1 -1	$-\frac{2}{1}$	-3 $-3$	-1	0		1 -1	(x, y,	z)	
				44.22	J.112 Fe	-19.)	6		1		8		
$C_{\infty v}$	100	E	$2C_{\alpha}$	,		$\infty \sigma_v$							
$A_1 \equiv A_2 \equiv$		1		1	7	1 1	z, x <sup>2</sup>	$+ y^2, z^2$	2				
$E_1 \equiv$		2	2 cc	os $\Phi$		0	(x v	), (xz, y.	7)				
$E_2 \equiv$		2	2 cc	os 2Φ	23.1.30	0		$-y^2, xy$					
$E_3 \equiv$	Φ	2	2 cc	os 3 $\Phi$	·	0							
		1		••••••									
$D_{\infty h}$	E	20	$C_{\infty}^{\Phi}$	, i.	$.$ $\infty \sigma_i$	i	2.5	, Φ , ∞			$\infty C_2$	Et E	
$\Sigma_g^+$	1		1		.) (1	1		1	0		- 1 /	$x^2 + y^2$ , $z^2$	
$\Sigma_g^-$	1	•	1	¥11.	-1	1		1			-1	1 1 9 , 2	
$\Pi_g$ $\Delta_g$	2 2		cos Φ			2		2 cos Φ			0	(xz, yz)	
<u>а</u> в		2	cos 24	,	. 0	2		2 cos 2d	Þ		0	$(x^2-y^2,x$	(y)
$\sum_{u}^{+}$	1		1		. 1	-1	• • • • • • • •						
$\sum_{u}$	1		1	3 14.		-1		-1 -1			-1	Z	
$\Pi_u$	2	7 - 2	cos Φ	100	. 0	-2		2 cos Φ			0	(x, y)	
$\Delta_u$	2	2	cos 2d	Þ	0	-2		2 cos 24				$(\lambda, y)$	
							• • • • • • • • • • • • • • • • • • • •					1	

ters. On the right side of the table are listed various functions, such as x, y, and  $x^2 - y^2$ . The symbols x, y, and z are the cartesian coordinates (which can stand for vectors of translation or dipole moments). Each of these functions can serve given on the same line. This statement will be clarified in the following paragraphs.

For most symmetric molecules it is possible to describe an entity (e.g., an atom, a bond vector, an atomic orbital, etc.) which lies on all the symmetry elements of the molecule. When any symmetry operation of the molecule is carried out, the position of this entity remains unchanged. If the entity is a property having sign (e.g., a vector or p orbital), the entity will have its sign either

unchanged or changed. We say that the entity is either "symmetric" or "antisymmetric," respectively, with respect to the symmetry operation. To each operation we assign a "character," which is the factor by which the magnitude of the entity is changed by the operation. Thus the character 1 corresponds to a symmetric transformation, and the character - 1 corresponds to an antisymmetric transformation.

For example, consider the  $p_x$  orbital of the oxygen atom of the water molecule, which is parallel to the x axis of the molecule and perpendicular to the plane of the molecule. The oxygen atom lies on all the symmetry elements of the molecule, and therefore all its orbitals obviously have symmetry properties characteristic of the symmetry of the molecule. The identity operation leaves the molecule and the p, orbital unchanged; hence the orbital is clearly symmetric with respect to this operation. Rotation about the  $C_2$  axis inverts the orbital, corresponding to a change in sign. Hence the orbital is antisymmetric with respect to this operation. Reflection through the vertical (xz) plane causes no change in the orbital; the orbital is symmetric with respect to this operation. However, the orbital changes sign on reflection through the plane of the molecule (vz) and therefore is antisymmetric with respect to this operation. Thus the four characters corresponding to the oxygen  $p_x$  orbital are, respectively, 1, -1, 1, -1. These characters constitute the irreducible representation of the oxygen  $p_x$  orbital of water. From the  $C_{2n}$  character table we see that the symmetry label for this irreducible representation, and hence for this orbital, is  $B_1$ . The reader should verify, as a useful exercise, that the oxygen  $2p_z$ ,  $3d_{xy}$ , and  $2p_y$  orbitals<sup>4</sup> are of  $A_1$ ,  $A_2$ , and  $B_2$  symmetry, respectively.

For a slightly more complicated case, consider the nitrogen  $p_x$  and  $p_y$  orbitals of the ammonia molecule. Rotation by 120 or 240° about the  $C_3$  axis converts  $p_*$ and  $p_n$  into two new p orbitals both of which have  $p_n$  and  $p_n$  character. (It should be remembered that a p orbital in the xy plane can be written as a linear combination of  $p_x$  and  $p_y$ .) That is,  $p_x$  and  $p_y$  are mixed by symmetry and must be considered as an inseparable degenerate pair. The character corresponding to  $C_3$ rotation for the nitrogen  $(p_x, p_y)$  pair of ammonia is calculated as the sum of the separate factors for  $p_x$  and  $p_y$ :

$$p_{x}' = -\frac{1}{2}p_{x} - \frac{1}{2}\sqrt{3}p_{y}$$
$$p_{y}' = +\frac{1}{2}\sqrt{3}p_{x} - \frac{1}{2}p_{y}$$

Hence  $-\frac{1}{2}$  from  $p_x$  and  $-\frac{1}{2}$  from  $p_y$  gives the character -1.

The irreducible representation of the  $(p_x, p_y)$  pair of orbitals of the nitrogen atom of ammonia is an example of a "doubly degenerate" representation.<sup>5</sup> The symmetry species of any doubly degenerate representation is E.6 Triply degener-

<sup>&</sup>lt;sup>4</sup> The oxygen 3d orbital would not be importantly involved in the bonding of H<sub>2</sub>O. However, sulfur 3d orbitals would perhaps be significant in H<sub>2</sub>S, an analogous molecule.

<sup>&</sup>lt;sup>5</sup> Some authors refer to the degeneracy of a representation as the "dimension" of the representation.

<sup>&</sup>lt;sup>6</sup> This E should not be confused with the identity operator.

ate representations are always designated by T. You will perhaps have already noticed that nondegenerate representations correspond to the symmetry species A or B.

In point groups with centers of inversion, the subscript g (from German gerade, even) is attached to the symbols of irreducible representations which are symmetric (no change in sign) with respect to inversion, and the subscript u (from German ungerade, uneven) is attached in the case of representations which are antisymmetric (change in sign) with respect to inversion.

### REDUCIBLE REPRESENTATIONS

In chemistry, it is often necessary to determine the representation of a set of entities (e.g., atoms, bonds, atomic orbitals, etc.) located at stereochemically equivalent points in a molecule. The following procedure is followed. For a particular member of the set, carry out one operation for each class of symmetry operation in the point group. Assign a number to each of these operations. If the operation does not move or change the sign of the entity, the number is 1. In the case of an entity having sign, if the operation leaves the entity unmoved but with a change of sign, the number is -1. For any other change the number is 0. Determine a similar series of numbers for each member of the set (always taking care to use the same operation for a given class of operation). Then add the numbers corresponding to the same class of symmetry operation. The resulting sums are the characters of the reducible representation of the entities.

As an example, we shall determine the reducible representation of the group of three N—H bonds of ammonia. For convenience, we make a table, using the headings of the  $C_{3\nu}$  point group. The sets of numbers corresponding to the three equivalent bonds are indicated.

a	N C H
Н	H

Bond	E	$2C_3$	30,
a	1	0	
b	100	0	1
C	1	0	0
Reducible representation	1 2	0	0
presentation	3	0	1

It is obvious from an inspection of the  $C_{3v}$  character table that the representation 3, 0, 1 is not one of the irreducible representations. However, it can be representations which, when the corresponding characters are added, yields the reducible representation 3, 0, 1. By inspection of the character table, it can be readily seen that these reducible representations are those of symmetry species  $A_1$  and E.

Incidentally, this result tells us that the N—H stretching vibrations of NH<sub>3</sub> are of two types:  $A_1$  (nondegenerate) and E (doubly degenerate). The sum of the degeneracies of the irreducible representations is the number of bonds.

Let us consider a more complicated set of entities, the four chlorine 3p orbitals of  $PtCl_4^{2-}$  (Fig. 2.1a) which are perpendicular to the plane of the molecule. The reducible representation of these four equivalent orbitals is obtained as follows:

n			
U	4	t.	
_	4		

E	$2C_4$	$C_2$	$2C_2'$	2C''_2	0-(i-5	2S <sub>4</sub>	$\sigma_h$	$2\sigma_v$	$2\sigma_d$
1	o o oitat	0	oli£juhs	0170	0	0	nys o <del>d</del> i im	t ball av	0
1	0	0	0	0	0	0	N bowl	0	0
1	0	0	-1	0	0	0	-1	1	0
1	0	0	0	0	0	0	-1	0	0
4	$\overline{0}$	0	$\overline{-2}$	0	0	0	$\overline{-4}$	$\overline{2}$	$\bar{0}$

In this case it is relatively difficult to reduce the reducible representation by mere inspection of the character table. Fortunately there is a foolproof analytical method for doing this. The number of times a particular irreducible representation contributes to a reducible representation may be calculated from the expression

$$N = \frac{1}{g} \sum_{R} g_{R} \chi(R) \cdot \gamma(R)$$

where  $\chi(R)$  is the character of the symmetry operation R in the irreducible representation (taken from the character table) and  $\gamma(R)$  is the character of the symmetry operation R in the reducible representation. Thus, the reducible representation of the four chlorine 3p orbitals of  $PtCl_4^{2-}$  which are perpendicular to the molecular plane may be reduced as follows:

$$N_{A_{1g}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot (-2) + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot (-4) + 2 \cdot 1 \cdot 2 + 2 \cdot 1 \cdot 0] = 0$$

$$N_{A_{2g}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot (-1) \cdot (-2) + 2 \cdot (-1) \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot (-4) + 2 \cdot (-1) \cdot 2 + 2 \cdot (-1) \cdot 0] = 0$$

$$N_{B_{1g}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot (-1) \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot (-2) + 2 \cdot (-1) \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot (-2) + 2 \cdot (-1) \cdot 0] = 0$$

$$N_{B_{2g}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot (-1) \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot (-1) \cdot (-2) + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot (-1) \cdot 0 + 1 \cdot 1 \cdot (-4) + 2 \cdot (-1) \cdot 2 + 2 \cdot 1 \cdot 0] = 0$$

$$N_{E_s} = \frac{1}{16} [1 \cdot 2 \cdot 4 + 2 \cdot 0 \cdot 0 + 1 \cdot (-2) \cdot 0 + 2 \cdot 0 \cdot (-2) + 2 \cdot 0 \cdot 0 + 1 \cdot 2 \cdot 0 + 2 \cdot 0 \cdot 0 + 1 \cdot (-2) \cdot (-4) + 2 \cdot 0 \cdot 2 + 2 \cdot 0 \cdot 0] = 1$$

$$N_{A_{1\mu}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot (-2) + 2 \cdot 1 \cdot 0 + 1 \cdot (-1) \cdot 0 + 2 \cdot (-1) \cdot 0 + 1 \cdot (-1) \cdot (-4) + 2 \cdot (-1) \cdot 2 + 2 \cdot (-1) \cdot 0] = 0$$

$$N_{A_{2u}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot 1 \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot (-1)(-2) + 2 \cdot (-1) \cdot 0 + 1 \cdot (-1) \cdot 0 + 2 \cdot (-1)(-2) + 2 \cdot (-1) \cdot 0 + 1 \cdot (-1) \cdot (-4) + 2 \cdot 1 \cdot 2 + 2 \cdot 1 \cdot 0] = 1$$

$$N_{B_{1u}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot (-1) \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot (-2) + 2 \cdot (-1) \cdot 0 + 1 \cdot (-1) \cdot 0 + 2 \cdot 1 \cdot 0 + 2 \cdot 1 \cdot 0] = 0$$

$$N_{B_{2u}} = \frac{1}{16} [1 \cdot 1 \cdot 4 + 2 \cdot (-1) \cdot 0 + 1 \cdot 1 \cdot 0 + 2 \cdot (-1) \cdot (-2) + 2 \cdot 1 \cdot 0 + 1 \cdot (-1) \cdot 0 + 2 \cdot 1 \cdot 0 + 1 \cdot (-1) \cdot (-4) + 2 \cdot 1 \cdot 2 + 2 \cdot (-1) \cdot 0] = 1$$

$$N_{E_u} = \frac{1}{16} [1 \cdot 2 \cdot 4 + 2 \cdot 0 \cdot 0 + 1 \cdot (-2) \cdot 0 + 2 \cdot 0 \cdot (-2) + 2 \cdot 0 \cdot 0 + 1 \cdot (-2) \cdot 0 + 2 \cdot 0 \cdot 0 + 1 \cdot (-2) \cdot 0 + 2 \cdot 0 \cdot 0 + 1 \cdot (-2) \cdot 0 + 2 \cdot 0 \cdot 0 + 1 \cdot (-2) \cdot 0 + 2 \cdot 0 \cdot 0] = 0$$

Thus we find that the symmetry species of the irreducible representations of the orbitals are  $E_g$ ,  $A_{2u}$ , and  $B_{2u}$ , with a total degeneracy of 4. As we shall see later (in Chap. 4), these symmetry species correspond to "group orbitals" which are suitable linear combinations of the four p orbitals.

#### PROBLEMS

- 2.1 Determine the point groups of the following molecules or objects:
  - (a) SiHDBr<sub>2</sub> ("tetrahedral")
  - (b) SiFClBrI ("tetrahedral")
  - (c) SiH<sub>2</sub>Br<sub>2</sub> ("tetrahedral")
  - (d) PCl<sub>3</sub> (pyramidal)
  - (e) OPCl<sub>3</sub> (pyramidal)
  - (f) CO<sub>2</sub> (linear)
  - (g) P<sub>4</sub>O<sub>6</sub> (tetrahedral)
- (h) B,B,B-Trichloroborazine, B<sub>3</sub>N<sub>3</sub>H<sub>3</sub>Cl<sub>3</sub> (planar six-membered ring of alternating B's and N's, shown in Fig. 2.8)
- (i)  $S_4N_4$  (N's square planar; S's approximately tetrahedral, as shown in Fig. 2.8) (j) Mn(CO)<sub>5</sub>I ("octahedral")
- (k) The letter "T"




Figure 2.8 The structures of B<sub>3</sub>N<sub>3</sub>H<sub>3</sub>Cl<sub>3</sub> and S<sub>4</sub>N<sub>4</sub>.

- (1) The letter "Z"
- (m) The numeral 8 (idealized)
- (n) A tennis ball (including seam)
- \*2.2 Show that the character corresponding to  $3\sigma_v$  for the  $(p_x, p_y)$  pair of NH<sub>3</sub> is 0.
  - 2.3 What are the symmetry species of the 3d orbitals of sulfur in  $SF_6$  ( $O_h$  point group)?
- 2.4 What are the symmetry species of the symmetry-allowed combinations of the following atomic orbitals?
  - (a) The six carbon 2p orbitals of benzene which are perpendicular to the plane of the molecule
  - (b) The four hydrogen 1s orbitals of CH4
- (c) The oxygen 2p orbitals of the terminal atoms of  $O_3$  ( $C_{2p}$  point group) which are perpendicular to the plane of the molecule

control by Cally deplayed and Valence and the Structure of Arogan additionals, 7.1 Econom. Openion

(d) The six hydrogen 1s orbitals of hypothetical SH<sub>6</sub> (O<sub>h</sub> point group)

### COVALENT BONDING

We envision two extremes of chemical bonding: covalent and ionic. We say that a bond is purely covalent when the bonding valence electrons are equally shared between the bonded atoms, and that a bond is purely ionic when the atoms have charges of opposite sign and there are no valence electrons shared between the atoms. Although the bonding in a homonuclear diatomic molecule such as Cl<sub>2</sub> obviously fits the criterion for pure covalency, there is no known example of purely ionic bonding. (In Chap. 11 we will show that the bonding in certain crystals only approximates the ionic extreme.) In other words, all chemical bonds are at least partially covalent, with some valence electron density shared between the atoms. In this chapter we discuss a simple theory for describing covalent bonds (the Lewis octet theory) and a method for predicting the geometries of molecules (the valence-shell electron repulsion theory). We also discuss methods used for systematizing properties of chemical bonds, such as bond distances, bond strengths, and bond polarities. All these topics are important in inorganic chemistry, particularly in the study of compounds of the nontransition elements. As was the case in Chap. 1, you may already be familiar with some of the material in this chapter; to that extent, this chapter will be a review.

### THE LEWIS OCTET THEORY

The Lewis octet theory<sup>1</sup> is extremely useful for describing the bonding in practically all compounds of the nontransition elements. The theory is based on the

<sup>&</sup>lt;sup>1</sup> The modern concept of the Lewis octet theory is an evolutionary product of the theory originally outlined by G. N. Lewis in "Valence and the Structure of Atoms and Molecules," Chemical Catalog, New York, 1923.

stability of valence shells containing eight electrons in the s and p orbitals ( $s^2p^6$ ). According to the theory, each atom in a compound achieves an octet of valence electrons by sharing electrons with the other atoms to which it is bonded. Of course, hydrogen atoms do not achieve octets; their complete valence shells contain only two electrons.

Lewis octet structures for molecules can be represented in several ways. For example, the structure of ammonia can be written in the following ways:

The first way, in which all the valence electrons are indicated by dots, is somewhat cumbersome and is usually abandoned in the introductory chemistry course. The second and third ways are commonly used by practicing chemists; the choice between these methods is determined by whether or not one wishes to emphasize the presence of nonbonding electron pairs.

In writing octet structures, it is common practice to indicate the charges which atoms would have if each pair of bonding electrons were equally divided between the bonded atoms. These charges are called "formal charges" and should not be confused with the actual charges on the atoms. In NH<sub>3</sub>, none of the atoms has a formal charge. However, many other molecules, and of course all ions, have formally charged atoms. The structures of a few of these are shown Sometimes more than one structure can be written for a species with m. wolad

H H 
$$\dot{O}$$
 H  $\dot{O}$  H  $\dot{O}$ 

All chemists should be proficient in the assignment of formal charges to the atoms of a Lewis octet structure. One simple method for making this assignment is based on the "total bond order" of an atom, i.e., the sum of the bond orders of the bonds to an atom. The total bond order has an easily remembered characteristic value for a given atom with zero formal charge. Thus it is 1 for a halogen atom, 2 for an atom of the oxygen family, 3 for an atom of the nitrogen family, etc. When the total bond order is 1 greater than the characteristic value, the formal charge is +1; when it is 2 greater, the formal charge is +2, etc. Similarly, when the total bond order is 1 less than the characteristic value, the formal charge is -1, etc. These rules<sup>2</sup> are summarized in Table 3.1.

Proficiency in the assignment of the formal charges can be very helpful in

<sup>&</sup>lt;sup>2</sup> There is some difficulty in extending the rules to elements to the left of group IV. Thus it is impossible for boron to have both a complete octet and a zero formal charge.

Table 3.1	Formal	charges	on	atoms	with	complete oct	ets
-----------	--------	---------	----	-------	------	--------------	-----

	rionier or s		Periodic	table group		
Total bond order	III 115	IV	V	rob VI note	VII	VIII
0	a		-3	-2	o own your	0
1		-3	-2	-1	0	+1
2		-2		0	Durity Id: 2	+2
3	-2	-1	0	+1	+2	+3
4	-1	0	+1	11 +2	+3	+4

writing Lewis structures. For example, if the structure of nitrosyl chloride were mistakenly written

the structure would immediately be recognized as wrong, because the oxygen and nitrogen atoms would each have -1 formal charges, corresponding to a -2 ion. By introducing the N=O double bond,

a satisfactory structure for the neutral molecule is achieved.

Sometimes more than one structure can be written for a species with multiple bonds. In such a case the multiple bonding is distributed throughout the molecule, a situation often referred to as resonance<sup>3</sup> or delocalized  $\pi$  bonding. (A write either

Neither structure is a satisfactory representation of the bonding because the two terminal oxygen atoms in ozone are known to be equivalent. The actual bonding is midway between these extreme "resonance structures." We may represent the actual molecule, which is a "resonance hybrid," by the structure

Here each bond has a bond order of  $1\frac{1}{2}$ , and each terminal oxygen atom has a formal charge of  $-\frac{1}{2}$ , corresponding to the average values of these quantities in the

<sup>&</sup>lt;sup>3</sup> L. Pauling, "The Nature of the Chemical Bond," 3d ed., Cornell University Press, Ithaca, N.Y.,

two resonance structures. Similarly, we may represent the bonding in the nitrate ion by the hybrid structure

where each bond has a bond order of 11/3.

The two examples of resonance which we have just discussed involve resonance structures which are equivalent, i.e., structures which are indistinguishable upon the execution of a symmetry operation such as rotation about an axis of symmetry or reflection through a mirror plane. However, sometimes nonequivalent resonance structures can be written, as in the case of the cyanate ion:

$$^{-}O-C\equiv N$$
  $O=C=N^{-}$   $^{+}O\equiv C-N^{2-}$ 

In such cases the best representation of the bonding is usually not just a simple average of the individual resonance structures but rather some weighted average of these structures. The third cyanate structure, with a negative formal charge on the nitrogen atom and a positive formal charge on the oxygen atom, has a charge distribution which contradicts the fact that oxygen is more electronegative (electron-attracting) than nitrogen. Therefore it is reasonable to suppose that the actual bonding is a resonance hybrid mainly of the first two structures, with negligible contribution from the third structure.

Let us consider a more complicated example, the S<sub>3</sub>N<sub>2</sub>Cl<sup>+</sup> ion, which is found in the salt (S<sub>3</sub>N<sub>2</sub>Cl)Cl.<sup>4</sup>

Of the six different resonance structures, structures I to III are very unimportant because they involve adjacent atoms with formal charges of the same sign—an electrostatically unfavorable situation. Structure IV is the most favorable in terms of the electrostatic interaction of the formal charges. Indeed, the measured

<sup>&</sup>lt;sup>4</sup> A Zalkin, T. E. Hopkins, and D. H. Templeton, Inorg. Chem., 5, 1767 (1966).

bond distances, given in the following diagram, are in accord with the main contribution from the structure IV. The shortest S-N bond corresponds to the

double bond of resonance structure IV.

A special kind of resonance, called "no-bond" resonance or "hyperconjugation," is occasionally employed to rationalize extraordinary bonding features. This special resonance involves an increase in the order of one bond at the expense of the order of another bond: To not provide the provide t

$$X-Y-Z \leftrightarrow +X=Y$$

 $X-Y-Z \leftrightarrow {}^+X=Y$  Z-For example, in ONF<sub>3</sub>, the N-F bonds appear to be abnormally long, as determined by electron diffraction.5 Resonance of the following type can explain this "abnormality." Manager is a proposed a proposed and (guitaenthe-nor

actual bonding is a resogued hybrid mair 
$$f$$
 the first two structures in the structure of  $f$  and  $f$  and  $f$  and  $f$  and  $f$  and  $f$  and  $f$  are the structure  $f$  are the structure  $f$  and  $f$  are the structure  $f$  are the structure  $f$  and  $f$ 

Similarly, the unexpectedly strong acid-base interaction between BH3 and CO has been explained in terms of hyperconjugation of the following type<sup>6</sup>:

Although many structural rationalizations based on hyperconjugation are somewhat ad hoc, they are nevertheless reasonable insofar as the hyperconjugation causes a change in formal charge distribution consistent with electronegativities.7 Thus in ONF<sub>3</sub> hyperconjugation causes a shift in negative formal charge from oxygen to fluorine, and in H<sub>3</sub>BCO it causes a shift in positive formal charge from oxygen to hydrogen.

Some species have more valence electrons than can be accommodated by a Lewis octet structure involving only single bonds. For example, if we write

<sup>&</sup>lt;sup>5</sup> V. Plato, W. D. Hartford, and K. Hedberg, J. Chem. Phys., 53, 3488 (1970).

<sup>&</sup>lt;sup>6</sup> B. E. Douglas, D. H. McDaniel, and J. J. Alexander, "Concepts and Models of Inorganic Chemistry," 2d ed., pp. 535-536, Wiley, New York, 1983.

<sup>&</sup>lt;sup>7</sup> Electronegativities are discussed on pp. 61-62 and 71-76.

single-bonded structures for I<sub>3</sub><sup>-</sup> and SF<sub>6</sub>, we find that the central atoms are required to have 10 and 12 valence electrons, respectively:

Such species are "electron-rich," and the central atoms are referred to as "hypervalent." There are two common ways of handling this problem. One way is to invoke "no-bond" resonance structures or, what is equivalent, fractional bonds. Thus we may write the following Lewis structures for I<sub>3</sub>-:

These correspond to a symmetric resonance hybrid which can be represented as follows:

In the latter structure each bond has a bond order of  $\frac{1}{2}$ . The molecule SF<sub>6</sub> may be similarly treated; the structure involves six  $\frac{1}{3}$  bonds:

Another way of handling hypervalent atoms is to invoke the use of valence-shell d orbitals. Then, instead of restricting atoms like iodine and sulfur to an  $s^2p^6$  valence shell, we can permit electrons to be accepted by the empty d orbitals of the same principal quantum number. In principle, we can thereby accommodate hypervalency for any atom heavier than neon. Such d-orbital participation has been postulated even in species for which satisfactory Lewis octet structures can be written. Thus, in recognition of the fact that the central atoms in  $SO_4^{2-}$  and  $SiF_4$  use 3d orbitals, resonance structures of the following type have been written:

THE ISOELECTRO! 
$$^{+}$$
 $^{-}$ 

Although d orbitals unquestionably participate to some extent in the bonding of compounds having atoms with empty valence-shell d orbitals,8 most of the

<sup>&</sup>lt;sup>8</sup> T. B. Brill, *J. Chem. Educ.*, **50**, 392 (1973). Also see pp. 116–118 and 128–129 in this text for a discussion of molecular orbitals involving *d* orbitals in nonmetal compounds.

properties of such compounds can be qualitatively accounted for using octet structures.

Straightforward octet structures cannot be written for molecules with an odd number of electrons, such as NO. However, Linnett<sup>9</sup> devised a procedure in which the valence electrons of a molecule are split into two parts (corresponding to electrons of opposite spin) so that each atom achieves a *quartet* of each type of electron. By this "double quartet" theory, one indicates the separate quartets for NO as follows:

Notice that we have accounted for all the valence electrons of NO: six electrons of one spin and five of the opposite spin. Five electrons are situated in the bonding region between the atoms, corresponding to 2.5 electron-pair bonds. Pairs of electrons having opposed spins in the same region of the molecule can be represented by lines; thus the molecule can be represented as follows:

$$^{\circ \times}N^{\circ \times}O^{\circ \circ}$$
 or  $^{\times}N^{\circ}O^{\times}$ 

Because nitric oxide has one more electron of one spin than of the other, it has a net electronic spin of  $\frac{1}{2}$ .

In the case of the molecule O2, we can combine electron quartets in two ways:

(1) 
$$\bullet O \bullet O \bullet$$
 and  $\bullet O \bullet O \bullet$  yielding  $\bullet O = O$ 
(2)  $\bullet O \bullet O \bullet$  and  $\bullet O \bullet O \bullet$  yielding  $\bullet O \bullet O \bullet O \bullet$ 

Both combinations give double-bonded molecular oxygen. However, the first gives oxygen with no unpaired electrons (an excited state of  $O_2$ ), and the second gives oxygen with two unpaired electrons (the ground state). The greater stability of the second structure can be rationalized in terms of reduced repulsion between the electrons of opposite spin. For further applications of this method, the book or article by Linnett<sup>10</sup> should be consulted. Probably the main significance of Linnett's method is that it reaffirms the fundamental importance of the octet theory and the strong tendency for atoms to achieve rare-gas electron configurations.

### THE ISOELECTRONIC PRINCIPLE

Molecules that have the same number of electrons and the same number of heavy atoms (i.e., atoms heavier than hydrogen) usually have similar electronic structures, similar heavy-atom geometries, and similar chemical properties. This

<sup>&</sup>lt;sup>9</sup> J. W. Linnett, "The Electronic Structure of Molecules," Wiley, New York, 1964; J. Am. Chem. Soc., 83, 2643 (1961).

<sup>10</sup> Linnett, loc. cit.

statement is the "isoelectronic principle," first discussed by Langmuir.<sup>11</sup> As an example of a set of isoelectronic species, the molecules and ions consisting of 3 heavy atoms and 22 electrons may be considered:

H <sub>2</sub> C=C=CH <sub>2</sub>	H <sub>2</sub> C=C=O Ketene	HN=C=O Isocyanic acid
O=C=O Carbon dioxide	-N=N=O Nitrous oxide	-N=N- Azide ion
$H_2C = \stackrel{+}{N} = N^-$ Diazomethane	O=N=O Nitryl ion	F—C≡N Cyanogen fluoride
H <sub>3</sub> B−C≡N Cyanoborohydride ion	H <sub>3</sub> C−C≡N Acetonitrile	-N=C=N- Cyanamide ion
H <sub>3</sub> B−C≡O <sup>+</sup> Borane carbonyl	O=B=O Metaborate ion	CH <sub>3</sub> −C≡CH Methyl acetylene

The important common feature of these species is not that they have the same total number of electrons, but rather that they have the same number of valence electrons (in this case, 16). Indeed, the word "isoelectronic" is usually loosely interpreted as meaning having the same number of valence electrons. Thus we may include the following species in the preceding group of 3-heavy-atom, 16-valence-electron species:

O=C=S	S=C=S	-N=C=S	$Br-C\equiv N$	etc.
Carbonyl sulfide	Carbon disulfide	Thiocyanate ion	Cyanogen	
			bromide	

One feature which all these species have in common is a linear heavy-atom skeleton. They also have similar values for their corresponding vibrational frequencies, as shown by the data in Table 3.2. Many of the species undergo

Table 3.2 Vibrational frequencies for linear triatomic species†

Molecule	Bond bending frequency, cm <sup>-1</sup>	Symmetric stretching frequency, cm <sup>-1</sup>	Asymmetric stretching frequency, cm <sup>-1</sup>	
NO <sub>2</sub> +	538	1400	2375	
H <sub>2</sub> CN <sub>2</sub>	564	1170 Jest 201 BAN	2102	
HNCO	572	1327	2274	
H <sub>2</sub> CCO	588	1120	2152	
N <sub>2</sub> O	589	1285	2223	
BO <sub>2</sub> -	610	1070	1970	
NCO-	629	1205	2170	
$N_3^-$	630	1348	2080	
CO <sub>2</sub>	667	1388	2349	

<sup>†</sup> H. A. Bent., J. Chem. Educ., 43, 170 (1966).

<sup>&</sup>lt;sup>11</sup> I. Langmuir, J. Am. Chem. Soc., 41, 868, 1543 (1919).

analogous reactions. Thus Lewis bases such as OH<sup>-</sup> and H<sub>2</sub>O react by attacking the middle atom:

$$H_{2}C = C = O \xrightarrow{OH} H_{3}C - C = O$$

$$O = C = O \xrightarrow{OH} O = O$$

$$H_{3}B - C = O^{+} \xrightarrow{OH^{-}} H_{3}B - C = O$$

$$O = N^{+} = O \xrightarrow{OH^{-}} O = O$$

$$H_{2}N - C = N \xrightarrow{H_{2}O} H_{2}N - C - NH_{2}$$

$$Br - C = N \xrightarrow{2OH^{-}} O = C = N^{-} + Br^{-} + H_{2}O$$

Many of the compounds, when irradiated with ultraviolet light, break into two fragments:

$$H_2CCO \xrightarrow{hv} CH_2 + CO$$
 $H_2CNN \xrightarrow{hv} CH_2 + N_2$ 
 $HNNN \xrightarrow{hv} NH + N_2$ 
 $OCO \xrightarrow{hv} O + CO$ 
 $OCS \xrightarrow{hv} S + CO$ 
etc.

The existence of isoelectronic analogs of an unknown compound has often served as the impetus for its first synthesis. For example, in 1971, the following and Mn(NO)<sub>3</sub>CO. The last member of this series, Cr(NO)<sub>4</sub>, was unknown. However, in 1972, several chemists<sup>12</sup> had sufficient faith in the isoelectronic principle to photolyze a solution of Cr(CO)<sub>6</sub> in the presence of NO, and thus they

B. I. Swanson and S. K. Satija, J. Chem. Soc. Chem. Commun., 40 (1973); M. Herberhold and
 A. Razavi, Angew. Chem. Int. Ed., 11, 1092 (1972).

For many years chemists unsuccessfully tried to prepare the perbromate ion BrO<sub>4</sub>, which is analogous to the well-known perchlorate and periodate ions. The first successful synthesis of perbromate involved an isoelectronic species as the starting material. The synthesis involved the  $\beta$  decay of radioactive 83Se incorporated in a selenate<sup>13</sup>:

$$^{83}\text{SeO}_4^{2-} \rightarrow ^{83}\text{BrO}_4^{-} + \beta^{-}$$

The 83Br is itself radioactive, and its coprecipitation with RbClO<sub>4</sub> was taken as evidence that it was in the form of BrO<sub>4</sub>. We now know that the difficulty in the synthesis of perbromate by conventional methods is due to the fact that perbromate is an extremely powerful oxidizing agent, much more powerful than either perchlorate or periodate. The most efficient method now known for the preparation of perbromate involves the oxidation of a strongly alkaline BrO<sub>3</sub> solution by elemental fluorine 14

One must use reasonable caution in applying the isoelectronic principle. For example, because of the large differences in the properties of the fluorine and nitrogen atoms, one should not expect FCN to be a close analog of CO<sub>2</sub>. Indeed, the trimerization reaction of FCN has no known parallel with CO<sub>2</sub>.

Similarly, borazine, B<sub>3</sub>N<sub>3</sub>H<sub>6</sub>, is an imperfect analog of benzene, C<sub>6</sub>H<sub>6</sub>:

Borazine forms an adduct with 3 mol of HCl in which the ring nitrogen atoms are protonated, 15 whereas benzene is inert toward HCl under ordinary conditions. Although hexamethylborazine forms transition-metal complexes such as B<sub>3</sub>N<sub>3</sub>(CH<sub>3</sub>)<sub>6</sub>Cr(CO)<sub>3</sub> (analogous to complexes formed by the corresponding benzene derivative), the B<sub>3</sub>N<sub>3</sub> ring in these complexes is believed to be puckered, in contrast to the planar C<sub>6</sub> rings of the benzene derivative complexes. 16

<sup>&</sup>lt;sup>13</sup> E. H. Appelman, J. Am. Chem. Soc., 90, 1900 (1968).

<sup>&</sup>lt;sup>14</sup> E. H. Appelman, Inorg. Syn., 13, 1 (1972).

<sup>&</sup>lt;sup>15</sup> A. W. Laubengayer, O. T. Beachley, Jr., and R. F. Porter, *Inorg. Chem.*, 4, 578 (1965).

<sup>16</sup> J. L. Adcock and J. J. Lagowski, Inorg. Chem., 12, 2533 (1973).

Interatomic distances are now known for many molecules with probable errors of  $\pm 0.03$  Å or less. <sup>17</sup> One finds that the distance between two bonded atoms (say Si and Cl) is very nearly the same in different molecules, as long as the general nature of the bonding is the same in the various molecules. Some idea of the constancy of covalent bond distances can be obtained from Table 3.3, where the experimental Si—Cl bond distances for 10 different compounds are listed. The average value, 2.02 Å, is taken as the characteristic Si—Cl bond distance and may be used as an estimate of the Si—Cl bond distance in any other molecule containing such a bond. A brief listing of other characteristic covalent single-bond distances is given in Table 3.4.

The Si—Cl bond distances listed in Table 3.3 have practically the same value because the bonds not only have the same order but they also involve silicon atoms which have similar bonding geometries. A bond distance changes significantly as the total number of bonds to the bonded atoms changes. The effect is quite obvious in the C—C bonds of hydrocarbons, as can be seen from the data in Table 3.5. As the number of secondary bonds to a C—C single bond is reduced from six (in ethane) to two (in a diacetylene), the bond distance decreases. This effect is undoubtedly related to the correlation of bond strength with orbital hybridization, <sup>18</sup> a topic which will be discussed in more detail in Chap. 4. At this point we will merely point out that, as the fractional s character of the bonding

Table 3.3 Silicon-chlorine bond distances in various molecules†

Compound	r <sub>Si-Cl</sub> , Å
SiClF <sub>3</sub>	2.00
SiClH <sub>3</sub>	2.05
SiCl <sub>2</sub> H <sub>2</sub>	2.02
SiCl <sub>3</sub> H	2.02
SiCl <sub>3</sub> SH	2.02
SiCl <sub>4</sub>	2.01
Si <sub>2</sub> Cl <sub>6</sub>	2.01
Si <sub>2</sub> Cl <sub>6</sub> O	2.02
Cl <sub>3</sub> CSiCl <sub>3</sub>	2.01
C <sub>6</sub> H <sub>5</sub> SiCl <sub>3</sub>	2.00

<sup>†</sup> L. E. Sutton (ed.), "Tables of Interatomic Distances and Configuration in Molecules and Ions," Special Publ. 11, The Chemical Society, London, 1958; Supplement, Special Publ. 18, 1965.

L. E. Sutton (ed.), "Tables of Interatomic Distances and Configuration in Molecules and Ions,"
 Special Publ. 11, The Chemical Society, London, 1958; Supplement, Special Publ. 18, 1965.
 H. A. Bent, Chem. Rev., 61, 275 (1961)

Bracketed values are probably high because of lone-pair repulsions or hyperconjugation, and parenthesized values are probably low because of multiple Table 3.4 Covalent single-bond distances for the nonmetals (in angstroms)

are	Te	2.51	2.33	tenel book	rbon single be	2.86
	Sn	2.46	2.15	1.70 2.69	2.05	2.81
	Si	2.16	1.87 2.02 1.56	1.48	1.74	2.34
	Se		1.98	1.46	2.24	2.32
	Sb	2.51	2.20	1.71	2.80	
	S	2.24	1.82 2.03 1.53	1.34	1.67 1.5 1.86 2.05	eder incluse
	P		1.84 2.01 1.52	1.44	1.66	nd exygen ;
	0	1.78 (1.36)	[1.70] [1.70] [1.42]	96.0	[1.41]	SC, the S- to SESSISTE bet In Plant
	z	(1.42) [2.14]	1.47	1.01	[1.45]	niverni Araksa Kabupatan kitu
tropied in	iibi	2.54	2.14	1.61	herel mest is p	
	Н	1.52 1.12 1.41	1.09	1.53	nik (seese From	Stanes Will However,
000	eg eg	2.30	1.94 2.08 1.68	2.44	with the held otice the corre	at as possible carbon. N
bonding.	F	1.71 1.42 1.76	1.35 1.63 [1.42]	Box SylviU Mys	d PRI of son	Coulson, Vale
	Cl	2.16 (1.74) 2.14	1.77	ni) liber	design bil	6 Single-bo
20 110	C	1.96 1.56 1.94	1.54			
and and	Br	2.33 1.93 2.28	06.0°	083	21 24 Ms	C C
	В	1.72	15	50.	22 q	
lg.	As	2.44	나를 다	81.	19 4A 14 (C)	Ge 1.22
bonding.		As B Br	CC	В Н	ZOA Số	Se Si Te

Table 3.5 Carbon-carbon single-bond lengths and hybridizations in various hydrocarbons

Bond type	Hybridization	r, Å
<b>&gt;</b> c−c <b>∈</b>	$sp^3$ - $sp^3$	1.54
>c-c€	$sp^3$ - $sp^2$	1.51
<u>&gt;</u> C-C≡	sp³-sp	1.46
>c-c<	$sp^2$ - $sp^2$	1.46
Ç-C≡	sp²-sp	1.44
<b>≡</b> C−C <b>≡</b>	sp-sp	1.37

orbitals increases on going from sp<sup>3</sup> to sp hybridization, the bond distance decreases and the bond strength increases. 19

By use of the data in Table 3.4, it can be shown that, in most cases, the distance of a heteronuclear covalent bond, A—B, is approximately the arithmetic average of the distances of the corresponding homonuclear covalent bonds, A—A and B—B. Therefore it is possible to assign covalent radii to atoms and to use these to estimate unknown covalent bond distances. The covalent radii listed in Table 3.6 are, in most cases, simply one-half of the homonuclear single-bond distances. However, in some cases the values were chosen so as to give as good agreement as possible with the heteronuclear bond distances, especially with the bonds to carbon. Notice the correlation of covalent radius with position in the periodic table. The data bear out the trends discussed in Chap. 1.

<sup>19</sup> C. A. Coulson, "Valence," p. 199, Oxford University Press, New York, 1952.

Table 3.6 Single-bond covalent radii (in ang-stroms)

Section Section 1				H 0.30
B	C	N	O	F
0.86	0.77	0.70	0.66	0.58
	Si	P	S	Cl
	1.17	1.12	1.02	1.00
	Ge	As	Se	Br
	1.22	1.22	1.16	1.14
	Sn	Sb	Te	I
	1.40	1.40	1.43	1.34

Table 3.7 Covalent radii for carbon, nitrogen, and oxygen

		r, Å	sat noow
Atom	Single bond	Double bond	Triple bond
C	0.77	0.67	0.60
N	0.70	0.60	0.55
0	0.66	0.55	0.53

As one might expect, bond distance decreases as bond order increases. This can be seen from the covalent radii for carbon, nitrogen, and oxygen in Table 3.7. This general correlation can be used to detect partial multiple-bond character, or delocalized  $\pi$  bonding, in molecules. For example, in SO<sub>2</sub> the S—O bond order is 1.5, and the observed bond distance, 1.43 Å, is 0.25 Å shorter than the sum of the single-bond covalent radii (1.02 + 0.66 = 1.68 Å). In BF<sub>3</sub>, the B—F bond order is 1.33, and the observed bond distance, 1.30 Å, is 0.14 Å shorter than the sum of the single-bond covalent radii (0.86 + 0.58 = 1.44 Å). The correlation of N—O bond distance with bond order can be seen from the data in Table 3.8.

In SiF<sub>4</sub>, the Si—F bond distance, 1.56 Å, is 0.19 Å shorter than the sum of the single-bond radii (1.17 + 0.58 = 1.75 Å). The cause of this apparent bond

Table 3.8 Nitrogen-oxygen bond distances

Compound	Formal bond order	Bond distance. Å
OÑ—OH, H₂Ñ—OH	d Markins	1.46
O2N—OH		1.41
(CH <sub>3</sub> ) <sub>3</sub> N-O-	WHILE WAR	~1.4
(C113)311 C	1.33	1.24
$NO_3^-$ $\begin{cases} N_2O_5 \\ NaNO_3 \end{cases}$	1.33	1.21
NO -	15	1.24
CINO, VINO ZI -4.0 III SOI	1.5	1.24
CH, NO, OX 9 1990 AND DATE	1.5	1.22
HONO <sub>2</sub> (nitro group)	1.5	1.22
$N \equiv \stackrel{+}{N} - \stackrel{-}{O} \leftrightarrow \stackrel{-}{N} = \stackrel{+}{N} = 0$	~1.5	1.19
NO <sub>2</sub>	1.75	1.19
CINI	2	1.14
NO <sub>2</sub> <sup>+</sup> round for the military to	2 2 2	1.15
NO	2.5	1.15
NO <sup>+</sup>	3	1.06

shortening is a subject of some dispute. Schomaker and Stevenson<sup>20</sup> proposed that the shortening is a result of the relatively high ionic character of the bond. That is, they proposed that the bond is extraordinarily strong and short because of the electrostatic attraction between the very positive silicon atom and the very negative fluorine atom. Others have proposed that the shortening of such bonds is a result of  $p\pi \to d\pi$  bonding,<sup>21</sup> which is not feasible in the case of bonds involving only first-row atoms, such as the C—F bond. Another possibility is that the Si—F bond distance is normal but that the C—F bond distance is extraordinarily long because of repulsion between the lone-pair electrons of the fluorine and the electrons of the other three bonds to the carbon atom. (We shall later say more about the repulsive interactions of nonbonding and bonding electrons.) Perhaps the apparent shortening of the Si—F bond is due to a combination of the effects that we have discussed. In any event, the phenomenon serves as an indication of the errors which one can make by incautious use of covalent atomic radii.

The covalent radius for hydrogen, which is consistent with the other covalent radii and the various X—H bond distances, is much less than one-half the H—H bond distance. Probably the H—H bond is abnormally long (and weak) because the 1s orbitals of the atoms cannot overlap adequately without undue proton-proton repulsion. On the other hand, when a hydrogen atom forms a bond to an atom which offers a highly directional bonding orbital (e.g., an orbital with appreciable p character), the hydrogen atom can immerse itself in the other atom's bonding orbital, and thus very strong orbital overlap can be achieved.

The covalent single-bond radii for fluorine, oxygen, and nitrogen in Table 3.6, which were calculated by subtracting the covalent radius of carbon from the C-F, C-O, and C-N bond distances, respectively, are considerably less than one-half the F-F, O-O, and N-N single-bond distances, respectively. It is generally supposed that the latter distances are abnormally large because of strong repulsive interaction between the lone-pair electrons on adjacent atoms. Because the fluorine, oxygen, and nitrogen atoms are relatively small, lone pairs on adjacent atoms are close together and repel each other more strongly than they do in bonds such as Cl-Cl and S-S. The N-N bond distance in hydrazine  $(H_2N-NH_2)$  is reduced from 1.47 to 1.40 Å by protonation of the two lone pairs and formation of the hydrazinium ion,  $H_3N-NH_3$ . The same sort of effect is observed on going from hydroxylamine,  $H_2N-NH_3$ . The same sort of effect is ylamine oxide,  $(CH_3)_3N-O^-(r_{N-O}=1.36 \text{ Å})$ .

It is rather interesting that the O—O bond distance in  $O_2F_2$  is only 1.22 Å, almost as short as that in  $O_2$  (1.21 Å).<sup>22</sup> This short bond has been explained in

<sup>&</sup>lt;sup>20</sup> V. Schomaker and D. P. Stevenson, J. Am. Chem. Soc., 63, 37 (1941).

<sup>21</sup> T. B. Brill, J. Chem. Educ., 50, 392 (1973).

<sup>&</sup>lt;sup>22</sup> R. H. Jackson, *J. Chem. Soc.*, 4285 (1962); J. K. Burdett, D. J. Gardiner, J. J. Turner, R. D. Spratley, and P. Tchir, *J. Chem. Soc. Dalton*, 1928 (1973).

terms of hyperconjugation, which shifts nonbonding electrons from the oxygen atoms to the fluorine atoms.

$$F-O-O-F \leftrightarrow F^-O=O^+-F \leftrightarrow F-O^+=O F^-$$

As would be expected on the basis of such resonance, the O—F bond length is exceptionally long, 1.58 Å.

It should come as no surprise that bonds of order less than 1 are longer than single bonds. Thus in  $I_3^-$ , which has two bonds of order 0.5, the I—I bond distance is 2.91 Å, or 0.24 Å longer than that in  $I_2$ . The molecule PF<sub>5</sub> has a trigonal bipyramidal structure, with two axial fluorines, each 1.58 Å from the phosphorus, and three equatorial fluorines, each 1.53 Å from the phosphorus. These bond distances are slightly longer than the P—F bond distance in PF<sub>3</sub>, 1.52 Å, and reflect the fact that the average bond order in PF<sub>5</sub> is 0.8, if we ignore the participation of phosphorus 3d orbitals in the bonding.

## BOND STRENGTH

## **Dissociation Energies**

The most straightforward measure of the strength of the bond in a diatomic molecule is the "dissociation energy," i.e., the energy required to break the gaseous molecule into its constituent atoms. A listing of dissociation energies for some diatomic molecules is given in Table 3.9.<sup>23</sup> From these data it can be seen that, within families of molecules such as HF, HCl, HBr, HI or C<sub>2</sub>, Si<sub>2</sub>, Pb<sub>2</sub>, the heavier analogs generally have lower dissociation energies. Comparison of the data for N<sub>2</sub>, O<sub>2</sub>, and F<sub>2</sub> and for P<sub>2</sub>, S<sub>2</sub>, and Cl<sub>2</sub> shows that, for similar molecules, the dissociation energy increases with increasing bond order. The data as a whole indicate that, for related molecules, there is an inverse relationship between dissociation energy and bond length.

In the case of a polyatomic molecule, the energy required to break just one bond, with formation of two molecular fragments, is called a "bond dissociation energy." A brief selection of bond dissociation energies is given in Tables 3.10 and 3.11.<sup>24</sup> Bond dissociation energies are valuable data for thermochemical calculations, but their interpretation as a measure of bond strength is somewhat hazardous because of the structural and electronic rearrangements which occur in

<sup>&</sup>lt;sup>23</sup> The dissociation energies, bond energies, and other thermodynamic data given in this chapter are taken from S. W. Benson, "Thermochemical Kinetics," Wiley-Interscience, New York, 1976; Rosenstock et al., *J. Phys. Chem. Ref. Data*, 6, suppl. 1 (1977); D. A. Johnson, "Some Thermodynamic Aspects of Inorganic Chemistry," Cambridge University Press, London, 1968; S. R. Gunn, *Inorg. Chem.*, 11, 796 (1972); L. Pauling, "The Nature of the Chemical Bond," 3d ed., Cornell University Press, Ithaca, N.Y., 1960; L. Brewer, Lawrence Berkeley Laboratory Report LBL 3720 Rev., May 4, 1977.

<sup>&</sup>lt;sup>24</sup> See footnote 23 above.

Table 3.9 Dissociation energies of some gaseous diatomic molecules at 298 K

Molecule	D, kcal mol <sup>-1</sup>	Molecule	D, kcal mol-1
H <sub>2</sub>	104.2	LiCl divided on	F 60114 (19072)
$D_2$	106.0	BeCl	93
	135.8	BCl	128
HF	103.2	CCI	80
HCl		OCI	64.3
HBr	87.5	NaCl	98
HI	71.3	MgCl	190718 74 STREETY
LiH	58	AlCl	118.1
BH	79	KCl	101.5
CH	81	CuCl	78
NH	75	AgCl	75
OH	102.3	HgCl	25
NaH	48		110.1
AlH	68	O <sub>2</sub>	119.1
PH	73	S <sub>2</sub> SO	102.6 124.7
SH	85		
KH	44	Se <sub>2</sub>	73.6
HgH	10	Te <sub>2</sub>	53.8
F <sub>2</sub>	37.8	BeO	107
Cl <sub>2</sub>	58.2	BO	182
Br <sub>2</sub>	46.1	CO	256.9
I <sub>2</sub>	36.1	NO	151.0
		MgO	91
CIF	61.0	AlO	116
BrF	59.4	SiO	190
IF D.C.	66.2	PO	141
BrCl	51.5	BrO	56.3
ICI	49.6		
IBr	41.9	C <sub>2</sub> Si <sub>2</sub>	142.4
LiF	137		81
BeF	147	Pb <sub>2</sub>	13
BF	180	N <sub>2</sub>	226.0
CF Items	129	P <sub>2</sub>	117
NF	72	Sb <sub>2</sub>	70
OF	52	PN	168
NaF	115	Li <sub>2</sub>	
MgF	107.3	Na <sub>2</sub>	26
AIF	159	K <sub>2</sub>	cause (1)
KF	118.1	Cu <sub>2</sub>	
			46
		Ag <sub>2</sub>	37
	Wat I bearing the latest of the	CN management	183
		CS d and he	183
		B <sub>2</sub>	imail) of person la

inversing Press, Brauca, N.Y. 1960; L. Brewen, Lawrence Stefance has nowing Reventing his court and the con-

Table 3.10	Some bond	dissociation	energies o	f gaseous	molecules and radicals
------------	-----------	--------------	------------	-----------	------------------------

Molecule	D, kcal mol <sup>-1</sup>	Molecule	D, kcal mol
но—н	119	CH <sub>2</sub> =NH	154
CH₃COO—H	112	H <sub>2</sub> N-NH <sub>2</sub>	58
Н₃СО—Н	102	но-он	51
ноо-н	90	NH <sub>2</sub> -Cl	60
C <sub>6</sub> H <sub>5</sub> O—H	85	HO-CI	60
CIO—H	78	но-і	56
NC-H	130	00-Н	47
Cl <sub>3</sub> C—H	96	CH <sub>2</sub> O—H	31
HC≡CH	230	соо-н	12
HC≡N	224	CH <sub>2</sub> —H	106
CH,=CH,	163	СН—Н	106
$CH_2 = O$	175	CH <sub>2</sub> CH <sub>2</sub> —H	39
HN=O	115		

the molecular fragments that form when a bond in a molecule is broken. Unfortunately, the sum of the separate dissociation energies of the bonds of a molecule is not equal to the energy of dissociating the molecule completely into atoms. For example, consider the molecule OCS:

$$OCS(g) \rightarrow CO(g) + S(g)$$
  $D(OC=S) = 74 \text{ kcal mol}^{-1}$   
 $OCS(g) \rightarrow O(g) + CS(g)$   $D(O=CS) = 31 \text{ kcal mol}^{-1}$   
 $OCS(g) \rightarrow O(g) + C(g) + S(g)$   $\Delta H_{\text{atom}}^{\circ}(OCS) = 331 \text{ kcal mol}^{-1}$ 

The sum of D(OC=S) and D(O=CS) is much less than the atomization energy of OCS. However, each of the sums D(OC=S) + D(C=O) and D(O=CS) + $D(C \equiv S)$  must equal the atomization energy of OCS.

At least a few remarks should be made regarding the methods used to obtain dissociation energies. In most cases, the dissociation energies were calculated from heats of formation such as those given in Appendix E and Table 3.12. Thus from the heats of formation of HCl(g), H(g), and Cl(g), one can readily calculate D(H—Cl). The heat of formation of HCl(g) was obtained by directly measuring the heat of reaction of H<sub>2</sub> and Cl<sub>2</sub> in a calorimeter; the heats of formation of H(g) and Cl(g) are calculated from the dissociation energies of H2 and Cl2, which in turn were obtained from electronic absorption spectral data. The heats of formation of molecules such as NaCl(g), which at room temperature are unstable with respect to crystalline phases, obviously cannot be directly measured in a calorimeter. One method for obtaining the heat of formation of such gaseous molecules is by measuring the vapor pressure of the diatomic molecule over the solid as a function of temperature. From the derived heat of vaporization and the known heat of formation of the solid (obtained calorimetrically), one readily

(1+387) (1+0) (185+1) Table 3.11 Bond-dissociation energies for some gaseous organic molecules R—X (in kilocalories per mole)†

C,H,	100 97 97 98 92 116 77 78 99 99
(8.0 ± 1) t-Bu	81 78 74 70 92 65 66 (69)
(18 ± 1) i-C <sub>3</sub> H,	84 80 80 80 77.5 74 95 67.5 69.5 80 82 (71)
(26 ± 1) C <sub>2</sub> H <sub>5</sub>	85 82 82 80 78 97 71.5 72 72 96
(34 ± 1) CH <sub>3</sub>	88 85 85 84 84 81 100 72 74.5 81 81 81 99
) (4 ± 1) OCH <sub>3</sub>	82 82 82 82 82 82 82 82 82 70 70 68 83 82 82 82 82 82 82 82 82 82 82 82 82 82
$\begin{array}{c} (46\pm1) \\ NH_2 \end{array}$	88 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8
(9.5) OH	91.5 91.5 91.5 92 92 92 92 112 77 80 108 43 (28)
(25.5)	56 53.5 53.5 53.5 53 51 64 40 43.5 51.6
(26.7) Rr	0,888,848
(28.9)	83.5 81.5 81.5 81.5 80 80 82.5
(19.8)	109 108 108 105 125 125
(52.1)	104 98 94.5 92. 110.5 85 87 87 104
o te grae	CH, C,H, i-C,H, i-C,H, i-C,H, c,H, C,H, C,H, C,H,CD, Allyl CH,CO CH,CH,O CH,CH,O
temo teno closs tota	(34 ± 1)‡ (26 ± 1) (26 ± 1) (21 ± 1) (18 ± 1) (18 ± 1) (18 ± 1) (18 ± 1) (18 ± 1) (18 ± 1) (18 ± 1) (18 ± 1) (19 ± 1) (1

Data taken with permission from S. W. Benson. "Thermochemical Kinetics," Wiley-Interscience, New York, 1976. Values in parentheses are estimates. Values in parentheses are estimates.

Table 3.12 Heats of formation of the gaseous atoms at 25°C (in kilocalories per mole)

Aluminum	78.7	Hydrogen	52.1	Radon	0
Americium	63	Indium	58.0	Rhenium	185.4
Antimony	63.5	Iodine	25.52	Rhodium	133
Argon	0	Iridium	160.3	Rubidium	19.33
Arsenic	68.4	Iron	99.3	Ruthenium	155.8
Barium	43.5	Krypton	0	Samarium	49.4
Beryllium	77.5	Lanthanum	103.1	Scandium	90.3
Bismuth	50.1	Lead	46.6	Selenium	52.0
Boron	135	Lithium	38.1	Silicon	107.7
Bromine	26.7	Lutecium	102.2	Silver	68.1
Cadmium	26.7	Magnesium	35.0	Sodium	25.6
Calcium	42.6	Manganese	67.7	Strontium	39.5
Carbon	171.29	Mercury	14.5	Sulfur	66.29
Cerium	99.5	Molybdenum	157.6	Tantalum	187
Cesium	18.18	Neodymium	78.3	Technetium	158
Chlorine	29.1	Neon	0	Tellurium	51.4
Chromium	95	Neptunium	109	Terbium	93
Cobalt	101.7	Nickel	102.9	Thallium	43.2
Copper	80.7	Niobium	175.2	Thorium	142.8
Dysprosium	68.5	Nitrogen	113.0	Thulium	55.5
Erbium	75.5	Osmium	188.6	Tin	72.5
Europium	42.4	Oxygen	59.2	Titanium	112.5
Fluorine	18.9	Palladium	90.0	Tungsten	205.5
Gadolinium	95.2	Phosphorus	79.8	Uranium	128
Gallium	65.0	Platinum	134.9	Vanadium	123
Germanium	89.5	Plutonium	83.1	Xenon	0
Gold	88.0	Polonium	34.5	Ytterbium	37.0
Hafnium	148.5	Potassium	21.33	Yttrium	101.0
Helium	0	Praeseodymium	85.0	Zinc	31.2
Holmium	71.9	Protactinium	146	Zirconium	144.5

calculates the heat of formation of the gaseous molecule. These and other techniques for determining dissociation energies are discussed by Cottrell.<sup>25</sup>

### **Bond Energies**

Because of the nonadditivity of bond dissociation energies of molecules, chemists commonly measure bond strengths in terms of bond energies which, for polyatomic molecules, are hypothetical because they are calculated on the assumption that the sum of the bond energies of a molecule equals the atomization energy of the molecule. The usefulness of this concept lies in the fact that the calculated bond energy for a particular type of bond, say an S—H bond, is found to be approximately constant in different molecules containing that type of bond. We

<sup>&</sup>lt;sup>25</sup> T. L. Cottrell, "The Strengths of Chemical Bonds," 2d ed., Butterworth, London, 1958.

may demonstrate the approximate validity of the method by a simple calculation. Consider the atomization energy of cyclooctasulfur:

$$S_8(g) \rightarrow 8S(g) \quad \Delta H_{atom}^{\circ}(S_8) = 508.4 \text{ kcal mol}^{-1}$$

We assume that the atomization energy is eight times the S—S bond energy, E(S-S); hence we calculate E(S-S) = 508.4/8 = 63.6 kcal mol<sup>-1</sup>. Similarly, for the atomization of hydrogen sulfide,

$$H_2S(g) \rightarrow 2H(g) + S(g) \qquad \Delta H_{atom}^{\circ}(H_2S) = 175.7 \text{ kcal mol}^{-1}$$

We assume that the atomization energy is two times the S—H bond energy, E(S-H). Thus we calculate E(S-H) = 175.7/2 = 87.8 kcal mol<sup>-1</sup>. Using these bond energies, we estimate 63.6 + 2(87.8) = 239.3 kcal mol<sup>-1</sup> for the atomization of disulfane,

$$H_2S_2(g) \rightarrow 2H(g) + 2S(g)$$

The actual atomization energy for this molecule is 235 kcal mol-1.

A wide variety of bond energies are listed in Table 3.13.26 These approximate

Table 3.13 Thermochemical (average) bond energies (in kilocalories per mole)

As—As	40	Ge—Ge	38	s-s	64
As—F	116	Ge-F	113	S-CI	65
As—Cl	74	Ge-Cl	81	S—Br	51
As—Br	61	Ge—Br	67	S—H	88
As—H	71	Ge—I	51	Sb—Sb	34
As-O	79	Ge—H	69	Sb—Cl	75
В-В	79	Ge-O	86	Sb—Br	63
B-F	154	Ge-N	61	Sb—H	61
B-Cl	106	N-N	38		
B—Br	88	N=N	100	Se—Se	38
B-1	65	N≡N	226	Se-Cl	58
В—Н	91	N-F	67	Se—H	73
В-О	125	N-Cl		Si—Si	46
C-C	83	N-H	45	Si—Ge	42
C=C	147	N-O	93	Si-F	143
C≡C	194	N=0	39	Si—Cl	96
C-F	117	0-0	142	Si-Br	H DE 79
C-CI	78	0=0	34	Si—H	76
C—Br	65	0-F	119	Si-O	OSDE 111
C-I	57	0-CI	51	Si-Non Vis	80
С-Н	99	0-н	49	Si-S	54
C-0	86	P—P	111	Si-C	73
C=0	174	P-F	47	Sn-Sn	36
C-N	0) 21 73	and the second s	119	Sn-Cl	75
C=N	Moderate 147	P—CI	79	Sn-Br	do bn 64
C≡N	213	P—Br	64	Sn-H	60
C=S	114	Р—Н	77	Sn-C	50
8081	EVONT LONGON	P-0	88		20

<sup>26</sup> See footnote 23 on p. 55.

bond energies, in combination with the relatively accurately known heats of formation of the gaseous atoms in Table 3.12,<sup>27</sup> may be used to estimate the heat of formation of any nonresonant molecule containing these bonds.

From the data in Table 3.13 and some of the data in Table 3.9, it can be shown that the bond energies for heteronuclear bonds are considerably greater than the average of those for the corresponding homonuclear bonds. For example, the As—Cl bond energy (74 kcal mol<sup>-1</sup>) is much greater than either the As—As bond energy (40 kcal mol<sup>-1</sup>) or the Cl—Cl bond energy (58.2 kcal mol<sup>-1</sup>). Pauling<sup>28</sup> ascribed this enhancement of a heteronuclear bond energy to the ionic character of the bond and showed that the bond energy in kilocalories per mole can be represented by the equation

$$E(A - B) = \frac{1}{2}[E(A - A) + E(B - B)] + 23(x_A - x_B)^2$$
(3.1)

where  $x_A$  and  $x_B$  refer to the empirically evaluated electronegativity values listed in Table 3.14. It is obvious from Eq. 3.1 that the bond energy for a bond between two atoms of equal electronegativity would be expected to be the arithmetic average of the homonuclear bond energies.<sup>29</sup> It should be emphasized that Eq. 3.1 is a very approximate relation and should be used only when a very crude estimate will suffice. Nevertheless, it serves as the basis for a very useful generalization: The most stable arrangement of covalent bonds connecting a group of

Table 3.14 The original Pauling scale of electronegativities showing periodic table trends†

H 2.1		1	3 50			iaCty- Control					100					H, HO
Li 1.0	Be 1.5	B 2.0													O 3.5	
Na	Mg												Si	P		Cl
K 0.8	Ca 1.0	Sc 1.3	Ti 1.5		Cr 1.6			Co 1.8					Ge	As	Se	Br
0.8		1.2	Zr 1.4	Nb	Мо	Tc 1.9	Ru		Pd	Ag	Cd	In	Sn	Sb	Te	I
0.7	0.9	1.1 - 1.2	1.3	Ta	W	Re	Os		Pt	Au	Hg	TI	Pb	Bi	Po	At
Fr 0.7	Ra 0.9	Ac 1.1	Th 1.3	Pa 1.5	U 1.7	Np-No										

<sup>†</sup> For revised Pauling values and values calculated by other methods, see Table 3.19.

<sup>&</sup>lt;sup>27</sup> See footnote 23 on p. 55.

<sup>28</sup> Pauling, op. cit.

<sup>&</sup>lt;sup>29</sup> Pauling (op. cit.) has pointed out that it is more accurate to use the geometric mean,  $[E(A-A)E(B-B)]^{16}$ . However, the arithmetic mean is easier to apply and in most cases is of similar magnitude.

atoms is that arrangement in which the atom with the highest electronegativity is bonded to the atom with the lowest electronegativity. There are many examples of spontaneous reactions, such as the following, which bear out this rule.

$$BBr_3 + PCl_3 \rightarrow BCl_3 + PBr_3$$

$$2HI + Cl_2 \rightarrow 2HCl + I_2$$

$$TiCl_4 + 4EtOH \rightarrow Ti(OEt)_4 + 4HCl$$

#### **Force Constants**

Another useful measure of the strength of a bond is the bond-stretching force constant. This is the constant of proportionality between the force tending to restore the equilibrium bond distance and an infinitesimal displacement from that distance. For small displacements, most bonds act as harmonic oscillators,

Table 3.15 Some bond-stretching force constants†

Bond	Force constant, mdyn Å <sup>-1</sup>	Bond	Force constant mdyn Å <sup>-1</sup>
N <sub>2</sub>	22.6	F <sub>2</sub>	4.5
CO	18.7	Cl <sub>2</sub>	3.7
HC≡CH	15.7	Br <sub>2</sub>	2.4
P <sub>2</sub>	5.5	$I_2$	1.7
As <sub>2</sub>	4.0		1.7
0,		HgCl <sub>2</sub>	2.11
$H_2C = CH_2$	11.4	HgCl <sub>3</sub> -	1.27
OC=S	9.6	HgCl <sub>4</sub> <sup>2-</sup>	0.82
00-3	7.5	GeCl <sub>4</sub>	
H <sub>2</sub>	5.1	GaCl <sub>4</sub>	3.27
CH <sub>4</sub>	5.0		2.50
NH <sub>3</sub>	6.4	ZnCl <sub>4</sub> <sup>2-</sup>	1.64
PH <sub>3</sub>	3.2	MnCl <sub>4</sub> <sup>2-</sup>	1.39
KH	0.53	MnBr <sub>4</sub> <sup>2-</sup>	1.16
Lil & 9		MnI <sub>4</sub> <sup>2-</sup>	0.92
PCl <sub>3</sub>	0.77	T:Cl 2-	
PBr <sub>3</sub>	2.1	TiCl <sub>6</sub> <sup>2-</sup>	1.13
Na <sub>2</sub>	1.6	ZrCl <sub>6</sub> <sup>2-</sup>	0.88
NO	1.7	HfCl <sub>6</sub> <sup>2-</sup>	0.86
NO THE REAL PROPERTY.	15.5	PtCl <sub>6</sub> <sup>2-</sup>	1.86
HF	8.8	The man of the	
HCI	4.8		
HBr	3.8	40 40 45 4	
HI	2.9	11 5 55 2 2 2 2	

<sup>†</sup> Data from T. L. Cottrell, "The Strengths of Chemical Bonds," 2d ed., Butterworth, London, 1958, and A. Finch, P. N. Gates, K. Radcliffe, F. N. Dickson, and F. F. Bentley, "Chemical Applications of Far Infrared Spectroscopy," Academic, London, 1970.

and we can write the following relationship between the vibrational frequency v and the force constant k of a bond A - B:

$$v = \frac{1}{2\pi c} \sqrt{\frac{k}{\mu}}$$

Here  $\mu$  is the reduced mass of A and B,  $\mu = m_A m_B / (m_A + m_B)$ . If we express v in wave numbers (reciprocal centimeters), k in millidynes per angstrom, and  $\mu$  in the usual atomic-weight units, we obtain the relation  $v^2 = (1.70 \times 10^6)k/\mu$ . A diatomic molecule has only one vibrational frequency, which obviously corresponds to the bond stretching. However, polyatomic molecules have a number of vibrational frequencies, and these are not necessarily directly related to the stretching of individual bonds. The calculation of bond force constants from the vibrational frequencies of a polyatomic molecule is a relatively complicated procedure, involving assumptions regarding the dependence of the energy of the molecule on the atomic coordinates. The calculated force constants are strongly dependent on the nature of these assumptions. Some bond force constants for both diatomic and polyatomic molecules, calculated using very simple assumptions,<sup>30</sup> are given in Table 3.15.

For a series of related bonds, the force constant increases with increasing bond energy, with increasing bond order, and with decreasing bond length. The relationship between force constant and bond length for Mo—O bonds is shown in Fig. 3.1.

<sup>30</sup> Force constants for the diatomics were calculated using the harmonic oscillator (Hooke's law) approximation. For polyatomics, the "valence force field" was assumed; that is, a force constant was associated with every valence bond, representing its resistance to stretching, and to every valence angle, representing its resistance to bending.




Figure 3.1 Plot of Mo—O force constants versus the corresponding bond lengths. [Reproduced with permission from F. A. Cotton and R. M. Wing, Inorg. Chem., 4, 867 (1965). Copyright 1965 American Chemical Society.]

#### BOND POLARITY

The electrons of a heteronuclear bond are generally not shared equally by the two bonded atoms. The bonding electron density is almost always greater near one atom (the more electronegative atom) than the other. This polarization is depicted graphically for the gaseous LiH molecule in Fig. 3.2. This figure is a plot of the electron density of LiH minus the electron density of the hypothetical pair of neutral, noninteracting atoms, for a plane passing through the two nuclei.<sup>31</sup> The plot shows that bond formation causes electron density to leave the outer regions of the lithium atom, including a region in the direction of the hydrogen atom, and to enter the region around the hydrogen atom (especially in the bonding region) and the region near the lithium nucleus. This polarization is qualitatively what one would expect for a bond between the electropositive lithium atom and the relatively electronegative hydrogen atom. The electron

<sup>31</sup> A. Streitwieser, Jr., and P. H. Owens, "Orbital and Electron Density Diagrams," Macmillan, New York, 1973.




Figure 3.2 Plot of electron density in LiH less electron density of neutral Li + H. (Reproduced with permission from A. Streitwieser, Jr., and P. H. Owens, "Orbital and Electron Density Diagrams."

flow is not complete, in the sense that the compound does not correspond to Li<sup>+</sup> and H<sup>-</sup>, but the covalent bond between the atoms does have a lot of ionic character. The effective nuclear charge of the lithium atom is increased because the reduced electron density gives poorer shielding; hence some electron density crowds around the nucleus, and the atom is effectively smaller. Conversely, the hydrogen atom has greater electron density, and is effectively larger, than a neutral H atom.

## **Dipole Moments**

One way of quantitatively expressing the ionic character of a bond is by assigning fractional charges to the atoms. The dipole moment  $\mu$  of LiH is  $5.88 \times 10^{-18}$  esu cm = 5.88 Debye units; if we assume that this moment is due to two point charges, +q and -q, separated a distance r equal to the Li—H bond distance (1.595 Å), it is an easy matter to calculate q from the relation  $\mu = qer$ .


$$q = \frac{\mu}{er} = \frac{5.88 \times 10^{-18}}{(4.8 \times 10^{-10})(1.595 \times 10^{-8})} = 0.768$$

Thus the dipole moment may be accounted for by assigning a charge of +0.768 to the lithium atom and a charge of -0.768 to the hydrogen atom.

The treatment of LiH as a pair of point charges, or even as a pair of charged spherically symmetric atoms, is an approximation. From Fig. 3.2 it can be seen that the charge distribution of the molecule would be better represented by a pair of charged atoms, each with a dipole moment. The atomic moments would be relatively small, however, and the representation of the overall dipole moment with simple atomic charges is fairly reasonable in the case of LiH. However, in the case of a molecule with nonbonding valence electrons, such as HCl or NH<sub>3</sub>, such a representation is extremely misleading because of the relatively large moments due to the nonbonding electrons. It is instructive to compare the dipole moments of the pyramidal molecules NF<sub>3</sub> ( $\mu = 0.23$  Debye unit) and NH<sub>3</sub> ( $\mu = 1.47$  Debye units). Although the bond angle of NF<sub>3</sub> is more acute than that of NH<sub>3</sub> and although the N—F bond would be expected to be at least as polar as the N-H bond (but with opposite sign), the dipole moment of NF<sub>3</sub> is much smaller than that of NH<sub>3</sub>. The apparent anomaly is caused by the large moment of the lone pair of electrons on the nitrogen atom. In NH<sub>3</sub>, the lone-pair – nitrogen moment adds to the resultant of the N—H moments. Thus NH<sub>3</sub> has a large dipole moment. However, in NF<sub>3</sub>, the lone-pair-nitrogen moment partly cancels the resultant of the N—F moments. Thus NF<sub>3</sub> has a small dipole moment. Reference to Fig. 3.3 will make this clear.

Simple electrostatic molecular models which provide both for the polarity of bonds and for the existence of lone-pair electrons have been devised. Benson<sup>32</sup> has described a molecular model in which atoms are point charges and in which lone pairs are point dipole moments. Halogen atom lone pairs are represented by

<sup>&</sup>lt;sup>32</sup> S. W. Benson, Angew. Chem. Int. Ed., 17, 812 (1978).







Figure 3.3 Explanation of the low dipole moment of NF<sub>3</sub>. Arrows indicate the direction from + to -.

single point dipoles centered at the nuclei and oriented along the bond axes. Thus a methyl halide is represented by this type of model as follows:

$$H^{+y}$$
 $C \xrightarrow{z-3y} Z \xrightarrow{-z} X \xrightarrow{+y} H$ 

Benson has shown that the heats of formation and dipole moments of molecules can be used to calculate consistent sets of atomic charges and lone-pair moments. In the  $CH_nF_{4-n}$  series a lone-pair moment for fluorine of about 0.7 Debye unit and a charge separation across each C-F bond of about 0.15 comes close to reproducing the thermochemical and dipole data. Scheraga et al. 33 have used a different model, in which molecules are made up of atomic cores (with point integral charges) and both bonding and "lone" electron pairs (-2 point charges). Thus the water molecule is represented by this type of model as follows:



By assuming that  $R_i(O)$  is a constant for all 2-coordinate oxygen compounds and by making certain approximations about the transferability of  $R_b(O)$  to other compounds, it has been shown that the dipole moment data for a variety of molecules are consistent with the following parameters:  $R_b(O) = 0.570 \text{ Å}$ ,  $\theta = 120^\circ$ . These methods of accounting for lone-pair electron find general applicability to both organic and inorganic molecules.

<sup>&</sup>lt;sup>33</sup> L. L. Shipman, A. W. Burgess, and H. A. Scheraga, *Proc. Nat. Acad. Sci. USA*, 72, 543 (1975);
A. W. Burgess, L. L. Shipman, and H. A. Scheraga, ibid., 72, 854 (1975); A. W. Burgess, L. L. Shipman, R. A. Nemenoff, and H. A. Scheraga, *J. Am. Chem. Soc.*, 98, 23 (1976).

## Nuclear Magnetic Resonance

Other physical properties of molecules are related to molecular charge distribution. Chemical shifts and spin-spin coupling constants from nuclear magnetic resonance (nmr) spectra<sup>34</sup> are sensitive to electron density at the nucleus. Thus in Fig. 3.4 is shown a correlation of proton chemical shift in methyl compounds with the electronegativity of the atom bonded to the methyl group. One can rationalize the data by arguing that the more electronegative atoms pull electrons away from the protons, thus deshielding them and allowing the protons to resonate at a lower applied magnetic field. Unfortunately, however, nmr parameters are affected by other features besides electron density, and these effects are not understood well enough to permit the use of nmr parameters as reliable measures of atomic charge.

## Nuclear Quadrupole Resonance

The nuclear quadrupole (nqr) coupling constant<sup>35</sup> of an atom is a measure of the asymmetry of the electric field at the nucleus. A free chloride ion, for example,

<sup>34</sup> Nuclear magnetic resonance spectroscopy, nuclear quadrupole resonance spectroscopy, and Mössbauer spectroscopy are discussed in W. L. Jolly, "The Synthesis and Characterization of Inorganic Compounds," Prentice-Hall, Englewood Cliffs, N.J., 1970; R. S. Drago, "Physical Methods in Chemistry," Saunders, Philadelphia, 1977; and H. A. O. Hill and P. Day (eds.), "Physical Methods in Advanced Inorganic Chemistry," Wiley-Interscience, New York, 1968.

35 See footnote 34 above.




Figure 3.4 Plot of pmr chemical shifts for methane derivatives versus the Pauling electronegativity of the substituent atoms. [Reproduced with permission from H. Spieseke and W. G. Schneider, J. Chem. Phys., 35, 722 (1961).]

should exhibit no quadrupole coupling. The greater the electronegativity of the atom bonded to a chlorine atom, the more asymmetric is the electric field at the chlorine nucleus, and the greater is the absolute magnitude of the nqr coupling constant. The trend of the chlorine-35 coupling constant with the electronegativity of the substituent is shown by the data in Table 3.16. Unfortunately the interpretation of these data in terms of chlorine's atomic charge is complicated by the fact that the electric field gradient is a function of the hybridization of the bonding orbital as well as the atomic charge. Because of the difficulty of estimating the s character of a chlorine bonding orbital, data such as those in Table 3.16 are restricted to qualitative interpretation.

# Mössbauer Spectroscopy

In Mössbauer spectroscopy<sup>36</sup> one can measure shifts in the energy of a nuclear transition caused by changes in the electronic environment of the nucleus. These "isomer shifts" are caused by changes in s electron density at the nucleus and are essentially independent of the population of other atomic orbitals. Thus isomer shifts can be meaningfully interpreted in terms of changes in atomic charge only for compounds having similar structures and orbital hybridizations. For example, shifts for the tin nucleus in a series of hexahalostannate salts, listed in Table 3.17, can readily be correlated with the electron-withdrawing abilities of the

Table 3.16 Chlorine-35 nuclear quadrupole coupling constants†

Compound	Court Constants
	Coupling constant, MHz
Free Cl-	0.0
LiCI	-6.1
(CH <sub>3</sub> ) <sub>3</sub> CCI	-62.1
(CH <sub>3</sub> ) <sub>2</sub> CHCl C <sub>2</sub> H <sub>5</sub> Cl	-64.1
CH <sub>3</sub> Cl	-65.8
CH <sub>2</sub> Cl <sub>2</sub>	-68.1
CHCl <sub>3</sub>	-72.0
CCI <sub>4</sub>	-76.7
CI	-81.2
BrCl	-82.5
71,	-103.6
CIF	-109.0
	-146.0

<sup>†</sup> J. E. Huheey, "Inorganic Chemistry." 2d ed., p. 178, Harper & Row, New

<sup>36</sup> See footnote 34 on p. 67.

Table 3.17 Mössbauer isomer shifts for some hexahalostannates†

Isomer shift, mm s <sup>-1</sup> :		
-0.36		
+0.29		
+0.52		
+0.53		
+0.67		
+0.77		
+0.78		
+0.84		
+0.96		
+1.09		
+1.23		

† C. A. Clasen and M. L. Good, *Inorg. Chem.*, **9**, 817 (1970).

‡ Shifts are customarily expressed as the experimentally measured relative velocities of the sample and a gamma-ray source required to give resonance absorption.

## X-ray Photoelectron Spectroscopy

Probably the most useful technique for the estimation of atomic charges is x-ray photoelectron spectroscopy (often referred to as ESCA).<sup>37</sup> We have already alluded to this technique in Chap. 1 in connection with the determination of the ionization potentials (binding energies) of the various kinds of electrons in argon. With respect to the estimation of atomic charges, *core*-electron binding energies are of principal interest. It has been shown that, for a given core level of an element in a set of compounds, the binding energies  $E_B$  may be fairly well represented by the following equation:

$$E_B = k_i Q_i + \sum_{j \neq i} \frac{Q_j e^2}{r_j} + l_i$$
 (3.2)

In this expression,  $Q_i$  is the charge of the atom i for which the core binding energy is being calculated,  $Q_j$  is the charge on another atom, j, of the compound,  $r_j$  is the distance between atoms j and i, and  $k_i$  and  $l_i$  are constants characteristic of the element. Inasmuch as the constant  $k_i$  is always positive, the first term in this expression shows that the core binding energy increases with increasing atomic charge. This relation is qualitatively reasonable; one would expect the difficulty

<sup>&</sup>lt;sup>37</sup> K. Siegbahn et al., "ESCA; Atomic, Molecular and Solid State Structure by Means of Electron Spectroscopy," Almqvist and Wiksells, Uppsala, Sweden, 1967; K. Siegbahn et al, "ESCA Applied to Free Molecules," North-Holland, Amsterdam, 1969; J. M. Hollander and W. L. Jolly, *Acc. Chem. Res.*, 3, 193 (1970).




Figure 3.5 X-ray photoelectron spectra of Xe, F<sub>2</sub>, XeF<sub>2</sub>, XeF<sub>4</sub>, XeOF<sub>4</sub>, and XeF<sub>6</sub>. [Reproduced with Permission from T. X. Carroll et al., J. Am. Chem. Soc., 96, 1989 (1974). Copyright 1974 American Chemical Society.]

Rev. 3, 193 (1970)

Table 3.18 Atomic charges de-

Compound	$Q_{\mathrm{Xe}}$	$Q_{F}$	Qo	
XeF,	0.48	-0.24		
XeF <sub>4</sub>	0.97	-0.24		
XeF <sub>6</sub>	1.43	-0.24		
XeOF <sub>4</sub>	1.37	-0.24	-0.43	

† T. X. Carroll, R. W. Shaw, T. D. Thomas, C. Kindle, and N. Bartlett, *J. Am. Chem. Soc.*, **96**, 1989 (1974).

of removing an electron from an atom to increase with the positive charge of the

The xenon  $3d_{5/2}$ , xenon  $3d_{3/2}$ , and fluorine 1s spectra for elementary xenon, molecular fluorine, and a series of xenon fluorides are shown in Fig. 3.5. It can be seen that, as expected, the xenon core binding energies increase as the oxidation state of the xenon increases and that the fluorine 1s binding energy decreases on going from the free element to the fluorides. By assuming that there is an equation analogous to Eq. 3.2 for every atom in the set of xenon compounds and by using the fact that the sum of the atomic charges is zero for each compound, the binding-energy data can be used to estimate atomic charges for the atoms in the xenon compounds. These estimated charges are given in Table 3.18.

# Electronegativities

Pauling defined electronegativity as the power of an atom in a molecule to attract electrons to itself. Clearly this property is closely related to bond polarity and deserves detailed discussion here. As we have shown on page 61, Pauling calculated electronegativities from thermodynamic data; his calculated values are given in Table 3.14. Allred<sup>38</sup> has recalculated these values by the Pauling method, using more recent thermochemical data; his "revised Pauling" values, for the nontransition elements, are given in Table 3.19. Ever since Pauling's pioneering work in this area, many other methods of evaluating electronegativities have been proposed, and we shall now consider a few of these.

It was pointed out by Mulliken<sup>39</sup> that the average of the first ionization potential (IP) and electron affinity (EA) of an atom should be a measure of the electron attraction of the neutral atom and hence of its electronegativity. Indeed if one defines Mulliken electronegativities by the linear relation<sup>40</sup>

$$x_M = 0.187(IP + EA) + 0.17$$

<sup>&</sup>lt;sup>38</sup> A. L. Allred, *J. Inorg. Nucl. Chem.*, **17**, 215 (1961).

<sup>&</sup>lt;sup>39</sup> R. S. Mulliken, J. Chem. Phys., 2, 782 (1934); 3, 573 (1935).

<sup>&</sup>lt;sup>40</sup> J. E. Huheey, "Inorganic Chemistry," 2d ed., p. 167, Harper & Row, New York, 1978.

Table 3.19 Electronegativities of the nontransition elements and a second secon

Element	Revised Pauling	Mulliken	Allred-Rochow	Sandersor
Н	2.2	2.8	2.20	2.31
Li	0.98	1.3	0.97	0.86
Be	1.57	73	1 47	1.61
В	2.04	1.8	2.01	1.88
C	2.55	2.5	2 50	2.47
N	3.04	2.9	3.07	2.93
0	3.44	3.0		
F	3.98	4.1	3.50	3.46
Na	0.93	1.2	4.10	3.92
Mg	1.31		1.01	0.83
Al	1.61	1.4	1.23	1.42
Si	1.90	1.4	1.47	1.54
P	2.19	2.0	1.74	1.74
S	2.58	2.3 01 1100	2.06 10113919 118 9	2.16
Cl	3.16	2.5	2.44	2.66
Ar The Ar	Harrich and transpart	3.3	2.83	3.28
K	0.82		time neuex Time nou	3.92
Ca	1.00	Edin H nonsk	0.91 s bas samoul	0.74
Sc		COLC DARRIERS CO.	s expected, th 40.1 non	1.06
Zn	1.36	parious of the	bn 1.20 coroni mores	1.09 9161
Ga	1.65	201 Turk	166	1.06
Ge	1.81	1.4	1.82	
As	2.01	1.9	2.02	2.10 2.31
Se	2.18	2.2	2.20	2.53
Br	2.55	2.4	2.48 and hisb years	4.00
Kr	2.96	3.0		
Rb	2.9			2.96 0.00
Sr	0.82	1.0	0.00	3.17
Y	0.95		0.89	0.70
Cd	1.22	1.4	eativities e.o.	0.96
In	1.69	is the power of	1.11	0.98
Sn	1.78	1.3	1.46 mortoola ban	1.10
Sb	1.96	1.8	itself Clear 94.1	1.88
Te	2.05	2.0	mod 1.72 anosin baling	2.02
Industry.	2.1	2.2	1.82	2 19
Xe	2.66	2.7 8091 881	2.01	2.34
	2.6		2.21 + L 5lds	2.50
Cs	0.79	ochemical dasa	ing more recent there	
Ba	0.89	1.0	0.86	0.69
La	1.10	v other suction	0.97	0.02
Hg	2.00	Clared won Heal	1.08	
TI	2.04	Safe Water W.	1.44	0.92
Pb	2.33		1.44 100 beinion	1.92
Bi	2.02	PR.10 (AL)	1.55 Whole bre	1.96
1-19-	12 7019 (1)	tom and hence y	1.67	2.01

(where IP and EA are in electronvolts), the calculated  $x_M$  values are similar to the corresponding Pauling electronegativities, as can be seen by comparing these values in Table 3.19.

Allred and Rochow<sup>41</sup> defined electronegativity as the electrostatic force exerted by the nucleus of an atom on the valence electrons. Using effective nuclear charges calculated by Slater's rules (see p. 17), they proposed the equation

$$x_{AR} = 0.359 \frac{Z - S}{r^2} + 0.744$$

(where r is the covalent radius in angstroms). This equation yields  $x_{AR}$  values that are remarkably similar to the corresponding Pauling values, as can be seen from Table 3.19.

Sanderson<sup>42</sup> reasoned that, because atomic size decreases and electronegativity increases on going from left to right in the periodic table, it should be possible to define electronegativity in terms of the average electron density of an atom,  $3Z/4\pi r^3$ , where r is the nonpolar covalent radius of the atom. He devised a procedure, too involved to describe here, for calculating electronegativities from these quantities, and it can be seen that the resulting values, given in Table 3.19, are again very similar to the corresponding Pauling values. The fact that comparable electronegativities can be calculated from a wide variety of atomic properties is simply due to the fact that, on going from one atom to another, the changes in various properties (ionization potential, effective nuclear charge, size, etc.) are all fundamentally due to the same thing, viz., the change in electronic structure.

It is now generally agreed, in view of the dependence of the electron-attracting power of an atom on the hybridization of the bonding orbital used by the atom, that electronegativity should be considered as an orbital property rather than an atomic property.<sup>43</sup> It is also recognized that the electronegativity of an orbital is a function of the charge of the orbital (i.e., a function of the orbital occupancy). If we define electronegativity as the tendency of an atomic orbital to attract electrons from another atomic orbital with which it has combined to form a bond, it is clear that in a molecule the electronegativities of each pair of bonding orbitals must be equal as a consequence of electron flow between the orbitals. As a fair approximation, the energy of an orbital is a quadratic function of the electron occupancy of the orbital. We may write

$$E - E_0 = aq + \frac{1}{2}bq^2$$

$$\frac{dE}{dq} = a + bq$$

<sup>&</sup>lt;sup>41</sup> A. L. Allred and E. G. Rochow, J. Inorg. Nucl. Chem., 5, 264 (1958).

<sup>&</sup>lt;sup>42</sup> R. T. Sanderson, "Inorganic Chemistry," pp. 72-75, Reinhold, New York, 1967.

<sup>&</sup>lt;sup>43</sup> J. Hinze and H. H. Jaffé, J. Am. Chem. Soc., 84, 540 (1962); J. Phys. Chem., 67, 1501 (1963); J. E. Huheey, "Inorganic Chemistry, Principles of Structure and Reactivity," 2d ed., pp. 167-173, Harper & Row, New York, 1978.

Here E is the energy of the system,  $E_0$  is the energy of the zero-charged reference state, q is the positive charge on the orbital, and a and b are positive empirical constants. The energy of a pair of combining orbitals is minimized for the following condition:

$$\frac{d(E_1 + E_2)}{dq_1} = 0 = \frac{dE_1}{dq_1} - \frac{dE_2}{dq_2} = (a_1 + b_1q_1) - (a_2 + b_2q_2)$$

Charge flows from one orbital to the other until the quantities  $dE_1/dq_1$  and  $dE_2/dq_2$  are equal. Thus it is logical to identify electronegativity with dE/dq or with a quantity linearly related to dE/dq. Values of the parameters a and b for some orbitals of first-row atoms are listed in Table 3.20. The charge flow in a bond can be calculated as follows:

$$a_1 + b_1 q_1 = a_2 + b_2 q_2 = a_2 - b_2 q_1$$

$$q_1 = \frac{a_2 - a_1}{b_1 + b_2}$$

$$a_1 + b_2 + b_2 + b_3 + b_4 + b_5$$

Thus for the molecule HF, if we assume  $sp^3$  hybridization for the fluorine, we calculate  $q_{\rm H} = (16.97 - 7.17)/(12.85 + 16.48) = +0.33$ . Somewhat more complicated calculations are required if one wishes to treat  $\pi$ -bonded systems and to account for the effects of formal charge and induction.<sup>44</sup>

44 W. L. Jolly and W. B. Perry, J. Am. Chem. Soc., 95, 5442 (1973); Inorg. Chem., 13, 2686 (1974).

Table 3.20 Some orbital electronegativity parameters†

Element	Orbital	a, eV/q	$b$ , $eV/q^2$	
H	S	7.17	12.85	
He	S	9.7	29.8	
Li	S	3.10	4.57	
Be	sp	4.78	7.59	
B	$sp^3$	5.99	8.90	
	$sp^2$	6.33	9.91	
C	sp <sup>3</sup>	7.98	13.27	
	$Sp^2$	8.79	13.67	
	sp	10.39	14.08	
N	sp <sup>3</sup>	11.54	14.78	
	Sp <sup>2</sup>	12.87	15.46	
0	p	9.65	15.27	
	$sp^3$	15.25		
F	p	12.18	18.28	
	$sp^3$	16.97	17.36 16.48	

<sup>†</sup> J. Hinze and H. H. Jaffé, J. Am. Chem. Soc., 84, 540 (1962); J. Phys. Chem., 67, 1501 (1963); J. E. Huheey, "Inorganic Chemistry, Principles of Structure and Reactivity," 2d ed., p. 162, Harper & Row, New York, 1978.

Electronegativities have many uses in chemistry. Of course the Pauling values can be used, together with Eq. 3.1, to estimate rough values of bond energies. Any set of electronegativities can be used to obtain a qualitative, if not a quantitative, measure of the relative charges on atoms in molecules. And because the charge distribution in a molecule affects the interactions of the molecule with other polar groups and ions, electronegativities give information regarding relative chemical reactivity. For example, the relative electronegativities of carbon and silicon indicate that the hydrogen atoms in silicon hydrides should be considerably more negatively charged than those in hydrocarbons:

Thus we can rationalize the fact that silicon hydrides react with sources of protons to give molecular hydrogen, whereas hydrocarbons do not. Many quantifiable chemical and physical properties are closely correlated with charge distribution, and one generally finds that a plot of such properties versus appropriate electronegativity values is a smooth curve or straight line. By interpolation or extrapolation in such plots, one can predict the properties of molecules for which there are no data. Examples of such plots are shown in Figs. 3.4, 3.6, and 3.7.




Figure 3.6 Plot of typical X—H stretching frequency (from infrared spectra) against the electronegativity of X. (Reproduced with permission from L. J. Bellamy, "The Infra-Red Spectra of Complex Molecules," 2d ed., p. 392, Wiley, New York, 1958.)




Figure 3.7 Plot of carbon 1s binding energy (relative to that of methane) for halomethanes against the sum of electronegativity differences over all the ligands. [Reproduced with permission from T. D. Thomas, J. Am. Chem. Soc., 92, 4184 (1970). Copyright 1970 American Chemical Society.]

## PREDICTION OF MOLECULAR TOPOLOGY

The empirical formula of a polyatomic molecule tells nothing about the structure of the molecule. For example, the formula  $S_2O$  could correspond to a three-membered ring,

or a chain with either an oxygen atom or a sulfur atom in the middle,

$$S \xrightarrow{O^+} S^- \longleftrightarrow -S \xrightarrow{O^+} S$$
 or  $S \xrightarrow{S^+} O^- \longleftrightarrow -S \xrightarrow{S^+} O$ 

The chain structures could be either linear or bent. From this and other examples we see that a description of molecular structure consists of two stages. The first topological description of the bonding. The second stage is the specification of predicting bonding topologies; methods for predicting structural parameters will

The following procedure may be used to predict the most stable of several possible bonding topologies for a molecule or ion. First, write valence structures for the various possible topologies. Then discard the less stable structures

according to the following rules, in the order given, until only one structure

1. Discard structures which do not satisfy the Lewis octet rule. Thus for CH<sub>3</sub>N discard the structure in which a central carbon atom is attached to each of the other four atoms in favor of the HN=CH, structure.

2. Discard structures with three-membered rings. Thus the ring structure for S<sub>2</sub>O is discarded in favor of the chain structures.

3. Discard structures that require adjacent atoms to have formal charges of the same sign. For example, for  $S_2N_2$  discard the  $-N=\dot{S}-\dot{S}=N^-$  structure in favor of the following ring structure:

- 4. Discard structures in which nearby atoms have unlike formal charges contradicting electronegativities, or in which an atom has an unlikely formal charge (according to electronegativities). Thus for  $N_2O$  discard the  $N=O=N^$ structure in favor of the N≡N+-O- structure.
- 5. Discard structures for which relatively few stable resonance forms can be written. For example, we predict nitramide, H<sub>2</sub>N-NO<sub>2</sub> (for which two equivalent stable resonance structures can be written), to be stable with respect to hyponitrous acid. HON=NOH (for which only one stable structure can be written). This example illustrates the utility of the procedure for estimating the relative stabilities of structural isomers.

6. The most stable structure of those remaining is generally that for which the sum of the electronegativity differences of adjacent atoms is the greatest. Discard all the other structures. Thus the structure H—O—Cl is predicted to

be more stable than the structure H-Cl-O-.

## VALENCE-SHELL ELECTRON REPULSION

The concept of valence-shell electron repulsion is the basis for a simple, yet remarkably accurate, scheme for predicting the structures of nontransition element molecules. The essentials of this valuable concept were outlined by Sidgwick and Powell in 194045; the method has been refined and popularized by Gillespie and Nyholm.46 Although some of the assumptions and rules of the method may not be theoretically justifiable, the method nevertheless has practical value for predicting and rationalizing structures.

45 N. V. Sidgwick and H. M. Powell, Proc. Roy. Soc. A, 176, 153 (1940).

<sup>&</sup>lt;sup>46</sup> R. J. Gillespie and R. S. Nyholm, *Q. Rev.*, 11, 339 (1957); R. J. Gillespie, *J. Chem. Educ.*, 47, 18 (1970); "Molecular Geometry," Van Nostrand Reinhold, Princeton, N.J., 1972. The discussion of the concept in the following pages includes some ideas quite different from those of previous authors.

The spatial arrangement of the bonds to an atom is strongly correlated with a quantity which we shall call the "total coordination number" of the atom. We define the total coordination number as the sum of the number of ligands and valence lone pairs. Thus the oxygen atom of H2O has a total coordination number of 4 (two ligands and two lone pairs), and the boron atom of BF3 has a total coordination number of 3 (three ligands and no lone pairs). The ligands and lone pairs of an atom are generally located at or near the vertices of a regular polyhedron which has as many vertices as the total coordination number of the atom. Such an arrangement is energetically favorable because it keeps all the valence-shell electron pairs as far apart as possible and minimizes the electronelectron repulsions. When more than one arrangement of ligands and lone pairs is possible at the vertices of a polyhedron, the observed stable geometry is generally consistent with the following empirical rules: (1) Electron repulsions decrease in the order lone-pair lone-pair repulsion > lone-pair bond-pair repulsion > bond-pair - bond-pair repulsion, and (2) repulsions between electrons at vertices which subtend an angle at the central atom greater than about 115° can be neglected. A summary of the stereochemistries of a wide variety of molecules which can be rationalized by valence-shell electron repulsion is presented in Table 3.21. We shall discuss some specific examples in the following paragraphs.

## **Total Coordination Number 2**

When only two ligands are coordinated to a central atom, with no nonbonding electrons on the central atom, the repulsions between the two ligands and between

Table 3.21 Predictions of the valence-shell electron repulsion theory of directed valency

Total coordination no.	Arrangement of lone pairs and ligands	No. of ligands	No. of lone pairs		be more stable than
110.	and figatius	nganus	pairs	Shape of molecule	Examples
2	Linear	2	0	Linear	BeCl <sub>2</sub> , HgCl <sub>2</sub> , ZnI <sub>2</sub> , CO <sub>2</sub>
3	Equilateral	3	0	Planar triangular	BCl <sub>3</sub> , NO <sub>3</sub> -
	Triangular	2	1	V-shaped	O <sub>3</sub> , NO <sub>2</sub> <sup>-</sup> , SnCl <sub>2</sub>
4	Tetrahedral	4	0	Tetrahedral	CH <sub>4</sub> , Al <sub>2</sub> Cl <sub>6</sub> , ClO <sub>4</sub>
		3	1	Pyramidal	NF <sub>3</sub> , H <sub>3</sub> O <sup>+</sup> , (TIOR) <sub>4</sub> , ClO <sub>3</sub>
		2	2	V-shaped	H <sub>2</sub> O, SCl <sub>2</sub> , ClO <sub>2</sub> <sup>-</sup>
5	Trigonal				AMERICA SHE SHAP THE
	bipyramidal	5	0	Trigonal bipyramidal	PCl <sub>5</sub> , PF <sub>3</sub> (CH <sub>3</sub> ) <sub>2</sub>
		4	1	Irregular tetrahedral	SF <sub>4</sub> , R <sub>2</sub> TeCl <sub>2</sub>
		3	2	T-shaped	ClF <sub>3</sub> , C <sub>6</sub> H <sub>4</sub> ICl <sub>2</sub>
		2	3	Linear	ICl <sub>2</sub> -, XeF <sub>2</sub>
6	Octahedral	6	0	Octahedral	SF <sub>6</sub> , PCl <sub>6</sub> <sup>-</sup> , S <sub>2</sub> F <sub>10</sub>
		5	1	Square pyramidal	BrF <sub>5</sub> , XeOF <sub>4</sub>
In multanasis		4	2	Square planar	ICl <sub>4</sub> -, XeF <sub>4</sub>

the bonding electrons are minimized when the ligands form a 180° bond angle with the central atom. Therefore a linear structure is generally observed in such cases. It is convenient to think of an s orbital and a p orbital in terms of their linear combinations, i.e., as two hybrid orbitals<sup>47</sup> directed 180° from each other. If we wish the hybrid orbitals to be equivalent, they are formed as the sum and difference of the atomic orbitals, as shown schematically in Fig. 3.8. In linear molecules such as CO2 and the high-temperature gaseous molecules BeCl2 and HgCl2, we may think of the central atoms as using such hybrid sp orbitals in the formation of the  $\sigma$  bonds between the central atoms and the ligands.

When the central atom is large and the ligand atoms are small, as in the high-temperature gaseous molecule BaF2, the molecule is V-shaped. This result may be rationalized by considering the molecule as a combination of a polarizable central cation and two anions. The two anions are not bound at an angle of 180°, because then the induced dipole moments in the central cation would cancel and there would be no extra bonding energy attributable to interaction of the negative anions with a polarized cation. However, if the angle between the anions is less than 180°, the central cation undergoes a net polarization and the system is stabilized by the interaction between the resultant induced dipole and the anions. As the bond angle decreases, the polarization stabilization increases and the anion-anion electrostatic repulsion increases. The observed bond angle corresponds to a balance of these effects.

<sup>47</sup> Hybridization is discussed in Chap. 4.




Figure 3.8 Formation of sp hybrid orbitals by combination of an s and a p orbital. Notice that, for simplicity, a 1s orbital is combined with a 2n orbital.

#### Total Coordination Number 3

When three ligands are coordinated to a central atom, with no nonbonding electrons on the central atom, repulsions are minimized when the ligands are disposed at the corners of an equilateral triangle, with 120° bond angles. In such cases it is often convenient to consider the  $\sigma$  bonds as being formed by the overlap of  $sp^2$  hybrid orbitals on the central atom with appropriate orbitals of the ligands.

If one of the ligands is replaced by a lone pair, the lone pair occupies the site of the replaced ligand, and the resulting molecule is V-shaped. Because of the relative stability of s orbitals compared with p orbitals, a lone pair is more stable the greater the s character of its orbital. This effect is somewhat counterbalanced by the fact that bond strength increases with increasing s character of the atomic orbitals involved (at least up to a hybridization of sp). Nevertheless, replacement of a ligand by a lone pair almost always causes rehybridization such as to shift more s character to the lone-pair orbital. Thus, in the case of species such as  $O_3$  and  $NO_2^-$ , the  $\sigma$  bonds are formed using orbitals from the central atoms which have more p character than corresponds to  $sp^2$  hybridization. Therefore the bond angles are less than  $120^\circ$ . For  $O_3$  and  $NO_2^-$ , the bond angles are 117 and  $115^\circ$ , respectively.

The singlet carbenes,  $CX_2$ , represent an interesting class of compound in which the carbon atom can have a total coordination number of either 2 or 3. The singlet carbenes in which X = F, OH, OMe,  $NH_2$ ,  $BH_2$ , BEH, Li, and H are believed to have the geometries given in Table 3.22. Schoeller has rationalized these data by claiming that singlet carbenes are linear when X is less electronegative (Li to B) than carbon and are bent when X is more electronegative (N to F) than carbon, and he and Pauling have offered simple explanations of the structures based on orbitals. However, the data may be equally well rationalized using valence-shell electron repulsion theory. In the case of X = F, OH, OMe, or

Table 3.22 Geometries of the singlet carbenes, :CX<sub>2</sub>†

25.0		got carbenes, .CA2		
)	$r_{C-X}$ , Å	∠XCX, degrees		
	1.323 1.354 1.358 1.356 1.127 1.419 1.612 1.842	102.8 101.9 101.0 109.2 100.2 180.0 180.0		

<sup>†</sup> W. W. Schoeller, *J. Chem. Soc. Chem. Commun.*, 124 (1980). The geometries are not experimental, but are based on high-quality *ab initio* quantum-mechanical calculations.

 <sup>&</sup>lt;sup>48</sup> W. W. Schoeller, J. Chem. Soc. Chem. Commun., 124 (1980).
 <sup>49</sup> L. Pauling, ibid., 688 (1980).

NH<sub>2</sub>, Lewis octet structures can be written for the singlet carbenes; thus,

Clearly in these compounds the carbon atom has a total coordination number of 3, and the molecules should be bent. In the case of  $X = BH_2$ , BeH, or Li, Lewis octet structures cannot be written, but the lone pair on the carbon atom would be expected to engage in bonding to the electron-deficient atoms; thus,

In these compounds the carbon atom has a total coordination number of 2, and the molecules should be linear. In the case of : CH<sub>2</sub>, the hydrogen atoms have no lone-pair electrons which can be used to double-bond to the carbon atom, and they have no empty valence orbitals which can share the lone pair of the carbon atom. Hence the carbon atom has a total coordination number of 3, and the molecule is bent: Holecule is bent:

H 101 funded was sometiment of the statement of the sta

# **Total Coordination Number 4**

In the case of an atom with four identical ligands, repulsions are minimized for a regular tetrahedral geometry with sp<sup>3</sup> hybridization and bond angles of 109.47°. Replacement of ligands by lone pairs causes a shift of s character to the lone pairs and a decrease in the bond angles. It is interesting to compare the bond angles of NH<sub>3</sub> and H<sub>2</sub>O with those for the corresponding hydrides of the second-, third-, and fourth-row elements; the data are given in Table 3.23. The bond angles for the first-row hydrides are slightly less than the tetrahedral value; the bond angles for the hydrides of the heavier elements are remarkably close to 90°, which corresponds to the use of pure p orbitals by the central atom. These results can be rationalized as follows: In the heavier hydrides, the central atoms are so big that there is very little repulsion between valence electrons. Thus bonding is accomplished using the p orbitals of the central atoms, without the need of the promotional energy required by hybridization. In the first-row hydrides, 90° bond angles would cause excessive crowding of the bonding electron pairs. Hybridization, with the introduction of s character into the bonding orbitals almost to the extent of  $sp^3$  hybridization, permits the lone pairs and bonding pairs to separate, with reduction of the repulsion.

Table 3.23 Bond angles of some hydrides

NH,			1000000
PH <sub>3</sub>	106.8°	H,O	104.5°
AsH <sub>3</sub>	93.3°	H <sub>2</sub> S	92.2°
SbH <sub>3</sub>	91.5°	H-Se	91.0°
30000	91.3°	H <sub>2</sub> Te	89.5°

The bond angle of  $OF_2$  is  $102^\circ$ , significantly less than that of  $H_2O$ . Presumably the bond angle is reduced because the highly electronegative fluorine atoms withdraw much more of the bonding electron density than the hydrogen atoms do. Such electron withdrawal is energetically favored by increasing the p character of the oxygen orbitals used in the bonding. On the other hand, the bond angle of  $OCl_2$  is  $\sim 111^\circ$ , appreciably greater than that of  $H_2O$ . Apparently the chlorine atoms are so big that repulsion between nonbonding electrons on separate chlorine atoms overwhelms the electronegativity effect.

The lone-pair electrons of a molecule such as water are often illustrated as separate lobes or "rabbit ears," as shown in the following structure:



Although such structures are helpful for illustrating the stereochemical influence of lone pairs, they are very misleading representations of valence-electron den-




Figure 3.9 Electron density plot for H<sub>2</sub>O in the plane of the lone pairs. (Reproduced with permission from A. Streitwieser, Jr., and P. H. Owens, "Orbital and Electron Density Diagrams," Macmillan, New York, 1973.)

sity. The electron density plot for H<sub>2</sub>O, given in Fig. 3.9, shows that the lone pairs overlap and that the separate lobes are fictitious. 50 110 T the gaptre bood and do and formal charges of -0.3 for the axial livend accors and

## **Total Coordination Number 5**

When an atom with no lone pairs is bonded to five ligands, the ligands are almost always located at the vertices of a trigonal bipyramid. Such a structure is obtained in the case of PF<sub>5</sub>, which is illustrated in Fig. 3.10. There are two stereochemically distinct types of ligands in a trigonal bipyramidal MX, molecule; two axial ligands and three equatorial ligands. For convenience, let us define the threefold axis of the molecule as the z axis of the central atom. Then the central atom's  $p_z$  orbital lies along the threefold axis and the  $p_x$  and  $p_y$  orbitals lie in the equatorial plane. Because the axial bonds must share the  $p_z$  orbital, each axial bond has available one-half of a p orbital, and because the equatorial bonds must share the  $p_x$  and  $p_y$  orbitals, each of these bonds has available two-thirds of a p orbital. The spherically symmetric s orbital could, in principle, be distributed in any proportion between the axial and equatorial bonding orbitals, although the two axial orbitals must have the same s character, and the three equatorial orbitals must have the same s character. At one extreme, there could be a full sp hybrid orbital for each axial bond and a 2 p orbital for each equatorial bond. At the other extreme, there could be a  $\frac{1}{2}$  p orbital for each axial bond and a full  $sp^2$  hybrid orbital for each equatorial bond. We shall assume, as a reasonable working

50 Streitwieser and Owens, op. cit.

Figure 3.10 Structures of PF<sub>5</sub>, PF<sub>4</sub>CH<sub>3</sub>, PF3(CH3)2, SF4, and CIF3. [Reproduced with permission from R. J. Gillespie, J. Chem. Educ., 47, 18 (1970).]

hypothesis, that the s orbital is equally distributed among all five bonds. Thus we obtain bond orders of 0.7 for the axial bonds and 0.867 for the equatorial bonds, and formal charges of -0.3 for the axial ligand atoms and -0.133 for the equatorial ligand atoms. Because the equatorial bond order is greater than the axial bond order, the equatorial bond lengths are shorter than the axial bond lengths. (For PF<sub>5</sub>,  $r_{ax} = 1.58$  Å and  $r_{eq} = 1.53$  Å; for PCl<sub>5</sub>,  $r_{ax} = 2.19$  Å and  $r_{eq} = 2.04$  Å.) Because, on the basis of our structural hypothesis, the formal charge on the axial ligand atoms is more negative than that on the equatorial ligand atoms, we would expect that, when more than one type of ligand is bonded to the same central atom, the more electronegative ligands would preferentially occupy the axial positions. This effect is clearly seen in the structures of PF<sub>4</sub>CH<sub>3</sub> and PF<sub>3</sub>(CH<sub>3</sub>)<sub>2</sub>, illustrated in Fig. 3.10. Because CH<sub>3</sub> groups are more electropositive than the F atoms, the CH<sub>3</sub> groups occupy equatorial positions.

The trigonal bipyramidal configuration for molecules with five ligands and no lone pairs on the central atom is not exceedingly stable with respect to other configurations. Distortions of the bond angles readily occur, and it is believed that many pentacoordinate molecules undergo rapid interconversion between a trigonal bipyramidal configuration and a square pyramidal configuration, even though the former configuration may be the stable, equilibrium configuration. For example, the 19F nmr spectrum of PF<sub>5</sub> shows a signal apparently due to only one kind of fluorine atom, even though one would expect separate signals due to the axial and equatorial fluorine atoms. Apparently the axial and equatorial atoms are scrambled at a rate greater than the difference in their nmr frequencies, and therefore the nmr signal corresponds to a weighted average signal of the axial and equatorial atoms. The mechanism shown in Fig. 3.11 has been postulated to explain the scrambling.<sup>51</sup> It will be noted that the molecule passes through an intermediate square pyramidal configuration in the scrambling process. It should also be noted that one fluorine atom (marked with an asterisk in Fig. 3.11) is essentially unmoved from its equatorial position during the illustrated process. In effect, the molecule undergoes a rotation about the P-F\* axis.

The <sup>19</sup>F nmr spectrum of CH<sub>3</sub>PF<sub>4</sub> shows only one kind of fluorine on the nmr to explain the interchange of fluorine atoms.

S. Berry, J. Chem. Phys., 32, 933 (1960); R. J. Gillespie, Angew. Chem. Int. Ed., 6, 819 (1967).
 E. L. Muetterties, W. Mahler, and R. Schmutzler, Inorg. Chem., 2, 613 (1963).




Figure 3.11 The mechanism postulated to account for fluorine scrambling in PF<sub>5</sub>. (a) Original positions of F atoms, o; final positions of F atoms, • (b) Pseudo-rotated trigonal bipyramid. [Reproduced with permission from R. J. Gillespie, Angew. Chem. Int. Ed.. 6, 819 (1967).]

$$CH_3$$
 $F$ 
 $F$ 
 $F$ 
 $F$ 
 $F$ 
 $F$ 
 $F$ 
 $F$ 

However, although the proton nmr spectrum of (CH<sub>3</sub>)<sub>2</sub>PF<sub>3</sub> shows only one kind of methyl group, the <sup>19</sup>F nmr spectrum shows two different kinds of fluorine atoms, in the ratio 2:1. The absence of scrambling in (CH<sub>3</sub>)<sub>2</sub>PF<sub>3</sub> can be explained by the pseudorotation mechanism and the tendency for relatively electropositive substituents to remain at equatorial positions.<sup>53</sup> Pseudorotation of (CH<sub>3</sub>)<sub>2</sub>PF<sub>3</sub> would force one of the methyl groups into an apical position.

Apparently the configuration with an apical methyl group is of such high energy that the pseudorotation does not occur and both methyl groups remain at equatorial positions.

Another kinetic manifestation of the tendency for relatively electropositive groups to occupy equatorial positions is found in the hydrolysis of five-membered cyclic esters of phosphoric acid.54 These hydrolyze rapidly, both with ring opening and with retention of the ring, as shown by the example of methyl ethylene phosphate:

The hydrolysis of the methyl ester of propylphostonic acid also occurs rapidly, but almost exclusively with ring opening:

<sup>&</sup>lt;sup>53</sup> F. H. Westheimer, Acc. Chem. Res., 1, 70 (1968). 54 Westheimer, loc. cit.

These results are explained by assuming the formation of a 5-coordinate intermediate which can undergo pseudorotation. The five-membered rings are assumed to span one equatorial and one apical position. It is also assumed that the incoming group is initially attached to an apical position and that the leaving group comes from an apical position. Thus the formation of two products in the hydrolysis of methyl ethylene phosphate is rationalized by the following mechanism:

$$\begin{array}{c} H & CH_2 \\ O & CH_2 \\ O & O \\ OCH_3 \\ OH_2 \\ \end{array} \begin{array}{c} CH_2 \\ O & CH_2 \\ O & OH_2 \\ \end{array}$$

$$\begin{array}{c} O \\ H \\ O \\ CH_3 \\ \end{array} \begin{array}{c} O \\ O \\ CH_3 \\ \end{array}$$

$$\begin{array}{c} O \\ O \\ CH_3 \\ \end{array}$$

$$\begin{array}{c} O \\ O \\ O \\ O \\ \end{array}$$

$$\begin{array}{c} O \\ O \\ O \\ O \\ \end{array}$$

$$\begin{array}{c} O \\ \end{array}$$

$$\begin{array}{$$

In the case of the phostonate, pseudorotation would give an unstable intermediate, and so essentially only one product is observed:

The rate of hydrolysis of cyclic phosphinates such as

is low because there is no way to form a trigonal bipyramidal intermediate of low energy; either the ring angle must be expanded to 120° or an alkyl group must occupy an apical position.

$$\begin{array}{c|cccc} OR & CH_2 \\ \hline OR & CH_2 & CH_2 \\ \hline CH_2 - CH_2 & OR \\ \hline CH_2 - CH_2 & OR \\ \hline OH_2 & OH_2 \\ \end{array}$$

A few molecules, including pentaphenylantimony<sup>55</sup> and the phosphorus compound56 pictured below,

$$F_{3}C \xrightarrow{CF_{3}} CH_{3} CH_{3}$$

$$C-O \xrightarrow{P} CH_{2}$$

$$F_{3}C \xrightarrow{CF_{3}} CH_{3} CH_{3}$$

are so distorted in the solid state that their configurations are closer to square pyramidal than to trigonal bipyramidal. These distortions are not understood. They may be a consequence of solid-state crystal packing forces; perhaps the free molecules would have trigonal bipyramidal configurations.

When one, two, or three of the ligands in a trigonal bipyramidal molecule are replaced by lone pairs, the lone pairs always occupy equatorial positions, presumably to minimize lone-pair-bonding-pair repulsions. Thus molecules of this type always have two ligands in the axial positions. The structures of SF<sub>4</sub> and CIF<sub>3</sub> are shown in Fig. 3.10. The deviations of the bond angles from those of a perfect trigonal bipyramid are significant. In both structures the fluorine atoms are "bent away" from the lone-pair electrons, in accord with the rule that lone-pair bonding-pair repulsion is greater than bonding-pair bonding-pair

<sup>&</sup>lt;sup>55</sup> A. L. Beauchamp, M. J. Bennett, and F. A. Cotton, *J. Am. Chem. Soc.*, **90**, 6675 (1968). <sup>56</sup> J. A. Howard, D. R. Russell, and S. Trippett, J. Chem. Soc. Chem. Commun., 856 (1973).

repulsion. Thus in  $SF_4$ , the angle subtended by the lone pair and an apical fluorine is considerably greater than 90° (93.5°), and the angle subtended by the lone pair and an equatorial fluorine is considerably greater than 120° (129.3°). Similarly, in  $CIF_3$ , the F—CI—F bond angle is less than 90° (87.5°).

#### **Total Coordination Number 6**

In a 6-coordinate molecule such as SF<sub>6</sub> the ligand atoms are situated at the vertices of a regular octahedron. If we arbitrarily place the ligand atoms on the x, y, and zaxes of the central atom, it is easy to see that each bonding orbital of the central atom consists of a combination of  $\frac{1}{2}$  p orbital and  $\frac{1}{6}$  s orbital. Neglecting any contributions of the valence-shell d orbitals, each bond has a bond order of  $\frac{2}{3}$ . If we replace one of the ligands with a lone pair, the resulting molecule has a square pyramidal configuration, with the axial ligand trans to the lone pair. As an illustration of this type of bonding, the structure of BrF, is shown in Fig. 3.12. Because of the relatively high lone-pair-bonding-pair repulsions, the bromine atom lies below the basal plane of the four equivalent fluorine atoms, and the bond angles are less than 90°. In order to replace a ligand of a 6-coordinate molecule by a lone pair, it is necessary to extract electron density from the other bonds. (The average bond order drops from  $\frac{2}{3}$  to  $\frac{3}{5}$ .) Because of the repulsion of the lone pair by the bonding electrons of the four basal bonds, it is to be expected that more electron density will be extracted from these basal bonds than from the axial bond. Hence the axial bond order is greater than the basal bond order, in qualitative agreement with the corresponding bond distances (1.68 and 1.79 Å, respectively, in BrF<sub>5</sub>). If we replace two of the ligands in a 6-coordinate molecule with lone pairs, it is reasonable to place these in trans positions to minimize the strong lone-pair -lone-pair repulsion. Thus we expect the ligands to occupy a square planar configuration. Indeed such a configuration is found for all tetracoordinate species with two lone pairs on the central atom (for example, BrF4-, shown in Fig. 3.12, and XeF<sub>4</sub>). In such species the bond order is ½, with one-half of a p orbital from the central atom involved in each bond.

The molecule SF<sub>4</sub>CH<sub>2</sub> has a trigonal bipyramidal arrangement of ligands around the sulfur atom, with the methylene group occupying an equatorial position.<sup>57</sup> These structural features are readily predicted using the rules we have

57 G. Kleemann and K. Seppelt, Angew. Chem. Int. Ed., 17, 516 (1978).

Figure 3.12 Structures of BrF<sub>5</sub> and BrF<sub>4</sub>-.

previously discussed for five-coordination. However, the fact that the hydrogen atoms of the CH2 group lie in a plane containing the axial fluorines, rather than in the equatorial plane, requires further explanation. In this case it is helpful to consider the carbon atom as 4-coordinate (tetrahedral) and the sulfur atom as 6-coordinate (octahedral). The observed structure corresponds to linking the octahedron with the tetrahedron, as follows:

Obviously the S—C bond should be considered a double bond.

#### Total Coordination Number 7

When the total coordination number exceeds 6, there are usually various symmetric, polyhedral configurations which have very similar energies, and one often finds examples of each of these configurations in actual compounds. It does not seem to be possible to predict structures with certainty in such cases, particularly if the ligands are not equivalent or if they are chelated. For example, let us consider total coordination number 7. Three plausible configurations are shown in Fig. 3.13. The first structure is a monocapped octahedron, the second is a monocapped trigonal prism, and the third is a pentagonal bipyramid. The first structure has been observed in the case of NbOF<sub>6</sub><sup>3-</sup> and ZrF<sub>7</sub><sup>3-</sup>, the second structure in the case of NbF<sub>2</sub><sup>2</sup> and TaF<sub>2</sub><sup>2</sup>, and the third structure in the case of UO<sub>2</sub>F<sub>5</sub><sup>3-</sup> and IF<sub>7</sub>. If one of the ligands is replaced with a lone pair, one might expect to obtain the structure in which the lone pair has the minimum number of nearest neighbors, i.e., the first structure, with the lone pair in the unique axial position. This configuration has been postulated58 for XeF<sub>6</sub>, but the exact structure of this molecule is not yet known. On the other hand, the structure of the trisoxalatoantimonate(III) ion,  $Sb(C_2O_4)_3^{3-}$ , has been shown to be based on a pentagonal bipyramid with the lone pair presumably occupying an axial posi-

58 R. J. Gillespie, Angew. Chem. Int. Ed., 6, 819 (1967); R. J. Gillespie, J. Chem. Educ., 47, 18




Figure 3.13 Three ways of achieving sevenfold coordination. [Reproduced with permission from R. J. Gillespie, Angew. Chem. Int. E., 6, 819 (1967).]




Figure 3.14 Perspective view of the  $Sb(C_2O_4)_3^{2-}$  ion. [Reproduced with permission from M. C. Poore and D. R. Russell, Chem. Commun., 18 (1971).]

tion.<sup>59</sup> The structure of this ion is shown in Fig. 3.14. Two oxalate ions lie in the equatorial plane, and one bridges an equatorial site and an axial site.

When the ligands are large, repulsions between ligands can be of primary importance in determining stereochemistry. For example, TeCl<sub>6</sub><sup>2-</sup>, TeBr<sub>6</sub><sup>2-</sup>, and SbBr<sub>6</sub><sup>3-</sup> have regular octahedral structures even though the central atoms have nonbonding electrons. Apparently the lone pair is forced inside the shell of ligands into a spherical *s* orbital.

Higher coordination numbers are known, but for none of these is the geometry known to be affected by the presence of lone pairs on the central atom. Therefore we shall defer consideration of such structures until we discuss transition-metal complexes.

#### A Caveat

There is no question that the valence-shell electron repulsion theory works; it fairly reliably predicts the structures of a wide variety of molecules, and it has been shown to be consistent with some theoretical studies. However, recent work has shown that some of the fundamental postulates of the theory are incorrect. In particular, the rule that repulsions decrease in the order lone pair—lone pair lone pair—bond-pair bond-pair is wrong; the repulsions between bond pairs are in fact the most important. Hall's papers should be consulted for a discussion of the relation between bond angles, bond-pair—bond-pair repulsions, and the *p-s* energy level separation of the central atom. Undoubtedly, further theoretical studies will have to be carried out before we have a simple, yet theoretically sound, scheme for predicting the structures of nontransition-metal molecules.

<sup>&</sup>lt;sup>59</sup> M. C. Poore and D. R. Russell, *Chem. Commun.*, 18 (1971).

<sup>&</sup>lt;sup>60</sup> G. W. Schnuelle and R. G. Parr, *J. Am. Chem. Soc.*, **94**, 8974 (1972); C. A. Naleway and M. E. Schwartz, *J. Am. Chem. Soc.*, **95**, 8235 (1973).

<sup>61</sup> W. E. Palke and B. Kirtman, J. Am. Chem. Soc., 100, 5717 (1978).

<sup>&</sup>lt;sup>62</sup> M. B. Hall, *J. Am. Chem. Soc.*, **100**, 6333 (1978); *Inorg. Chem.*, **17**, 2261 (1978); also see J. K. Burdett, "Molecular Shapes," chaps. 3–7, Wiley, New York, 1980.

# CONFORMATIONAL ISOMERISM BASED ON BOND and add to ROTATIONS The cyclogeness of the structures showed the cyclogeness of the cy

Many molecules have groups of atoms joined by a bond such that rotation of the groups with respect to one another around the bond axis causes a continuous change in the energy of the molecule. Rotation about a double bond causes the molecule to pass through conformations of such high energy that rotation is strongly resisted. However, in the case of a single bond, the rotational barriers are low (usually less than 4 kcal mol-1), and rotation is relatively unrestricted at ordinary temperatures. Nevertheless the stable conformation for a single bond is of considerable interest both because of its relation to the diplole moment of the molecule and because of the theoretical problems posed. A conformation is generally described in terms of the dihedral angle between two atoms or lone pairs on the adjacent atoms, i.e., the angles projected by the atoms or lone pairs on a plane perpendicular to the bond axis. Conformational data for several molecules are given in Table 3.24. Such data are difficult to rationalize. Probably one must consider nucleus-electron attractions, nucleus-nucleus repulsions, and electronelectron repulsions; and no simple theory seems to be adequate. For a discussion a ne molecule S.M.F. contains a mehly puekered erzy membered megal

Table 3.24 Stable conformations of several molecules†

Compound	Projected conformation	Dihedral angle $(\phi)$ , degrees		
N <sub>2</sub> H <sub>4</sub>	cr, a simpler,	double 5—N bo 62-06 lowers double 5—N bo 62-06 lowers examination of 001-06 of its		
H <sub>2</sub> O <sub>2</sub>	Constallation H	* S. Wolfe de . Chem. Par. 5., 10  * B. Meyer, Chem. Sev. 5a, 107 (  * C. G. Davies, R. J. Gillespie, J  * G. A. Wiegers and MT os. Acta  * G. A. Wiegers and MT os. Acta  * G. A. Wiegers and MT os. Acta		
H <sub>2</sub> S <sub>2</sub> O <sub>2</sub> F <sub>2</sub> S <sub>2</sub> F <sub>2</sub>		91 88 88		
FCH <sub>2</sub> OH	FHH	60		

<sup>†</sup> S. Wolfe, Acc. Chem. Res., 5, 102 (1972).

of the theoretical aspects of bond conformations, the reader is referred to a paper by Wolfe.<sup>63</sup>

It is interesting to compare the structures, shown in Fig. 3.15, of the cyclooctasulfur molecule, S<sub>8</sub>, its two-electron oxidation product, S<sub>8</sub><sup>2+</sup>, and an isoelectronic analog of its four-electron oxidation product, S<sub>4</sub>N<sub>4</sub>. The eight-membered Se ring is puckered; the sulfur atoms lie in two parallel planes, giving the ring a crown shape, with an S-S distance of 2.05 Å and an S-S-S angle of 108°.64 The ion S<sub>8</sub><sup>2+</sup> consists of an eight-membered ring in which one of the sulfur atoms has flipped up into an exo position and in which a trans-annular bond has formed.65 The S—S bonds around the S<sub>8</sub>2+ ring have an average length of 2.04 Å, essentially the same as in S<sub>8</sub>. However, the trans-annular bond has a length of 2.86 Å, corresponding to a rather weak bond. The reason for the endo-exo conformation is not clear, but the conformation presumably minimizes nonbonding electron repulsions between the atoms adjacent to the trans-annularly bonded atoms. The S<sub>8</sub><sup>4+</sup> cation is unknown; it appears to be unstable with respect to S<sub>4</sub><sup>2+</sup>. However, the isoelectronic S<sub>4</sub>N<sub>4</sub> is well known; it has a structure in which a second sulfur atom has flipped up and a second trans-annular S-S bond has formed. The four coplanar atoms are nitrogen atoms.

The molecule  $S_4N_4F_4$  contains a highly puckered eight-membered ring of alternating sulfur and nitrogen atoms, as shown in Fig. 3.16.66 The remarkable feature of this structure is that there are two S-N bond distances (1.66 and 1.54 Å), which occur alternately in the ring. In Fig. 3.16, the  $S_1-N_1$  distance is 1.66 Å, the  $N_1-S_2$  distance is 1.54 Å, and so on around the ring. These alternating bond lengths are often interpreted in terms of localized single and double S-N bonds. However, a simpler, a priori, explanation is available. By examination of Fig. 3.16, it is seen that the  $S_1-N_1$  and  $N_1-S_2$  bonds have quite

<sup>66</sup> G. A. Wiegers and A. Vos, Acta Crystallogr., 14, 562 (1961); 16, 152 (1963).
 <sup>67</sup> W. L. Jolly, Adv. Chem. Ser., 110, 92 (1972)




Figure 3.15 Relationships between the structures of S<sub>8</sub>, S<sub>8</sub><sup>2+</sup>, and S<sub>4</sub>N<sub>4</sub>. [Reproduced with permission from R. J. Gillespie, Chem. Soc. Rev., 8, 315 (1979).]

<sup>63</sup> S. Wolfe, Acc. Chem. Res., 5, 102 (1972).

<sup>64</sup> B. Meyer, Chem. Rev., 76, 367 (1976).

<sup>65</sup> C. G. Davies, R. J. Gillespie, J. J. Park, and J. Passmore, *Inorg. Chem.*, 10, 2781 (1971).




Figure 3.16 The structure of the S<sub>4</sub>N<sub>4</sub>F<sub>4</sub> molecule. [Reproduced with permission from G. A. Wiegers and A. Vos, Acta Crystallogr. 14, 562 (1961), 16, 152 (1963).]

different stereochemical environments. The S<sub>1</sub>-N<sub>1</sub> bond is longer, probably because of repulsive interaction of the nonbonding electrons of fluorine atom F<sub>1</sub> with the nonbonding electrons of nitrogen atom N<sub>1</sub>. The N<sub>1</sub>—S<sub>2</sub> bond is shorter, probably because there is much less interaction between the nonbonding electrons of atoms F<sub>2</sub> and N<sub>1</sub>. If atoms F<sub>1</sub> and F<sub>3</sub> were flipped to the upper side of the ring, there would be no resultant net advantage in terms of nonbonding electron interactions. In such a conformation, the S-N bonds would be expected to occur in the sequence s, s, l, l, s, s, l, l (s = short, l = long).

#### PROBLEMS

- 3.1 Write Lewis octet structures for the following species. (Show all nonbonding valence electrons and indicate formal charges.) (a)  $Al_2Cl_6$ , (b)  $SnCl_3^-$ , (c)  $XeF_2$ , (d)  $BrF_4^-$ , (e)  $NS^+$ , (f)  $SO_3F^-$ , (g)
- HOCIO, (h) S<sub>4</sub>N<sub>3</sub>+ (S-S-N-S-N-S-N).
- 3.2 The S—O bond distance in  $SO_2F_2$  is 1.37 Å, whereas that in  $SO_2$  is 1.43 Å. Explain in terms of
- 3.3 How can you account for CH<sub>5</sub><sup>+</sup> in terms of an octet structure?
- 3.4 For each of the following, name three well-known isoelectronic species containing the same number of atoms: (a) O<sub>3</sub>, (b) OH<sup>-</sup>, (c) BH<sub>4</sub><sup>-</sup>, (d) NO<sub>3</sub><sup>-</sup>.
- 3.5 How might you estimate or predict, by analogy with known compounds, (a) the ultraviolet spectrum of  $CO_2^-$ , (b) the bond distance in BF, (c) the dissociation energy of  $F_2$ , (d) the symmetric stretching  $G_2^-$ , (e) the bond distance in BF, (c) the dissociation energy of  $G_2^-$ , (d) the symmetric stretching  $G_2^-$ , (e) the bond distance in BF, (e) the dissociation energy of  $G_2^-$ , (e) the symmetric stretching  $G_2^-$ , (e) the bond distance in BF, (e) the dissociation energy of  $G_2^-$ , (e) the symmetric stretching  $G_2^-$ , (f) the symmetric stretching  $G_2^-$ , (g) the symmetric stretching  $G_2^-$ , ( stretching frequency of BF<sub>2</sub><sup>+</sup>, (e) the bond angles in NH<sub>3</sub><sup>+</sup>, (f) the structure of solid AlPO<sub>4</sub>, (g) the infrared infrared spectrum of  $ClO_2^+$ , and (h) the bond distances and angles in  $B_2F_4$ ?
- 3.6 What are the values of n and m in the anionic species  $Fe(CO)_n^{-m}$ ? Hint: Consider Ni(CO)<sub>4</sub>.
- \*3.7 The Mössbauer tin isomer shifts, relative to IS = 0.00 for grey tin metal, are positive for tin(II) salts such salts such as SnCl<sub>2</sub>, and negative for tin(IV) compounds such as SnCl<sub>4</sub>. Explain.
- \*3.8 The Mn  $2p_{3/2}$  binding energy of MnF<sub>2</sub> is greater than that of MnO<sub>2</sub>, even though the manganese 0xidation. oxidation states in these compounds are +2 and +4, respectively. Explain.
- \*3.9 Using the electronegativity parameters of Table 3.20, calculate atomic charges for NH<sub>3</sub> and CF<sub>4</sub>. (Assume sp<sup>3</sup> hybridization for N, C, and F.)

3.10 Which of the following structures for N<sub>2</sub>F<sub>3</sub><sup>+</sup> is more stable? (The lines do not necessarily indicate single bonds; they merely indicate bonds.)

$$\begin{bmatrix} F \\ N-N-F \\ F \end{bmatrix}^+ \begin{bmatrix} N-N \\ F \end{bmatrix}^+$$

- 3.11 Draw valence-bond octet-satisfying structures for the following species, showing all nonbonding electron pairs and formal charges: HNO<sub>3</sub>, NOF, NSCl, NOF<sub>3</sub>, NSF<sub>3</sub>, ClO<sub>3</sub><sup>-</sup>, N<sub>3</sub><sup>-</sup>, PH<sub>2</sub><sup>-</sup>, SbCl<sub>3</sub><sup>2</sup>-, IO<sub>2</sub>F<sub>2</sub><sup>-</sup>. Indicate when other resonance structures are important. Indicate the shapes of the molecules.
- 3.12 Which of the following molecules would you expect to have permanent dipole moments: SO<sub>2</sub>, CO<sub>2</sub>, BF<sub>3</sub>, NF<sub>3</sub>, SiF<sub>4</sub>, XeF<sub>4</sub>, SF<sub>4</sub>, SF<sub>2</sub>, C<sub>2</sub>H<sub>2</sub>, N<sub>2</sub>F<sub>4</sub>, trans-N<sub>2</sub>F<sub>2</sub>, SiH<sub>3</sub>Cl, O<sub>3</sub>, PF<sub>5</sub>, BrF<sub>5</sub>, S<sub>2</sub>Cl<sub>2</sub>?
- 3.13 Predict structures, including estimated bond distances and bond angles, for the molecules ClO<sub>2</sub>F, N<sub>2</sub>O<sub>5</sub>, and N<sub>4</sub>O.
- 3.14 Estimate the heats of formation of the gaseous molecules N<sub>3</sub>H<sub>5</sub> and (GeH<sub>3</sub>)<sub>2</sub>Se.
- 3.15 Rationalize the following bond-angle data for alkaline-earth dihalide molecules.

MX <sub>2</sub> $\angle$ XMX, o	
MgF <sub>2</sub>	158
CaF,	140
SrF,	108
BaF <sub>2</sub>	~ 100
CaCl <sub>2</sub>	~180
SrCl <sub>2</sub>	120
BaCl <sub>2</sub>	~100

- 3.16 From data in Table 3.6, estimate the N—F bond length in NF<sub>3</sub>. Rationalize the marked difference between this value and the actual value, 1.37 Å.
- 3.17 Assuming octet structures, what are the bond orders in the species  $XeF_4$ ,  $XeF_6$ ,  $SO_2$ ,  $CH_3^-$ , and  $NO_2$ ?
- 3.18 Which S—N bonds in the seven-membered ring of  $S_4N_3^+$  would you expect to be the shortest [See Prob. 3.1(h).]
- 3.19 Explain why the sum of D(OC=S) and D(O=CS) is much less than the atomization energy of OCS.
- \*3.20 In diamond, each carbon atom is bonded to four other carbon atoms. Rationalize the relative magnitudes of the sublimation energy of diamond (170.8 kcal mol<sup>-1</sup>) and the C—C bond energy.
- **3.21** From simple electronegativity considerations, predict whether or not the following gas-phase reaction proceeds as written:

Explain the fact that ONCI undergoes hydrolysis in liquid water.

3.22 Using Slater's rules, estimate the 1s binding energies of C(g) and  $C^+(g)$ .

\*3.23 The base-catalyzed hydrolysis of

proceeds through an intermediate anion

to give methanol and

when  $R = OCH_3$ , and to give

and methyl methylphosphonate when  $R=CH_3$ . Rationalize the results, assuming that the intermediate anion rearranges to form a species with a five-membered ring and a 5-coordinate phosphorus atom.

\*3.24 The dissociation energy of  $F_2$  seems out of line when compared with the values for the other halogens (see Table 3.9). Explain.

3.25 Estimate the P-P bond energy from the atomization energy of tetrahedral P<sub>4</sub>, 305 kcal mol<sup>-1</sup>.

In Chap. I. we distussed the effection of their associated with an atomic nucleus

#### MOLECULAR ORBITAL THEORY

The Lewis octet theory and the valence-shell electron repulsion theory discussed in Chap. 3 are usually adequate for predicting the nature of the bonding and the structures of molecules of non-transition-element compounds. However, these simple theories have serious limitations. There are many properties of molecules (e.g., spectral properties) that cannot be explained by the theories. And, in the case of transition-metal compounds, many aspects of bonding and structure cannot be treated using these theories. In this chapter we will show that molecular orbital (MO) theory is a much broader concept which is, in principle, applicable to all substances and capable of predicting most of the phenomena in which chemists are interested.

#### SIMPLE LCAO THEORY

In Chap. 1, we discussed the electron orbitals associated with an atomic nucleus, that is, atomic orbitals. In this chapter we shall discuss the orbitals associated with a set of two or more atomic nuclei, i.e., MOs. We shall make the reasonable approximation that an MO is a linear combination of atomic orbitals (LCAO). The approximation is based on the assumption that, as a valence electron circulates among the nuclei, it will at any one time be much closer to one nucleus than any other and the MO wave function will be fairly well represented by a valence atomic orbital for that nucleus. To illustrate this idea we shall develop the MOs and their energies for the case of a single valence electron associated with 1s atomic orbitals are involved in the bonding),  $\text{Li}_2^+$  (two 2s orbitals), and  $\text{LiH}^+$  (a

1s orbital and a 2s orbital). (In the case of Li<sub>2</sub>+ and LiH+ we make the further very good approximation that the  $1s^2$  closed shells are not involved in bonding.)

The Schrödinger equation which was introduced in Chap. 1 may be rear-

ranged as follows:

$$\left[V - \frac{h^2}{8\pi^2 m} \left(\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial y^2} + \frac{\partial^2 \psi}{\partial z^2}\right)\right] \psi = E\psi$$

The left side of the equation can be considered the action of an operator (called the "hamiltonian operator") on  $\psi$ , where  $\psi$  is now an MO. Therefore we can abbreviate the expression as

$$H\psi = E\psi \tag{4.1}$$

where H is the hamiltonian operator. Just as in the case of atomic wave functions, the MO wave function  $\psi$  can be either positive or negative, and  $\psi^2$  is a quantity proportional to electron density. If we multiply both sides of Eq. 4.1 by  $\psi$  and integrate over all space, we obtain

$$\int \psi H \psi \ d\tau = E \int \psi^2 \ d\tau \tag{4.2}$$

In Eq. 4.2 we have allowed a single integral sign to stand for a triple integral sign and have made the substitution  $d\tau = dx dy dz$ . By simple rearrangement we obtain the following expression for the MO energy:

$$E = \frac{\int \psi H \psi \, d\tau}{\int \psi^2 \, d\tau} \tag{4.3}$$

The wave function  $\psi$  is represented by the following linear function,

$$\psi = c_1 \phi_1 + c_2 \phi_2 \tag{4.4}$$

where  $\phi_1$  and  $\phi_2$  are the atomic orbital wave functions of atoms 1 and 2, and  $c_1$  and  $c_2$  are coefficients to be determined. Combination of Eqs. 4.3 and 4.4 yields

$$E = \frac{\int (c_1\phi_1 + c_2\phi_2)H(c_1\phi_1 + c_2\phi_2) d\tau}{\int (c_1\phi_1 + c_2\phi_2)^2 d\tau}$$

$$= \frac{\int (c_1\phi_1Hc_1\phi_1 + c_1\phi_1Hc_2\phi_2 + c_2\phi_2Hc_1\phi_1 + c_2\phi_2Hc_2\phi_2) d\tau}{\int (c_1^2\phi_1^2 + 2c_1c_2\phi_1\phi_2 + c_2^2\phi_2^2) d\tau}$$

Now we shall accept, without proof, the facts that

$$Hc_1\phi_1=c_1H\phi_1$$

and

The second map 
$$\int \phi_1 H \phi_2 d\tau = \int \phi_2 H \phi_1 d\tau$$
 has the second second map  $\int \phi_1 H \phi_2 d\tau = \int \phi_2 H \phi_1 d\tau$ 

M. C. Day, Jr., and J. Selbin, "Theoretical Inorganic Chemistry," 2d ed., pp. 165-166, 571-574, Reinhold, New York, 1969.

Therefore we may write

$$E = \frac{c_1^2 \int \phi_1 H \phi_1 \, d\tau + 2c_1 c_2 \int \phi_1 H \phi_2 \, d\tau + c_2^2 \int \phi_2 H \phi_2 \, d\tau}{c_1^2 \int \phi_1^2 \, d\tau + 2c_1 c_2 \int \phi_1 \phi_2 \, d\tau + c_2^2 \int \phi_2^2 \, d\tau}$$

For simplification, we make the following substitutions:

$$H_{11} = \int \phi_1 H \phi_1 \ d\tau$$

$$H_{22} = \int \phi_2 H \phi_2 \ d\tau$$

$$H_{12} = \int \phi_1 H \phi_2 \ d\tau$$

$$S_{11} = \int \phi_1^2 \ d\tau$$

$$S_{22} = \int \phi_2^2 \ d\tau$$

$$S_{12} = \int \phi_1 \phi_2 \ d\tau$$

$$S_{12} = \int \phi_1 \phi_2 \ d\tau$$

$$S_{13} = \int \phi_1 \phi_2 \ d\tau$$

Hence

$$E = \frac{c_1^2 H_{11} + 2c_1 c_2 H_{12} + c_2^2 H_{22}}{c_1^2 S_{11} + 2c_1 c_2 S_{12} + c_2^2 S_{22}}$$
(4.5)

We are interested in determining the minimum value of E, corresponding to the equations

$$\left(\frac{\partial E}{\partial c_1}\right)_{c_2} = 0$$
 and  $\left(\frac{\partial E}{\partial c_2}\right)_{c_1} = 0$ 

Differentiation yields the equations

$$c_1(H_{11} - ES_{11}) + c_2(H_{12} - ES_{12}) = 0$$
  
$$c_1(H_{12} - ES_{12}) + c_2(H_{22} - ES_{22}) = 0$$

These are called the "secular equations." A nontrivial solution to these equations can be expressed in terms of the "secular determinant":

$$\begin{vmatrix} H_{11} - ES_{11} & H_{12} - ES_{12} \\ H_{12} - ES_{12} & H_{22} - ES_{22} \end{vmatrix} = 0$$
 (4.6)

The terms  $H_{11}$  and  $H_{22}$  are called "coulomb integrals." From our previous definition and Eq. 4.3, we see that a coulomb integral is approximately the energy of an electron in the valence atomic orbital,  $\alpha$ . At least this approximation is reasonable for a neutral molecule, in which electron-electron and nucleus-nu-

cleus repulsions somewhat compensate. Hence we may write  $H_{11} = \alpha_1$  and  $H_{22} = \alpha_2$ . The term  $H_{12}$  is called the "exchange integral" and is essentially the interaction energy of the two atomic orbitals,  $\beta$ . Both  $\alpha$  and  $\beta$  have negative values.

If we assume that the atomic orbital wave functions  $\phi_1$  and  $\phi_2$  of Eq. 4.4 are "normalized," then

$$S_{11} = \int \phi_1^2 d\tau = S_{22} = \int \phi_2^2 d\tau = 1$$
 (4.7)

Equation 4.7 simply states that the probability of finding an electron in the orbital is exactly unity. The term  $S_{12}$  is called the "overlap integral" because it is a measure of the extent to which orbitals 1 and 2 overlap. For simplification we shall omit the subscripts and write S for the overlap integral. The secular determinant reduces to

$$\begin{vmatrix} \alpha_1 - E & \beta - ES \\ \beta - ES & \alpha_2 - E \end{vmatrix} = 0 \tag{4.8}$$

For a homonuclear species such as  $H_2^+$ , we may substitute  $\alpha_1 = \alpha_2 = \alpha$  The determinantal equation then corresponds to

$$(\alpha - E)^2 = (\beta - ES)^2$$

The two solutions of this equation are period at viscos noticels-somely on I

$$\alpha - E = -(\beta - ES)$$
 or  $E = \frac{\alpha + \beta}{1 + S}$  (4.9)

and

$$\alpha - E = (\beta - ES)$$
 or  $E = \frac{\alpha - \beta}{1 - S}$  (4.10)

By appropriate substitution in the first secular equation, we obtain

The energy level of the current problem in 
$$c_1(\alpha - E) + c_2(\beta - ES) = 0$$
 (in the energy level of the current problem). We form the current problem in the current problem in the current problem is the current problem.

$$c_1 = -\frac{\beta - ES}{\alpha - E} c_2$$

to  $\psi_1$  as the "antibonding"  $\Delta M$  for which  $\Delta R = (\alpha - E)/(1 - \alpha)$  is the internoclear line. In Fig. 4.1 is shown a plot of  $\frac{ES}{\alpha - E} = \frac{\beta}{\alpha} + \frac{ES}{\alpha - E}$  to the individual of the dashed three individual  $\frac{1}{\alpha} + \frac{1}{\alpha} + \frac{1}{\alpha}$ From this relation it can be seen that, when  $E = (\alpha + \beta)/(1 + S)$ , then  $c_1 = c_2$ , and when  $E = (\alpha - \beta)/(1 - S)$ , then  $c_1 = -c_2$ . Thus the MO wave function can be written as S: be written as follows:

orbitats. Overlap integrals are 
$$g_1\phi_1 \pm f_1\phi_2 = \psi$$
 all (often in the range 0.2 to 0.3) hence the antibonding MO is destablished approximately the same amount that the bonding MO is destablished approximately the same amount that

often assumed that S = 0. This assumption simplifies the calculations and is <sup>2</sup> Sometimes referred to as the "resonance integral" or "bond integral."

To evaluate  $c_1$ , we must normalize the wave function:

$$\int \psi^2 d\tau = c_1^2 \int \phi_1^2 d\tau \pm 2c_1^2 \int \phi_1 \phi_2 d\tau + c_1^2 \int \phi_2^2 d\tau = 1$$

$$= c_1^2 S_{11} \pm 2c_1^2 S + c_1^2 S_{22} = 1$$

Hence

$$c_1^2(2 \pm 2S) = 1$$

and

Equation 4.7 simply states that the 
$$\frac{1}{c_1} \pm \frac{1}{c_2 \pm 2\sqrt{2 \pm 2}} \pm \frac{1}{c_3} \pm \frac{1}{c_4} \pm \frac{1}{c_5} \pm \frac{1}$$

The + sign under the radical sign corresponds to  $c_1 = c_2$ , and the - sign under the radical sign corresponds to  $c_1 = -c_2$ . Obviously the following wave functions are normalized.

$$\psi_B = \frac{1}{\sqrt{2+2S}} (\phi_1 + \phi_2) \tag{4.11}$$

$$\psi_A = \frac{1}{\sqrt{2 - 2S}} (\phi_1 - \phi_2) \tag{4.12}$$

The valence-electron density is obtained by squaring these functions:

$$\psi_{B}^{2} = \frac{1}{2 + 2S} (\phi_{1}^{2} + \phi_{2}^{2} + 2\phi_{1}\phi_{2})$$

$$\psi_{A}^{2} = \frac{1}{2 - 2S} (\phi_{1}^{2} + \phi_{2}^{2} - 2\phi_{1}\phi_{2})$$

 $\psi_B^2$  shows an increase in electron density in the region of overlap between the atoms over that of the individual atoms. Such an electron distribution stabilizes the system, and we refer to  $\psi_B$  as the "bonding" MO. The energy level of  $\psi_B$  is given by  $E = (\alpha + \beta)/(1 + S)$ .  $\psi_A^2$  shows a decrease in electron density in the overlap region, and the system is unstable relative to the separate atoms. We refer to  $\psi_A$  as the "antibonding" MO, for which  $E = (\alpha - \beta)/(1 - S)$ .

In Fig. 4.1 is shown a plot of  $\phi_1^2$ ,  $\phi_2^2$ ,  $\psi_B^2$ , and  $\psi_A^2$  along the internuclear line. The dashed lines indicate  $\phi_1^2$  and  $\phi_2^2$ , i.e., the electron density of the individual atomic orbitals. The lower solid line indicates  $\psi_A^2$ , the electron density of the bonding MO, and the upper solid line indicates  $\psi_B^2$ , the electron density of the bonding MO. Figure 4.2 is an energy level diagram which graphically indicates orbitals. Overlap integrals are generally fairly small (often in the range 0.2 to 0.3); the bonding MO is destabilized approximately the same amount that often assumed that S = 0. This assumption simplifies the calculations and is




Figure 4.1 Plot of electron densities for the orbitals  $\phi_1$  and  $\phi_2$  (dashed lines),  $\psi_B$  (upper solid line), and  $\psi_A$  (lower solid line) along the internuclear axis of  $H_2^+$ .

actually not as drastic an approximation as it might appear.<sup>3</sup> With this approximation, the energy levels of  $\psi_B$  and  $\psi_A$  are  $\alpha + \beta$  and  $\alpha - \beta$ , respectively.

In the case of a heteronuclear bond (such as in LiH<sup>+</sup>), the secular determinant yields, if we neglect S.

$$(\alpha_1 - E)(\alpha_2 - E) = \beta^2$$

Solving for E gives

$$E = \frac{\alpha_1 + \alpha_2}{2} \pm \frac{1}{2} \sqrt{\alpha_1^2 + \alpha_2^2 + 2\alpha_1\alpha_2 - 4\alpha_1\alpha_2 + 4\beta^2}$$

$$= \frac{\alpha_1 + \alpha_2}{2} \pm \frac{1}{2} \sqrt{(\Delta \alpha)^2 + 4\beta^2}$$
(4.13)

<sup>3</sup> A. Streitwieser, Jr., "Molecular Orbital Theory for Organic Chemists," pp. 101–103, Wiley, New York, 1961.




Figure 4.2 Energy level diagram for the molecular orbitals formed from similar atomic orbitals in a homonuclear molecule.




Figure 4.3 Energy level diagram for the molecular orbitals formed from dissimilar atomic orbitals in a heteronuclear molecule. The overlap integral has been neglected.

The corresponding energy level diagram is given in Fig. 4.3. Notice that, according to the approximate LCAO method that we are now employing, the energy of the bonding MO is depressed from that of the more stable atomic orbital by the same amount that the energy of the antibonding MO is raised from that of the less stable atomic orbital. If  $|\beta|$  is very small, the energy spread between the bonding and antibonding levels is very little more than the separation between  $\alpha_1$  and  $\alpha_2$ , and the MOs are essentially slightly perturbed atomic orbitals.

It should be remembered that the MOs which we have been discussing are "one-electron" MOs, for which the calculated energies are valid only for one-electron occupancy. However, the results we have obtained are at least qualitatively applicable to many-electron systems. Hence the energy level diagrams of containing one to four valence electrons. The MOs are filled in the order of increasing energy. Table 4.1 gives the electron configurations for four species represented by the symbol  $(1s\sigma_B)$ , and the antibonding MOs, represented by the case of  $\psi_A$ . Asterisks are used to designate antibonding MOs, except in the bonding electrons minus one-half the number of antibonding electrons. Hence that the species  $He_2$  is predicted to have a bond order of zero, corresponding to no net bonding between the atoms.

Table 4.1


Species	Electron configuration	P- 1
H <sub>2</sub> <sup>+</sup> H <sub>2</sub> HHe He <sub>2</sub>	$(1s\sigma_B)^1$ $(1s\sigma_B)^2$ $(1s\sigma_B)^2(1s\sigma^*)^1$ $(1s\sigma_B)^2(1s\sigma^*)^2$	Bond order  1 1 2 0

<sup>&</sup>lt;sup>4</sup> The symbol  $\psi^*$  is reserved for the complex conjugate of  $\psi$ .

#### CRITERIA FOR STABLE MOLECULAR ORBITALS

The energy  $-\beta$  may be taken as a rough measure of the covalent bond energy. is commonly assumed in simple MO theory that  $-\beta$  is proportional to the corresponding overlap integral S and to the average energy of the atomic orbitals. Thus stable covalent bonds can form whenever the overlap integral is large. The following three criteria must be met to ensure large values of S.

1. The energies of the atomic orbitals must be comparable. A small negative value for  $\alpha$  corresponds to a large, diffuse atomic orbital, and a large negative value for  $\alpha$  corresponds to a small, compact atomic orbital. Two orbitals with dissimilar values of  $\alpha$  overlap poorly, as indicated by the following diagram:





Poor overlap; low S Dan Island C Good overlap; high S Hard Tedlio

Examples of diatomic molecules which have low overlap integrals because of a mismatch of atomic orbital energies are high-temperature gaseous KF and the hypothetical molecule NeS. In spite of a low  $\beta$  value, the KF molecule is stable because of the large amount of energy released on transferring a valence electron from potassium to the bonding MO, which has an energy slightly lower than that of the fluorine atomic orbital. The bonding in KF is principally ionic. The NeS molecule has very low stability because very little energy is released on transferring two electrons from the neon atomic orbital to the bonding MO.

2. The atomic orbitals must be positioned so that good overlap can occur. For example, consider the C—C bonds in cyclopropane and cyclohexane. The C-C-C bond angles in cyclopropane are 60°, which is much lower than the tetrahedral angle or even the 90° angle corresponding to use of pure p orbitals. Obviously the C-C bonds in cyclopropane must be "bent"; i.e., the overlapping atomic orbitals meet at an angle less than 180°. Such overlap is poorer (i.e., S is lower) than in the case of normal "straight" bonds such as probably exist in cyclohexane, in which the C-C-C bond angles are essentially tetrahedral angles. Evidence for the strain in the cyclopropane configuration is found in the high exothermicity of the hypothetical conversion of cyclopropane into cyclohexane:

$$2C_3H_6 \rightarrow C_6H_{12}$$
  $\Delta H^\circ = -54.9 \text{ kcal mol}^{-1}$ 

3. The atomic orbitals must have the same, or approximately the same, symmetry with respect to the bond axis. (Symmetry is briefly discussed in Chap. 2.) For example, consider the overlap between two orbitals on atoms whose z axes lie on the bond axis. In the case of an s orbital and  $p_y$  orbital, the overlapping volume element on one side of the  $p_y$  orbital has the same magnitude but opposite sign as that on the other side of the  $p_y$  orbital. This




Figure 4.4 Overlap between s and p orbitals. In the case of the  $p_y$  orbital, S = 0; in the case of the  $p_z$  orbital, S > 0.

fact is obvious from Fig. 4.4. Thus the integration over all space is exactly zero; i.e., S=0. The atomic orbitals are said to be "orthogonal." On the other hand, the overlap of an s orbital and a  $p_z$  orbital is finite, and  $S \neq 0$ . Such orbitals are "nonorthogonal." As another example, consider the overlap of a  $p_y$  orbital on one atom with a d orbital on another atom. In the case of  $d_{xz}$ ,  $d_{x^2-y^2}$ , and  $d_{z^2}$  orbitals, the overlap integral is exactly zero. However, in the case of the  $d_{yz}$  orbital, S is finite. The reader is invited to ponder the orthogonalities of all the other possible combinations of s, p, and d orbitals.

## SIGMA, PI, AND DELTA MOLECULAR ORBITALS

An MO can be classified in terms of the number of nodal surfaces which pass through at least one atomic nucleus.

A nodal surface is a surface where the MO wave function has zero amplitude as a result of its changing sign on going from one side of the surface to the other. In simple or highly symmetric molecules (such as water and benzene), the pertinent nodal surfaces are usually planes. A sigma ( $\sigma$ ) MO has no nodal surface least one nucleus. A pi ( $\pi$ ) MO has one nodal surface passing through at one nucleus.

Consider the bonding and antibonding MOs resulting from the interaction of two atoms. If we take the internuclear axis as the z axis, then  $\sigma$  orbitals are formed from atomic orbital overlaps of the type s+s,  $s+p_z$ ,  $p_z+p_z$ ,  $p_z+d_{zz}$ , the relatively rare  $\delta$  MOs are formed from overlaps of the type  $p_x+p_x$ ,  $p_y+p_y$ ,  $p_y+d_{yz}$ , etc. The relatively rare  $\delta$  MOs are formed from overlaps of the type  $d_{xy}+d_{xy}$ , and illustrated in Fig. 4.5. It is not possible to have more than two orthogonal  $p\pi$  perpendicular and which pass through the bond axis, as shown in Fig. 4.6. It can negative overlap between lobes of the same sign exactly cancels the




Figure 4.5 Some examples of the formation of  $\sigma$  and  $\pi$  MOs.




Figure 4.6 Schematic diagram showing two  $\pi$  bonds between a pair of atoms and the mutually perpendicular nodal planes. (Reproduced with permission from F. A. Cotton, "Chemical Applications of Group Theory," 2d ed., Wiley-Interscience, New York, 1971.)

### DIATOMIC MOLECULES

Let us now consider all the MOs which form by the overlap of the valence-shell s and p orbitals in a homonuclear diatomic molecule in which the internuclear axis is taken as the z axis. The two s orbitals yield an  $s\sigma_B$  and an  $s\sigma^*$  MO, and the six p orbitals yield a  $p\sigma_B$  and a  $p\sigma^*$  MO, and two equivalent  $p\pi_B$  and  $p\pi^*$  MOs. Because

the  $p\pi$  overlap is poorer than the  $p\sigma$  overlap,  $|\beta_{p\sigma}| > |\beta_{p\pi}|$ . If there were no interaction between the s and  $p_z$  orbitals, the energy level diagram would look like that shown in Fig. 4.7a. However, in the molecules of the first-row elements, a significant amount of  $2s-2p_z$  overlap occurs, causing the energies of the  $2s\sigma$  orbitals to be depressed and the energies of the  $2p\sigma$  orbitals to be raised. Consequently the  $2p\pi_B$  levels lie below the  $2p\sigma_B$  level, as shown in Fig. 4.7b.

Just as the electron configurations of the elements can be deduced by appropriate filling of the atomic orbitals, the electron configurations of the first-row diatomic molecules can be deduced by filling the MOs shown in Fig. 4.7b. The configurations for the homonuclear molecules from Li<sub>2</sub> to Ne<sub>2</sub>, as well as that of  $O_2^-$ , are given in Table 4.2. It should be noted that, as expected, dissociation energy increases and bond distance decreases with increasing bond order. The series  $O_2^+$  (r = 1.122 Å),  $O_2$  (r = 1.21 Å),  $O_2^-$  (r = 1.28 Å), and  $O_2^{2-}$  (r = 1.49 Å) also shows the expected inverse correlation of bond order and bond distance.

Probably the most significant feature of the simple MO treatment of the diatomic molecules is the ease with which the paramagnetism of  $B_2$  and  $O_2$  is two electrons. According to Hund's rule, these electrons occupy separate orbitals and have parallel spins. Thus, although each of these molecules has an even netic. Another valuable achievement of the simple MO treatment is the prediction of zero bond order (i.e., no net bonding) in  $Be_2$ . This result is not at all

In heteronuclear molecules such as CO, NO, CS, and SiC, the corresponding valence atomic orbitals of the two atoms do not have the same energy. Nevertheless, if the electronegativities of the two atoms are not too dissimilar, the qualitative ordering of the MO energy levels in such molecules is similar to that in Fig.




Figure 4.7 Valence-shell energy level diagrams for a homonuclear diatomic molecule containing first-row atoms. (a) corresponds to no interaction between 2s and 2p levels; (b) corresponds to substantial 2s-2p interaction.

Table 4.2 Diatomic species of first-row elements

Species	Valence electron configuration	Unpaired electrons	Bond order	D, kcal mol <sup>-1</sup>	r, Å
Li <sub>2</sub>	$(s\sigma_R)^2$	0	(1)	26	2.67
Be <sub>2</sub>	$(s\sigma_B)^2(s\sigma^*)^2$	0	0		
B <sub>2</sub>	$(s\sigma_B)^2(s\sigma^*)^2(p\pi_B)^2$	2	1	71	1.59
C <sub>2</sub>	$(s\sigma_B)^2(s\sigma^*)^2(p\pi_B)^4$	0	2	142	1.31
N <sub>2</sub>	$(s\sigma_B)^2(s\sigma^*)^2(p\pi_B)^4(p\sigma_B)^2$	0	3	226	1.10
02	$(s\sigma_B)^2(s\sigma^*)^2(p\pi_B)^4(p\sigma_B)^2(p\pi^*)^2$	2	2	119	1.21
O <sub>2</sub> -	$(s\sigma_B)^2(s\sigma^*)^2(p\pi_B)^4(p\sigma_B)^2(p\pi^*)^3$	nets risin s	1.5	fanction.is s	1.33
F <sub>2</sub>	$(s\sigma_B)^2(s\sigma^*)^2(p\pi_B)^4(p\sigma_B)^2(p\pi^*)^4$	0	1	38	1.42
Ne <sub>2</sub>	$(s\sigma_B)^2(s\sigma^*)^2(p\pi_B)^4(p\sigma_B)^2(p\pi^*)^4(p\sigma^*)^2$	0	0		

4.7b, and the bonding can be discussed in terms of analogous MOs. For example, consider carbon monoxide, which is isoelectronic with molecular nitrogen. The MOs of CO are like those of N2, with perturbations due to the difference in symmetry and the electronegativity difference between carbon and oxygen. A schematic representation of the MO energy level diagram is given in Fig. 4.8. The  $1\sigma$  and  $2\sigma$  orbitals are the oxygen 1s and carbon 1s atomic orbitals, respectively, and are not shown. Notice that the g and u subscripts are omitted from the symmetry labels because the molecule lacks a center of symmetry. The MO nomenclature scheme used in Fig. 4.8 is described on the next page.




Figure 4.8 MO energy level diagram for carbon monoxide.

#### ELECTRON DENSITY CONTOUR MAPS

With modern computing facilities, it is a relatively easy problem to calculate accurate wave functions for the first-row diatomic molecules. Electron density contour maps for the MOs of the O2 molecule, based on such calculations,5 are shown in Fig. 4.9. The contours correspond to the electron densities in a plane passing through the two atoms. The MOs are labeled according to a scheme which is now common in the literature: A symbol such as  $\sigma$  or  $\pi$  is used to indicate the symmetry of the orbital; the subscript g (for "gerade") is used if the orbital wave function is symmetric with respect to inversion, and the subscript u (for "ungerade") is used if the orbital wave function is antisymmetric with respect to inversion.6 The initial arabic numeral indicates the relative position of that particular type of orbital on an absolute energy scale; the lowest energy orbital of a particular symmetry is given the number 1, the next higher in energy the number 2, etc. This MO nomenclature scheme is superior to that used in Table 4.2 and Fig. 4.7 because it avoids the incorrect implication that the MOs are constructed from pure atomic orbitals, without any atomic orbital interaction or "mixing." It should be noted that the 1s core shells are so contracted because of the higher effective nuclear charge in the core region that they are essentially spherical with no significant overlap. Therefore the core electrons contribute very little to chemical bonding. It can be seen that the bonding orbitals  $(2\sigma_g, 3\sigma_g, \text{ and } 1\pi_u)$ show an increase in electron density in the region between the nuclei and that the antibonding orbitals  $(2\sigma_u$  and  $1\pi_g)$  show a reduction in electron density between

A different graphical method for representing the valence MOs of the oxygen molecule, which gives a good indication of the three-dimensional nature of the orbitals, is shown in Fig. 4.10. Here, for the sake of completeness, the unoccupied  $3\sigma_u$  (or " $2p\sigma^*$ ") orbital is illustrated, as well as the various occupied MOs.

Wave function contours for some of the carbon monoxide valence MOs are shown in Fig. 4.11.8 Orbital  $4\sigma$  is related to the " $2s\sigma$ \*" orbital of  $N_2$ , but the contours indicate that the oxygen  $2p\sigma$  orbital on the bond axis makes a significant overlapping with a mixture of oxygen 2s and 2p orbitals. Some  $\sigma$  bonding results, but the MO is mainly a nonbonding lone-pair orbital.

The two  $1\pi$  orbitals are bonding, but the contours show the dominance of the oxygen  $p\pi$  orbitals; the bonding  $\pi$  electron density is concentrated on the more electronegative oxygen atom.

<sup>&</sup>lt;sup>5</sup> A. C. Wahl, Science, 151, 961 (1966).

<sup>6</sup> Inversion corresponds to reversing the directions of the x, y, and z coordinates. See Chap. 2 for a discussion of symmetry operations. A function which is symmetric with respect to inversion does not upon inversion.

W. L. Jorgensen and L. Salem, "The Organic Chemist's Book of Orbitals," Academic, New York, 1973.
 I. B. Johnson

<sup>&</sup>lt;sup>8</sup> J. B. Johnson and W. G. Klemperer, J. Am. Chem. Soc., **99**, 7132 (1977).




Figure 4.9 Electron density contour maps for the MOs of O<sub>2</sub>. [Reproduced with permission from A. C. Wahl, Science, 151, 961 (1966).]





Figure 4.10 Three-dimensional representations of the  $O_2$  MOs. The solid and dashed contours correspond to  $\psi > 0$  and  $\psi < 0$ , respectively. (Reproduced with permission from W. L. Jorgensen and L. Salem, "The Organic Chemist's Book of Orbitals," Academic, New York, 1973.)



that the excess "bonding charge" is correlated with the C C bond length. The highest occupied orbital,  $5\sigma$ , is strongly polarized toward carbon. This MO has some  $\sigma$ -bonding character but is essentially a carbon lone-pair orbital.

teon density in the bonding region of various carbon-carbon bonds have show!

The lowest unoccupied MOs, the  $2\pi$  orbitals, are analogs of the  $2p\pi^*$  orbitals of N<sub>2</sub> but are mainly located on the carbon atom. These orbitals figure importantly in the interaction of CO with transition-metal atoms. Notice that, if we

consider the  $3\sigma$  and  $1\pi$  orbitals as bonding, and the  $4\sigma$  and  $5\sigma$  orbitals as nonbonding, we end up with a total of three bonds, just as in the : C=0: representation.

To illustrate the flow of electron density which occurs when atoms form chemical bonds, electron density "difference" plots can be used. One plots contours corresponding to the difference in electron density of the actual molecule and that of the hypothetical noninteracting spherical atoms. Figure 4.12 shows calculated electron density difference contours for molecular hydrogen and diatomic lithium.9 The solid lines denote regions of increased electron density, and the dotted lines denote regions of decreased electron density. It is clear in each case that electron density moves from the far sides of the molecule into the overlap region between the nuclei. In both H2 and Li2, there is a distinct buildup of electron density near the atomic nuclei. This latter phenomenon is at first sight surprising but becomes reasonable upon recognizing that the large increase in electron density between the atoms allows the remaining electron density to become more concentrated in the region near the nuclei.

The amount of electron density which moves into the overlap region is quite small, typically about 0.1 to 0.3 of an electron. The smallness of this electron flow explains why, until recent years, experimental evidence for it was quite poor. However, now accurate x-ray and neutron diffraction data yield good electron density difference maps that show essentially the same sort of information as given by the theoretically calculated maps of Fig. 4.12. For example, accurate x-ray diffraction data for 2,5-di-N-chlorothioimino-3,4-dicyanothiophene, 10 yield

$$\begin{array}{cccc}
N & & & & & \\
C & & & & & \\
C & & & & & \\
N & & & & & \\
N & & & & & \\
N & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & & \\
C & & & & & \\
S & & & & \\
S & & & & \\
S & & & \\
S & & & \\
S & & \\
S$$

the electron density difference map shown in Fig. 4.13. This diagram reveals both the expected buildup of density in the C-C, C-S, C-N, and N-S bond regions and the concentration of density in the lone-pair regions of the sulfur and chlorine atoms. Quantitative measurements by this method of the excess electron density in the bonding region of various carbon-carbon bonds have shown that the excess "bonding charge" is correlated with the C-C bond length."

<sup>&</sup>lt;sup>9</sup> Data of R. W. F. Bader, reported by C. A. Coulson, "The Shape and Structure of Molecules," pp. 36-37, Clarendon, Oxford, 1973.

<sup>&</sup>lt;sup>10</sup> F. Wudl and E. T. Zellers, J. Am. Chem. Soc., 102, 4283 (1980).

Z. Berkovitch-Yellin and L. Leiserowitz, J. Am. Chem. Soc., 99, 6106 (1977).




Figure 4.12 Calculated electron density difference plots for H<sub>2</sub>(a) and Li<sub>2</sub>(b). The contours refer to electron density differences between the molecules and the atoms. Solid lines denote increased electron density, and dotted lines denote decreased electron density, and dotted lines denote decreased electron density. (Reproduced with permission from C. A. Coulson, "The Shape and Structure of Molecules," Clarendon, Oxford, 1973.)




Figure 4.13 Electron density difference plot for 2,5-di-N-chlorothioimino-3,4-dicyanothiophene, obtained from x-ray diffraction data. Solid lines denote increased electron density. (Reproduced with permission from Molecular Structure Corporation, College Station, Texas.)

Figure 4.14 shows a plot of measured bonding charge versus bond length. The bonding density falls off almost linearly with increasing bond length, in accord with the idea that a chemical bond is due to the accumulation of negative charge in the region between atoms to an extent sufficient to balance the nuclear repulsion forces.

## SYMMETRY AND POLYATOMIC MOLECULES

In symmetric molecules, there are sets of equivalent atoms and atomic orbitals. When considering the MOs of such molecules, it is helpful to form linear combinations of the equivalent atomic orbitals, called "group orbitals." These group orbitals can then be treated just like individual atomic orbitals; they can be combined with other atomic orbitals or with other group orbitals to form MOs.




Figure 4.14 Plot of "bonding charge" (increased electron density in the bonding region) versus bond length for various C—C bonds. TP = tetraphenylbutatriene; AD = allenedicarboxylic acid-acetamide; PN = p-nitropyridine oxide; D = diamond; TCB = tetracyanocyclobutane; P = perylene; BCB = a bicyclobutane derivative. [Reproduced with permission from Z. Berkovitch-Yellin and L. Leiserowitz, J. Am. Chem. Soc., 99, 6106 (1977). Copyright 1977 American Chemical Society.]

However, no matter what types of orbitals are combined to form MOs, they must have the same symmetry properties and they must have satisfactory overlap.<sup>12</sup>

To illustrate the use of group orbitals, we shall discuss the MOs of the triiodide ion,  $I_3$ . From valence-shell electron repulsion theory (Chap. 3) we know that this is a linear species. The middle atom can be considered as having three nonbonding electron pairs in  $sp^2$  hybrid orbitals in a plane normal to the bonds. Each of the terminal atoms also has a set of three nonbonding electron pairs, but the orientation of these pairs is not certain; they probably occupy orbitals having somewhat more p character than  $sp^2$ . Thus we have three collinear atomic orbitals which can be involved in  $\sigma$  bonding: a p orbital on the middle atom, and hybrid orbitals on the terminal atoms. The two equivalent hybrid orbitals on the terminal atoms,  $\phi_1$  and  $\phi_3$ , can be combined into two group orbitals:

$$\phi_G = \frac{1}{\sqrt{2}} \left( \phi_1 \pm \phi_3 \right)$$

 $<sup>^{12}</sup>$  Group-theoretical labels such as  $\sigma_g^+$ ,  $b_1$ , and  $t_2$ , are useful for designating the symmetry properties of orbitals and combinations of orbitals. A full understanding of their significance is not necessary to follow the discussions of this text. A brief introduction to the subject is given in Chap. 2.

These combinations are pictured below:

$$\frac{1}{\sqrt{2}}(\phi_1 + \phi_3)$$

$$\sigma_g^+ \text{ symmetry}$$

$$\frac{1}{\sqrt{2}}(\phi_1 - \phi_3)$$

$$\sigma_g^+ \text{ symmetry}$$

$$\frac{1}{\sqrt{2}}(\phi_1 - \phi_3)$$

$$\sigma_g^+ \text{ symmetry}$$

Note that the  $\sigma_g^+$  group orbital<sup>13</sup> is symmetric with respect to inversion through the center of the  $I_3^-$  ion and that the  $\sigma_u^+$  group orbital is antisymmetric with respect to inversion. The p orbital on the middle atom is antisymmetric with respect to inversion; like the  $\phi_1 - \phi_3$  group orbital, it has  $\sigma_u^+$  symmetry.<sup>13</sup>



The overlap integral of the symmetric group orbital and the middle p orbital is exactly zero. Thus only the antisymmetric group orbital can interact with the middle p orbital to form a bonding and an antibonding MO. These MOs are represented as follows:

$$\psi = \frac{1}{\sqrt{2}} \, \phi_2 \pm \frac{1}{2} \, (\phi_1 - \phi_3)$$

The symmetric group orbital  $(1/\sqrt{2})(\phi_1 + \phi_3)$  is essentially a nonbonding MO. The reader may wish, as an exercise, to prove that all three MOs, as written, are normalized (under the assumption that S = 0).

An energy level diagram for  $I_3^-$  is shown in Fig. 4.15. Note that these orbitals are occupied by four valence electrons. Two are nonbonding and two are bonding. Obviously we should look upon the I-I bonds in  $I_3^-$  as half-bonds, in agreement with simple octet structure considerations. The other 18 valence electrons occupy the 9 nonbonding orbitals that we referred to earlier. The nonbonding orbital of Fig. 4.15 is shared by the terminal atoms; thus  $3\frac{1}{2}$  lone pairs are located on each terminal atom.

The model of  $I_3^-$  which we have just described completely ignores valenceshell d-orbital participation. If we choose to have the z axis of the middle atom lie along the bonds, we see that the  $d_{z^2}$  orbital of the middle atom has the same symmetry as that of the symmetric group orbital  $(1/\sqrt{2})(\phi_1 + \phi_3)$ . Now it is likely that the overlap between this  $d_{z^2}$  orbital and the terminal-atom hybrid

<sup>&</sup>lt;sup>13</sup> See footnote 12.





Figure 4.15 Energy level diagram for the  $\sigma$  molecular orbitals of  $I_3^-$  formed from the atomic orbitals lying on the bonding axis. Valence-shell d orbitals are ignored.

orbitals is very poor; the orbital energies are probably quite far apart. However, if we are willing to admit a weak interaction between the middle-atom  $d_{z^2}$  orbital and the symmetric group orbital, we may draw a modified energy level diagram as shown in Fig. 4.16. Most evidence indicates that d-p bonding of the type shown is very weak; for all practical purposes the  $\sigma_g^+$  orbital is nonbonding.<sup>14</sup>

Let us now consider the  $\pi$  bonding in the ozone molecule. Assume that this V-shaped molecule lies in the yz plane; we are then concerned with the overlap of the  $p_x$  orbitals on each oxygen atom. The two terminal  $p_x$  orbitals are equivalent; their corresponding group orbitals are

$$\phi_G = \frac{1}{\sqrt{2}} \left( \phi_1 \pm \phi_3 \right)$$

These may be shown as the following projections:



<sup>14</sup> T. B. Brill, J. Chem. Educ., **50**, 392 (1973); C. D. Cornwell and R. S. Yamasaki, J. Chem. Phys., 27, 1060 (1957)





Figure 4.16 Energy level diagram for the  $\sigma$  molecular orbitals of  $I_3^-$  formed from the atomic orbitals lying on the bonding axis. A valence-shell  $d_{z^2}$  orbital is included.

The  $p_x$  orbital on the middle oxygen atom has the same symmetry,  $b_1$ , as the  $(1/\sqrt{2})(\phi_1 + \phi_3)$  group orbital.



Therefore these orbitals combine to form antibonding and bonding MOs, and the group orbital of  $a_2$  symmetry is essentially a nonbonding MO. The corresponding energy level diagram is shown in Fig. 4.17. Inasmuch as there are only two bonding  $\pi$  electrons, the  $\pi$  bond order in O<sub>3</sub> is  $\frac{1}{2}$ .




Figure 4.17 Energy level diagram for the  $\pi$  molecular orbitals of ozone,  $O_3$ . The vertical arrowindicates  $\pi \to \pi^*$  transition energy.

Finally we shall consider the  $\sigma$  bonding in a tetrahedral species such as BH<sub>4</sub><sup>-</sup>, CH<sub>4</sub>, NH<sub>4</sub><sup>+</sup>, ClO<sub>4</sub><sup>-</sup>, or PCl<sub>4</sub><sup>+</sup>. The central atom has an s orbital and three p orbitals in its valence shell, which are involved in bonding. Each ligand atom has one atomic orbital involved in the bonding (a 1s orbital in the case of a hydrogen atom, and a hybrid orbital in the case of an oxygen or chlorine atom). The group orbital wave function which can combine with the central-atom s orbital is

$$\phi_G = \frac{1}{\sqrt{4}} \left( \phi_1 + \phi_2 + \phi_3 + \phi_4 \right)$$

where  $\phi_1$ ,  $\phi_2$ ,  $\phi_3$ , and  $\phi_4$  are the individual ligand orbital wave functions. The corresponding MO wave functions are

$$\psi = \frac{1}{\sqrt{2}} \phi_s \pm \frac{1}{2\sqrt{2}} (\phi_1 + \phi_2 + \phi_3 + \phi_4)$$

In order to see which combinations of ligand orbitals can combine with the central-atom p orbitals, it is helpful to refer to Fig. 4.18. Figure 4.18a shows the bonding combination,

$$\psi_B(p_z) = \frac{1}{\sqrt{2}} \phi_{p_z} + \frac{1}{2\sqrt{2}} (\phi_1 + \phi_2 - \phi_3 - \phi_4)$$

and Fig. 4.18b shows the antibonding combination,

$$\psi_A(p_z) = \frac{1}{\sqrt{2}} \phi_{p_z} - \frac{1}{2\sqrt{2}} (\phi_1 + \phi_2 - \phi_3 - \phi_4)$$




Figure 4.18 Bonding (a) and antibonding (b) combinations of the hydrogen s orbitals and a carbon  $2p_z$  orbital in methane. Similar combinations can be drawn for the degenerate  $2p_x$  and  $2p_y$  orbitals.

Similarly, for the  $p_x$  and  $p_y$  orbitals, we write  $\frac{1}{2}$  and  $\frac{1}{2}$  and  $\frac{1}{2}$  and  $\frac{1}{2}$  are  $\frac{1}{2}$  and  $\frac{1}{2}$  are  $\frac{$ 

$$\psi_{B}(p_{x}) = \frac{1}{\sqrt{2}} \phi_{p_{x}} + \frac{1}{2\sqrt{2}} (-\phi_{1} + \phi_{2} - \phi_{3} + \phi_{4})^{\text{lay 2}} \text{ in a lating}$$

$$\psi_{A}(p_{x}) = \frac{1}{\sqrt{2}} \phi_{p_{x}} - \frac{1}{2\sqrt{2}} (-\phi_{1} + \phi_{2} - \phi_{3} + \phi_{4})^{\text{lay 2}} \text{ in a lating 2}$$

$$\psi_{B}(p_{y}) = \frac{1}{\sqrt{2}} \phi_{p_{y}} + \frac{1}{2\sqrt{2}} (-\phi_{1} + \phi_{2} + \phi_{3} - \phi_{4})$$

$$\psi_{A}(p_{y}) = \frac{1}{\sqrt{2}} \phi_{p_{y}} - \frac{1}{2\sqrt{2}} (-\phi_{1} + \phi_{2} + \phi_{3} - \phi_{4})^{\text{lay 2}} \text{ gain processing}$$

Because of the symmetry of the molecule, the  $p_x$ ,  $p_y$ , and  $p_z$  orbitals are equivalent. Therefore  $\psi_B(p_x)$ ,  $\psi_B(p_y)$ , and  $\psi_B(p_z)$  are degenerate; i.e., they have the same




Figure 4.19 Energy level diagram for the valence molecular orbitals of methane.




Figure 4.20 Ultraviolet photoelectron spectrum of methane. The photon energy was 41 eV; the signal at 24.6 eV is due to helium. [Reproduced with permission from G. Bieri and L. Asbrink, J. Electron Spectrosc. Rel. Phen., 20, 149 (1980).]

energy levels. The same is true of  $\psi_A(p_x)$ ,  $\psi_A(p_y)$ , and  $\psi_A(p_z)$ . Thus the energy level diagram for this system, in Fig. 4.19, shows that the eight bonding electrons occupy a single orbital (of  $a_1$  symmetry) and three degenerate orbitals (of  $t_2$ symmetry). Although the four  $\sigma$  bonds are equivalent, there are essentially two kinds of bonding electrons, with entirely different ionization potentials. The separate ionization potentials corresponding to the two MOs are obvious in the ultraviolet photoelectron spectrum of Fig. 4.20. To No. 14 or Ashimery graups to Ichimaryaid iscond Tromally am tab

#### HYBRIDIZATION15

Although the concept of hybridization is strictly a part of valence bond theory, we have postponed discussion of this topic until now, when the reader is familiar with the concept of linear combinations of atomic orbitals and can directly compare the application of hybridization theory and MO theory to a particular molecule.

We know from experiment that the methane molecule is tetrahedral and that the four C-H bonds are equivalent. If we assume that the C-H bonds are single bonds, formed by combination of the hydrogen 1s orbitals with the carbon 2s and 2p orbitals, then each bond must involve, or "use," one-quarter of the carbon 2s orbital and one-quarter of the three carbon 2p orbitals. If we wish to describe the bonding of methane in terms of localized two-electron bonds, we can assume that the one 2s and three 2p orbitals of carbon "mix" to form four equivalent hybrid orbitals directed toward the hydrogen atoms. Then each bond can be considered the result of the overlap of an sp3 hybrid orbital of carbon and a Is orbital of hydrogen. If we let the symbols s,  $p_x$ ,  $p_y$ , and  $p_z$  stand for the valence atomic orbitals of carbon, the four hybrid orbitals can be represented as the following linear combinations:

$$\phi_1 = \frac{1}{2}(s + p_x + p_y + p_z)$$

$$\phi_2 = \frac{1}{2}(s + p_x - p_y - p_z)$$

$$\phi_3 = \frac{1}{2}(s - p_x - p_y + p_z)$$

$$\phi_4 = \frac{1}{2}(s - p_x + p_y - p_z)$$

Similar sets of hybrid orbitals can be constructed from other combinations of atomic orbitals. Some of these types of hybridization are listed in Table 4.3. In each case, except  $dsp^3$ , it is possible to construct the hybrid orbitals so that they are equivalent. However, in the case of trigonal bipyramidal and square pyramidal geometries, such equivalence is obviously impossible.

The properties of a hybrid orbital are highly dependent on the relative proportions of the different kinds of atomic orbitals which are combined to form the hybrid orbital. For example, the overlap of a hybrid orbital with another

<sup>15</sup> L. Pauling, "The Nature of the Chemical Bond," 3d ed., pp. 111 – 123, Cornell University Press, Ithaca, N.Y., 1960; F. A. Cotton, "Chemical Applications of Group Theory," 2d ed., chap. 8, Wiley I., Wiley-Interscience, New York, 1971.

Table 4.3 Some common hybridizations and their geometries

sp	Linear
sp <sup>2</sup>	Trigonal (120° bond angles)
sp3, sd3	Tetrahedral (109.5° bond angles)
$d^2sp^3$	Octahedral
dsp <sup>2</sup>	Square planar
dsp <sup>3</sup>	Trigonal bipyramidal or square pyramidal

orbital changes markedly as the fractional s (or p) content of the hybrid changes. The calculated overlap integrals for C—C and C—H bonds as a function of the percent s character of the carbon orbital  $^{16}$  are plotted in Fig. 4.21. It can be seen that the overlap integrals have maximum values at hybridizations intermediate between pure s and pure p, and that in the hybridization range generally found in molecules (i.e., between pure p and sp hybridization), the overlap integral increases with s character. We have already pointed out that covalent bond strength is proportional to the overlap integral. Hence we expect that bond strength should increase as the s character of a hybrid orbital increases. Stronger bonds correspond to shorter bonds, and thus we have an explanation of the data we saw in Table 3.5, which show a shortening of the C—C single bond on going from aliphatic hydrocarbons to compounds in which the other bonds to the carbon atoms are involved in  $\pi$  bonding. The  $\pi$  bonding uses only the p orbitals of the carbon atoms, and therefore the remaining  $\sigma$  bonds must be formed from hybrid orbitals possessing relatively high s character.

<sup>16</sup> A. Maccoll, Trans. Faraday Soc., 46, 369 (1950).




Figure 4.21 The calculated overlap integral, S, for C—C and C—H bonds as a function of percent s character. [Adapted from a plot of A. Maccoll, Trans. Faraday Soc., 46, 369 (1950).]

An s orbital is lower in energy, and has a higher electronegativity, than a p orbital. Therefore the effective electronegativity of an s, p hybrid orbital increases as the fractional s content (s character) increases. 17 Consider the hybridization of the lone-pair orbitals in ammonia, pyridine, and molecular nitrogen. In pyridine one nitrogen p orbital is involved in  $\pi$  bonding, and in molecular nitrogen two p orbitals of each nitrogen atom are involved in  $\pi$  bonding. Thus the average s character of the  $\sigma$  orbitals (the lone-pair and the  $\sigma$ -bonding orbitals) increases on going from NH3 to NC5H5 to N2. If the s character were divided equally among the lone-pair and  $\sigma$ -bonding orbitals in each of these cases, the lone pair would occupy an sp3 hybrid in NH3, an sp2 hybrid in NC5H5, and an sp hybrid in N2. The relative base strengths of the compounds are in accord with this simple picture. Ammonia is a stronger base than pyridine, which is a much stronger base than molecular nitrogen.

In the absence of steric effects, replacement of X in the structure X—A—Y by a more electronegative group causes the adjacent A-Y bond to become The effect is most pronounced when fluorine is introduced into a molecule (the C-F distances in CH<sub>3</sub>F and CF<sub>4</sub>, for example, are 1.391 and 1.323 Å, respectively) but generally can be seen whenever an atom is replaced by a

more electronegative atom. Some examples follow.

Bond	Molecule	Bond length, Å
C-CI	CH3CI CH3CI DE	1.783
	CH.CL	1.772
	CIICII	of am 1.764 seconds of
	tod of CCl <sub>4</sub>	1.766
C-Br	CH <sub>1</sub> Br	1.939
	3	1.930
C-CI	CH <sub>3</sub> Cl	
	CF <sub>3</sub> Cl	1.751
C-C	A COLUMN TO SERVICE AND ADDRESS OF THE PARTY	
	2116	
No. Co.	$C_2F_6$	1.51
N-Cl	N(CH <sub>3</sub> ) <sub>2</sub> Cl	1.77 or 5 tank
	N(CH <sub>3</sub> )Cl <sub>2</sub>	1.74
C=0	H <sub>2</sub> CO	1.225
	HFCO	1.192
William and	F <sub>2</sub> CO	1.17

The data can be understood by recognizing that atomic p character concentrates in orbitals directed toward electronegative substituents (and, of course, that atomic s character concentrates in orbitals directed toward electropositive substituents). This rule follows from the fact that an electron in a p orbital is on the average farther from the nucleus than an electron in an s orbital; the p-orbital electron is more readily shared by an orbital centered on another atom. Replace-

<sup>&</sup>lt;sup>17</sup> H. A. Bent, Chem. Rev., 61, 275 (1961).

ment of a substituent by a more electronegative atom causes a rehybridization, i.e., a shift of p character to the orbital involved in bonding to the electronegative atom and a shift of s character to the other bonds. Hence the other bonds are

strengthened and shortened.

It is instructive to discuss the bonding in the water molecule in terms of orbital hybridization and valence-shell electron repulsion. The ground-state electron configuration of the oxygen atom is 2s22p4, with two unpaired 2p electrons. If this atom were to react with two hydrogen atoms without any hybridization, one would expect the resulting water molecule to have an H-O-H bond angle of 90°. In such a molecule the lone pairs would occupy the 2s and one 2p orbital or, what is precisely equivalent, two sp hybrid orbitals directed at right angles to the plane of the molecule. Obviously in such a molecule there would be a particularly strong repulsion between the lone-pair electrons and the bonding electrons. Now let us assume that we start with an oxygen atom in which the two lone pairs occupy hybrid orbitals which have more than 50 percent p character and in which the unpaired electrons occupy orbitals which have less than 100 percent p character. Energy is required to promote a ground-state oxygen atom to this hypothetical hybridized state, because the promotion corresponds to the excitation of a fraction of an electron from a 2s orbital to a 2p orbital. (If a complete electron were excited, one would obtain an atom with the configuration  $2s^{1}2p^{5}$ .) In the hybridized oxygen atom, the angle between the lone pairs would be less than 180°, and the promotion energy can be partly ascribed to the resultant extra electron-electron repulsion. The hybridized atom would react with two hydrogen atoms to form a molecule in which the H-O-H bond angle is greater than 90° and in which the angle between either lone pair and either O-H bond is greater than 90°. The promotion energy would be compensated by the reduction in the electron-electron repulsions and by the fact that an increase in the s character of an orbital causes an increase in the bond energy. Obviously in the actual water molecule these energy terms are exactly compensating. Such balancing of promotion energy, electron repulsion energy, and bond energy is a common feature of orbital hybridization schemes.

It should be emphasized that the concept of hybridization is essentially a mathematical operation which we use mainly for convenience in the description of bonding. One must be careful not to draw incorrect conclusions regarding the excited states of molecules for which the ground states can be described in terms of hybridized orbitals. For example, in the case of methane, if we consider only the four equivalent bonding orbitals corresponding to the use of hybrid  $sp^3$  orbitals, it is not apparent that there should be two different ionization potentials for the bonding electrons. However, evidence for these two ionizations is seen in the photoelectron spectrum of Fig. 4.20, which shows two separate photolines.

thents). This rule follows from the fact that an electron

# WALSH DIAGRAMS

When considering the structure of a molecule which could conceivably assume any conformation between, or including, two limiting conformations, it is in-




Figure 4.22 Walsh diagram for AH<sub>2</sub> molecule, with diagrams of the valence MOs.

structive to study the correlation of MOs of one limiting conformation with those of the other. Walsh<sup>18</sup> was the first to apply this method extensively, and correlation diagrams of this type are now often called "Walsh diagrams." Consider the general case of an  $AH_2$  molecule, for which we may consider the limiting values of the H-A-H bond angles to be 90 and 180°. We shall assume that the MOs are formed solely from valence s and p orbitals of atom A and 1s orbitals of the hydrogen atoms. Crude pictures of these MOs and a qualitative Walsh diagram are shown in Fig. 4.22.19

The lowest-energy valence MO for the linear geometry,  $2\sigma_g$ , is formed from the s orbital of A and the symmetric combination of hydrogen 1s orbitals. Upon bending the molecule, the  $2a_1$  orbital which forms is slightly lower in energy than the original  $2\sigma_g$  because the hydrogen 1s orbitals then overlap better with each other and with the p orbital of A on the twofold molecular axis, which becomes a minor component of  $2a_1$ . The  $1\sigma_u$  MO of the linear molecule is formed from the p orbital of A on the molecular axis and the asymmetric combination of hydrogen 1s orbitals. Bending the molecule converts this MO to the  $1b_2$  MO, which has higher energy because the hydrogen 1s orbitals then do not overlap as well with

<sup>19</sup> B. M. Gimarc, J. Am. Chem. Soc., 93, 593 (1971).

<sup>&</sup>lt;sup>18</sup> A. D. Walsh, *J. Chem. Soc.*, 2260, 2266, 2288, 2296, 2306 (1953). The method was first outlined by R. S. Mulliken, *Rev. Mod. Phys.*, **14**, 204 (1942).

the p orbital. The highest occupied MOs of the linear molecule are the doubly degenerate  $1\pi_n$  orbitals, which consist of the two p orbitals of A perpendicular to the molecular axis which have no net overlap with the hydrogen 1s orbitals. On bending, the p orbital which lies on the twofold molecular axis overlaps with the symmetric combination of hydrogen 1s orbitals and thus forms the 3a, orbital with lower energy than  $1\pi_n$ . In the bent molecule, a small amount of A-atoms orbital can also contribute to  $3a_1$ . In Fig. 4.22 it can be seen that the  $3a_1$  level falls from the  $1\pi$ , level faster than the  $1b_2$  level rises from the  $1\sigma$ , level. This difference can be rationalized by the fact that, on bending the molecule, the overlap integral of  $3a_1$  is greater than the decrease in the overlap integral on going from  $1\sigma_u$  to  $1b_2$ . The p orbital perpendicular to the molecular plane (the  $1b_1$  MO) has no overlap with the hydrogen 1s orbitals and therefore has the same energy as  $1\pi_{\mu}$ .

Because the diagram of Fig. 4.22 is based on approximate calculations, and because factors such as nucleus-nucleus repulsions and electron-electron repulsions have not been taken into account, it can only be used to predict approximate shapes of molecules—i.e., whether a molecule is linear or bent. Let us consider some examples. A molecule containing only four valence electrons, such as BeH<sub>2</sub>, will have the lowest two orbitals filled. From the diagram, we see that a minimum in energy will be achieved by having a linear molecule, with the  $2\sigma_e$  and  $1\sigma_u$  orbitals filled. On the other hand, the first excited state of BeH<sub>2</sub> should be bent, corresponding to one electron each in the  $3a_1$  and  $1b_2$  orbitals.

The CH<sub>2</sub> molecule, with six valence electrons, is similarly expected to be From the qualitative diagram, the bond angle cannot be predicted. However, very accurate calculations<sup>21</sup> have shown that the ground state has a bond angle of 134°. At that bond angle, the  $3a_1$  and  $1b_1$  energy levels are so close together that the energy difference is less than the repulsion energy between two electrons in the  $3a_1$  orbital. Hence the ground state is a triplet, and the electron configuration is

### $2a_1^2 1b_2^2 3a_1^1 1b_1^1$

The singlet state lies only 8 to 9 kcal above the ground state; the bond angle 15 102.4°, and the electron configuration is

$$2a_1^2 1b_2^2 3a_1^2$$

The water molecule has two more electrons than CH<sub>2</sub>, and all the orbitals in Fig. 4.22 are filled. Because of the steepness of the  $3a_1 - 1\pi_\mu$  correlation line, we

predict the water molecule, like CH<sub>2</sub>, to be bent.

In general, we can rationalize why a given AH, molecule is bent or linear in terms of the tendency for the molecule to lower its total energy by keeping the lower-energy s orbital of atom A as fully occupied as possible. In the case of molecules containing fewer than eight valence electrons, this condition is usually achieved by making the empty or partially filled orbitals pure p orbitals. The

<sup>&</sup>lt;sup>21</sup> C. W. Bauschlicher, H. F. Schaefer, and P. S. Bagus, J. Am. Chem. Soc., 99, 7106 (1977).

particular bond angle assumed by a bent AH, molecule is determined by other considerations, the most important of which are electron-electron repulsions.<sup>22</sup>

#### PI BONDING BEYOND THE FIRST ROW OF THE PERIODIC TABLE

There are many known compounds containing elements of the first row of the periodic table in which these elements are  $\pi$ -bonded either to themselves or to other first-row elements. However, there are few examples of compounds in which the heavier analogs of these elements are  $\pi$ -bonded. For example, carbon forms double bonds in CO2, CH3COOH, C2H4, etc., whereas silicon and germanium form no analogous molecules that are stable under ordinary conditions. Nitrogen forms N2, NO3-, HCN, etc., whereas the phosphorus and arsenic analogs are extremely unstable species. Because of these facts, it was once believed that only elements of the first row are capable of forming stable  $\pi$  bonds. However, high-quality calculations<sup>23</sup> on compounds of heavier elements tend to refute this conclusion. For example, it has been calculated that H<sub>2</sub>Si=CH<sub>2</sub> is stable with respect to the triplet state H,Si—CH<sub>2</sub> by about 28 kcal mol<sup>-1</sup> and that the bond strength of the Si-C  $3p\pi$ - $2p\pi$  bond as determined by the rotational barrier is about 46 kcal mol-1. Therefore we conclude that the paucity of π-bonded compounds of silicon, phosphorus, etc., is not due to an intrinsic instability of the  $\pi$  bonds, but rather to a high reactivity which leads to conversion of the  $\pi$ -bonded compounds to more stable  $\sigma$ -bonded compounds. For example, the existence of short-lived intermediates of the type R<sub>2</sub>SiCH<sub>2</sub> has been concluded from studies of the thermal decomposition of monosilacyclobutanes which yield 1,3-disilacyclobutanes and ethylene. Kinetic data support the mechanism

$$R_{2}Si \longrightarrow R_{2}SiCH_{2} + C_{2}H_{4}$$

$$2R_{2}SiCH_{2} \longrightarrow R_{2}Si \longrightarrow SiR_{2}$$

Kinetically stable compounds containing carbon-silicon double bonds have been prepared by surrounding the Si=C bond with extremely bulky groups. The large groups prevent cyclization and polymerization. For example, the substituted silaethylene with the following structure has been isolated as a crystalline solid, stable at room temperature<sup>24</sup>

<sup>&</sup>lt;sup>22</sup> M. B. Hall, J. Am. Chem. Soc., **100**, 6333 (1978); Inorg. Chem., **17**, 2261 (1978).

R. Ahlrichs and R. Heinzmann, J. Am. Chem. Soc., 99, 7452 (1977). However, theoretical studies of HC $\equiv$ SiH indicate that it is unstable with respect to the isomer H<sub>2</sub>C $\equiv$ Si. See M. S. Gordon and L. A. and J. A. Pople, J. Am. Chem. Soc., 103, 2945 (1981).

<sup>&</sup>lt;sup>24</sup> A. G. Brook et al., J. Am. Chem. Soc., **103**, 2945 (1961).


$$(CH_3)_3Si$$
  $OSi(CH_3)_3$   $Si=C$   $(CH_3)_3Si$   $OSi(CH_3)_3$   $OSi(CH_3)$ 

Similarly, tetramesityldisilene, a compound containing a silicon-silicon double bond, is a solid stable at room temperature.<sup>25</sup> The latter material is formed by the ultraviolet photolysis of 2,2-bis(2,4,6-trimethylphenyl)hexamethyltrisilane and undergoes addition reactions across the Si=Si double bond analogous to those of olefins:

The nonexistence of molecular  $SiO_2$  under ordinary conditions is due to the fact that  $SiO_2$  readily polymerizes to form solid silica, in which each silicon atom is  $\sigma$ -bonded to four oxygen atoms. Carbon dioxide undergoes no analogous polymerization, probably because four oxygen atoms would be crowded if bonded to a single carbon atom.

Although trimethylamine has a pyramidal conformation (with a C-N-C bond angle of 110.9°), trisilylamine, (SiH<sub>3</sub>)<sub>3</sub>N, has a planar conformation for the

Si<sub>2</sub>N skeleton (with an Si—N—Si bond angle of 120°). This planarity has often been attributed to  $p\pi \to d\pi$  bonding, in which the nitrogen lone-pair orbital expands onto the silicon atoms because of the overlap of the nitrogen 2p orbital (perpendicular to the Si<sub>3</sub>N plane) with empty 3d orbitals of the silicon atoms.



This type of  $\pi$  bonding, or delocalization of the nitrogen lone pair, would necessarily be much reduced in a pyramidal conformation, because then the nitrogen 2p and silicon 3d orbitals would not be appropriately oriented for good overlap. Indeed, theoretical calculations show that there is a small but significant amount of  $p\pi \to d\pi$  bonding in trisilylamine.<sup>26</sup> However, it is not clear whether this  $\pi$  bonding is primarily responsible for the planarity of the molecule. It has been argued that the planarity is caused by electrostatic repulsion between SiH<sub>3</sub> groups. The calculations indicate, as one might expect from the electronegativities, that the Si-N bond is much more polar than the C-N bond. The calculated carbon atom charge in (CH<sub>3</sub>)<sub>3</sub>N is +0.23, and the calculated silicon atom charge in  $(SiH_3)_3N$  is +0.80.

## SIMPLE HÜCKEL THEORY

One of the best known and most important applications of simple MO theory is the study of  $\pi$  bonding in the cyclic aromatic hydrocarbons,  $C_nH_n$ , as originally carried out by Hückel.<sup>27</sup> Because aromatic hydrocarbons are planar, one can rigorously separate the MOs into  $\sigma$  MOs and  $\pi$  MOs. In the simple Hückel theory, one considers only the  $\pi$  MOs derived from the n orbitals of  $p\pi$  symmetry and makes the approximations that  $all S_{ij} = 0$  and that  $H_{ij} = 0$  except when the *i*th and *j*th  $p\pi$  orbitals are on adjacent atoms. Thus the general form of the secular determinant for a cyclic hydrocarbon,  $C_nH_n$ , is


$$\begin{vmatrix} H_{11} - E & H_{21} & 0 & \dots & H_{n1} \\ H_{12} & H_{22} - E & H_{32} & \dots & 0 \\ 0 & H_{23} & H_{33} - E & \dots & 0 \\ \vdots & \vdots & \vdots & \vdots & \vdots \\ H_{1n} & 0 & 0 & \dots & H_{nn} - E \end{vmatrix} = 0$$

<sup>&</sup>lt;sup>26</sup> L. Noodleman and N. L. Paddock, *Inorg. Chem.*. **18**, 354 (1979).

L. Noodleman and N. L. Paddock, *Inorg. Chem.*, **18**, 354 (1979).

E. Hückel, Z. *Physik*, **70**, 204 (1931); **76**, 628 (1932); *Z. Elektrochem.*, **43**, 752 (1937).

To illustrate the calculational methods, we shall apply the simple Hückel theory to the hypothetical square planar cyclobutadiene,  $C_4H_4$ . The p orbitals perpendicular to the plane of the molecule can be numbered as follows:



We write  $\psi = c_1\phi_1 + c_2\phi_2 + c_3\phi_3 + c_4\phi_4$ . We again make the substitutions  $H_{ii} = \alpha$  and, when the *i*th and *j*th orbitals are adjacent,  $H_{ij} = \beta$ . The secular determinant for the  $\pi$  orbitals of  $C_4H_4$  then becomes

$$\begin{vmatrix} \alpha - E & \beta & 0 & \beta \\ \beta & \alpha - E & \beta & 0 \\ 0 & \beta & \alpha - E & \beta \\ \beta & 0 & \beta & \alpha - E \end{vmatrix} = 0$$

For simplification, we divide through by  $\beta$  and replace  $(\alpha - E)/\beta$  by x.

$$\begin{vmatrix} x & 1 & 0 & 1 \\ 1 & x & 1 & 0 \\ 0 & 1 & x & 1 \\ 1 & 0 & 1 & x \end{vmatrix} = 0$$

This equation is equivalent to  $x^2(x^2 - 4) = 0$ , whose roots are -2, 0, 0, and +2. Hence there are two nonbonding MOs of energy  $\alpha$ , a bonding MO of energy  $\alpha + 2\beta$ , and an antibonding MO of energy  $\alpha - 2\beta$ .

When similar calculations are carried out for other  $C_nH_n$  molecules, it becomes apparent that the planar  $C_nH_n$   $\pi$  energy level diagram always has a lying at higher energies and, when n is an even number, a strongly antibonding nondegenerate level. The energy level diagrams for n=3,4,5,6,7, and 8, are "center of gravity" of the levels are filled. Thus the species  $C_3H_3^+$  (2  $\pi$  electrons), electrons) are stable species. Hückel long ago pointed out that cyclic coplanar and possess relative electronic stability. That is, aromaticity is associated with n of  $C_nH_n$ . This important relation is now known as the 4n+2 rule or the Hückel criterion of aromaticity.

In the case of  $C_4H_4$ , we would predict the square planar molecule to have a triplet ground state, with only two bonding  $\pi$  electrons, corresponding to an average  $\pi$  bond order of  $\frac{1}{4}$ . Cyclobutadiene has been observed only at very low

$$\alpha - 2\beta \qquad \qquad \alpha + (2\cos\frac{4\pi}{3})\beta$$

$$-\bigcirc \qquad \alpha + (2\cos\frac{4\pi}{3})\beta$$

$$-\bigcirc \qquad \alpha + (2\cos\frac{2\pi}{3})\beta$$

$$-\bigcirc \qquad \alpha + 2\beta \qquad \qquad \alpha + 2\beta$$

$$C_3H_3 \qquad C_4H_4 \qquad C_5H_5$$

$$-\bigcirc \qquad \alpha - 2\beta \qquad \qquad -\alpha - 2\beta$$

$$-\bigcirc \qquad \alpha - \beta \qquad \qquad -\alpha - 2\beta$$

$$-\bigcirc \qquad \alpha - \beta \qquad \qquad -\alpha - 2\beta$$

$$-\bigcirc \qquad \alpha - \beta \qquad \qquad -\alpha - 2\beta$$

$$-\bigcirc \qquad \alpha - \beta \qquad \qquad -\alpha - 2\beta$$

$$-\bigcirc \qquad \alpha - \beta \qquad \qquad -\alpha - 2\beta$$

$$-\bigcirc \qquad \alpha - \beta \qquad \qquad -\alpha - 2\beta$$

$$-\bigcirc \qquad \alpha - \beta \qquad \qquad -\alpha - \beta$$

Figure 4.23 MO energy level diagrams for planar cyclic  $C_nH_n$  molecules; n = 3, 4, 5, 6, 7, and 8.

temperatures or as an unstable transient species; however, both experimental and theoretical evidence indicate that it has a rectangular configuration, with two more-or-less localized double bonds:<sup>28</sup>

This distortion of the molecule from the square configuration causes the doubly degenerate level to split, and stabilization occurs by having the two unpaired electrons pair up in the lower of the split levels. However, the square form of  $C_4H_4$  can be stabilized in the form of complexes with transition metals, as in  $C_4H_4Fe(CO)_3$ . (See Chap. 16.) Cyclooctatetraene,  $C_8H_8$ , would also be expected to be a triplet molecule if it were planar with all the C-C bonds equivalent. However, it is in fact a conjugated but nonplanar tetraolefin. It can readily be reduced to the planar aromatic  $C_8H_8^{2-}$  ion, which forms a "sandwich" complex with uranium(IV):  $C_8H_8UC_8H_8$ .

<sup>&</sup>lt;sup>28</sup> S. Masamune, F. A. Souto-Bachiller, T. Machiguchi, and J. E. Bertie, J. Am. Chem. Soc., 100, 4889 (1978).

<sup>&</sup>lt;sup>29</sup> A. Streitwieser, Jr., and U. Muller-Westerhoff, J. Am. Chem. Soc., 90, 7363 (1968).

It is interesting to apply simple Hückel theory to inorganic systems. The molecule  $P_4$  contains just as many valence electrons as cyclobutadiene,  $C_4H_4$ , and if one ignores the phosphorus lone pairs just as one ignores the C—H bonds in simple Hückel theory, one can discuss the instability of the hypothetical square planar structure of  $P_4$  just as one does for  $C_4H_4$ . If  $P_4$  were analogous to  $C_4H_4$ , it would have a rectangular configuration, with two localized double bonds:

Instead  $P_4$  exists in a tetrahedral configuration, with a total of six equivalent P-P bonds. Apparently these six  $\sigma$  bonds are more stable than the combination of four  $\sigma$  bonds and two  $\pi$  bonds of the rectangular configuration. Perhaps eventually somebody will stabilize square planar  $P_4$  in the form of a transition-metal complex, just as square planar  $C_4H_4$  has been stabilized.

A large number of cyclic sulfur-nitrogen species are known. Many of these sulfur-nitrogen ring systems, including  $S_4N_4$ ,  $S_4N_4H_4$ ,  $S_7NH$ , and  $S_3N_3Cl_3$ , are nonplanar, but at least four species are known which are planar<sup>30</sup>:  $S_2N_2$ ,  $S_3N_3^-$ ,  $S_4N_3^+$ , and  $S_5N_5^+$ . The species  $S_2N_2$  and  $S_3N_3^-$  have square and hexagonal geometries, respectively, with alternating sulfur and nitrogen atoms in the rings. The structures of the cations  $S_4N_3^+$  and  $S_5N_5^+$  are as follows:

Each of the planar species is consistent with the 4n + 2 rule if one assumes that each ring atom is  $\sigma$ -bonded to its neighboring atoms and that it possesses one  $\sigma$  nonbonding electron pair.<sup>31</sup> All the remaining valence electrons are assumed to occupy the  $\pi$  orbitals. On this basis we calculate that the species  $S_2N_2$ ,  $S_3N_3$ ,  $S_4N_3$ , and  $S_5N_5$  have 6, 10, 10, and 14  $\pi$  electrons, respectively. It is remarkable that the  $S_4N_3$  cation "obeys" the 4n + 2 rule even though there are two adjacent sulfur atoms in the ring. Apparently the overlap of the  $\pi$  orbitals on these adjacent sulfur atoms is comparable to that on adjacent sulfur and nitrogen atoms. In fact, it appears that it is possible to insert a group which provides no further  $\pi$  electrons into a Hückel ring without destroying the planarity of the

<sup>31</sup> A. J. Banister, Nature (London) Phys. Sci., 237, 92 (1972); W. L. Jolly, Adv. Chem. Ser., 110, 92

(1972).

<sup>&</sup>lt;sup>30</sup> J. Bojes, T. Chivers, W. G. Laidlaw, and M. Trsic, *J. Am. Chem. Soc.*, **101**, 4517 (1979); D. A. Johnson, G. D. Blyholder, and A. W. Cordes, *Inorg. Chem.*, **4**, 1790 (1965); A. J. Banister and H. G. Clark, *J. Chem. Soc. Dalton Trans*. 2661 (1972).

system: Thus the insertion of Cl-\$\frac{+}{2}\$ into \$S\_2N\_2\$ gives \$S\_3N\_2\$Cl+, which contains a planar five-membered ring32: little son is a supredistribution but beigunoo hyperconjugation. The lowest orbitals, derived from the @ prand N=F a


## The data in Table 4.4 permit us to compare t

In Chap. 3, the phenomenon known as hyperconjugation was alluded to in a discussion of the bonding in molecules such as ONF<sub>3</sub>. Hyperconjugation may be defined generally as the interaction within a molecule of a  $\pi$  system with a  $\sigma$ system. Consider the interaction of nonbonding  $p\pi$  orbitals on the oxygen atom of ONF3 with the bonding and antibonding MOs of the N-F bonds.33 These hyperconjugative interactions are illustrated in Fig. 4.24, and an MO energy level diagram showing the effects of these interactions is shown in Fig. 4.25. The N-F $\sigma^*$  levels are raised and the N-F $\sigma$  levels are lowered as a consequence of interactions with the O  $p\pi$  orbitals, but there is little net change in the energy of the

<sup>32</sup> A. Zalkin, T. E. Hopkins, and D. H. Templeton, *Inorg. Chem.*, 5, 1767 (1966).

33 C. J. Eyermann, W. L. Jolly, S. A. Kinkead, J. M. Shreeve, and S. F. Xiang, J. Fluorine Chem. P - F bonds. In the case of NF., because of the smallness of the pitrosen s(881)

ter strengthens and shortens the P - F bonds. It is also probable that, because of



Oxygen  $p\pi$  orbital and N-F σ\* orbital.

Oxygen  $p\pi$  orbital and  $N-F\sigma$  orbital.

Figure 4.24 Schematic drawing showing the steric relation of an oxygen  $p\pi$  orbital with  $\sigma$  and  $\sigma^*$ N- F orbitals in ONF<sub>3</sub>.




Figure 4.25 Energy level diagram illustrating hyperconjugation in ONF3.

O  $p\pi$  orbitals, so that the latter orbitals remain essentially nonbonding as far as their energy is concerned. However, only the lower four energy levels are occupied, and consequently there is a net stabilization of the system by the hyperconjugation. The lowest orbitals, derived from the O  $p\pi$  and N-F  $\sigma$  orbitals, acquire considerable N-O  $\pi$ -bonding character and lose some of their N-F  $\sigma$ -bonding character. The oxygen lone-pair orbitals become quite delocalized; considerable nonbonding electron density shifts from the oxygen atom to the nitrogen and fluorine atoms. Thus qualitative MO theory allows us to rationalize the shortening of the N-O bond and the lengthening of the N-F bonds in ONF<sub>3</sub>.

The data in Table 4.4 permit us to compare the changes in the structural parameters on going from NF<sub>3</sub> to ONF<sub>3</sub><sup>34</sup> with those on going from PF<sub>3</sub> to OPF<sub>3</sub>.35 It is remarkable that the changes in the P-F bond length and the F—P—F bond angle are in opposite directions from the changes in the N—F bond length and the F-N-F bond angle. The data suggest that, on going from PF<sub>3</sub> to OPF<sub>3</sub>, the effects of rehybridization and an increase in phosphorus 3d orbital participation dominate, whereas, on going from NF<sub>3</sub> to ONF<sub>3</sub>, the effects of hyperconjugation in ONF3 dominate. In PF3, the F-P-F bond angle is rather small, corresponding to considerable p character in the phosphorus bonding orbitals. In OPF<sub>3</sub> the bond angle approaches the tetrahedral value, corresponding to an increase in the s character of the  $\sigma$ -bonding orbitals of the phosphorus (an approach toward sp³ hybridization).36 This increase in s character strengthens and shortens the P—F bonds. It is also probable that, because of the greater positive charge on the phosphorus atom in OPF<sub>3</sub>, the phosphorus 3d orbitals play a significant part in the P-F  $\sigma$  bonding and thus strengthen the P—F bonds. In the case of NF<sub>3</sub>, because of the smallness of the nitrogen atom, there is considerable repulsion between the valence electrons and the nitrogen bonding orbitals have much more s character than the phosphorus bonding orbitals in PF<sub>3</sub>. Hence there is much less rehybridization on going from NF<sub>3</sub> to ONF<sub>3</sub> than on going from PF<sub>3</sub> to OPF<sub>3</sub>, and hyperconjugation in ONF<sub>3</sub> is probably mainly responsible for the changes on going from NF<sub>3</sub> to ONF<sub>3</sub>.

Table 4.4 Structural parameters of MF<sub>3</sub> and OMF<sub>3</sub> molecules

Molecule	$r_{\mathrm{M-F}}$ , Å	∠F—M—F, degree
NF <sub>3</sub>	1.371	102.2
ONF <sub>3</sub>	1.432	100.5
PF <sub>3</sub>	1.570	97.8
OPF <sub>3</sub>	1.524	101.3

<sup>&</sup>lt;sup>34</sup> V. Plato, W. D. Hartford, and K. Hedberg, J. Chem. Phys., 53, 3488 (1970).

<sup>35</sup> T. Moritani, K. Kuchitsu, and Y. Morino, *Inorg. Chem.*, 10, 344 (1971).

<sup>&</sup>lt;sup>36</sup> A. Serafini, J.-F. Labarre, A. Veillard, and G. Vinot, *Chem. Commun.*, 996 (1971). Also see H. Wallmeier and W. Kutzelnigg, *J. Am. Chem. Soc.*, **101**, 2804 (1979).

We have just considered the hyperconjugative interaction of a filled  $\pi$  orbital with a  $\sigma$  orbital. Another type of hyperconjugation involves the interaction of an empty  $\pi$  orbital with a  $\sigma$  orbital. This is exemplified by the  $\sigma \to \pi^*$  delocalization in borane carbonyl:

The planar B(CH<sub>3</sub>)<sub>3</sub> molecule is another example:

$$H_3C$$
 $B-CH_3 \longleftrightarrow H_3C$ 
 $H_3C$ 
 $H_3C$ 
 $H_4$ 
 $H_3C$ 
 $H_4$ 
 $H_$ 

Indeed such hyperconjugation of methyl groups is probably responsible for the fact that the methyl group generally acts as a better electron donor than does a hydrogen atom.

The existence of hyperconjugation shows that the distinction between  $\sigma$  and  $\pi$  bonding is rather fuzzy in many molecules. The distinction is clean-cut and unambiguous only in the case of molecules in which all the atoms are coplanar, such as benzene, ethylene, formaldehyde, and water.

#### CALCULATIONS

### Extended Hückel Theory

The simple Hückel theory is quite restricted in its applications. It only considers  $\pi$  MOs derived from  $p\pi$  atomic orbitals of planar systems, and the values of the parameters  $\alpha$  and  $\beta$  are usually determined empirically by fitting theoretical calculations to observed data. Because the parameters required to fit one property often differ from those required to fit another, the predictive value of the method is rather low

Hückel theory was widely broadened with the development of extended Hückel theory by Hoffmann.<sup>37</sup> In this method, s, p, and d orbitals can be considered, all overlap integrals are evaluated, and definite procedures are followed for the evaluation of coulomb integrals and resonance integrals.

For the "basis set" of approximate atomic orbital wave functions, Slater<sup>38</sup> functions are used

$$\phi = Ar^{n-1}e^{-\zeta r}Y_{lm}(\theta,\phi)$$

<sup>38</sup> J. C. Slater, *Phys. Rev.*, **36**, 57 (1930).

Quantum Chemistry," pp. 97–156, Holt, Rinehart and Winston, New York, 1972.

where A is a normalization constant, r is the electron-nucleus distance in units of the Bohr radius of the hydrogen atom (0.529 Å),  $\zeta = (Z - S)/n$  (the effective nuclear charge<sup>39</sup> divided by the principal quantum number), and  $Y_{lm}(\theta, \phi)$  is a spherical harmonic introduced to give angular dependence to the function when l > 0. Values of  $\zeta$  can be evaluated using the simple Slater recipe for the shielding constants outlined in Chap. 1, or theoretically calculated values (such as those

Table 4.5 Valence state ionization potentials calculated from self-consistent field atomic orbital energy parameters†

Atom	Orbital	VSIP, eV	Atom	Orbital	VSIP, eV
Hallow	18	13,600	Ti	3 <i>d</i>	11.976
Li	28	5.340	dos vileranau	4 <i>s</i>	6.006
Be	2s	8.412	V	3 <i>d</i> 4 <i>s</i>	13.856 6.274
B one inc	2s 2p	13.455 8.428	Cr	3 <i>d</i>	15.473 6.258
C	2s 2p	19.193 11.787	Mn	3 <i>d</i>	17.386
N	2s 2p	25.710 15.437	Fe Table	4s 3d	6.746 17.601
0	2s 2p	33.844	Co	4 <i>s</i> 3 <i>d</i>	7.026 18.375
F	28	17.186 42.773	is at the sma	4s	7.274
Na	$\frac{2p}{3s}$	19.856 4.953	Ni	3 <i>d</i> 4 <i>s</i>	19.227 7.514
Mg	at 3s	6.883	Cu	3 <i>d</i> 4 <i>s</i>	20.138 7.746
Al	$\frac{3s}{3p}$	10.703 5.717	Zn	3 <i>d</i>	21.288 7.955
is of the is	3s 3p	14.686 8.081	Ga	4s 4s 4s	11.546
P	3s 3p	18.943 10.654	Ge	4 <i>p</i> 4 <i>s</i>	15.056
S Landard	$\frac{3s}{3p}$	23.926 11.897	As Coulo As	thi densvo lie	7.815 18.657
c	3s 3p	29.188 13.777	Se Se	4s present	10.056 22.774
Sc	3 <i>d</i> 4 <i>s</i>	9.346 5.715	Br	4p 4s 4p	10.956 27.006 12.431

<sup>†</sup> Data of E. Clementi, tabulated by L. C. Cusachs and J. H. Corrington in "Sigma Molecular Orbital Theory." O. Sinanoglu and K. B. Wiberg, eds., chap. VI-4, Yale University Press, New Haven, 1970.

<sup>&</sup>lt;sup>39</sup> In this case, S represents the screening constant, not the overlap integral.

given by Clementi and Raimondi<sup>40</sup> or Cusachs and Corrington<sup>41</sup>) can be used. The diagonal  $H_{ii}$  values (coulomb integrals) are chosen as valence-state ionization potentials (VSIPs), which can be obtained from various tabulations.<sup>42</sup> The VSIP values of Clementi are given in Table 4.5. The off-diagonal  $H_{ij}$  values (resonance integrals) are usually approximated by the following relation, first discussed by Mulliken. 43 and parameterized by Wolfsberg and Helmholtz44:

$$H_{ij} = 1.75 \left(\frac{H_{ii} + H_{jj}}{2}\right) S_{ij}$$
 (4.14)

The calculations are carried out using a computer program. The input data include the number of filled MOs, the number of half-filled MOs (if any), the cartesian coordinates of the atoms, and specification of the basis set, i.e., the atomic orbitals to be used. To illustrate the use of the method, we shall give the results of a calculation for the phosphine molecule, PH3, which has a P-H bond length of 1.4206 Å and an H-P-H bond angle of 93.8°.45 The x, y, z coordinates were chosen to make the threefold axis coincide with the z axis: P, 0.0, 0.0, 0.0; H, 1.19773, 0.0, -0.76390; H, -0.59887, 1.03727, -0.76390; H,-0.59887, -1.03727, -0.76390. The basis set was composed of the 3s orbital of phosphorus (atomic orbital 1), the phosphorus 3p orbitals (atomic orbitals 2, 3, and 4), and the hydrogen 1s orbitals (atomic orbitals 5, 6, and 7).

A matrix of the overlap integrals,  $S_{ii}$ , is given in Table 4.6. The diagonal

Table 4.6 Extended Hückel study of phosphine. Matrix of the atomic orbital (AO) overlap integrals,  $S_{ij}$ 

	3 7		АО		MO energies		
1	2	3	4	-Value 5	6	7**	
1.0000	0.0000	0.0000	0.0000	0.4118	0.4118	0.4118	
0.0000	1.0000	0.0000	0.0000	-0.2809	-0.2809	-0.2809	
0.0000	0.0000	1.0000	0.0000	0.4404	-0.2202	-0.2202	
0.0000	0.0000	0.0000	1.0000	0.0000	0.3814	-0.3814	
0.4118	-0.2809	0.4404	0.0000	1.0000	0.1185	0.1185	
0.4118	-0.2809	-0.2202	0.3814	0.1185	1.0000	0.1185	
0.4118	-0.2809	-0.2202	-0.3814	0.1185	0.1185	1.0000	

<sup>&</sup>lt;sup>40</sup> E. Clementi and D. L. Raimondi, J. Chem. Phys., 38, 2686 (1963).

<sup>&</sup>lt;sup>41</sup> L. C. Cusachs and J. H. Corrington, in "Sigma Molecular Orbital Theory," O. Sinanoglu and

K. B. Wiberg, eds., chap. VI-4, Yale University Press, New Haven, 1970. <sup>42</sup> Cusachs and Corrington tabulate VSIPs from various sources; also see G. Pilcher and H. A.

Skinner, J. Inorg. Nucl. Chem., 24, 937 (1962), and J. Hinze and H. H. Jaffe, J. Am. Chem. Soc., 84, 540 (1962).

<sup>&</sup>lt;sup>43</sup> R. S. Mulliken, J. Phys. Chem., **56**, 295 (1952).

<sup>&</sup>lt;sup>44</sup> M. Wolfsberg and L. Helmholtz, J. Chem. Phys., 20, 837 (1952).

<sup>45</sup> C. A. Burrus, Jr., A. Jache, and W. Gordy, Phys. Rev., 95, 700 (1954).

Table 4.7 Extended Hückel study of phosphine. Matrix of the coulomb and resonance integrals,  $H_{ii}$ 

AO	minery sizes, which can be of OA. Them various label and the											
	ist dilectese	2	3	4	5	6	7					
1	-18.9430	0.0000	0.0000	0.0000	-11.7270	-11.7269	-11.7269					
2	0.0000	-10.6540	0.0000	0.0000	5.9616	5.9615	5.9615					
3	0.0000	0.0000	-10.6540	0.0000	-9.3473	4.6736	4.6736					
4	0.0000	0.0000	0.0000	-10.6540	0.0000	-8.0950	8.0950					
5	-11.7270	5.9616	-9.3473	0.0000	-13.6000	-2.8193	-2.8193					
6	-11.7269	5.9615	4.6736	-8.0950	-2.8193	-13.6000	-2.8192					
7	-11.7269	5.9615	4.6736	8.0950	-2.8193	-2.8192	-13.6000					

values of unity simply indicate that normalized wave functions were used. The off-diagonal values were obtained from integrals<sup>46</sup> of the type

$$S_{ij} = \int \phi_i \phi_j \, d\tau$$

The zeros correspond to orbitals *i* and *j* which are orthogonal. Notice the small but finite overlap between the orbitals of the hydrogen atoms, which we ordinarily consider to be nonbonded.

A matrix of the coulomb and resonance integrals is given in Table 4.7. Notice that the diagonal elements are simply VSIPs and that the off-diagonal elements are the  $H_{ij}$  values calculated by Eq. 4.14.

Table 4.8 lists the MO energies, and Table 4.9 is a matrix of the atomic orbital coefficients,  $c_{ij}$ . From the magnitudes of the coefficients, one sees that the lowest-energy MO corresponds to a bonding MO formed by overlap of the phosphorus 3s orbital with the hydrogen 1s orbitals. The next two MOs are

Table 4.8 Extended Hückel study of phosphine.

MO energies

МО	Energy, eV
1 160 813	-21.83
2	-15.07
3	-15.07
4	-11.97
5	1.82
6	1.82
7	19.72

<sup>&</sup>lt;sup>46</sup> Formulas for calculating overlap integrals, and extensive tables of values, are given by R. S. Mulliken, C. A. Rieke, D. Orloff, and H. Orloff, *J. Chem. Phys.*, 17, 1248 (1949).

Table 4.9 Extended Hückel study of phosphine. Matrix of the AO coefficients,  $c_{ij}$ 

	a atom ch	regernyd by	osphorus at	MO	inat the o	1 Fablos 1 1	HEISTON.
AO	1	2	3	4 10/11/00/25		6	7011
Long	0.6562	0.0000	0.0000	-0.4122	0.0000	0.0000	1.1979
2	0.0107	0.0000	0.0000	-0.8373	0.0000	0.0000	-0.8836
3	0.0000	0.5007	0.0038	0.0000	0.0000	-1.1145	0.0000
4	0.0000	0.0038	-0.5007	0.0000	1.1145	0.0000	0.0000
5110	0.2313	0.5431	0.0041	0.1410	0.0000	0.9132	-0.7778
6	0.2313	-0.2680	-0.4723	0.1410	-0.7909	-0.4566	-0.7778
7	0.2313	-0.2751	0.4683	0.1410	0.7909	-0.4566	-0.7778

degenerate and correspond to bonds formed by overlap of the phosphorus  $3p_x$  and  $3p_y$  orbitals with the hydrogen 1s orbitals. The fourth, highest occupied, MO is principally located on the phosphorus atom and is essentially a nonbonding (lone-pair) orbital comprising the phosphorus 3s and  $3p_z$  orbitals.

Table 4.10 is a listing of the net and overlap electron populations of the atomic orbitals. Each element of the matrix is the sum of the  $c_ic_j$  products for the four occupied MOs, multiplied by 2 times the overlap integral:

$$P_{ij} = 2S_{ij} \sum_{k=1}^{\text{occ}} c_i^k c_j^k$$

The diagonal values  $P_{ii}$  may be loosely interpreted as the "net" or "unshared" electron populations of the atomic orbitals. Each off-diagonal value  $P_{ij}$  may be interpreted as one-half of the electron population in the overlap region of the ith and jth atomic orbitals. In the process of assigning electrons to atomic orbitals, the overlap populations are split equally between the two atoms involved. Thus the sum of the numbers in any column or row is taken to be the total electron population of the corresponding atomic orbital. By adding up the electron populations of all the atomic orbitals of an atom, one obtains the total valence electron population of the atom, from which one can readily calculate the atomic

Table 4.10 Extended Hückel study of phosphine. Net and overlap orbital electronic populations

an emerge	or these pr	i ajabaugi	AO	details of m	merely in details of m		
1	2	3	4	5	6	7	
1.2010	0.0000	0.0000	0.0000	0.0771	0.0771	0.0771	
0.0000	1.4022	0.0000	0.0000	0.0649	0.0649	0.0649	
0.0000	0.0000	0.5014	0.0000	0.2395	0.0599	0.0599	
0.0000	0.0000	0.0000	0.5014	0.0000	0.1797	0.1797	
0.0771	0.0649	0.2395	0.0000	0.7365	-0.0176	-0.0176	
0.0771	0.0649	0.0599	0.1797	-0.0176	0.7365	-0.0176	
0.0771	0.0649	0.0599	0.1797	-0.0176	-0.0176	0.7365	

charge. This procedure for calculating orbital electron populations and atomic charges is called a "Mulliken population analysis." The reader can verify, from the data in Table 4.10, that the calculated phosphorus and hydrogen atom charges are +0.249 and -0.083, respectively.

Extended Hückel theory is useful for assessing the nature and relative importance of  $\sigma$  and  $\pi$  orbitals and for predicting the ground-state conformations of molecules. (Conformational prediction is accomplished by studying the total molecular energy as a function of systematic structural changes.) Atomic charges obtained from extended Hückel theory often appear to be too large (i.e., the ionic character of bonds appears to be exaggerated), and spectral energy predictions are usually quite poor.

### Self-Consistent Field Methods

You may have noticed that, in the simple Hückel and extended Hückel methods, the hamiltonian is never used in an explicit form. In self-consistent field (SCF) methods, the full hamiltonian is actually calculated. The hamiltonian consists of the kinetic energy operator for an electron, the potential energy of attraction between an electron and all atomic cores of the molecule, and the potential energy of repulsion of the electrons. The algebraic expression for the hamiltonian involves the coefficients of the atomic orbitals, which of course are among the important quantities to be calculated. Hence the equations must be solved iteratively. A rough estimate is made of the coefficients (say, by a Hückel calculation), and then one solves the secular equations to obtain improved values of the coefficients. The cycle of the calculation is repeated until the coefficients do not change significantly, i.e., until the input and output coefficients are self-consistent.

In the "complete neglect of differential overlap" (CNDO) method, <sup>48</sup> various approximations are made to simplify the SCF calculations. The most important approximation is the neglect of all electron repulsion integrals involving the overlap distributions of different atomic orbitals,  $\phi_i$  and  $\phi_j$ . In addition, the corresponding overlap integrals  $S_{ij}$  are neglected in the normalization of the MOs. Some other integrals, instead of being evaluated rigorously, are chosen in a semiempirical manner to fit experimental data.

A version of CNDO known as CNDO/2 is most commonly used. There are various computer programs for making CNDO/2 calculations which differ merely in details of parameterization. The input data for these programs are very similar to those used in the extended Hückel program. We shall illustrate the use of the method by presenting the results of a calculation<sup>49</sup> for the molecule CIF, in

<sup>&</sup>lt;sup>47</sup> R. S. Mulliken, J. Chem. Phys., 23, 1833, 1841 (1955).

<sup>&</sup>lt;sup>48</sup> J. A. Pople and D. L. Beveridge, "Approximate Molecular Orbital Theory," McGraw-Hill, New York, 1970.

<sup>&</sup>lt;sup>49</sup> Using a CNDO program as modified by P. M. A. Sherwood, *J. Chem. Soc. Faraday Trans.* 2,72, 1791 (1976).

Table 4.11 CNDO/2 study of chlorine fluoride. MO energies

МО	Symmetry label	Calculated energy, eV	Experimental adiabatic ionization potential, eV				
1	5σ	-44.77					
2	6σ	-29.50					
3, 4	$2\pi$	-21.92	16.39				
5	$7\sigma$	-19.95	17.80				
6, 7	$3\pi$ = - 0 5 5 5	-16.16	12.66				
8	000000	-0.17					
9, 10		5.32					
11, 12	88888	5.70					
13	88888	7.99					

which the basis set consisted of the following atomic orbitals, in order: chlorine 3s,  $3p_x$ ,  $3p_y$ ,  $3p_z$ ,  $3d_{z^2}$ ,  $3d_{xz}$ ,  $3d_{yz}$ ,  $3d_{x^2-y^2}$ ,  $3d_{xy}$ , and fluorine 2s,  $2p_x$ ,  $2p_y$ ,  $2p_z$ . The Cl-F bond distance was taken as 1.628 Å.50 In Table 4.11 are listed the calculated MO energy levels and experimental values of the ionization potentials from the three highest occupied MOs, as determined by ultraviolet photoelectron spectroscopy.<sup>51</sup> It is generally a fair approximation to assume, on the basis of Koopmans' theorem, 52 that an orbital ionization potential is equal to the negative of the orbital energy as obtained from a good SCF calculation. In the data we see the typical result of the use of CNDO/2 to calculate orbital energies: The calculated energy levels are in approximately the right order, but the calculated energies are too large. From the matrix of atomic orbital coefficients given in Table 4.12, we see that the  $3\pi$  level is antibonding and principally on the  $p\pi$ orbitals of the chlorine atom. Similarly we see that the  $2\pi$  level is bonding and located mainly on the  $p\pi$  orbitals of the fluorine atom. Together, the four orbitals which comprise the  $2\pi$  and  $3\pi$  levels are effectively the lone-pair  $p\pi$  orbitals on the Cl and F atoms. We see that the  $7\sigma$  level is bonding and comprised largely of the fluorine  $2p_z$  and chlorine  $3p_z$  orbitals, but with significant contributions from the chlorine 3s and  $3d_{z^2}$  orbitals. The combination of the  $5\sigma$  and  $6\sigma$  orbitals are essentially nonbonding orbitals on the chlorine 3s and fluorine 2s orbitals.

Table 4.13 shows the CNDO/2 density matrix for CIF. The diagonal elements of this matrix, when summed over the orbitals on a given atom, yield the valence electron population for that atom. The reader can verify that the calculated atomic charges in CIF are +0.152 for Cl and -0.152 for F.

In general, CNDO/2 calculations are useful for estimating charge distributions (including derived properties such as dipole moments) but are less successful

<sup>52</sup> T. Koopmans, *Physica*, 1, 104 (1934).

<sup>&</sup>lt;sup>50</sup> D. A. Gilbert, A. Roberts, and P. A. Griswold, *Phys. Rev.*, 76, 1723 (1949).

C. P. Anderson, G. Mamantov, W. E. Bull, F. A. Grimm, J. C. Carver, and T. A. Carlson, Chem. Phys. Lett., 12, 137 (1971); R. L. DeKock, B. R. Higginson, D. R. Lloyd, A. Breeze, D. W. J. Cruickshank, and D. R. Armstrong, Mol. Phys., 24, 1059 (1972).

Table 4.12 CNDO/2 study of chlorine monofluoride. Matrix of the AO coefficients,  $c_{ij}$ 

					9 9	いまる	МО						
AO	0 1 4	2	3	4	5	6	7	8	9	10	11	12	13
1	0.2448	-0.9325	0.0000	0.0000	-0.2231	0.0000	0.0000	0.1181	0.0000	0.0000	0.0000	0.0000	-0.0824
2	0.0000	0.0000	-0.2687	-0.1471	0.0000	-0.5274	0.7916	0.0000	-0.0000	0.0000	0.0207	0.0303	0.0000
3	0.0000	0.0000	0.1471	-0.2687	0.0000	-0.7916	-0.5274	0.0000	0.0000	0.0000	0.0303	-0.0207	0.0000
4	0.1782	0.0383	0.0000	0.0000	0.5327	0.0000	0.0000	0.8031	0.0000	0.0000	0.0000	0.0000	-0.1953
5	0.1401	0.0126	0.0000	0.0000	0.2195	0.0000	0.0000	-0.3919	0.0000	0.0000	0.0000	0.0000	-0.8823
6	0.0000	0.0000	-0.1349	-0.0739	0.0000	0.0485	-0.0728	0.0000	0.0000	0.0000	0.5548	0.8129	0.0000
7	0.0000	0.0000	0.0739	-0.1349	0.0000	0.0728	0.0485	0.0000	0.0000	0.0000	0.8129	-0.5548	0.0000
8	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	-0.9440	0.3298	0.0000	0.0000	0.0000
9	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	-0.3298	-0.9440	0.0000	0.0000	0.0000
10	0.9425	0.2389	0.0000	0.0000	-0.0924	0.0000	0.0000	-0.1152	0.0000	0.0000	0.0000	0.0000	0.1812
11	0.0000	0.0000	-0.8240	-0.4512	0.0000	0.1640	-0.2462	0.0000	0.0000	0.0000	-0.0976	-0.1430	0.0000
12	0.0000	0.0000	0.4512	-0.8240	0.0000	0.2462	0.1640	0.0000	0.0000	0.0000	-0.1430	0.0976	0.0000
13	0.0205	0.2678	0.0000	0.0000	-0.7809	0.0000	0.0000	0.4175	0.0000	0.0000	0.0000	0.0000	-0.3792

Table 4.13 CNDO/2 study of chlorine monofluoride. Density matrix

1	1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1												
AO	e la se	2	3	4	5	6	979	8	9	10	11.	12	13
1	1.9585	0.0000	0.0000	-0.2219	-0.0529	0.0000	0.0000	0.0000	0.0000	0.0571	0.0000	0.0000	-0.1611
2	0.0000	1.9973	0.0000	0.0000	0.0000	-0.0721	0.0000	0.0000	0.0000	0.0000	0.0127	0.0000	0.0000
3	0.0000	0.0000	1.9973	0.0000	0.0000	0.0000	-0.0722	0.0000	0.0000	0.0000	0.0000	0.0127	0.0000
4	-0.2219	0.0000	0.0000	0.6339	0.2848	0.0000	0.0000	0.0000	0.0000	0.2558	0.0000	0.0000	-0.8187
5 3	-0.0529	0.0000	0.0000	0.2848	0.1359	0.0000	0.0000	0.0000	0.0000	0.2294	0.0000	0.0000	-0.3419
6	0.0000	-0.0721	0.0000	0.0000	0.0000	0.0626	0.0000	0.0000	0.0000	0.0000	0.3407	0.0000	0.0000
7	0.0000	0.0000	-0.0722	0.0000	0.0000	0.0000	0.0626	0.0000	0.0000	0.0000	0.0000	0.3407	0.0000
8	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
9	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
10	0.0571	0.0000	0.0000	0.2558	0.2294	0.0000	0.0000	0.0000	0.0000	1.9078	0.0000	0.0000	0.2336
11	0.0000	0.0127	0.0000	0.0000	0.0000	0.3407	0.0000	0.0000	0.0000	0.0000	1.9401	0.0000	0.0000
12	0.0000	0.0000	0.0127	0.0000	0.0000	0.0000	0.3407	0.0000	0.0000	0.0000	0.0000	1.9401	0.0000
13	-0.1611	0.0000	0.0000	-0.8187	-0.3419	0.0000	0.0000	0.0000	0.0000	0.2336	0.0000	0.0000	1.3638

for predicting molecular energies and ionization potentials. It has been found that the method tends to overestimate the exent of  $\pi$  bonding in molecules.

Various offshoots of the CNDO method have been devised, in which different approximations have been made. For example, we have "partial neglect of differential overlap"53 (PNDO), "intermediate neglect of differential overlap"54 (INDO), "modified intermediate neglect of differential overlap"55 (MINDO), "neglect of diatomic differential overlap"56 (NDDO), and "modified neglect of diatomic overlap"57 (MNDO). Of these alternative methods, MINDO and MNDO appear to have been the most useful.58 The reader interested in these methods is referred to the original references or to the comparative discussion by Murrell and Harget.59

Two other SCF MO methods which have found considerable application in inorganic chemistry are the parameter-free MO methods of Fenske and his coworkers60 and the X-alpha scattered wave method of Slater.61 approach, in conjunction with the "transition state" method for accounting for relaxation energy, yields relatively accurate values for electronic transition energies.62 For an interesting application of the X-alpha method to sulfur tetrafluoride and for a comparison of the results with those from several other M0 studies, the reader is referred to a paper by Cowley, Lattman, and Walker.63

Finally we mention ab initio methods, in which no approximations (such as neglect of certain integrals) are made when the wave function is determined by SCF minimization of the total energy. These methods have risen in popularity in recent years because of the availability of high-speed digital computers and the development of sophisticated theoretical and computational methods. Some of them are easy to use because of the availability of appropriate computer programs, such as the STO-3G/Gaussian-70 program.<sup>64</sup> The main factor determin-

<sup>&</sup>lt;sup>53</sup> M. J. S. Dewar and G. Klopman, J. Am. Chem. Soc., 89, 3089 (1967).

<sup>&</sup>lt;sup>54</sup> R. N. Dixon, *Mol. Phys.*, **12**, 83 (1967); J. A. Pople, D. L. Beveridge, and P. A. Dobosh, *J. Chem.* Phys., 47, 2026 (1967).

<sup>55</sup> N. C. Baird and M. J. S. Dewar, J. Chem. Phys., 50, 1262 (1969).

<sup>&</sup>lt;sup>56</sup> J. A. Pople, D. P. Santry, and G. A. Segal, J. Chem. Phys., 43, S129 (1965).

<sup>&</sup>lt;sup>57</sup> M. J. S. Dewar and W. Thiel, J. Am. Chem. Soc., 99, 4899 (1977); M. J. S. Dewar, M. L. McKee, and H. S. Rzepa, J. Am. Chem. Soc., 100, 3607 (1978).

<sup>58</sup> M. J. S. Dewar, Chem. Brit., 11, 97 (1975); "Further Perspectives in Organic Chemistry," Ciba Symposium 53, p. 107, ASP, Amsterdam, 1978.

<sup>59</sup> J. N. Murrell and A. J. Harget, "Semi-empirical Self-Consistent-Field Molecular Orbital Theory of Molecules," Wiley-Interscience, New York, 1972.

<sup>60</sup> R. F. Fenske and D. D. Radtke, *Inorg. Chem.*, 7, 479 (1968); M. B. Hall and R. F. Fenske, *Inorg.* Chem., 11, 768 (1972).

<sup>61</sup> J. C. Slater and K. H. Johnson, Phys. Today, 34 (October 1974).

<sup>62</sup> J. C. Slater and K. H. Johnson, Phys. Rev., B5, 844 (1972); J. C. Slater, in "Quantum Theory of Molecules and Solids," vol. 4, p. 583, McGraw-Hill, New York, 1974.

<sup>63</sup> A. H. Cowley, M. Lattman, and M. L. Walker, J. Am. Chem. Soc., 101, 4074 (1979).

<sup>64</sup> W. J. Hehre, R. F. Stewart, and J. A. Pople, J. Chem. Phys., 51, 2657 (1969); W. J. Hehre, W.A. Lathan, R. Ditchfield, M. D. Newton, and J. A. Pople, Program No. 236, QCPE, Indiana University Bloomington, Ind. STO-3G stands for Slater-type orbital—approximated by a linear combination

ing the accuracy of an ab initio calculation is the size of the basis set used. The so-called minimum basis set includes one function (such as a Slater function) for each occupied atomic orbital in the free atoms of the compound. Thus for H<sub>2</sub>S, the minimum basis set consists of sulfur 1s, 2s, 3s, 2p, 3p and hydrogen 1s functions. A very popular basis set is the "double zeta" set, which includes two Slater functions for each occupied atomic orbital. Larger basis sets are called "extended basis" sets; these include functions for atomic orbitals higher than the occupied levels. Some two lowest energy bands in the photoelectron spectrum of F. correspondences

The speed and accuracy of various MO calculations, using the more popular semiempirical and minimum basis set ab initio methods, have been compared in two independent studies. 65 The interested reader is advised to consult these 4.14 Assuming the unlikelihood of ionic charges greater than ± 2, what charge, if papers.

\*4.15 Show that, if the overlap integral is not ignored, an antibonding orbital is destabilized more than

#### repulsion, such as in the F. molecule, and (b) explains why this repulsion is great 2MAJHOOP

- \*4.1 Explain the fact that (SiH<sub>3</sub>)<sub>3</sub>N is a much weaker base than (CH<sub>3</sub>)<sub>3</sub>N.
- 4.2 Calculate by simple MO theory whether the linear [H · · · H · · · H]+ or triangular

form of H<sub>3</sub><sup>+</sup> is the more stable.

\*4.3 Mulliken has shown that the overlap integral for two Slater-type  $2p\pi$  orbitals can be calculated using the following formula when the two bonded atoms are identical or have similar Slater  $\zeta$  values [i.e., similar  $(Z - S)/n^*$  values]:

$$S(2p\pi - 2p\pi) = e^{-p}(1 + p + \frac{2}{5}p^2 + \frac{1}{15}p^3)$$

where  $p = 0.946(\zeta_A + \zeta_B)r$ . The  $\zeta$  values are calculated by Slater's recipe, taking account of the formal charges of the atoms, and r is expressed in angstroms. Use this formula, together with simple Hückel theory, to calculate the  $\pi \to \pi^*$  transition energies of (a) ozone, O<sub>3</sub> (O—O distance 1.28 Å), and (b) the nitrite ion,  $NO_2^-$  (N—O distance 1.24 Å). The experimental values are 4.9 and 6.0 eV, respectively.

- 4.4 Construct a qualitative MO energy level diagram for the linear ion HF<sub>2</sub>-, involving only the hydrogen 1s orbital and the two fluorine hybrid orbitals that lie on the bonding axis.
- 4.5 For each of the following species, indicate the bond order and the number of unpaired electrons: NeO+, O<sub>2</sub>+, CN+, BN, SiF+, NO-, PCl, I<sub>2</sub>+, NeH+.
- 4.6 Why is  $\pi$  bonding generally weaker than  $\sigma$  bonding?
- 4.7 Propose a structure for the  $P_4^{2+}$  ion.
- \*4.8 Explain why the  $\pi \to \pi^*$  transition energy of N<sub>3</sub><sup>-</sup> is lower than that of CO<sub>2</sub>.
- 4.9 Predict the structures of Bi<sub>4</sub><sup>2-</sup>, Te<sub>4</sub><sup>2-</sup>, and S<sub>4</sub>N<sub>4</sub><sup>2+</sup>.
- \*4.10 If you have available an extended Hückel or CNDO/2 program and a suitable computer, use the program to calculate (a) a Walsh diagram for NH<sub>3</sub>, in which the MO energy levels are plotted for H\_N\_H bond angles from 90 to 120°, or (b) an energy-versus-bond distance plot for a diatomic molecule such as N2.

<sup>65</sup> T. A. Halgren, D. A. Kleier, J. H. Hall, L. D. Brown, and W. N. Lipscomb, J. Am. Chem. Soc., 0, 6505 (1070) 100, 6595 (1978); M. J. S. Dewar and G. P. Ford, J. Am. Chem. Soc., 101, 5558 (1979).

- \*4.11 Can you rationalize the fact that planar pseudoaromatic sulfur-nitrogen species (e.g.,  $S_4N_3^+$ ) are known, whereas analogous nitrogen-oxygen, phosphorus-oxygen, and phosphorus-sulfur species and unknown? laied donne orbifal anthe free atomy of the compound
- \*4.12 The electron density difference plot (showing the difference in density between the molecule and the hypothetical noninteracting atoms) for ethane shows a buildup of electron density in the C-C bonding region, whereas that for molecular fluorine shows a diminution of electron density in the F-F bonding region. Explain. Hint: Consider the electron distribution for a pair of fluorine atoms which are "prepared" for bonding, i.e., with one electron in each of the  $p_z$  orbitals.
- \*4.13 The two lowest-energy bands in the photoelectron spectrum of F<sub>2</sub> correspond to removal of electrons from the  $2p\pi^*$  and  $2p\pi_B$  MOs (consistent with Fig. 4.7a), whereas the lowest ionization potential of  $N_2$  corresponds to ionization of a  $\sigma$  MO (consistent with Fig. 4.7b). Explain the difference in terms of the effective nuclear charges and the 2s-2p energy separations.
- 4.14 Assuming the unlikelihood of ionic charges greater than ±2, what charge, if any, would you expect to find on the planar  $S_3N_3$  ring? How many  $\pi$  electrons would the species have?
- \*4.15 Show that, if the overlap integral is not ignored, an antibonding orbital is destabilized more than the corresponding bonding orbital is stabilized. Show how this result (a) explains lone-pair-lone-pairrepulsion, such as in the  $F_2$  molecule, and (b) explains why this repulsion is greater in  $F_2$  than in  $G_1$

sheld hi D Norman, and J A. Paple, Program No. 236, OCPE, Indiana University

"Had deligned D. A. Kleimi & Hall all & D. Brown and W. M. Papstoink. J. and Cheese Nov. M. 6595 (1978); M. J. S. Dewar and G. P. Ford, J. Am. Chem. Soc., 101, 5588 (1979).

# THE KINETICS AND MECHANISMS OF GAS-PHASE REACTIONS

It is not enough to know the structures and energetics of molecules. It is also important to know the rates at which they react with one another and to have an understanding of the mechanisms of their reactions. In this chapter we will study the kinetics and mechanisms of some relatively simple reactions between molecules in the gas phase, including some systems in which MO symmetry rules are important. The principles are applicable to all kinds of reactions, and even the mechanisms of the specific reactions discussed can be generalized to many other systems. In later chapters we will discuss the kinetics of more complicated reactions, including reactions in solutions.

Most of the exemplary reactions in this chapter are reactions of molecular hydrogen. These reactions were chosen for the following reasons. (1) The reactions have been thoroughly studied. (2) Hydrogen is a simple molecule, and therefore complicating side reactions are rare. (3) Hydrogen is by far the most abundant element in the universe, and there are probably more known compounds of hydrogen than of any other element. Therefore the reactions of

hydrogen and its compounds are important.

# REACTIONS OF HYDROGEN WITH HALOGENS

Molecular hydrogen is capable of reacting with many elements and compounds, but at room temperature most of these reactions are extremely slow. This seeming inertness is undoubtedly related to the high dissociation energy of the molecule,  $104.2 \text{ kcal mol}^{-1}$ . Obviously, when an  $H_2$  molecule reacts, the H-H bond must be broken. However, it is not necessary to supply the entire  $104 \text{ kcal mol}^{-1}$  to the reacting molecules as activation energy in order to obtain a reaction.

Usually, when an H2 molecule reacts with another molecule, at least one of the hydrogen atoms forms a bond to another atom at the same time that the H-H bond is broken. Thus the bond-breaking contribution to the activation energy's partly compensated by the bond-forming contribution.

For example, consider the reaction of hydrogen with bromine vapor:

$$H_2 + Br_2 \rightarrow 2HBr$$

The reaction rate is negligible in the absence of light (which promotes the reaction) unless the temperature is raised above 200°C. Kinetic studies<sup>1-3</sup> of the reaction have shown that the rate is given by the following expression:

$$\frac{d[HBr]}{dt} = \frac{k[H_2][Br_2]^{1/2}}{1 + k'[HBr]/[Br_2]}$$
(5.1)

where k and k' are constants at a given temperature. This rate law is consistent with the following chain mechanism:

 $H + Br_2 \xrightarrow{5} HBr + Br$ Reaction 1, in which radicals are produced, is the chain-initiating step, and reaction 2, in which radicals are consumed, is the chain-terminating step. Reactions 3 to 5 are called chain-propagating steps; the number of radicals is unchanged by these reactions. Note that the sum of reactions 3 and 5 corre sponds to the net reaction of H<sub>2</sub> and Br<sub>2</sub> to form two molecules of HBr. If a finite concentration of H and Br atoms is maintained, these steps can proceed as long as the supply of H2 and Br2 molecules lasts.

It is not difficult to show that the mechanism is consistent with the experimental rate law. For every molecule of HBr produced by reaction 5, another is produced by reaction 3. Therefore the overall rate of formation of HBr is equal to

$$\frac{d[HBr]}{dt} = 2k_s[H][Br_2]$$
If we assume that a large state of the second distance of

If we assume that a low, steady-state concentration of H atoms is achieved, then we may write

$$\frac{d[H]}{dt} = 0 = k_3[Br][H_2] - k_4[HBr][H] - k_5[H][Br_2]$$

<sup>3</sup> S. W. Benson, "Foundations of Chemical Kinetics," McGraw-Hill, New York, 1960.

M. Bodenstein and S. C. Lind, Z. Physik. Chem., 57, 168 (1907). <sup>2</sup> A. A. Frost and R. G. Pearson, "Kinetics and Mechanism: A Study of Homogeneous Chemical Reactions," 2d ed., pp. 236-241, Wiley, New York, 1961.

Solving for [H], we obtain

[H] = 
$$\frac{k_3[Br][H_2]}{k_5[Br_2] + k_4[HBr]}$$
 (5.3)

Substitution in Eq. 5.2 yields

$$\frac{d[HBr]}{dt} = \frac{2k_3k_5[H_2][Br_2][Br]}{k_5[Br_2] + k_4[HBr]}$$
(5.4)

In the steady state, the rates of reactions 1 and 2 are equal; i.e., the Br<sub>2</sub> molecules are in equilibrium with the Br atoms. We may write

$$\frac{[\mathrm{Br}]^2}{[\mathrm{Br}_2]} = \frac{k_1}{k_2}$$

$$[Br] = \left(\frac{k_1}{k_2}\right)^{1/2} [Br_2]^{1/2}$$

Substitution in Eq. 5.4, followed by rearrangement, gives

$$\frac{d[HBr]}{dt} = \frac{2k_3(k_1/k_2)^{1/2}[H_2][Br_2]^{1/2}}{1 + (k_4/k_5)[HBr]/[Br_2]}$$

This equation has the same form as Eq. 5.1; it can be seen that  $k' = k_4/k_5$  and k = 1 $2k_3(k_1/k_2)^{1/2}$ .

A rate constant may be expressed as  $Ae^{-E_a/RT}$ , and an equilibrium constant may be expressed as  $e^{\Delta S'/R}e^{-\Delta H'/RT}$ . Hence the last equation, in which k is represented as a function of the rate constant  $k_3$  and the equilibrium constant  $k_1/k_2$ , may be rewritten as follows:

$$Ae^{-E_a/RT} = 2A_3e^{-E_a(3)/RT}e^{\Delta S^2/2R}e^{-\Delta H^2/2RT}$$

where  $E_a$  is the activation energy of the overall reaction,  $E_a(3)$  is the activation energy of reaction 3, and  $\Delta H_1^{\circ}$  is the heat of reaction 1 (i.e., the dissociation energy of bromine). Hence and total and tot

$$E_a = E_a(3) + \frac{1}{2}\Delta H_1^{\circ}$$
 (5.5)

From studies of the  $H_2 + Br_2$  reaction as a function of temperature it is known that k' is temperature-independent and that the overall activation energy  $E_a$  is  $40.2 \text{ kcal mol}^{-1}$ . From Table 3.9, we find that  $\Delta H_1^{\circ}$  is 46.1 kcal mol $^{-1}$ . Thus we calculate

$$E_a(3) = 40.2 - 23.0 = 17.2 \text{ kcal mol}^{-1}$$

From data in Table 3.9 we calculate that the energy of reaction 3 is 16.7 kcal mol-1, a value just slightly less than  $E_a$ . As a matter of fact, this result is expected. Most exothermic reactions involving radicals are very fast and have low activation energies — typically a few kilocalories per mole. A schematic plot of the energies of the species involved in such a reaction is shown in Fig. 5.1




Figure 5.1 Energy level diagram for the reaction  $A + BC \rightarrow AB + C$ , where A and C are atoms or radicals.

From the plot we see that the activation energy of an *endothermic* reaction of this type is just slightly greater than the energy of the reaction.

Although reactions 1 to 5 satisfactorily account for the rate law of the reaction, it is of interest to consider why the following reactions are not involved in the reaction mechanism.

From data in Table 3.9, we calculate that the activation energies of reactions 6,7, and 9 are greater than 41.4, 87.5, and 104.2 kcal mol<sup>-1</sup>, respectively. The activation energy of reaction 6 is much greater than that of any one of the analogous chain-propagating steps, reaction 3, 4, or 5. Similarly, the activation energies of reactions 7 and 9 are much greater than that of the analogous chain-initiating step, reaction 1. Hence the rate constants of reactions 6, 7, and 9 are negligible compared with those of the analogous reactions in the actual mechanism. Rearrangement of Eq. 5.3 gives

$$\frac{[H]}{[Br]} = \frac{k_3[H_2]}{k_5[Br_2] + k_4[HBr]}$$

In the early stages of the reaction, when [HBr] is low, and when  $H_2$  and  $Br_2$  have comparable concentrations, [H]/[Br]  $\approx k_3/k_5$ . At a typical reaction temperature, say 300°C,  $k_3/k_5 \approx e^{-17.2/RT} \approx 10^{-7}$ . Therefore reaction of H and Br atoms (reaction 8) would be  $\sim 10^{-7}$  as likely as recombination of two Br atoms (reaction 2), and recombination of two H atoms would be  $\sim 10^{-14}$  as likely.

The chain reaction of hydrogen and chlorine, which proceeds by a mecha-

nism analogous to reactions 1 to 5, is faster than that of hydrogen and bromine, whereas the chain reaction of hydrogen and iodine is slower. These qualitative results are readily predictable from the energetics of the steps in the general mechanism. If, as a rough approximation, we equate the energy of the  $X + H_2 \rightarrow HX + H$  reaction to the activation energy of that reaction, then from Eq. 5.5 we obtain, for the overall activation energy,

$$E_a \approx D(H_2) - D(HX) + \frac{1}{2}D(X_2)$$

For chlorine, we calculate

$$E_a \approx 104.2 - 103.2 + 29.1 = 30.1 \text{ kcal mol}^{-1}$$

and, for iodine,

$$E_a \approx 104.2 - 71.3 + 18.0 = 50.9 \text{ kcal mol}^{-1}$$

Notice that the main factor in establishing the trend in the reactivity of the halogens with hydrogen is the trend in the H-X dissociation energy. In the case of chlorine, most of the energy required to break the H-H bond is compensated by the energy released upon formation of the H-Cl bond. In the case of iodine, a relatively small amount of energy is provided by formation of the H-I bond.

The reaction of hydrogen with iodine by the chain mechanism is so slow that, under ordinary conditions, an entirely different mechanism predominates. rate law has long been known to be

For many years this rate law was interpreted in terms of a simple bimolecular the low k versus 1/1 plat of kig. 5 process with a four-center activated complex: ac calculated gate constant

any given temperature. This 
$$IHC_1 \leftarrow I_2 + I_2 \leftarrow I_3$$
 he simple bimolecular process

However, relatively recent experimental data show that the following, entirely different, mechanism is responsible for the reaction4:

$$I_2 \implies 2I \qquad K = \frac{[I]^2}{[I_2]}$$

$$2I + H_2 \xrightarrow{k'} 2HI$$

In the latter mechanism, I<sub>2</sub> molecules are in equilibrium with I atoms, and the latter species react with H<sub>2</sub> by a termolecular reaction (or perhaps two bimolecular reactions) to form the product. The corresponding rate law is indistinguishable from that for the simple bimolecular process:

$$\frac{d[HI]}{dt} = k'[H_2][I]^2 = k'K[H_2][I_2] = k[H_2][I_2]$$

G. Wandward and R. Hoffman, "The Conservation of Orbital Symmetry." Academia <sup>4</sup> J. H. Sullivan, J. Chem. Phys., 46, 73 (1967).




Figure 5.2 Plot of log(10-5k') versus 1000/T for the  $H_2 + I_2$  reaction. Solid circles correspond to k/K values. open circles correspond to directly measured k' values. [Reproduced with permission from J. H. Sullivan, J. Chem. Phys., 46, 73 (1967).]


The termolecular rate constant k' has been measured directly at low temperature. tures, using photochemically generated I atoms. The same rate constant can also be calculated from the relation k' = k/K, using values of k obtained from kinetic data on the  $H_2 + I_2$  reaction at high temperatures and values of K obtained from equilibrium thermodynamic data. Both types of k' values have been plotted in the  $\log k'$  versus 1/T plot of Fig. 5.2. Both sets of points fall on the same straight line, indicating that both sets of data yield the same calculated rate constant for any given temperature. This result proves that the simple bimolecular process must be relatively unimportant; otherwise k' values calculated from kinetic data on the  $H_2 + I_2$  reaction would be higher than k' values obtained from direct measurement of the  $2I + H_2$ , reaction rate.

### ORBITAL SYMMETRY EFFECTS

In recent years chemists have come to realize the importance of molecular orbital symmetry in determining the rates of reactions. 5,6 We now know, for example that the simple bimolecular  $H_2 + I_2$  reaction mechanism involving a trapezoidal activated complex

<sup>&</sup>lt;sup>5</sup> R. G. Pearson, Chem. Eng. News, 66 (Sept. 28, 1970); Acc. Chem. Res., 4, 152 (1971); J. All. Chem. Soc., 94, 8287 (1972); "Symmetry Rules for Chemical Reactions," Wiley-Interscience, New York, 1976. York, 1976.


<sup>&</sup>lt;sup>6</sup> R. G. Woodward and R. Hoffman, "The Conservation of Orbital Symmetry," Academic, New 1969 York, 1969.




is symmetry-forbidden, whereas a mechanism involving the preliminary dissociation of iodine is symmetry-allowed.

For a bimolecular reaction, the important orbitals are the highest occupied molecular orbital (HOMO) of one molecule and the lowest unoccupied molecular orbital (LUMO) of the other molecule. 6a In the course of the reaction, electrons flow from the HOMO to LUMO. This process will occur (i.e., the reaction will be allowed) if the following conditions are fulfilled. (1) As the reactants approach one another, the HOMO and LUMO must have a finite net overlap. (2) The energy of the LUMO must be lower than, or no more than about 6 eV higher than, the energy of the HOMO. (3) The HOMO must be either a bonding MO of a bond to be broken or an antibonding MO of a bond to be formed; and vice versa for the LUMO

Let us apply these rules to the bimolecular  $H_2 + I_2$  reaction. The HOMO of  $H_2$  is the  $s\sigma_B$  MO, and the LUMO of  $I_2$  is the  $p\sigma^*$  MO. These orbitals are illustrated below; the shading indicates electron occupancy. It is obvious that, if




the H<sub>2</sub> and I<sub>2</sub> approach each other broadside, the net overlap of these orbitals is zero and the reaction is forbidden. An alternative approach is to consider the HOMO of  $I_2$  (the  $p\pi^*$  MO) and the LUMO of  $H_2$  (the  $s\sigma^*$  MO):



Although these orbitals have appropriate symmetries, i.e., the net overlap is positive, electron flow cannot occur for two reasons: The electron flow would correspond to the strengthening rather than the weakening of the I—I bond, and the electron flow from electronegative atoms to relatively electropositive atoms is energetically unfeasible. On the other hand, the reactions of an H<sub>2</sub> molecule with I do not strongly interact with the c MO of the C — C hond . I have oct did in

Pearson, op. cit.


one or two iodine atoms, as in alternative mechanisms of the reaction, are symmetry- and energy-allowed processes:



For another example, let us consider the hydrogenation of ethylene to give ethane:

$$H_2 + C_2H_4 \rightarrow C_2H_6$$

If we assume a symmetric approach of  $H_2$  on one side of the  $C_2H_4$  plane, neither the flow of electrons from the HOMO of  $H_2$  to the LUMO of  $H_2$  is allowed by symmetry. In each case the net orbital overlap is zero.



Thus the reaction is symmetry-forbidden. The nonreactivity of hydrogen with ethylene is in striking contrast to the reaction of hydrogen with B<sub>2</sub>Cl<sub>4</sub>, which proceeds readily even below room temperature.

$$3H_2 + 3B_2Cl_4 \rightarrow 4BCl_3 + B_2H_6$$

The first step in this complex reaction probably involves the broadside attack of an H<sub>2</sub> molecule on a B<sub>2</sub>Cl<sub>4</sub> molecule to form intermediate BHCl<sub>2</sub> molecules:

$$H_2 + B_2Cl_4 \rightarrow 2BHCl_2$$

A series of exchange processes could then lead to the observed products:

$$2BHCl2 \rightarrow BH2Cl + BCl3$$


$$BH2Cl + BHCl2 \rightarrow BH3 + BCl3$$

$$2BH3 \rightarrow B2H6$$

It is easy to show that the first step of the proposed mechanism is both symmetry and energy-allowed.<sup>8</sup> Electrons can flow from the  $s\sigma_B$  MO of H<sub>2</sub> to the empty  $p\pi_B$  MO of B<sub>2</sub>Cl<sub>4</sub>:

<sup>&</sup>lt;sup>7</sup> The HOMO of  $C_2H_4$  is a  $\pi$  MO, not a  $\sigma$  MO. The  $\sigma$  MOs associated with the C-H bonds have quite low energies and do not strongly interact with the  $\sigma$  MO of the C-C bond. Thus one does not observe the type of  $\sigma$ - and  $\pi$ -orbital ordering found in the first-row diatomic molecules (see Fig. 3.5b). 

8 See R. A. Geanangel, J. Nucl. Inorg. Chem., 34, 1083 (1972)



#### Explosions stens I to J have been separately studied as SNOISOIR

The temperature of a reaction mixture is stable when the rate of loss of heat by conduction and convection equals the rate of heat production by the reaction. If the rate of heat loss cannot compensate for the rate of heat production, the reaction temperature and rate may increase rapidly, causing a "thermal explosion." Such an explosion can occur for highly exothermic reactions when the reactant concentrations are high. For example, an equimolar mixture of hydrogen and chlorine at a pressure of 50 torr in a glass vessel will explode at temperatures above 400°C. At lower temperatures the reaction rate is so slow that the heat of reaction can be carried off by conduction and convection. Explosion can occur at a lower temperature if the pressure of the reaction mixture is increased, and a higher temperature is required for explosion if the pressure is reduced

It is interesting that the addition of only 0.5 torr of nitric oxide to 50 torr of  $H_2 + Cl_2$  mixture lowers the critical explosion temperature from 400 to 270°C. This sensitization of the explosion is probably caused by an increase in the Cl atom concentration by the reaction

$$NO + Cl_2 \rightarrow NOCl + Cl$$

The latter reaction has an activation energy of only 22 kcal mol<sup>-1</sup>, whereas the  $Cl_2 \rightarrow 2Cl$  reaction has an activation energy of at least 57 kcal mol<sup>-1</sup>.

The reaction of hydrogen with oxygen to produce water is the classical example of a "branching-chain" reaction:

$$2H_2 + O_2 \rightarrow 2H_2O_{(g)} \qquad \Delta H^\circ = -115.6 \text{ kcal mol}^{-1}$$

Many kinetic studies have shown that the following three basic steps are important in the mechanism of this chain reaction<sup>10</sup>:


OH + H<sub>2</sub> 
$$\xrightarrow{1}$$
 H<sub>2</sub>O + H  $k_1 = 2.2 \times 10^{10} e^{-5.15/RT} \text{ L mol}^{-1} \text{ s}^{-1}$   
H + O<sub>2</sub>  $\xrightarrow{2}$  OH + O  $k_2 = 2.2 \times 10^{11} e^{-16.8/RT} \text{ L mol}^{-1} \text{ s}^{-1}$   
O + H<sub>2</sub>  $\xrightarrow{3}$  OH + H  $k_3 = 3.5 \times 10^{10} e^{-10.0/RT} \text{ L mol}^{-1} \text{ s}^{-1}$ 

<sup>9</sup> See footnote 3.

<sup>10</sup> R. R. Baldwin and R. W. Walker, in "Essays in Chemistry," J. N. Bradley, R. D. Gillard, and R. F. Hudson, eds., vol. 3, pp. 1–37, Academic, London.

The first step is chain-propagating and is the major process by which  $H_2O$  is formed. The second and third steps differ from the usual chain-propagating steps of chain reactions in that they produce more chain carriers (OH, O, or H) than they consume; thus they are called chain-branching reactions. If these reactions are allowed to predominate, the overall reaction rate will increase essentially without bound; i.e., an explosion will occur. Whether or not an explosion takes place depends on whether or not the chain-terminating steps of the mechanism can compensate for these chain-branching steps.

Reaction steps 1 to 3 have been separately studied over a wide range of temperature by flow-discharge methods, conventional methods, shock tubes, and flames. The kinetic parameters (with the activation energies in kilocalories per mole) are given after the chemical equations, and the  $\log k$  versus 1/T plots are shown in Fig. 5.3. Because step 2 has by far the highest activation energy of the



three processes, it is the slowest step and controls the production of chain carriers. Consequently the main radical species in a preexplosion  $H_2$ – $O_2$  mixture is always atomic hydrogen, and the most important chain-terminating steps are those in which atomic hydrogen is consumed.

At low temperatures, atomic hydrogen is lost principally by diffusion to the vessel walls:

$$H + wall \xrightarrow{4} stable species$$

At low temperatures and pressures, reaction 4 prevents reactions 1 to 3 from proceeding uncontrolledly, and no explosion occurs. However, because reactions 1 to 3 are of higher kinetic order than reaction 4, an increase in pressure causes the combination of reactions 1 to 3 to increase in rate more than reaction 4. If the temperature of the reaction mixture is high enough, increasing the pressure beyond a particular value (called the "first explosion limit") causes explosion. If the pressure is increased considerably beyond the first limit, a second limit is reached, above which no explosion occurs. This quenching of the explosion is caused by the following reaction, which forms the relatively unreactive HO<sub>2</sub> species:

$$H + O_2 + M \xrightarrow{5} HO_2 + M$$

The third body (M), which can be any other molecule such as  $O_2$ ,  $H_2O$ , or a spectator gas molecule such as Ar, serves to carry off some of the heat of reaction and prevents the  $HO_2$  from falling apart to OH and O. Note that reaction 5 is of higher kinetic order than reaction 2 and therefore would be expected to predominate at higher pressures. In fact, the concentration of M necessary to prevent explosion (the second explosion limit) can be calculated by equating the rate of chain termination and the rate of chain branching<sup>11</sup>:

$$k_5(H)(O_2)(M) = 2k_2(H)(O_2)$$

or

Thus the reduced production by 
$$\frac{2k_2}{k_5} = \frac{2k_2}{k_5}$$
 and at a sufficient  $\frac{2k_2}{k_5} = \frac{2k_2}{k_5}$  and at a sufficient  $\frac{2k_2}{k_5} = \frac{2k_2}{k_5}$  which explosion again occurs of the various limits and  $\frac{2k_2}{k_5} = \frac{2k_2}{k_5}$ 

Even though  $HO_2$  is a radical, process 5 is chain-terminating because  $HO_2$  is too slowly reactive to propagate a chain. It serves to break the chain reaction by decomposition at the wall:

$$HO_2 + HO_2 + wall \xrightarrow{6} H_2O_2 + O_2$$

The factor of 2 arises from the fact that reactions 1, 2, and 3 are stoichiometrically constrained to occur with relative rates of 2:1:1, respectively. Thus two H atoms are produced for every  $O_2$  molecule consumed by step 2, whereas only one H atom is consumed for every  $O_2$  molecule consumed by step 5.




Figure 5.4 Plot showing the explosion limits of a stoichiometric mixture of  $H_2 + O_2$  in a KCl-coated spherical vessel (7.4-cm diameter). Dashed parts of the curve are extrapolations. (From S. W. Benson, "Foundations of Chemical Kinetics," McGraw-Hill, New York, 1960.)

Therefore near the second explosion limit, the main combustion product is hydrogen peroxide produced by reaction 6, rather than water.

Above the second limit, the reaction rate is relatively slow and proceeds by a complicated mechanism involving steps 1 to 3 and 5, and reactions involving  $H_2O_2$ . Increasing the pressure causes a significant amount of  $HO_2$  to react with  $H_2$  in the gas phase:

$$HO_2 + H_2 \xrightarrow{7} H_2O_2 + H$$

Thus the radical production by this reaction competes with the quenching effect of reaction 5, and at a sufficiently high pressure a third limit is reached above which explosion again occurs. The regions of explosion and the various limits are delineated in the pressure-temperature plot of Fig. 5.4.

#### **PROBLEMS**

- **5.1** The conversion of p-H<sub>2</sub> (nuclear spins antiparallel) to o-H<sub>2</sub> (nuclear spins parallel) follows the rate law: Rate = k[p-H<sub>2</sub>][H<sub>2</sub>]<sup>1/2</sup>. Propose a reaction mechanism.
- \*5.2 Why would you expect the kinetics of the  $H_2 + F_2$  reaction to be more complicated than that of the  $H_2 + Br_2$  reaction?
- \*5.3 Under what conditions would you expect the chain mechanism to compete with the nonchain mechanism in the  $H_2 + I_2$  reaction?

5.4 Which of the following concerted reactions are "forbidden" because of high activation energies?

$$\begin{array}{rcl} 2\text{NO} & \rightarrow & \text{N}_2 + \text{O}_2 \\ \\ \text{N}_2\text{H}_2 + \text{C}_2\text{H}_4 & \rightarrow & \text{N}_2 + \text{C}_2\text{H}_6 \\ \\ \text{H}_2 + \text{N}_2 & \rightarrow & \text{N}_2\text{H}_2 \\ \\ \text{SO}_2 + \text{F}_2 & \rightarrow & \text{SO}_2\text{F}_2 \\ \\ \text{SF}_2 + \text{F}_2 & \rightarrow & \text{SF}_4 \\ \\ \text{O} + \text{F}_2 & \rightarrow & \text{OF}_2 \\ \\ \text{O} + \text{O}_2 & \rightarrow & \text{O}_3 & \text{(terminal addition of O)} \\ \\ \text{O} + \text{O}_2 & \rightarrow & \text{O}_3 & \text{(middle insertion of O)} \end{array}$$

\*5.5 Can singlet methylene, CH<sub>2</sub>, react with H<sub>2</sub> by a least-motion concerted reaction to give CH<sub>4</sub>? How about a non-least-motion pathway of the following type?



- \*5.6 A spark between two wires can set off an explosion in an  $H_2 + O_2$  mixture which lies outside the explosion region of Fig. 5.4. Explain.
  - 5.7 Discuss the nuclear fission of  $^{235}$ U in terms of a branching-chain mechanism. Note the analogies between this reaction and the  $H_2 + O_2$  reaction.
  - 5.8 Explain why a concerted four-center mechanism (with a rectangular activated complex) is unlikely for the reaction  $H_2 + D_2 \rightarrow 2HD$ .

#### COMPOUNDS OF HYDROGEN

In Chap. 5 we pointed out that there are probably more known compounds of hydrogen than of any other element in the periodic table. There is no question that hydrogen-containing compounds (hydrides) constitute the majority of the compounds that we work with and that we should be familiar with their physical and chemical properties. In this chapter we describe the various kinds of hydrides and discuss periodic-table trends in their reactivities.

#### CLASSIFICATION OF THE HYDRIDES

Hydrides represent a wide variety of compounds having many different types of structure and bonding. This variety in structure and bonding is attributable to the unique electronic structure of the hydrogen atom: The atom possesses no core electrons, it has only one valence electron (and thus is *formally* analogous to the alkali-metal atoms), and it is only one electron short of a stable rare-gas electron configuration (and thus is analogous to halogen atoms). The known hydrides may be roughly categorized as saline hydrides, metallic hydrides, transition-metal hydride complexes, and nonmetal hydrides.

#### Saline Hydrides

At high temperatures hydrogen reacts with the alkali metals and the alkaline-earth metals heavier than beryllium to form salts, such as NaH and CaH<sub>2</sub>, containing the hydride ion H<sup>-</sup>. Inasmuch as the ionic radii of H<sup>-</sup> and F<sup>-</sup> are very similar

<sup>&</sup>lt;sup>1</sup> T. R. P. Gibb, Progr. Inorg. Chem., 3, 315 (1962).

(1.40 and 1.36 Å, respectively, on the Pauling scale), the physical properties of the saline hydrides are similar to those of the corresponding fluorides. Even the periodic-table trend in the heats of formation of the alkali-metal hydrides resembles that for the alkali-metal fluorides. In each case, the lithium compound is more stable than the cesium compound. (See Table 6.1.)

Striking evidence for the negative charge of the hydrogen in lithium hydride is obtained when molten lithium hydride (mp 691°C) is electrolyzed: Lithium metal forms at the cathode, and hydrogen is evolved at the anode. The saline hydrides react vigorously with protonic solvents such as water, alcohol, and liquid ammo-

nia to form molecular hydrogen and the basic anions of the solvents:

$$CaH_2 + 2H_2O \rightarrow Ca^{2+} + 2OH^- + 2H_2$$
  
 $LiH + C_2H_5OH \rightarrow Li^+ + C_2H_5O^- + H_2$   
 $KH + NH_3 \rightarrow K^+ + NH_2^- + H_2$ 

Sodium hydride finds considerable use as a reducing agent in synthetic chemistry. Sodium hydroborate, NaBH<sub>4</sub>, is prepared by the reaction of sodium hydride with methyl borate at elevated temperatures:

$$4NaH + B(OCH_3)_3 \rightarrow NaBH_4 + 3NaOCH_3$$

Aqueous solutions of sodium hydroborate are kinetically stable at high pH; however, acidic solutions decompose rapidly to boric acid and hydrogen:

$$BH_4^- + H^+ + 3H_2O \rightarrow 4H_2 + H_3BO_3$$

Sodium hydroborate is often used as a reducing agent in both inorganic and organic syntheses. When ether solutions of sodium hydroborate are heated at 100°C with diborane, the octahydrotriborate ion, B<sub>3</sub>H<sub>8</sub>-, is formed:

$$B_2H_6 + NaBH_4 \rightarrow NaB_3H_8 + H_2$$

Table 6.1 Properties of the saline hydrides†

Formula	Density, g ml <sup>-1</sup>	$\Delta H^{\circ}$ of formation, kcal mol <sup>-1</sup>	Crystal structure analog
LiH	0.778	-21.67	NaCl
NaH	1.36	-13.49	NaCl
KH	1.43	-13.82	NaCl
RbH	2.60	murballe 1113 villadimos	NaCl
CsH	3.41	-11.92	NaCl
MgH <sub>2</sub>	1.42	-17.79	TiO <sub>2</sub>
CaH <sub>2</sub>	1.9	-41.65	Distorted PbCl <sub>2</sub>
SrH <sub>2</sub>	3.27 are toward 2018	-42.3	Distorted PbCl <sub>2</sub>
BaH <sub>2</sub>	4.15	-40.9	Distorted PbCl <sub>2</sub>

<sup>†</sup> K. M. Mackay, "Hydrogen Compounds of the Metallic Elements," Spon, London, 1966.

By suitable changes in reaction time, temperature, diborane pressure, and solvent, these same reagents will yield various anions of the general formula  $B_n H_n^2$  (*n* ranging from 6 to 12). These ions are remarkably resistant toward hydrolysis, and their boron skeletons remain intact throughout a wide variety of reactions in which the hydrogen atoms are replaced by other groups. (See Chap. 10 for further discussion of the boron hydrides and their derivatives.)

Lithium hydride is used in the preparation of lithium aluminum hydride

(lithium hydroaluminate), LiAlH<sub>4</sub>: Moss a resorbed bus shortles out the amount

$$4LiH + AlCl_3 \rightarrow LiAlH_4 + 3LiCl$$

Both LiAlH<sub>4</sub> and NaAlH<sub>4</sub> can be prepared directly from the elements:

$$M + Al + 2H_2$$
  $\xrightarrow[1000-5000 \text{ lb in}^{-2}]{\text{ether solvent}}$   $MAlH_4$   $\xrightarrow[120-150^{\circ}\text{C}]{\text{ether solvent}}$ 

Lithium aluminum hydride is an important reagent in synthetic chemistry; it is a much more powerful reducing agent than an alkali-metal hydroborate, and it reacts vigorously with protonic solvents such as alcohols.

#### Metallic Hydrides

The binary hydrides of the transition metals have metallic properties and are usually obtained as powders or brittle solids which are dark and metallic in appearance and which have electric conductivities and magnetic properties characteristic of metals. Most of these hydrides have nonstoichiometric compositions; the stoichiometries and properties depend on the purity of the metals used in the preparations. Some typical limiting formulas are ScH<sub>2</sub>, LaH<sub>2</sub>, SmH<sub>2</sub>, ThH<sub>2</sub>, PaH<sub>3</sub>, UH<sub>3</sub>, VH, and CrH. An early theory of the metallic hydrides was implied in their classification, along with carbides, nitrides, borides, etc., as "interstitial." It was believed that the hydrogen entered the interstices of the metal lattice as atoms. This theory, which suggested very little interaction between the interstitial atoms and the metal, soon became untenable in the light of structural studies. In most hydrides their metal atoms are not in the same positions as in the parent metal (although in some hydrides metal-atom positions correspond to a high-temperature modification of the metal). Other facts which must be explained by any theory of metallic hydrides are the following:

1. In several of the hydrides, the bonded hydrogen is very mobile and has only a small activation energy of diffusion.

2. The magnetic susceptibility of palladium falls as hydrogen is added, and the material becomes diamagnetic at a composition of about  $PdH_{0.6}$ .

3. If a potential is applied across a filament of a hydride, such as one of palladium, titanium, or tantalum, the hydrogen migrates toward the negative electrode.

In one theory which is used to describe the metallic hydrides, hydrogen atoms are assumed to have lost their electrons to the d orbitals of the metal atoms and to

be present in the lattice as protons. Thus the compound is like an alloy. In another theory of metallic hydrides, the hydrogen atoms are assumed to have acquired electrons from the conduction band and to be present as hydride ions. The partially depleted conduction band gives residual metallic bonding in the compound. Thus the compound can be described as a saline hydride with metallic properties. The various properties of metallic hydrides have been explained on the basis of both theories.

#### Hydrogen Storage with Metallic Hydrides

When the time comes that the combustion of petroleum is no longer an economical source of energy, hydrogen may be an important fuel. Hydrogen is an attractive fuel because it has an extremely high density of energy per unit weight, it is nonpolluting (the main combustion product is water), and it can be oxidized in a variety of devices ranging from internal combustion engines to fuel cells. In the past, the problems of storing hydrogen safely and compactly have retarded the development of hydrogen as a fuel. However, solutions to those problems may be found in the form of certain metallic hydrides which can be reversibly decomposed to give hydrogen gas and the metals.<sup>2</sup> It is possible to store more hydrogen in the form of these hydrides than in the same volume of liquid hydrogen. The hydrogen storage capacities of some representative hydrogen storage systems can be compared in Table 6.2.

Consider the various steps in the absorption of hydrogen by a metal. A small amount of hydrogen first simply dissolves in the metal. In this state the hydrogen exists as atoms in interstitial lattice sites. As the pressure of hydrogen gas in contact with a metal is increased, more and more hydrogen atoms are forced into the metal. At some critical concentration and pressure the metal becomes saturated, and a new phase, the metal hydride, begins to form. Then further

Table 6.2 Hydrogen storage capacities of some hydrogen storage systems

Storage medium	Weight percent hydrogen	Hydrogen density, g ml <sup>-1</sup>
MgH <sub>2</sub>	Ovide 4 Overland	0.101
Mg <sub>2</sub> NiH <sub>4</sub>	3.16	0.081
VH <sub>2</sub>	2.07	0.095
FeTiH <sub>1.95</sub>	010/01/75	0.096
LaNi <sub>s</sub> H <sub>7</sub>	1.37	0.089
Liquid H <sub>2</sub>	100	0.07
Gaseous H <sub>2</sub> (100 atm)	100	0.008

<sup>&</sup>lt;sup>2</sup> J. J. Reilly and G. D. Sandrock, *Sci. Am.*, **242**, 118 (February 1980); R. L. Cohen and J. H. Wernick, *Science*, **214**, 1081 (1981).

hydrogen is absorbed with essentially no increase in pressure. Ultimately all the hydrogen-saturated metal phase is converted into the hydride, and further hydrogen can be dissolved in the hydride phase only by increasing the pressure.

Pressure-composition isotherms for the hydrogen-iron-titanium system are shown in Fig. 6.1. This system is an example of the formation of a ternary hydride from an intermetallic compound. Most of the hydrides that are of interest for storing hydrogen are of this type. Plots of the midplateau hydrogen dissociation pressure versus 1000/T for several metals and intermetallics are shown in Fig. 6.2.

Of the various hydrides which have been considered for hydrogen storage, the leading contender is FeTiH<sub>1.95</sub>, because of its cheapness and its relatively high




Figure 6.1 Pressure-composition isotherms for the hydrogen-iron-titanium system. The upper curve corresponds to the equilibrium pressure as hydrogen was added stepwise to the alloy; the lower curve cause of his hysteresis is unknown. Regions A-B correspond to solid solutions of hydrogen in metal hydrogen in the monohydride; regions B-C to mixtures of the saturated metal and the monohydride; regions C-D to solid solutions of and regions E-F to solutions of hydrogen in the dihydride. [Adapted from J. J. Reilly and G. D. Sandrock, Sci. Am., 242, 118 (Feb. 1980)]




Figure 6.2 Dissociation pressure versus 1000/T for several hydrides. Calculated heats of reaction (kcal per mole of  $H_2$ ) are indicated. [Reproduced with permission from E. L. Huston and G. D. Sandrock, J. Less Common Met., 74, 435 (1980).]

hydrogen density. Magnesium hydride is only a borderline possibility for such use because a rather high temperature (289°C) is required to liberate its hydrogen at 1 atm pressure.

#### Transition-Metal Hydride Complexes

Until the late 1950s, very few hydrides were known in which hydrogen atoms were covalently bonded directly to transition-metal atoms. Since then, numerous compounds of this type have been characterized. Most of them have the general formula  $MH_xL_y$ , where M is a transition metal and L is a ligand capable of acting both as a  $\sigma$  donor and a  $\pi$  acceptor. Examples are  $K_3[CoH(CN)_5]$  (a homogeneous hydrogenation catalyst for the conversion of alkynes to alkenes), trans-PtHCl[P( $C_2H_5$ )<sub>3</sub>]<sub>2</sub> (a compound so stable that it can be sublimed in a vacuum),  $OsHCl_2[P(C_4H_9)_2C_6H_5]_3$  (a complex with an odd number of electrons and therefore paramagnetic), and  $K_2ReH_9$  (remarkable because the transition metal is bonded to an unusually large number of hydrogen atoms, and no other ligands<sup>3</sup>).

Some transition-metal ions and complexes react directly with molecular hydrogen to form complexes containing metal-hydrogen bonds. These reactions will be discussed in Chap. 20. In general, transition-metal hydride complexes are prepared by the reduction of transition-metal compounds in the presence of π-bonding ligands. Besides the obvious reducing agents BH<sub>4</sub><sup>-</sup> and LiAlH<sub>4</sub>,

<sup>&</sup>lt;sup>3</sup> A similar complex ion, FeH<sub>6</sub><sup>4-</sup>, has recently been identified. See R. Bau and D. M. Ho, *J. Am. Chem. Soc.*, **103**, 4960 (1981).

reagents such as alcoholic KOH, hydrazine, and hypophosphorous acid have been used. A typical procedure is to treat the anhydrous halide with NaBH<sub>4</sub> or LiAlH<sub>4</sub> in an ether solvent. For example,

$$\begin{array}{ccc} C_5H_5Fe(CO)_2Cl & \xrightarrow{NaBH_4} & C_5H_5Fe(CO)_2H \\ \\ \textit{trans-Pt}(PR_3)_2Cl_2 & \xrightarrow{LiAlH_4} & \textit{trans-Pt}(PR_3)_2(H)Cl \\ \end{array}$$

Many hydrides and carbonyl hydrides can be prepared by the treatment of anhydrous halides with triphenylphosphine or triphenylarsine in an alcohol. For example,

In early research, many of the transition-metal hydride complexes were believed to involve low oxidation states of the metals, and the presence of hydrogen was not suspected. It is now known that the hydrogen in such compounds can be identified by an infrared absorption, due to the M—H stretch, in the range 1600 to 2250 cm<sup>-1</sup> and a proton magnetic resonance signal at very high field, corresponding to  $\tau$  values in the range 15 to 50.

#### Nonmetal Hydrides

Nonmetal hydrides contain hydrogen atoms covalently bonded to the elements of main groups III to VII of the periodic table. The compounds generally consist of discrete molecules having considerable volatility. Properties of some of the volatile nonmetal hydrides are listed in Table 6.3.

A wide variety of synthetic methods have been used in the synthesis of nonmetal hydrides. Some of these methods and typical examples are

1. The reaction of lithium aluminum hydride with a nonmetal halide,

2. The reduction of a nonmetal oxyacid with borohydride in aqueous solution,

$$3BH_4^- + 4H_3AsO_3 + 3H^+ \xrightarrow{H_2O} 4AsH_3 + 3H_3BO_3 + 3H_2O$$

3. The solvolysis of a binary compound of a nonmetal (e.g., calcium phosphide) in acid solution,

$$Ca_3P_2 + 6H^+ \xrightarrow{H_2O} 3Ca^{2+} + 2PH_3$$

4. The pyrolysis of a nonmetal hydride,

$$B_2H_6 \xrightarrow{\Delta} H_2 + B_4H_{10} + B_5H_{11} + \cdots$$

Table 6.3 Properties of some volatile hydrides†‡

Formula (2000)	Melting point, °C	Boiling point,	ΔH° of formation of gas, kcal mol <sup>-1</sup>
B <sub>2</sub> H <sub>6</sub>	-165	-90	7.5
B <sub>4</sub> H <sub>10</sub>	-120 mole sy	16.1	13.8
B <sub>5</sub> H <sub>9</sub>	-46.1 org ba	58.4	15.0 15.0
B <sub>5</sub> H <sub>11</sub>	-123.3	63 12 1110	1 of 2922.2 Trive to see 1 940 f
B <sub>6</sub> H <sub>10</sub>	-63.2	108	lydrides of the 8.61 cents
$B_{10}H_{14}$	100	ada a antonoma sibir	to 1 4.4 an on sved V
SiH <sub>4</sub>	-185	-111.2	7.3
$Si_2H_6$	-129.3	-14.2	17.1
Si <sub>3</sub> H <sub>8</sub>	-114.8	53.0	25.9
GeH <sub>4</sub>	-165.9	-88.51	21.6
Ge₂H <sub>6</sub>	-109	29	38.7 + Hord abirm
Ge <sub>3</sub> H <sub>8</sub>	-101.8	110.5	53.6
SiH <sub>3</sub> GeH <sub>3</sub>	-119.7	7.0	27.8
SnH <sub>4</sub>	-150 manyb	-51.8	38.9
PbH <sub>4</sub>	d-by-the govern	~-13	60
PH <sub>3</sub>	-133.8	-87.74	1.3500000 08860-6
$P_2H_4$	-99	63.5	5.0
SiH <sub>3</sub> PH <sub>2</sub>	<-135	4 (a) H 12.7 (a) N	2 (6.
AsH <sub>3</sub>	-116.9	-62.5	15.9
SbH <sub>3</sub>		-18.4	34.7
BiH <sub>3</sub>	-88	~ 17	66

† M. F. Hawthorne, in "The Chemistry of Boron and Its Compounds," E. L. Muetterties, ed., pp. 223-323, Wiley, New York, 1967.

‡ W. L. Jolly and A. D. Norman, Prep. Inorg. React., 4, 1 (1968).

5. The treatment of a nonmetal hydride, or a mixture of such hydrides, with an electric discharge,

$$GeH_4 + PH_3 \xrightarrow{electric} GeH_3PH_2 + Ge_2H_6 + P_2H_4 + \cdots$$

6. The coupling of an alkali-metal salt of a nonmetal hydride with a halogen derivative of a nonmetal hydride,

$$KSiH_3 + SiH_3Br \rightarrow KBr + Si_2H_6$$

The study of the hydrides of carbon and their derivatives constitutes the enormous discipline of organic chemistry. Carbon atoms are remarkable for their ability to catenate, i.e., to form chains, as in the aliphatic hydrocarbons, or alkanes. Other elements show this ability to a much lesser extent. Silicon and germanium hydrides analogous to the organic alkanes have been characterized up to  $\mathrm{Si}_{10}\mathrm{H}_{22}$  and  $\mathrm{Ge}_{10}\mathrm{H}_{22}$ , that is, up to silicon and germanium chain lengths of 10. The longest molecular-chain hydrides which have been definitely characterized for other elements are  $\mathrm{Sn}_2\mathrm{H}_6$ ,  $\mathrm{HN}_3$ ,  $\mathrm{P}_3\mathrm{H}_5$ ,  $\mathrm{As}_3\mathrm{H}_5$ ,  $\mathrm{Sb}_2\mathrm{H}_4$ ,  $\mathrm{H}_2\mathrm{O}_3$ , and  $\mathrm{H}_2\mathrm{S}_6$ .

#### HYDRIDIC AND PROTONIC CHARACTER

The hydrides of boron, a relatively electropositive nonmetal, react as if the hydrogen atoms had "hydridic" character (i.e., as if they were  $H^-$  ions). Thus these hydrides react with water to form hydrogen:  $B_2H_6 + 6H_2O \rightarrow 6H_2 + 2H_3BO_3$ . Hydrides of the more electronegative elements such as those of groups VI and VII react as if the hydrogen atoms had protonic ( $H^+$ ) character. Thus these react with bases to form salts or adducts:  $HCl + C_5H_5N \rightarrow (C_5H_5NH)Cl$ . Hydrides of the elements of intermediate electronegativity, such as those of group IV, have no marked hydridic or protonic character. These hydrides may show, depending on the reagent, either hydridic or protonic character. Thus germane,  $GeH_4$ , shows hydridic character in the reaction with hydrogen bromide,  $GeH_4 + HBr \rightarrow GeH_3Br + H_2$ , and shows protonic character in its reaction with sodium amide,  $GeH_4 + NaNH_2 \rightarrow NaGeH_3 + NH_3$ .

It is instructive to study the trends in the hydridic and protonic characters of the binary molecular hydrides from a thermodynamic viewpoint. The hydridic character of a hydride  $H_nX$  can be measured by the energy of the following gas-phase process:

$$H_n X(g) \rightarrow H^-(g) + H_{n-1} X^+(g)$$
 (6.1)

The question is: How does this energy change as we change element X by moving from one place to another in the periodic table? The problem is somewhat simplified if we consider the energy of reaction 6.1 as a combination of energies. The energy can be broken up into the energies of the following separate processes:

$$H_{n}X(g) \rightarrow H(g) + H_{n-1}X(g)$$
  $D(H - XH_{n-1})$   
 $H(g) + e^{-}(g) \rightarrow H^{-}(g)$   $-EA(H)$   
 $H_{n-1}X(g) \rightarrow H_{n-1}X^{+}(g) + e^{-}(g)$   $IP(H_{n-1}X)$ 

These energies are (1) the energy required to remove a hydrogen atom from the gaseous molecular hydride, (2) the negative electron affinity of hydrogen, and (3) another, the change in hydridic character is the sum of the changes in fairly easy to predict using concepts learned in Chaps. 1 and 3. Both the bond dissociation energy and the ionization potential would be expected to increase table. Hence, we would expect the energy of reaction 6.1 to show the same FrH and at a minimum for HF. Actual values of the energy of the reaction in Eq. data are consistent with our expectations.

Table 6.4 Values of  $\Delta H^{\circ}$  of the reaction  $H_nX \rightarrow H^- + H_{n-1}X^+$  (in kilocalories per mole)†

LiH 165	- 11	CH₄ 312	NH <sub>3</sub> 349	H <sub>2</sub> O 404	HF 521
NaH 149		SiH₄ ~ 260	PH₃ ~ 290	H <sub>2</sub> S 315	HCI 386
KH 112	2011	1991	, ,	HEM	HBr 344
				5.1 24.5	HI 295

<sup>†</sup> J. L. Franklin et al., Ionization Potentials, Appearance Potentials, and Heats of Formation of Gaseous Positive Ions, *Natl. Bur. Std.* (U.S.), *Natl. Std. Ref. Data Ser.*, NSRDS-NBS 26, 1969; R. S. Berry, *Chem. Rev.*, 69, 533 (1969).

The protonic character of a hydride  $H_nX$  can be measured by the energy of the process

$$H_n X(g) \rightarrow H^+(g) + H_{n-1} X^-(g)$$
 (6.2)

This energy can be broken up into the energies of the following processes:

$$H_{n}X(g) \rightarrow H(g) + H_{n-1}X(g) \qquad D(H-XH_{n-1})$$

$$H(g) \rightarrow H^{+}(g) + e^{-}(g) \qquad IP(H)$$

$$e^{-}(g) + H_{n-1}X(g) \rightarrow H_{n-1}X^{-}(g) \qquad -EA(H_{n-1}X)$$

We have already pointed out that  $D(H-XH_{n-1})$  would be expected to increase toward the upper right-hand corner of the periodic table. By recognizing that the electron affinity of a species is the ionization potential of the negative ion, we predict the same sort of trend for  $EA(H_{n-1}X)$ . However, a change in protonic character is equal to the corresponding change in the difference  $D(H-XH_{n-1})$  $EA(H_{n-1}X)$ , and therefore it is not possible to predict trends in protonic character without quantitative data on the trends in  $D(H-XH_{n-1})$  and  $EA(H_{n-1}X)$ . Values of  $D(H-XH_{n-1})$ , EA $(H_{n-1}X)$ , and the energy of reaction 6.2 for various molecular hydrides are given in Table 6.5. It can be seen that, within a given form family (vertical column of the periodic table), the dissociation energy changes more rapidly than the electron affinity. Hence the general tendency is for the gas-phase acidity to increase on descending a given family. However, from left to right in the periodic table, the change in electron affinity is generally slightly greater than the corresponding change in dissociation energy, at least in the case of the nonmetal hydrides. Hence there is a small increase in gas-phase acidity on going from left to right in the table. Tables 6.4 and 6.5 reveal some interesting

Table 6.5 Thermodynamic data for molecular binary hydrides, H.X

Dissociation energies, electron affinities of  $H_{n-1}X$ , and energies for the reaction  $H_nX \rightarrow$ H+ + H, X-, all in kilocalories per molet. ±

	LiH	CH <sub>4</sub>	NH <sub>3</sub>	H <sub>2</sub> O	HF
D	58	104	103	119	136
EA	14	2	17	42	78
$\Delta H^{\circ}$	358	416	400	391	372
	NaH	SiH <sub>4</sub>	PH,	H <sub>2</sub> S	HCI
D	48	91	84	93	103
EA	13	33	29	54	83
$\Delta H^{\circ}$	349	372	369	353	334
	KH	GeH₄	AsH <sub>3</sub>	H <sub>2</sub> Se	НВг
D	44	87	~73	1000 Marie 1 ~ 75	88
EA	12	40	29	10 10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	78
$\Delta H^{\circ}$	346	361	358	(1969) EEE, 533 (1969).	324
					HI
D			e-modana	nie viewpenn he h	71
EA	one struct being	Commence of the	FOR LOSS	his one or in fa	71
$\Delta H^{\circ}$		THE PERSON AND THE	Lamination 1	o reported and an arrest of a	314
				******	2293000

<sup>†</sup> J. L. Franklin et al., Ionization Potentials, Appearance Potentials, and Heats of Formation of Gaseous Positive Ions, Natl. Std. Bur. (U.S.), Natl. Std. Ref. Data Ser., NSDR-NBS 26, 1969; R.S. Berry, Chem. Rev., 69, 533 (1969).

‡ J. I. Brauman et al., J. Am. Chem. Soc., 93, 6360 (1971); K. C. Smyth and J. I. Brauman, J. Chem. Phys., 56, 1132 (1972); J. I. Brauman, private communication.

facts. For example, the gas-phase acidity of NaH is greater than that of HF Note, however, that the ionization of NaH to give Na<sup>+</sup> and H<sup>-</sup> is favored by 200 kcal mol-1 over the ionization to give H+ and Na-. On the other hand, the ionization of HF to give H+ and F- is favored by 149 kcal mol-1 over the ionization to give F+ and H-.

#### **PROBLEMS**

- 6.1 Write equations for the net reactions which occur in the following cases
  - (a) Calcium hydride is added to an aqueous solution of sodium carbonate. (b) Sodium hydride is heated to 500°C in vacuo.
- (c) LiAlH<sub>4</sub> and (C<sub>2</sub>H<sub>5</sub>)<sub>2</sub>O · BF<sub>3</sub> react in ether to form diborane. (d) Germane is passed into a stirred suspension of finely divided potassium in a high-molecular other such as dialyma. weight ether such as diglyme.
  - (e) Arsine is passed into a liquid ammonia solution of KGeH<sub>3</sub>.
  - (f) Excess of water is added to an ether solution of LiAIH<sub>4</sub>.
- 6.2 Suggest a sequence of reactions for preparing GeH<sub>3</sub>AsH<sub>2</sub> from As<sub>2</sub>O<sub>3</sub> and GeCl<sub>4</sub>.
- 6.3 Suggest a sequence of reactions for preparing CH<sub>3</sub>GeH<sub>2</sub>Br from GeH<sub>4</sub> and CH<sub>3</sub>I.
- \*6.4 In the synthesis of Ge<sub>2</sub>H<sub>6</sub> from GeH<sub>3</sub>Br and KGeH<sub>3</sub>, large amounts of (GeH<sub>2</sub>)<sub>x</sub> and GeH<sub>4</sub> form as by-products. Explain. [Hint: GeH<sub>2</sub>Br would be expected to decompose to give (GeH<sub>2</sub>)<sub>x</sub> and Br

#### **ACID-BASE REACTIONS**

We have learned that protonic character, or acidity, is an important feature of many hydrogen compounds. In this chapter we will systematically study various aspects of protonic acid-base reactions, including hydrogen bonding, the kinetics of proton-transfer reactions, and reactions in protonic nonaqueous solvents. We will conclude with a study of aprotic acid-base systems (i.e., acid-base systems not involving protons) and the completely general Lewis acid-base theory.

# GAS-PHASE PROTON AFFINITIES

## Proton Affinities of Anions

In Chap. 6 we considered the factors which influence the heats of ionization of the simple binary hydrides. A more extensive list of heats of ionization for gas-phase protonic acids, i.e., the "proton affinities" of the corresponding anions, is given in Table 7.1. These values were derived from various experimental data, including ionization potentials and appearance potentials measured by electron impact and photoionization mass spectrometry, and equilibrium data for ion-molecule reactions studied by high-pressure mass spectrometry, flowing afterglow, and ion cyclotron resonance spectrometry. The data in this table give us information regarding substituent effects free of the complications of solvation. Let us consider the effects of the substituents, R, on the acidity of an acid HAR<sub>n</sub>.

 $HAR_n \longrightarrow H^+ + AR_n^-$ 

When considering the relative acid-strengthening or acid-weakening effects of various substituents, it is helpful to break up the ionization process into the considering of the considering the relative acid-strengthening or acid-weakening effects of various substituents, it is helpful to break up the ionization process into the considering of the considering the relative acid-strengthening or acid-weakening effects of various substituents, it is helpful to break up the ionization process into the considering of the considering the relative acid-strengthening or acid-weakening effects of various substituents, it is helpful to break up the ionization process into the considering of the considering the consideri

Table 7.1 Heats of ionization of protonic acids in the gas phase (proton affinities of anions†)

Acid	$\Delta H_{\rm ion}^{\circ},$ kcal mol <sup>-1</sup>	Acid	$\Delta H_{\rm ion}^{\circ},$ kcal mol-
CH4 OTTO ARR	416.6	HCCl <sub>3</sub> ‡	~ 362
H <sub>2</sub>	400.4	GeH <sub>4</sub>	360.7
NH <sub>3</sub>	399.6	CH <sub>3</sub> SH	359.0
H <sub>2</sub> O	390.8	AsH <sub>3</sub> ‡	~ 359
CH <sub>3</sub> OH	379.2	CH <sub>3</sub> NO <sub>2</sub>	358.7
C <sub>6</sub> H <sub>5</sub> CH <sub>3</sub>	379.0	C <sub>2</sub> H <sub>5</sub> SH	357.4
C <sub>2</sub> H <sub>5</sub> OH	376.1	Cyclopentadiene	356.1
HCF <sub>3</sub>	375.6	H <sub>2</sub> S	353.4
$C_2H_2$	375.4	HCN	353.1
n-C <sub>3</sub> H <sub>7</sub> OH	374.7	C <sub>6</sub> H <sub>5</sub> OH	351.4
CH <sub>3</sub> CN	372.2	CH <sub>3</sub> COOH±	348.5
HF	371.5	HCOOH±	345.2
SiH <sub>4</sub>	371.5	H <sub>2</sub> Se	338.7
PH <sub>3</sub>	370.4	HCI	333.3
CH <sub>3</sub> COCH <sub>3</sub>	368.8	HNO <sub>3</sub> ‡	324.6
C <sub>6</sub> H <sub>5</sub> NH <sub>2</sub>	367.1	HBr	323.6
CH <sub>3</sub> SO <sub>2</sub> CH <sub>3</sub>	366.6	CF <sub>3</sub> COOH‡	322.7
CH <sub>3</sub> CHO	366.4	HI HI	314.3

<sup>†</sup> Except as noted, from J. E. Bartmess, J. A. Scott, and R. T. McIver, J. Am. Chem. Soc., 101,6046 (1979).

hypothetical steps. In the first step, the proton is removed from the acid without any rearrangement of the electrons in the remaining anion. That is, the electrons of the anion are "frozen" as they were in the neutral acid.

$$HAR_n \longrightarrow H^+ + AR_n^{-*}$$

The asterisk indicates that the anion has this frozen electron configuration. The energy of this first step is merely the coulombic interaction energy between the energy is determined by the charge on atom A, which, in turn, is determined by withdrawing) R is, the more positively charged A is and the lower the energy of increase acidity. In the second hypothetical step, electronic relaxation occurs in ground-state anion  $AR_n^{-*}$  redistribute to give the distribution of the

$$AR_n^{-*} \longrightarrow AR_n^{-}$$

This electronic relaxation step consists principally of a flow of electron density from atom A to the substituents R. The more readily the substituents can delocalize the negative charge of the anion, the more exothermic is the electronic

<sup>‡</sup> J. E. Bartmess and R. T. McIver, in "Gas-Phase Ion Chemistry," M. T. Bowers, ed., chap. 11,p. 87, Academic, New York, 1979.

relaxation step and the stronger is the acid HAR<sub>n</sub>. In principle, a third step, corresponding to the stereochemical rearrangement of the atoms in AR, , should be considered, but the energy of this step is usually relatively small and can be

ignored as a first approximation.

Table 7.1 includes data for various substituted methanes which can lose a proton from the carbon atom. All the substituted methanes in the table are stronger acids than methane itself. Fluoroform, HCF<sub>3</sub>, is a relatively weak acid even though the three fluorine atoms undoubtedly make the carbon atom highly positive in charge. This surprisingly weak acidity of HCF3 indicates a low electronic relaxation energy; apparently there is relatively little delocalization of the negative formal charge on the carbon atom in : CF<sub>3</sub>-. On the other hand, nitromethane, CH<sub>3</sub>NO<sub>2</sub>, is a relatively strong carbon acid. In this case much of the acidity is due to extensive electronic relaxation in which the carbon lone pair is delocalized into the  $\pi^*$  orbital of the NO<sub>2</sub> group.

$$\overline{\phantom{a}}: CH_2 - \stackrel{+}{N} \stackrel{O}{\longrightarrow} CH_2 = \stackrel{+}{N} \stackrel{O^-}{\longrightarrow} O^-$$

It is interesting to note the effects of methyl substitution on H<sub>2</sub>S and H<sub>2</sub>O. The methyl group is generally considered to be electron-donating relative to hydrogen. Therefore if we were to consider only the electrostatic potential term, we would predict both CH3SH and CH3OH to be weaker acids than their parent hydrides. In fact, CH<sub>3</sub>SH is a weaker acid than H<sub>2</sub>S, and CH<sub>3</sub>OH is a stronger acid than H<sub>2</sub>O. The increased acid strength of CH<sub>3</sub>OH is probably due to extensive delocalization of the negative charge of the anion by hyperconjugation:

$$CH_3-O^- \longleftrightarrow ^-H CH_2=O$$

Apparently, on going from H<sub>2</sub>O to CH<sub>3</sub>OH, the increased electronic relaxation energy overcomes the change in electrostatic potential. However, in the case of CH<sub>3</sub>SH, the data suggest that  $\pi$ - $\sigma$ \* overlap in CH<sub>3</sub>S- is so weak (because of the great difference in size between carbon and sulfur) that the electronic relaxation energy is relatively small.

Although the replacement of a hydrogen by a methyl group is sometimes acid-strengthening and other times acid-weakening, the evidence suggests that increasing the size of the alkyl group is always acid-strengthening because of an increase in polarizability and a consequent increase in the electronic relaxation energy. In Table 7.1 this effect can be seen in the decreasing  $\Delta H_{\text{ion}}^{\circ}$  values in the series CH<sub>3</sub>OH, C<sub>2</sub>H<sub>5</sub>OH, n-C<sub>3</sub>H<sub>7</sub>OH.

The energy required to dissociate a proton from a gas-phase cationic species, BH+, is called the "proton affinity" of the base B and is a measure of both the

acidity of BH+ and the basicity of B.

One of BH+ and the basicity of B.

$$BH^{+} \longrightarrow H^{+} + B \qquad \Delta E = PA(B)$$

A wide variety of proton affinities are listed in Table 7.2. Most of the bas Table 7.2 possess nonbondipe lone-pair electrons which become bondi

Table 7.2 Proton affinities of some neutral molecules and atoms

Molecule	Proto	on affinity	Enchemical realist	Prot	on affinity
or atom	eV	kcal mol-1	Molecule or atom	eV	arahizanan
Не	1.82	42	DESCRIPTION AND THE PROPERTY OF THE PROPERTY O	SEAL OF T	T MARK
Ne <sup>b</sup>	2.12	49	PH <sub>3</sub>	8.31	191.6
Ar	3.90	90	NH <sub>2</sub> OH <sup>d</sup>	~ 8.3	~ 192
H <sub>2</sub>	4.38		C <sub>2</sub> H <sub>5</sub> SH	8.35	192.6
O <sub>2</sub>	4.38	101.0	n-PrOH	8.35	192.6
Kr	4.40	101.0	n-PrSH	8.40	193.
HFc HFc	4.86	101.4	(CH <sub>3</sub> ) <sub>2</sub> O	8.42	194.
N <sub>2</sub>	4.93	112	California (Garage	it in a mail to the last	
Xe	4.93	113.7	OP(OCH <sub>2</sub> ) <sub>2</sub> CH	8.52	196.5
CO <sub>2</sub>		114.2	(CH <sub>3</sub> ) <sub>2</sub> CO	8.61	198.5
CH <sub>4</sub>	5.50	126.8	$(C_2H_5)_2O$	8.76	201.9
N <sub>2</sub> O	5.56	128.2	(CH <sub>3</sub> ) <sub>2</sub> S	8.76	202.1
CO	5.88	135.6	$B_3N_3H_6^b$	~ 8.8	~ 203
C <sub>2</sub> H <sub>6</sub>	6.03	139.0	Fe(CO) <sub>5</sub> 8	~ 8.8	~ 203
HCl <sup>c</sup>	6.07	140	CH <sub>3</sub> PH <sub>2</sub>	8.95	206.5
HBr <sup>c</sup>	6.11	141	NH <sub>3</sub>	8.98	207.0
HI¢	6.11	141	(C <sub>2</sub> H <sub>5</sub> ) <sub>2</sub> S	8.99	207.4
NF <sub>3</sub> <sup>d</sup>	6.29	145	1,6-C <sub>2</sub> B <sub>4</sub> H <sub>6</sub>		211
C <sub>2</sub> H <sub>2</sub> b	~ 6.3	~146	P(OCH <sub>2</sub> ) <sub>3</sub> CCH <sub>3</sub>	9.2	212.4
	6.59	152	Fe(C <sub>5</sub> H <sub>5</sub> ) <sub>2</sub> <sup>h</sup>	9.21	212.4
SiH <sub>4</sub> <sup>b</sup>	6.63	153	C <sub>6</sub> H <sub>5</sub> NH <sub>2</sub>	9.26	
PF <sub>3</sub> e	~6.9	~160	(CH) SO	9.27	213.7
$C_2H_4^b$	6.94	160	(CH <sub>3</sub> ) <sub>2</sub> SO <sub>2</sub>	9.28	213.9
H <sub>2</sub> O	7.50	172.9	OP(OCH <sub>3</sub> ) <sub>3</sub> °	9.29	214.2
CS <sup>b</sup>	7.55	174	HCON(CH <sub>3</sub> ) <sub>2</sub>	9.29	214.2
$2,4-C_2B_5H_7$	7.6	176	(CH <sub>3</sub> ) <sub>3</sub> As	9.34	215.4
H <sub>2</sub> S	7.66	THE RESIDENCE OF THE PARTY OF T	CH <sub>3</sub> NH <sub>2</sub>	9.39	216.6
HCN	7.69	176.7	SP(OCH <sub>3</sub> ) <sub>3</sub> e	9.39	216.6
H <sub>2</sub> CO	7.70	177.4	(CH <sub>3</sub> ) <sub>2</sub> PH	9.50	219.1
H <sub>2</sub> Se	7.70	177.5	P(OCH <sub>3</sub> ) <sub>3</sub>	9.67	222.9
OPF <sub>3</sub> e	7.8	177.6	(CH <sub>3</sub> ) <sub>2</sub> NH	9.70	223.7
CICN	7.83	179	C <sub>5</sub> H <sub>5</sub> N	9.71	223.9
AsH <sub>3</sub>	7.99	180.5	(CH <sub>3</sub> ) <sub>3</sub> N	9.90	228.2
C <sub>6</sub> H <sub>6</sub>	8.01	184.2	(CH <sub>3</sub> ) <sub>3</sub> P	9.93	228.9
CH <sub>3</sub> OH	8.05	184.8	$(C_2H_5)_3P$	10.20	235.1
NCl <sub>3</sub> d	~ 8.2	185.6	$(C_2H_5)_3N$	10.20	235.6
CH <sub>3</sub> SH	8.22	~189	LiOH	10.22	241
2H <sub>5</sub> OH	8.26	189.6	NaOH	THE RESERVE OF THE PARTY OF THE	248
CH <sub>3</sub> CN	8.27	190.4	КОН	10.8	263
" In most cas		190.7	Cooli	11.4	269

a In most cases the absolute values were calculated from values relative to NH<sub>3</sub>, using 207 kcalculated from values relative to NH<sub>3</sub>, us mol<sup>-1</sup> as the absolute proton affinity of NH<sub>3</sub>. Except as noted, data are from tabulations of R. W. Taff (private communication), R. V. Hodges, F. A. H. L. and J. G. and J. G. (private communication), R. V. Hodges, F. A. Houle, J. L. Beauchamp, R. A. Montag, and J. G. Verkade, J. Am. Chem. Soc., 102, 932 (1980), and D. L. Beauchamp, R. A. Montag, and J. G. 20, 445 (1977). Verkade, J. Am. Chem. Soc., 102, 932 (1980), and P. Kebarle, Ann. Rev. Phys. Chem., 28, 445 (1977).

<sup>&</sup>lt;sup>b</sup> R. L. DeKock and M. R. Barbachyn, J. Am. Chem. Soc., 101, 6516 (1979). <sup>c</sup> M. S. Foster and J. L. Beauchamp, *Inorg. Chem.*, **30**c., **101**, 6516 (1979).

<sup>d</sup> W. L. Jolly and C. Gin. *Int. I. Mass. Supercharge Chem.*, **14**, 1229 (1975).

W. L. Jolly and C. Gin, Int. J. Mass Spectr. Ion Phys., 25, 27 (1977). <sup>e</sup> R. V. Hodges, T. J. McDonnell, and J. L. Beauchamp, J. Am. Chem. Soc., 102, 1327 (1980).
<sup>f</sup> D. A. Dixon. Inorg. Chem. 10, 502 (1980).

<sup>\*</sup> M. S. Foster and J. L. Beauchamp, J. Am. Chem. Soc., 97, 4808 (1975). <sup>h</sup> M. S. Foster and J. L. Beauchamp, J. Am. Chem. Soc., 97, 4814 (1975).

trons in the protonated species. However, some of the bases contain no lone-pair electrons; these are  $\sigma$  or  $\pi$  bond-pair bases which react with protons to form species containing three-center bonds. For example, the protonations of methane and hydrogen may be written as follows:

$$CH_4 + H^+ \longrightarrow H_3C \stackrel{H^+}{\smile} H$$

$$H_2 + H^+ \longrightarrow H \stackrel{H^+}{\smile} H^+$$

In Chap. 10, the concept of three-center bonding is discussed further.

We have shown that the energy of ionization,  $\Delta H_{\text{ion}}^{\circ}$ , of a neutral acid HAR, can be expressed as follows:

$$\Delta H_{\text{ion}}^{\circ} = D(H - AR_n) + IP(H) - EA(AR_n)$$

On going from one acid to another, IP(H) of course is constant and  $D(H-AR_n)$  might be expected to be fairly closely correlated with  $\Delta H_{\rm ion}^{\circ}$ , particularly when the molecules  $HAR_n$  have similar electronic structures. Hence for the isoelectronic sets of  $AH_n$  molecules  $CH_4$ ,  $NH_3$ ,  $H_2O$ , HF and  $SiH_4$ ,  $PH_3$ ,  $H_2S$ , HCI, the heat of ionization would be expected to be linearly related to the electron affinity of the radical. This expectation is confirmed in Fig. 7.1, which is a plot of  $\Delta H_{\rm ion}^{\circ}(AH_n)$  versus  $EA(AH_{n-1})$ .




Figure 7.1 Plot of heat of ionization for the acids  $AH_n$  versus electron affinity for the  $AH_{n-1}$  radicals. The lines correspond to isoelectronic series.




Figure 7.2 Plot of proton affinity versus ionization potential for isoelectronic sets of bases. [Adapted with permission from R. L. DeKock and M. R. Barbachyn, J. Am. Chem. Soc., 101, 6516 (1979). Copyright 1979 American Chemical Society.]

Similarly, the proton affinity of a base B can be expressed as follows:

$$PA(B) = D(H - B^{+}) + IP(H) - IP(B)$$

where  $D(H - B^+)$  is the energy required to dissociate a hydrogen atom from the protonated base and IP(B) is the ionization potential of B. For reasons analogous of bases to be linearly related to the corresponding ionization potentials. Such linear correlations are shown for the isoelectronic bases NH<sub>3</sub>, H<sub>2</sub>O, HF, Ne and Correlation of proton affinity with ionization potential for a wide variety of bases. They found that the data for lone-pair bases are approximately represented by the following equation:

$$PA = 14.7 - 0.597IP$$

and that the data for  $\pi$  and  $\sigma$  bond-pair bases are approximately represented by the equation

$$PA = 13.3 - 0.593IP$$

#### AQUEOUS ACIDITIES OF PROTONIC ACIDS

#### Binary Hydrides

The aqueous pK values ( $pK = -\log K_a$ ) of the binary hydrides of the nonmetals are listed in Table 7.3. These values have been obtained by various methods which we shall briefly describe. The pK values for HF, H<sub>2</sub>O, H<sub>2</sub>S, H<sub>2</sub>Se, and H<sub>2</sub>Te were obtained by conventional electrochemical methods generally involving emf data from cells with pH-sensitive glass electrodes. The values for HCl, HBr, and HI were estimated from thermodynamic data, making the assumption that the standard free energy of dissolution of gaseous HX to form undissociated aqueous HX is zero.<sup>2</sup> Thus, in the case of HBr,

$$\begin{array}{ccc} \text{HBr}(g) & \rightarrow & \text{H}^+(aq) + \text{Br}^-(aq) \\ \text{HBr}(aq) & \rightarrow & \text{HBr}(g) \\ \text{HBr}(aq) & \rightarrow & \text{H}^+(aq) + \text{Br}^-(aq) \end{array} \qquad \begin{array}{c} \Delta G^\circ = -11.85 \text{ kcal mol}^{-1} \\ \Delta G^\circ \approx 0 \\ \overline{\Delta G^\circ} \approx -11.85 \text{ kcal mol}^{-1} \end{array}$$

Hence

$$pK = -\log K \approx \frac{-11.85}{2.3RT} = \frac{-11.85}{1.364} = -8.7$$
The pK value for DH was at a form biratio data on the base catalyzed

The pK value for PH<sub>3</sub> was estimated from kinetic data on the base-catalyzed exchange of hydrogen and deuterium atoms between PH<sub>3</sub> and D<sub>2</sub>O.<sup>3</sup> The rate of reaction was found to be first order in both PH<sub>3</sub> and OD<sup>-</sup>, and the mechanism of the reaction was assumed to be

$$PH_3 + OD^- \xrightarrow{slow} PH_2^- + HOD$$
  
 $PH_2^- + D_2O \xrightarrow{fast} PH_2D + OD^-$ 

<sup>3</sup> R. E. Weston, Jr., and J. Bigeleisen, J. Am. Chem. Soc., 76, 3078 (1954).

Table 7.3 Aqueous pK values of the binary hydrides of the nonmetals

	11112	. STATE TA SOLDING	
CH <sub>4</sub> ~ 44	NH <sub>3</sub> 39	H <sub>2</sub> O 15.74	HF 3.15
$SiH_4$ $\sim 35$ $GeH_4$	PH <sub>3</sub> 27 210 m 5	H₂S 6.89	HCl -6.3
25	AsH <sub>3</sub> ≤ 23	H <sub>2</sub> Se 3.7	HBr -8.7
n aqueous	in de 82≥ ne acetyl group stable acidity ii	H <sub>2</sub> Te 2.6	HI -9.3

<sup>&</sup>lt;sup>2</sup> R. T. Myers [*J. Chem. Educ.*, **53**, 17, 802 (1976)] has made the assumption that the molecules HCl, HBr, and HI all form hydrogen bonds with water in the same way that HF does and that therefore the standard free energy of solution has the same value, – 5.6 kcal mol<sup>-1</sup>. Thus he obtains pK values for HCl, HBr, and HI which are 4.1 units greater than those in Table 7.3. However, see the comments of L. Pauling [*J. Chem. Educ.* **53**, 762 (1976)].

The rate constant for the exchange, and presumably for the slow step of the proposed mechanism, is  $0.4 \, M^{-1} \, \mathrm{s}^{-1}$  at 25°C. Now, in ordinary aqueous solution exchange probably proceeds by the same sort of mechanism, i.e.,

$$PH_3 + OH^- \xrightarrow{k_1 \atop k_2} PH_2^- + H_2O$$

If we neglect isotope effects, then  $k_1 = 0.4 \ M^{-1} \ s^{-1}$ , and, because the reverse reaction is an extremely exothermic proton transfer, we may assume  $k_2 \approx 10^{\circ}$  $M^{-1}$  s<sup>-1</sup>. Hence for the latter reaction we can calculate the equilibrium constant  $K' = k_1/k_2 = 4 \times 10^{-12}$ . This value is based on the concentrations of all species expressed as molarity. To obtain the value based on the usual convention of unit activity for water, we must divide K' by the molarity of water; hence, K= $(4/55.5) \times 10^{-12} \approx 10^{-13}$ . Multiplication by the ionization constant of water yields  $K_a = 10^{-27}$  for  $PH_3 \Rightarrow H^+ + PH_2^-$ 

$$PH_3 \rightleftharpoons H^+ + PH_2^-$$

The relative pK values in liquid ammonia for PH<sub>3</sub>, GeH<sub>4</sub>, and AsH<sub>3</sub> were determined from equilibrium measurements.4 The tabulated values for the aqueous pKs of GeH<sub>4</sub> and AsH<sub>3</sub> are based on the assumption that the relative pK values of the acids are the same in water and liquid ammonia. The pK value for NH<sub>3</sub> is based on the measured self-ionization constant for liquid ammonia and the general observation that pK values of acids are about 10 units lower  $\mathbb{I}$ ammonia than in water. The value for CH4 is an estimate based on correlations between base-catalyzed hydrogen exchange rates for hydrocarbons and the comsponding pK values. The value for SiH<sub>4</sub> is obtained from a simple interpolation

From the data in Table 7.3 it is obvious that the trend in the aqueous acidity of binary hydrides within a family or group of elements is the same as the corresponding trend in gas-phase acidity; i.e., acidity increases on descending the family. It is also obvious that there is a marked trend toward greater acidity from left to right within a horizontal series of elements. This horizontal trend is in contrast to the absence of a marked trend in the corresponding gas-phase acidities. ties. Undoubtedly the strong horizontal trend in aqueous acidities is due to the increase in anionic hydration energy from left to right (i.e., from larger ions 10 smaller ions). The interaction energy of a point charge with a dipole increases with decreasing distance between the charge and the dipole; therefore ionic hydration energy is expected to increase with decreasing ionic radius. For most practical purposes, only the hydrides of groups VI and VII show any detectable acidity in aqueous solution. The acids with negative pK values (HCl, HBr, and HI) are essentially completely ionized at all concentrations.

The acidity of a hydride of group IV, V, or VI can be increased by replacing one (or more, when possible) of the hydrogen atoms in the molecule by a relatively electronegative atom or group. electronegative atom or group. The relative effects of various substituents on the aqueous pK values of water, ammonia, and methane can be seen in the data of Table 7.4. Notice that substitutions, and methane can be seen in the data of CH (0). Table 7.4. Notice that substitution of ammonia with the acetyl group, CH<sub>3</sub>CO, vields a compound (acetamida) yields a compound (acetamide) which has a barely detectable acidity in aqueous

<sup>&</sup>lt;sup>4</sup> T. Birchall and W. L. Jolly, Inorg. Chem., 5, 2177 (1966).

Table 7.4 Aqueous pK values of some derivatives of water, ammonia, and methane

	p <i>K</i>				
X	нох	NH <sub>2</sub> X	CH <sub>3</sub> X		
Н	16	39	~44		
C <sub>6</sub> H <sub>5</sub>	10	27	38		
CH <sub>3</sub> CO	5	15	~ 20		
CN	4	10.5	20		
NO <sub>2</sub>	-2	7	10		

solution. Methane must be substituted with the much more electronegative nitro group,  $NO_2$ , to obtain a compound (nitromethane) with detectable acidity in aqueous solution. It is significant that the order of the acidifying strength of the various groups is the same for the aquo acids, the ammono acids, and the methane acids and that for a given substituent, X, the acidity always increases in the order  $CH_3X < NH_2X < HOX$ .

#### **Hydroxy Acids**

By far the most important family of acids in aqueous solutions are the aquo or "hydroxy" acids, HOX. A very simple method for estimating the pK value of such an acid is based on the formal charge of the atom to which the OH group is attached.<sup>5</sup> When the formal charge on this atom is zero, as in H-O-Cl, the pK value is about 8. When the formal charge is +1, as in phosphorous acid,

the pK value is about 3. When the formal charge is +2, as in sulfuric acid,

the pK is about -2. When the formal charge is +3, as in perchloric acid,

<sup>&</sup>lt;sup>5</sup> J. Ricci, J. Am. Chem. Soc., 70, 109 (1948); W. M. Latimer, "Oxidation Potentials," 2d e Prentice-Hall, Englewood Cliffs, N.J., 1952.

Table 7.5 pK values for some hydroxy acids†

arge +3	13	yd	© ♥ ♥ Prevente Smort An about to
Formal charge +3			HCIO <sup>4</sup> HMnO <sup>4</sup>
2		pK <sub>2</sub>	2.0
Formal charge +2		pK,	♥ ♥ ♥ V
Form			HNO <sub>3</sub> S H <sub>2</sub> SO <sub>4</sub> H <sub>2</sub> SeO <sub>4</sub>
		pK <sub>3</sub>	13.0 12.3 12.3 13.0
1+ 001	1 2 2 1 7	pK <sub>2</sub>	10.3 8.0 8.3 7.0 7.1 6.2 6.2 6.0
Lormol charge +1	rollinai ciie	pK <sub>1</sub>	3.6¶ 3.2 2.7 2.6 2.3 2.2 2.0 2.0 1.8 1.6
			H,CO,\$ HNO,\$ H,TeO, H,SeO, H,AsO, H,PO, H,PO, H,PO, H,PO, H,PO, H,PO, H,PO, H,PO, H,PO, H,PO,
		pK <sub>2</sub>	15.7
	Formal charge; U	pK,	~ 16 11.0 11.0 9.2 8.8 8.7 8.6 7.2
	FOI		HOCH, HOH HOI H,AsO, H,TeO, HOB HOB HOCI

+ W. L. Jolly, "The Chemistry of the Non-Metals," p. 16, Prentice-Hall, Englewood Cliffs, N.J., 1966. ‡ Formal charge of atom bonded to hydroxy group.

 $\S$  Formal charge for structure in which  $\pi$  bonds are ignored and in which the central atom lacks an octet.

Corrected for unhydrated CO2.

the pK is about -7. In the case of di- and tribasic acids (e.g.,  $H_3PO_3$  and  $H_3PO_4$ , respectively) the successive ionization constants decrease by factors of  $10^{-5}$ .

For non- $\pi$ -bonded hydroxy acids that conform to the Lewis octet theory, the formal charge on the central atom is simply equal to the number of nonhydroxyl oxygen atoms,  $n_0$ . Thus the formal charge in the case of HOCl, for which  $n_0 = 0$ , is zero, and the formal charge in the case of  $H_2SO_4$ , for which  $n_0 = 2$ , is +2. Using the rough pK rules we have outlined, the pK of a *neutral* hydroxy acid is then given by the formula

$$pK = 8 - 5n_0$$

This formula gives approximately the right pK even in the case of  $\pi$ -bonded acids such as  $H_2CO_3$  and  $HNO_3$ . Of course, in the case of *anionic* acids such as  $HSO_4^-$ , one must take account of the 5-unit increase in pK upon ionization; thus in the case of  $HSO_4^-$ , the pK is estimated as -2 + 5 = 3.

The pK values for various hydroxy acids given in Table 7.5 generally agree with the values predicted by these simple rules within  $\pm 1$  pK unit.<sup>6</sup> For many purposes rough estimates of this sort are quite adequate. However, the data in Table 7.5 show that the pK values are influenced by more than just the formal charge of the atom bonded to the hydroxyl group or the number of nonhydroxyl oxygen atoms. It can be seen that, for acids having analogous structures and the same formal charges, the acidity increases with increasing electronegativity of the atom bonded to the hydroxyl group. When greater predictive accuracy is required, the following equation of Branch and Calvin<sup>7</sup> can be used for estimating the pK of a hydroxy acid.

pK = 
$$16 - \sum I_{\alpha} \left(\frac{1}{2.8}\right)^i - \sum I_{c} \left(\frac{1}{2.8}\right)^i - \log \frac{n}{m}$$

The summations are carried out over all the atoms in the group attached to the OH group. The value of  $I_{\alpha}$  is a measure of the electron-attracting ability of the atom; values of  $I_{\alpha}$  for several important elements are given in Table 7.6. The term  $I_{c}$  is 12.3 times the formal charge of the atom, and i is the number of atoms

<sup>6</sup> W. L. Jolly, "The Chemistry of the Non-Metals," p. 16, Prentice-Hall, Englewood Cliffs, N.J., 966.

G. E. K. Branch and M. Calvin, "The Theory of Organic Chemistry," Prentice-Hall, Englewood Cliffs, N.J., 1941.

Table 7.6 Values of I for use in Branch and Calvin's equation†

0	0	4.0	P	1.1
8.5	S	3.4	As	1.0
7.5	Se	2.7	C	-0.4
6.0	N	1.3	C <sub>6</sub> H <sub>5</sub>	MOT N 2.

† G. E. K. Branch and M. Calvin, "The Theory of Organic Chemistry," Prentice-Hall, Englewood Cliffs, N.J., 1941

separating the OH group from the atom in question. The last term in the equation accounts for the increase in acidity due to multiple —OH groups in the acid and the decrease in acidity due to multiple —O groups in the anion; n is the number of —OH groups in the acid, and m is the number of —O groups in the anion. We shall illustrate the use of this equation in the estimation of the pK of the dihydrogen phosphate ion,

The calculated value 7.3 is in good agreement with the experimental value 7.1. Qualitative trends in acidity are not always the same in aqueous solution and in the gas phase. For example, in aqueous solution, the acid strengths of the haloacetic acids decrease in the order<sup>8</sup> FCH,COOH > ClCH<sub>2</sub>COOH > BrCH<sub>2</sub>COOH, whereas in the gas phase the acid strengths decrease in the opposite order BrCH2COOH > CICH2COOH > FCH2COOH. In the gas phase, these acidities do not show the trend that one would predict from the relative electrone gativities of the halogens. Obviously the gas-phase trend must be established by the relative electronic relaxation energies accompanying the ionizations: The relaxation energy and the stability of the anion increase as the polarizability of the halogen atom increases. However, in aqueous solution, the relaxation energy is affected by the polarization of the solvent in addition to the polarization of the halogen atom. The solvent polarization is greatest for the smallest halogen because the solvent molecules are closest to the center of the negatively charged halogen atom in this case. In aqueous solution, the polarization of the solvent dominates over the polarization of the halogen atom, and the order of acidity is the opposite of that in the gas phase.

<sup>\*</sup> R. T. Morrison and R. N. Boyd, "Organic Chemistry," 3d ed., p. 600, Allyn and Bacon, Boston.
1973.

<sup>&</sup>lt;sup>9</sup> H. Hiraoka, R. Yamdagni, and P. Kebarle, J. Am. Chem. Soc., 95, 6833 (1973).

### Transition-Metal Carbonyl Hydrides and state of the second threat sint second 10

Hydrogen atoms bonded to transition-metal atoms generally do not exhibit significant acidic character, but when the other ligands of the metal atom are strongly electron-withdrawing, acidic behavior is observed. Thus the carbonyl hydrides, in which the metal atoms have rather high positive charges because of back bonding to the CO groups (see Chap. 18), are acids in aqueous and alcohol solutions. The pK values in methanol of some carbonyl hydrides are given in Table 7.7. It can be seen that replacement of a CO in HCo(CO)<sub>4</sub> by a much better σ donor, P(C<sub>6</sub>H<sub>5</sub>)<sub>3</sub>, causes a great reduction in acidity.

The acidity of these compounds should not be taken as evidence that the hydrogen atoms in the compounds are positively charged. In fact, x-ray photoelectron spectroscopic studies of such compounds indicate that the hydrogen atoms are negatively charged.10 It is interesting that HMn(CO)5, which is a fairly strong acid (pK = 7.1), shows hydridic behavior when treated with a sufficiently strong acid. Neat trifluoromethanesulfonic acid reacts with HMn(CO), to give

hydrogen and a solution containing Mn(CO)<sub>5</sub>+ ions:11

$$HMn(CO)_5 + HO_3SCF_3$$
  $\xrightarrow{HO_3SCF_3}$   $H_2 + [Mn(CO)_5](O_3SCF_3)$ 

<sup>10</sup> H. W. Chen, W. L. Jolly, J. Kopf, and T. H. Lee, J. Am. Chem. Soc., 101, 2607 (1979). <sup>11</sup> W. C. Trogler, J. Am. Chem. Soc., 101, 6459 (1979).

Table 7.7 pK values of some carbonyl hydrides in methanol at 25°C†

pK
<0
6.8
6.96‡
7.1‡
11.8
12.2
12.8
13.4
14.3
14.7

<sup>†</sup> Data from H. W. Walker, C. T. Kresge, P. C. Ford, and R. G. Pearson, J. Am. Chem Soc., 101, 7428 (1979), and R. A. Schunn, in "Transition Metal Hydrides," E. L. Muetterties, ed., chap. 5, Dekker, New York, 1971. ‡ In H<sub>2</sub>O.

Of course this result does not imply a mechanism with the improbable step  $H^+ + H^- \rightarrow H_2$ . However, the observed products are those expected from the reaction of a proton from  $HO_3SCF_3$  with a hydride ion from  $HMn(CO)_5$ .

#### HYDROGEN BONDING12

In some compounds, individual hydrogen atoms are bound simultaneously to two (or sometimes more) electronegative atoms. The electronegative atoms are said to be "hydrogen-bonded." The first proposal of such bonding was made by Moore and Winmill,<sup>13</sup> who explained the weakness of trimethylammonium hydroxide relative to tetramethylammonium hydroxide by postulating the structure

Of course it is now recognized that the hydrogen atom, with only one valence atomic orbital, cannot exceed a total covalency of 1. Hydrogen bonds are generally indicated by dotted lines, as follows:

Evidence for hydrogen bonding is found in a wide variety of experimental data. In the following paragraphs we shall describe some of this evidence.

The data in Table 7.1 show that the gas-phase acidity of toluene is greater than that of water. That is, the proton affinity of  $OH^-$  is greater than that of  $C_6H_5CH_2^-$ . Yet every chemist knows that toluene shows no significant ionization in aqueous solution, whereas water itself self-ionizes to an important extent. It has been estimated that the  $pK_a$  of toluene in water is about 38; this should be compared with the  $pK_a$  of water which, when the concentration of water is expressed as molarity, is about 16. The enormous change in the relative acidities upon going to aqueous solution is due to the relatively strong stabilization of the aqueous hydroxide ion by hydrogen bonding. It is believed that the aqueous hydroxide ion is hydrated to form species of the type

<sup>&</sup>lt;sup>12</sup> L. Pauling, "The Nature of the Chemical Bond," 3d ed., pp. 449 – 504, Cornell University Press, Ithaca, N.Y., 1960; G. C. Pimentel and A. L. McClellan, "The Hydrogen Bond," Freeman, San Francisco, 1959.

<sup>&</sup>lt;sup>13</sup> T. S. Moore and T. F. Winmill, *J. Chem. Soc.*, **101**, 1635 (1912). Also see W. M. Latimer and W. H. Rodebush, *J. Am. Chem. Soc.*, **42**, 1419 (1920), and M. L. Huggins, *Phys. Rev.*, **18**, 333 (1921); **19**, 346 (1922).

To some extent, this hydrogen bonding may be looked upon as an interaction of the dipole moment of the O—H bonds in the water molecules with the negative charge of the OH<sup>-</sup> ion. Because the OH<sup>-</sup> ion is very small, the water dipoles can approach the ion very closely and interact strongly. On the other hand, the benzyl anion is relatively large, and the energy of interaction with water molecules is relatively small.

The effect of anion size on gas-phase hydration energy is shown by the data in Table 7.8. Notice that the fluoride ion, which has a size comparable to that of the hydroxide ion, also has very high hydration energies. One would expect that the  $-\Delta H^{\circ}$  for the reaction  $X^{-}(H_{2}O)_{n-1}(g) + H_{2}O(g) \rightarrow X^{-}(H_{2}O)_{n}(g)$  would approach the heat of vaporization of water, 10.5 kcal mol<sup>-1</sup>, as n approached  $\infty$ . The data of Table 7.8 show that the  $-\Delta H^{\circ}$  values for iodide have essentially this value even for low values of n. In other words, a water molecule interacts with an iodide ion with about the same energy that it does with other water molecules in liquid water.

Because of the strong hydrogen bonding of the hydroxide ion in water and other hydroxylic solvents such as alcohols, much of the intrinsic basicity of the ion is lost when it is dissolved in such solvents. However, by using a solid alkali-metal hydroxide it is possible to take advantage of the strong basicity of the hydroxide ion. Thus a suspension of potassium hydroxide in a nonhydroxylic solvent such as dimethyl sulfoxide can be used to deprotonate extremely weak acids, such as triphenylmethane (aqueous  $pK \approx 30$ ), phosphine (aqueous  $pK \approx 27$ ), and germane (aqueous  $pK \approx 25$ ). 14

$$2KOH(s) + HA \rightarrow K^+ + A^- + KOH \cdot H_2O(s)$$

<sup>14</sup> W. L. Jolly, J. Chem. Educ., 44, 304 (1967); Inorg. Synth., 11, 113 (1968).

Table 7.8 Gas-phase hydration energies of anions†  $\Delta H^{\circ}$  in kilocalories per male for  $X^{\circ}(H, O)$ ,  $(g) + H_{\circ}O(g) \rightarrow X^{\circ}(H, O)$ 

OH- F-	Cl-	Br	I-
15.1	.3 .6 .7 .7 .11.7 .5	12.6 12.3 11.5 10.9	10. 9. 9.

<sup>&</sup>lt;sup>†</sup> M. Arshadi, R. Yamdagni, and P. Kebarle, *J. Phys. Chem.*, **74**, 1475 (1970); M. Arshadi and Kebarle, *J. Phys. Chem.*, **74**, 1483 (1970).

This result is particularly impressive when one remembers that, in aqueous solution, the hydroxide ion is incapable of quantitatively deprotonating any acid with a pK higher than about 14.

The compounds HF, H<sub>2</sub>O, and NH<sub>3</sub> are hydrogen-bonded in both the solid and liquid states. However, only in the case of the H<sub>2</sub>O molecule, which contains two hydrogen atoms and one oxygen atom in a nonlinear arrangement, is the bonding ideally suited for forming a three-dimensional network of hydrogen bonds.<sup>15</sup> Each water molecule can act both as a donor and as an acceptor of two hydrogen atoms. This dual ability is clearly illustrated by the crystal structure of ordinary hexagonal ice, shown in Fig. 7.3. In ice each oxygen atom is surrounded by four other oxygen atoms, and the hydrogen atoms are located between the oxygen atoms, but not midway. Each oxygen atom is directly

15 F. H. Stillinger, Science, 209, 451 (1980).




Figure 7.3 Structure of ice, showing the hydrogen bonds. Notice the irregular arrangement of the O—H···O bonds. (From L. Pauling, "The Nature of the Chemical Bond," 3d ed., pp. 449-504. Cornell University Press, Ithaca, N.Y., 1960. Used by permission of Cornell University Press.)

bonded to two hydrogen atoms at a distance of 1.01 Å and is hydrogen-bonded to the other two hydrogen atoms at a distance of 1.75 Å. (This asymmetry is typical of most hydrogen bonds.) Except for the restriction that there are always two hydrogen bonds and two normal O-H bonds to each oxygen atom, the distribution of these bonds throughout the lattice is random, even in ice which has been slowly cooled to the neighborhood of 0 K. This randomness is responsible for a residual entropy of  $R \ln \frac{3}{2} = 0.81$  cal deg<sup>-1</sup> mol<sup>-1</sup> in ice at 0 K. From Fig. 7.3 it can be seen that ice has a rather open structure, with many holes in the lattice. When ice melts, many of the hydrogen bonds are broken, permitting the structure to collapse and causing an increase in density. Because the processes of melting and vaporization for HF, H<sub>2</sub>O, and NH<sub>3</sub> require the breaking of hydrogen bonds, these hydrides have abnormally high heats of melting and vaporization as well as high melting points and boiling points. In Fig. 7.4 the boiling points for various nonmetal hydrides are plotted against the periodic-table positions of the nonmetals. Clearly the points for HF, H2O, and NH3 deviate markedly from the positions expected if these compounds were unassociated in the liquid state. The point for HCl also shows a significant deviation, probably attributable to a small amount of hydrogen bonding.

The hydrogen bonding in HF is so strong that it persists even in the gaseous state. At 20°C and 745 torr, 80 percent of the HF molecules are in the form of




Figure 7.4 Boiling points of some molecular hydrides and, for comparison, the noble gases. (Reproduced with permission from W. L. Jolly, "The Chemistry of the Non-Metals," Prentice-Hall, Englewood Cliffs. N.J., 1966.)

(HF)6 polymers. In aqueous solution, HF is a weak acid which interacts with the fluoride ion to form the bifluoride ion HF, -: be to the bifluoride ion HF, -:

$$F^- + HF \implies HF_2^- \qquad K = 3.9$$

In salts containing this anion, the proton is located midway between the two fluoride ions; hence this hydrogen-bonded system has no residual entropy at 0 K.

The open structure of ice is a consequence of the hydrogen bonding. Many other compounds have structures based on hydrogen bonding. For example, the helical configurations of polypeptide chains would not be possible if the chains were not "knit" together by N-H · · · O hydrogen bonds. (See Fig. 7.5.) Crystalline boric acid contains layers of B(OH), molecules held together by hydrogen bonds, as shown in Fig. 7.6. Crystalline potassium dihydrogen phosphate, KH<sub>2</sub>PO<sub>4</sub>, contains PO<sub>4</sub> tetrahedra, each of which is surrounded tetrahedrally by four other PO4 groups. A drawing of the structure is shown in




Figure 7.5 The  $\alpha$  helix of polypeptide chains, showing the N—H...O hydrogen bonds. (From L. Pauling, "The Nature of the Chemical Bond," 3d ed., Cornell University Press, Ithaca, N.Y., 1960. Used by permission of Cornell University D. University Press.)

Figure 7.6 Arrangement of atoms in a layer of crystalline boric acid.

Figure 7.7 The environment of an H<sub>2</sub>PO<sub>4</sub> ion in KH,PO4.

Fig. 7.7. A feature not shown by the drawing is that the PO<sub>4</sub> groups are connected by hydrogen bonds, with two short O — H bonds and two long O · · · H bonds to each PO<sub>4</sub> group. Below 121 K, all the short O — H bonds are on the same side of the PO<sub>4</sub> groups, as indicated schematically in the following:

By appropriate application of an electric field to the crystal, the polarization of the hydrogen bonds can be reversed, as indicated in the following:

Because of this spontaneous and reversible electric polarization of KH<sub>2</sub>PO<sub>4</sub>, it is a member of the class of materials known as "ferroelectrics." Above 121 K, thermal agitation breaks down the ordering of the hydrogen bonds to produce a random structure with no net spontaneous polarization. Above this temperature, the crystal is said to be "paraelectric." Evidence for the ferroelectric-paraelectric transition can be seen in the plot of heat capacity versus temperature shown in Fig. 7.8. The shaded area under the peak around 121 K corresponds to the energy required to randomize the hydrogen bonds.

The oxonium ion,  $H_3O^+$ , is a species found in many solid acid hydrates. Thus  $HClO_4 \cdot H_2O$  is really a salt,  $H_3O^+ClO_4^-$ . Similarly,  $HCl \cdot H_2O$  is  $H_3O^+ClO_4^-$ .

<sup>16</sup> W. C. Hamilton and J. A. Ibers, "Hydrogen Bonding in Solids," Benjamin, New York, 1968.




Figure 7.8 Plot of heat capacity versus temperature for KH<sub>2</sub>PO<sub>4</sub>. The peak corresponds to the ferroelectric-paraelectric transition. (Reproduced with permission from W. C. Hamilton and J. A. Ibers. "Hydrogen Bonding in Solids." Benjamin, New York, 1968.)

and  $\text{HNO}_3 \cdot 3\text{H}_2\text{O}$  is  $\text{H}_3\text{O}^+\text{NO}_3^- \cdot 2\text{H}_2\text{O}$ . In these and similar compounds, the  $\text{H}_3\text{O}^+$  ion is pyramidal, with an H-O-H bond angle of approximately 115°. The <sup>17</sup>O nmr spectrum of a solution, in liquid  $\text{SO}_2$  at  $-15^\circ\text{C}$ , of approximately equimolar amounts of <sup>17</sup>O-enriched  $\text{H}_2\text{O}$ , HF, and  $\text{SbF}_5$ , consists of a 1:3:3:1 quartet indicative of the three equivalent protons in the  $\text{H}_3\text{O}^+$ . The magnitude of the <sup>17</sup>O-H coupling constant (i.e., the separation of the lines in the quartet) corresponds to essentially  $sp^2$  hybridization of the oxygen and is suggestive of a planar or near-planar oxonium ion.<sup>17</sup> In aqueous solutions of strong acids, the oxonium ion undoubtedly exists in a highly hydrated, or hydrogen-bonded, form. Cations of the general formula  $\text{H}(\text{H}_2\text{O})_n^+$  have been identified in the gas phase by mass spectroscopy and in various solid compounds by x-ray and neutron diffraction. For example, the ions  $\text{H}_5\text{O}_2^+$ ,  $\text{H}_7\text{O}_3^+$ ,  $\text{H}_9\text{O}_4^+$ , and  $\text{H}_{13}\text{O}_6^+$  have been structurally characterized in crystalline hydrates.

Relatively few hydrates of the hydroxide ion have been characterized. However, a complex mixed salt containing sodium and triethylmethylammonium cations and tris(thiohydroximato)chromate(III) and hydroxide anions has been shown by an x-ray study to contain the hydroxide analog of the bifluoride ion,  $H(OH)_2^-$  or  $H_3O_2^-$ , shown in Fig. 7.9. The O—O distance of 2.29 Å is remarkably short; the proton of the hydrogen bond probably lies midway between the oxygen atoms, analogously to the proton in  $HF_2^-$ . It has been suggested on the basis of spectral data that the anion in the monohydrate of tetramethylammonium hydroxide is  $H_6O_4^{2-}$ , with a tetrahedral arrangement of oxygen atoms,

<sup>17</sup> G. D. Mateescu and G. M. Benedikt, J. Am. Chem. Soc., 101, 3959 (1979).

<sup>18</sup> K. Abu-Dari, K. N. Raymond, and D. P. Freyberg, *J. Am. Chem. Soc.*. **101**, 3688 (1979); A. Bino and D. Gibson, *J. Am. Chem. Soc.*. **103**, 6741 (1981).

<sup>19</sup> I. Gennick, K. M. Harmon, and J. Hartwig, *Inorg. Chem.*, **16**, 2241 (1977).




Figure 7.9 A perspective view of the H<sub>3</sub>O<sub>2</sub>-anion, showing the weak hydrogen bonds between it and four adjacent waters of crystallization. [Adapted with permission from K. Abu-Dari, K. N. Raymond, and D. P. Freyberg, J. Am. Chem. Soc., 101, 3688 (1979). Copyright 1979 American Chemical Society.]

Table 7.9 Ionic conductances in water at 25°C

250	OH-	192	
330	THE RESIDENCE OF LUCY LAND	TO THE PROPERTY OF THE PARTY OF	
51	Cl-	76	
74	NO <sub>3</sub>	H 69/171/10-UV	
64	C <sub>2</sub> H <sub>3</sub> O <sub>2</sub> -	three (14) waler	
	74 74	51 74 Cl- NO <sub>3</sub> -	51 74 Cl- 76 NO <sub>3</sub> - 71

each of which is hydrogen-bonded to the other three oxygen atoms, as shown in the following:

Infrared spectroscopy is commonly used to detect, and to measure quantitatively, hydrogen bonding. A change in the frequency, width, and intensity of an X—H stretching band is particularly diagnostic. For example, the stretching frequency band of an isolated O—H bond might occur around 3500 cm<sup>-1</sup> and have a width of less than 10 cm<sup>-1</sup>. After strong hydrogen bonding, the frequency might occur around 1700 cm<sup>-1</sup>, the bandwidth would be several hundred wave numbers, and the band intensity would probably have increased markedly.

The data in Table 7.9 show that the aqueous ionic conductances of the hydrogen ion and the hydroxide ion are extremely high in comparison with those of other ions.

It is believed that these abnormally high conductances are due to the hydrogen bonding in water and to the fact that the H<sup>+</sup> and OH<sup>-</sup> ions are strongly hydrogen-bonded. Consider the following picture of an oxonium ion and some of its associated water molecules:

By the slight shift of the protons in three hydrogen bonds, the oxonium ion can in effect move to the other end of the chain of water molecules:

A similar conduction mechanism is possible for the hydroxide ion:

Thus these ions can migrate through an aqueous solution without having to shove aside water molecules and without having to carry along shells of coordinated water molecules, as is necessary in the migration of other aqueous ions.

#### KINETICS OF PROTON-TRANSFER REACTIONS

The migration of a proton through water involves steps corresponding to the transfer of a proton from one water molecule to another. This process may be written as a chemical reaction:

$$H_{2}O + H_{3}O^{+} \rightarrow H_{3}O^{+} + H_{2}O$$

The rate constant for this bimolecular aqueous reaction has been determined by nmr line width measurements<sup>20</sup> to be  $k = 6.0 \times 10^{11} e^{-2.4/RT} \ M^{-1} \ s^{-1}$  or  $k = 1 \times 10^{10} \ M^{-1} \ s^{-1}$  at 25°C. The migration of a hydroxide ion through water likewise corresponds to successive transfers of protons, but between *hydroxide* ions,  $H_2O + OH^- \rightarrow OH^- + H_2O$ . The nmr-determined<sup>20</sup> rate constant for this reaction is  $k = 1.0 \times 10^{11} e^{-2.1/RT} \ M^{-1} \ s^{-1}$ , or  $k = 3 \times 10^9 \ M^{-1} \ s^{-1}$  at 25°C. Both of these reactions are among the fastest known reactions in aqueous solution. The fastest aqueous reaction is the transfer of a proton from a water molecule to a hydroxide ion:  $H_3O^+ + OH^- \rightarrow H_2O + H_2O$ . This reaction, for which  $k = 1.4 \times 10^{11} \ M^{-1} \ s^{-1}$  at 25°C, is the net reaction which occurs whenever a strong acid is neutralized by a strong base.<sup>21</sup>

We may state as a general rule that any hydrogen-bond proton-transfer reaction for which  $\Delta H^{\circ} < 0$  has a very low activation energy and is very fast, with  $k \sim 10^{10}$  to  $10^{11}$   $M^{-1}$  s<sup>-1</sup>. Consequently endothermic proton-transfer reactions

<sup>&</sup>lt;sup>20</sup> Z. Luz and S. Meiboom, *J. Am. Chem. Soc.*, **86**, 4768 (1964).
<sup>21</sup> M. Eigen, *Angew. Chem. Int. Ed.*, **3**, 1 (1964).

have activation energies slightly greater than  $\Delta H^{\circ}$  and rate constants approximately equal to  $K_{\rm eq} \times 10^{10}$ , where  $K_{\rm eq}$  is the equilibrium constant of the reaction. The forward and reverse rate constants for various reactions of the type

$$\overset{\text{H}}{\overset{\text{-}}{\bigcirc}} - \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} - \overset{\text{H}}{\overset{\text{-}}{\bigcirc}} \cdots \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} - \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} \overset{\text{-}}{\overset{\text{-}}{\overset{\text{-}}{\bigcirc}}} \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} \overset{\text{-}}{\overset{\text{-}}{\bigcirc}} \overset{\text{-}}{\overset{\text{-}}{\overset{\text{-}}{\bigcirc}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}{\overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}{\overset{-}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}} \overset{\text{-}}} \overset{\text{-}}} \overset{\text{-}}}$$

and

$$\begin{array}{ccc}
H & & H \\
- & & | \\
- & & O - H \cdots B
\end{array}$$

are given in Table 7.10.

A technique based on the measurement of nmr line widths has been used to determine the rates of symmetric proton exchange for ammonia and various amines.<sup>22</sup> Two types of processes were detected: direct exchange.

$$H_3N-H\cdot\cdot\cdot NH_3 \xrightarrow{k_1} H_3N\cdot\cdot\cdot H-NH_3$$

and exchange via an intervening water molecule,

$$H_3\overset{+}{N}-H\cdots O-H\cdots NH_3 \xrightarrow{k_2} H_3N\cdots H-O\cdots H-\overset{+}{N}H_3$$

<sup>22</sup> A. Loewenstein and S. Meiboom, *J. Chem. Phys.*, **27**, 1067 (1957); S. Meiboom, A. Loewenstein and S. Alexander, *J. Chem. Phys.*, **29**, 969 (1958).

Table 7.10 Rate constants for aqueous proton-transfer reactions†

Reaction	$k_f, M^{-1} s^{-1}$	$k_r$ , s <sup>-1</sup> or $M^{-1}$ s <sup>-1</sup>
$H^+ + OH^- \rightarrow H_2O$	STATE OF THE STATE	A MANAGEMENT OF STREET
$H^+ + NH_3 \rightarrow NH_4^+$	$1.4 \times 10^{11}$	$2.5 \times 10^{-5}$
$H^+ + HS^- \rightarrow H_2S$	$4.3 \times 10^{10}$	24
$H^+ + OAc^- \rightarrow HOAc$	$7.5 \times 10^{10}$	$8.3 \times 10^{3}$
$H^+ + F^- \rightarrow HF$	$4.5 \times 10^{10}$	$8.4 \times 10^{5}$
$H^+ + SO_4^{2-} \rightarrow HSO_4^{-}$	$1.0 \times 10^{11}$	$7 \times 10^7$
$H^+ + H_2O \rightarrow H_3O^+$	1 × 10 <sup>11</sup>	1 × 10°
$H^+ + SO_2(NH_2)_2 \rightarrow NH_2SO_2NH_3^+$	1 × 1010	$1 \times 10^{10}$
$OH^- + H^+ \rightarrow H_2O$	$3 \times 10^7$	>108
$OH^- + HATP^{3-} \rightarrow H_2O + ATP^{4-}$	1.4 × 10 <sup>11</sup>	$2.5 \times 10^{-5}$
$OH^- + NH_4^+ \rightarrow H_2O + NH_3$	$1.2 \times 10^{9}$	38
$OH^{-} + HCO_{3}^{-} \rightarrow H_{2}O + CO_{3}^{2}$	$3.4 \times 10^{10}$	$6 \times 10^{5}$
$OH^{-} + HPO^{2-}$	6 × 109	1.2 × 10 <sup>6</sup>
$OH^{-} + HPO_{4}^{2-} \rightarrow H_{2}O + PO_{4}^{3-}$	2 × 10°	$4 \times 10^7$
$OH^{-} + SO_{2}(NH_{2})_{2} \rightarrow H_{2}O + NH_{2}SO_{2}NH^{-}$	1011	delice es apide
$OH^{-} + H_{2}O \rightarrow H_{2}O + OH^{-}$	3 × 10°	3 × 10°
$OH^- + SO_3NH_2^- \rightarrow H_2O + SO_3NH^2$		3 7 19
$OH^- + CH_3OH \rightarrow H_2O + CH_3O^-$	~108	
	3 × 10 <sup>6</sup>	and a military

<sup>†</sup> M. Eigen, Angew. Chem. Int. Ed., 3, 1 (1964).

<sup>‡</sup> ATP = adenosine triphosphate.

Table 7.11 Rate constants for proton-exchange reactions†

Reaction	$k_1, M^{-1} s^{-1}$	$k_2, M^{-1}$ s <sup>-1</sup>	$k_2/k_1$
NH <sub>4</sub> <sup>+</sup> + NH <sub>3</sub> CH <sub>3</sub> NH <sub>3</sub> <sup>+</sup> + CH <sub>3</sub> NH <sub>2</sub> (CH <sub>3</sub> ) <sub>2</sub> NH <sub>2</sub> <sup>+</sup> + (CH <sub>3</sub> ) <sub>2</sub> NH (CH <sub>3</sub> ) <sub>3</sub> NH <sup>+</sup> + (CH <sub>3</sub> ) <sub>3</sub> N	$ \begin{array}{c} 10.6 \times 10^8 \\ 2.5 \times 10^8 \\ 0.4 \times 10^8 \\ < 0.3 \times 10^8 \end{array} $	$0.9 \times 10^{8}$ $3.4 \times 10^{8}$ $5.6 \times 10^{8}$ $3.1 \times 10^{8}$	0.09 1.4 14 >10

<sup>†</sup> A. Loewenstein and S. Meiboom, J. Chem. Phys., 27, 1067 (1957); S. Meiboom, A. Loewenstein, and S. Alexander, J. Chem. Phys., 29, 969 (1958).

The rate constants  $k_1$  and  $k_2$  are listed in Table 7.11. It can be seen that, as the hydrogen atoms of ammonia are replaced by methyl groups, the rate of the direct process decreases relative to that of the indirect process.

# THE ENTROPY OF IONIZATION OF AQUEOUS ACIDS

Protonic acids differ in acidity principally because of corresponding differences in the enthalpy of ionization. This statement of course implies that the entropy of ionization is essentially a constant for aqueous acids. Indeed, this generalization was stated many years ago by Pitzer,  $^{23}$  who pointed out that the entropies of ionization of weak acids generally have values around -21 cal deg $^{-1}$  mol $^{-1}$ . In Table 7.12 the enthalpies, free energies, and entropies of ionization of some common acids are listed. It can be seen that Pitzer's rule is a fairly good approximation. It should be noted that, at 25°C, a change in  $\Delta S^{\circ}$  of 3 cal deg $^{-1}$ 

Table 7.12 Thermodynamic constants for the ionization of aqueous acids†

Acid	Δ <i>H</i> °, kcal mol <sup>-1</sup>	$\Delta G^{\circ}$ , kcal mol <sup>-1</sup>	$\Delta S^{\circ}$ , cal deg <sup>-1</sup> mol <sup>-1</sup>
HClO <sub>2</sub>	-4.10	2.67	-22.7
Sulfurous (SO <sub>2</sub> + H <sub>2</sub> O)	-4.00	2.72	-22.6
11 <sub>3</sub> FO <sub>4</sub>	-1.88	2.90	-16.0
CICH <sub>2</sub> COOH	-1.17	3.90	-17.0
Butyric	-0.69	6.57	-24.4
Propionic	-0.09	6.65	-22.9
CH <sub>3</sub> COOH	-0.17	6.49	-22.1
НСООН	The second secon	5.12	-17.2
Carbonic (CO <sub>2</sub> + H <sub>2</sub> O)	-0.01	8.68	-22.9
HOCI (CO <sub>2</sub> + H <sub>2</sub> O)	1.84	10.10	-22.8
H <sub>2</sub> O	3.32 13.36	19.09	-19.2 (-27‡)

<sup>†</sup> K. S. Pitzer, J. Am. Chem. Soc., 59, 2365 (1937).

‡ For the 1 M standard state of H<sub>2</sub>O.

<sup>&</sup>lt;sup>23</sup> K. S. Pitzer, J. Am. Chem. Soc., 59, 2365 (1937).

mol<sup>-1</sup> corresponds to a change in TΔS° of almost 1 kcal mol<sup>-1</sup>; obviously the total range of  $\Delta H^{\circ}$  values in Table 7.12 is much greater than the total range of  $T\Delta S^{\circ}$ values. The approximate constancy of  $\Delta S^{\circ}$  is due to the fact that the difference in entropy between a weak acid HA and its anion A- is approximately independent of the nature of A. The total entropy difference is negative because of the considerable structure introduced into the solvent by hydrogen-bonding to the proton and the anion A-. It should be noted that the entropy of ionization of water itself, when the hypothetical 1 m solution is taken as the standard state (as in the case of all the other acids), is considerably more negative than the average value. This very negative value for water is probably attributable to the fact that the charge of the hydroxide ion is highly localized on the oxygen atom, causing extraordinarily strong hydrogen bonding.

Pitzer's idea can be extended to cationic and anionic protonic acids. An entropy of dissociation of zero is a good approximation for acids with a +1 charge, as shown by the values for H<sub>3</sub>O<sup>+</sup> and NH<sub>4</sub>+:

$$H_3O^+ \Longrightarrow H^+ + H_2O$$
  $\Delta S^\circ = 0$   
 $NH_4^+ \Longrightarrow H^+ + NH_3$   $\Delta S^\circ = -0.7 \text{ cal deg}^{-1} \text{ mol}^{-1}$ 

In the case of acids with a -1 charge (second ionizations) the entropy of ionization appears to be around -30 cal deg-1 mol-1, as seen from the following data for HCO<sub>3</sub><sup>-</sup>, H<sub>2</sub>PO<sub>4</sub><sup>-</sup>, and HSO<sub>4</sub><sup>-</sup>.

$$HCO_3^- \Longrightarrow H^+ + CO_3^{2-}$$
 $H_2PO_4^- \Longrightarrow H^+ + HPO_4^{2-}$ 
 $HSO_4^- \Longrightarrow H^+ + SO_4^{2-}$ 
 $\Delta S^\circ = -30 \text{ cal deg}^{-1} \text{ mol}^{-1}$ 
 $\Delta S^\circ = -26 \text{ cal deg}^{-1} \text{ mol}^{-1}$ 

# SOME SPECIAL AQUEOUS ACIDS

It is often assumed, for convenience, that in an aqueous solution of carbon disvide the dissolved dioxide the dissolved gas exists entirely as carbonic acid, H<sub>2</sub>CO<sub>3</sub>. The ionization constant for carbonic acid that is usually quoted is based on that assumption.

$$H_2CO_3 \rightleftharpoons H^+ + HCO_3^- \qquad K = 4.16 \times 10^{-7}$$
  
equilibrium constant is:

Actually this equilibrium constant is incorrect because most of the dissolved carbon dioxide exists as loosely hydrated CO<sub>2</sub>, and the true ionization constant of the small amount of  $H_2CO_3$  present is much greater, 2.5  $\times$  10<sup>-4</sup>. The latter value is more in agreement with that expected for an acid with the structure (HO),  $^{CO}$ . (Compare CH<sub>3</sub>COOH,  $K = 1.8 \times 10^{-5}$ .) Dissolved carbon dioxide comes to equilibrium with H<sub>2</sub>CO<sub>3</sub> and its dissociation products at a measurably slow rate. This slow reaction can be demonstrated by separately adding a sodium hydroxide solution Containing phenolphthalein to a CO<sub>2</sub> solution and to an acetic acid solution. The decolorization of the phenolphthalein takes several seconds with the CO<sub>2</sub> solution, whereas it occurs instantaneously with the acetic acid. The slowness of the reaction of CO<sub>2</sub> is of considerable importance in biological processes, and in Chap. 22 we shall discuss the function of the enzyme carbonic anhydrase in catalyzing the reaction.

The rate constants for the following processes have been determined.24

$$CO_{2} + H_{2}O \xrightarrow{k_{1}} H_{2}CO_{3}$$

$$OH^{-} + CO_{2} \xrightarrow{k_{2}} HCO_{3}^{-}$$

$$k_{1} = 3.9 \times 10^{-2} \text{ s}^{-1}$$

$$k_{-1} = 23 \text{ s}^{-1}$$

$$k_{2} = 9.4 \times 10^{3} M^{-1} \text{ s}^{-1}$$

$$k_{-2} = 2.2 \times 10^{-4} \text{ s}^{-1}$$

The second ionization of carbonic acid appears to be perfectly normal:

$$HCO_3^- \iff H^+ + CO_3^{2+} \qquad K = 4.84 \times 10^{-11}$$

Solutions of sulfur dioxide in water have long been referred to as solutions of "sulfurous acid,"  $H_2SO_3$ . However, Raman spectra of the solutions show only the presence of dissolved  $SO_2$ , with no evidence for the hydroxy acid  $(HO)_2SO$ . Hence the first ionization of sulfurous acid should be represented as follows:

$$H_2O + SO_2 \iff H^+ + HSO_3^- \qquad K_1 = 1.3 \times 10^{-2}$$

In crystalline bisulfite salts for which structures have been determined, the HSO<sub>3</sub>-ion has a threefold axis of symmetry, with the hydrogen atom attached to the sulfur atom, not an oxygen atom. The presence of a strong band in the S—H stretching region around 2500 cm<sup>-1</sup> in Raman spectra of bisulfite solutions indicates that the same structure exists in aqueous bisulfite solutions.<sup>25</sup> In solution, bisulfite ions are in equilibrium with *dis*ulfite ions<sup>26</sup>;

$$2HSO_3^- \iff O_2S - SO_3^{2-} + H_2O \qquad K = 0.088 \text{ at } \mu = 1.0$$

The disulfite ion has a sulfur-sulfur bond with the indicated asymmetric structure. Indeed, commercial solid sodium and potassium "bisulfites" are actually the corresponding disulfites. Of course, in strongly alkaline solutions both bisulfite and disulfite are converted to the sulfite ion:

$$HSO_3^- \iff H^+ + SO_3^{2-} \qquad K_2 = 6.2 \times 10^{-8}$$

The structure of solid boric acid, B(OH)<sub>3</sub>, is well established from x-ray diffraction studies. The individual molecules are trigonal planar, and the crystal

<sup>&</sup>lt;sup>34</sup> M. J. Welch, J. F. Lifton, and J. A. Seck, *J. Phys. Chem.*, 73, 3351 (1969).

<sup>&</sup>lt;sup>25</sup> A. Simon and H. Kriegsmann, *Chem. Ber.*, **89**, 2442 (1956). Also see earlier papers cited therein.

<sup>&</sup>lt;sup>26</sup> R. E. Connick, T. M. Tam, and E. von Deuster, *Inorg. Chem.*, 21, 103 (1982).

is sheetlike, with the molecules being held together by hydrogen bonds in the common molecular plane. (See Fig. 7.6.) Raman spectra of aqueous boric acid solutions are very similar to those of the solid acid, and there is little doubt that the species in solution is like that in the solid, i.e., that aqueous solutions contain planar B(OH)3 units, with no significant formation of tetrahedral B(OH)3OH3 species.27 In strongly alkaline solutions, Raman spectra indicate that the borate ion exists as the mononuclear tetrahedral B(OH)<sub>4</sub>. Thus we must conclude that B(OH)<sub>3</sub> does not lose a proton upon ionization; it abstracts a hydroxide ion from

$$B(OH)_3 + H_2O \implies H^+ + B(OH)_4^- \qquad K = 5.8 \times 10^{-10}$$

At boron concentrations greater than about 0.025 M and pH values between 8 and 10, polyborate species are important. Unfortunately there is little agreement as to the nature of these species. However, there is agreement that a polyborate with three boron atoms and one negative charge is most important. A cyclic structure has been postulated for this anion:

Other polyanions, both mononegative and dinegative, containing three, four, five, and six borons, have been postulated, but the evidence for these is not

One of the acids with which most beginning students of chemistry become familiar is hydrogen sulfide. The aqueous equilibria between this dibasic acid and various slightly soluble sulfides are commonly used as examples in exercises in which students calculate, for example, the solubility of a sulfide in an H<sub>2</sub>S solution at a particular pH. The first ionization constant of H<sub>2</sub>S at 25°C is fairly well established as  $1.3 \times 10^{-7}$ , and the second ionization constant, although less the certain, is reported fairly consistently in the older literature to have a value in the vicinity of 10<sup>-14</sup>. However, Giggenbach<sup>28</sup> has shown that most of the previous studies of the HS<sup>-</sup> + OH<sup>-</sup>  $\rightleftharpoons$  H<sub>2</sub>O + S<sup>2-</sup> equilibrium are probably invalid because of air oxidation of the sulfide ion to polysulfide ions.

$$\left(\frac{x-1}{2}\right)$$
 O<sub>2</sub> +  $x$ S<sup>2-</sup> +  $(x-1)$ H<sub>2</sub>O  $\rightarrow$  S<sub>x</sub><sup>2-</sup> +  $(2x-2)$ OH<sup>-</sup> improved technique to an  $A$ 

Using an improved technique to exclude oxygen from strongly alkaline sulfide solutions, he found an ultraviolet absorption band at 40,600 cm<sup>-1</sup> due to the S<sup>2</sup>

of H<sub>2</sub>S, see S. R. Rao and L. G. Hepler, Hydrometallurgy, 2, 293 (1976–1977).

<sup>&</sup>lt;sup>27</sup> V. F. Ross, J. O. Edwards, R. P. Bell, and R. B. Jones, in "The Chemistry of Boron and Its Compounds," E. L. Muetterties, ed., chaps. 3 and 4, Wiley, New York, 1967. <sup>28</sup> W. Giggenbach, *Inorg. Chem.*, **10**, 1333 (1971). For a discussion of the available data on the pK<sub>2</sub>

ion. From the data obtained at various hydroxide concentrations, a p $K_2$  value of  $17.1 \pm 0.2$  was derived. If this value is correct, then all the tabulated solubility products of metal sulfides, which have been calculated using  $pK_2$  values around 14, are grossly in error. In fact, this predicament shows that instead of tabulating equilibrium constants for reactions such as

CuS 
$$\rightleftharpoons$$
 Cu<sup>2+</sup> + S<sup>2-</sup>

it would be better to tabulate equilibrium constants for reactions such as

$$CuS + H_2O \rightleftharpoons Cu^{2+} + OH^- + HS^-$$

or

$$CuS + 2H^+ \iff Cu^{2+} + H_2S$$

for which the equilibrium constants are independent of  $pK_2$  for  $H_2S$ .

## ACIDS AND BASES IN PROTONIC SOLVENTS

Under ordinary conditions, the ionization of a protonic acid does not involve the liberation of free protons. In Chap. 5 we have seen that such a process ocurring in aqueous solution is best looked upon as the transfer of a proton to a water molecule (or, better, a group of water molecules). In fact, almost all reactions of protonic acids consist of transfers of protons from one base to another. Long ago Brönsted<sup>29</sup> pointed out that acids and bases may be related by the following half-reaction:

Acid 
$$\rightleftharpoons$$
 H<sup>+</sup> + base

Thus an acid is a species which can act as a proton donor, and a base is a species which can act as a proton acceptor. A typical acid-base reaction may then be written

Acid 
$$1 + base 2 \implies acid 2 + base 1$$

By removing a proton from acid 1, we obtain base 1. Acid 1 is said to be the conjugate acid of base 1 and base 1 the conjugate base of acid 1. Similar

relationships exist between acid 2 and base 2.

Certain solvents resemble water in that they self-ionize to give solvated protons and anions and dissolve salts to give conducting solutions. A list of such solvents, with their physical properties, is given in Table 7.13. In these solvents the Brönsted concept is quite applicable. For example, in liquid ammonia<sup>30</sup> the following self-ionization, or "autoprotolysis," occurs:

$$2NH_3 \implies NH_4^+ + NH_2^- \qquad K_{-33^{\circ}C} \approx 10^{-30}$$

<sup>29</sup> J. N. Brönsted, Rec. Trav. Chim., 42, 718 (1923).

W. L. Jolly and C. J. Hallada, in "Non-aqueous Solvent Systems," T. C. Waddington, ed., Pp. 1-45, Academic, London, 1965; J. J. Lagowski and G. A. Moczygemba, in "The Chemistry of Non-agus New York, 1967. Non-aqueous Solvents," J. J. Lagowski, ed., vol. 2, pp. 320–371, Academic, New York, 1967.

Table 7.13 Physical properties of some protonic solvents†

Ag a sa butagal A value	the data bota interalment of description of the many was don't be the first along it correct them all line to metals sulfidest which have from calculated using	
Viscosity 1000η	15.6 (25°C) 245 (25°C) 8.9 (20°C) 1780 (25°C) 2.4 (6°C) 5.1 (-95°C) 18.0 (20°C) 11.6 (25°C) 11.6 (25°C) 11.6 (25°C) 11.1 (20°C) 4.3 (-60°C) 11.1 (20°C) 5.45 (25°C) 17.7 (30°C) 17.7 (30°C	
ΔS <sub>vap</sub>	6.1 6.1 20.4 14.9 14.9 20.2 21.0 27.3 26.0 25	
-log Kion at 25°C	7.4 3.4 (10°C) ~ 1.7 (~40°C) 0.9 >11.7 (0°C) 6.2 14.45 ~ 18.7 (12°C) 13 14.0 16.6 18.9 24.7	
Electric conductivity, mho cm	1.1 × 10 <sup>-4</sup> (25°C) 1.04 × 10 <sup>-2</sup> (20°C) 8.9 × 10 <sup>-3</sup> (0°C) 4.6 × 10 <sup>-2</sup> (25°C) 1.4 × 10 <sup>-3</sup> (-15°C) 3.5 × 10 <sup>-9</sup> (-85°C) 6 × 10 <sup>-3</sup> 5 × 10 <sup>-9</sup> (25°C) 5 × 10 <sup>-9</sup> (25°C) 1.3 × 10 <sup>-9</sup> (25°C) 1.5 × 10 <sup>-9</sup> (25°C) 1.35 × 10 <sup>-9</sup> (25°C) 1.35 × 10 <sup>-9</sup> (25°C) 1.35 × 10 <sup>-9</sup> (25°C)	
Dielectric constant at 25°C	~ 120 100 ~ 61 60 (19°C) 9.28 (-95°C) 57.9 (20°C) 6.19 106.8 10.2 (-60°C) 93.7 78.5 32.6 24.3 19.7 18.3 9.8 (60°C) 51.7 16.9 5.5 (20°C) 6.89 (20°C)	12 22 22
Boiling point, °C	162.7 330 86 86 86 19.51 -84.1 100.5 118.2 71.8 25.7 -60.3 151.4 100.0 64.7 78.5 97.8 82.5 113.5 34.4	B
Melting point, °C	-89.0 10.37 -41.6 42.35 -89.4 -114.6 8.3 16.6 -15.4 -13.2 -85.5 -0.9 0.0 -97.9 -114.6 -12.7 -85.8 41 1.5 -101.2	
Solvent	HSO,F H,SO, H,NO, H,PO, H,F HCI HOOCCH HOOCCH, H,O H,O CH,OH C,H,OH C,H,OH C,H,OH C,H,OH C,H,OH C,H,OH N,M, N,M,	7.11.151.19

† Reproduced with permission from W. L. Jolly, "The Synthesis and Characterization of Inorganic Compounds," p. 99, Prentice-Hall, Englewood Cliffs, J., 1970. N.J., 1970.

In liquid ammonia any species which gives (or reacts to give) ammonium ions is an acid, and any species which gives (or reacts to give) amide ions is a base. Thus the following reactions are acid-base reactions in ammonia.

$$H_2NCONH_2 + NH_2^- \rightarrow H_2NCONH^- + NH_3$$
  
 $NH_4^+ + KOH(s) \rightarrow K^+ + NH_3 + H_2O$   
 $H_2O + K^+ + NH_2^- \rightarrow KOH(s) + NH_3$ 

In anhydrous sulfuric acid,31 the following autoprotolysis occurs:

$$H_2SO_4 \rightleftharpoons H^+ + HSO_4^-$$

For simplicity, we write  $H^+$  for the solvated proton in  $H_2SO_4$  rather than  $H_3SO_4^+$  or  $H(H_2SO_4)_n^+$ . When water is dissolved in anhydrous sulfuric acid, the following solvolysis takes place:

$$H_2O + H_2SO_4 \implies H_3O^+ + HSO_4^-$$

Hence water is a base in sulfuric acid. Similar reactions occur with many other oxygen-containing compounds. Often dehydration accompanies the basic hydrolysis:

$$HONO_2 + 2H_2SO_4 \rightarrow NO_2^+ + H_3O^+ + 2HSO_4^-$$

A major, reactive constituent of solutions of nitric acid in concentrated sulfuric acid, which are often used in the nitration of aromatic compounds, is the nitryl ion, NO<sub>2</sub><sup>+</sup>. The NO<sub>2</sub><sup>+</sup> ion can be detected by Raman spectroscopy in HNO<sub>3</sub>-H<sub>2</sub>SO<sub>4</sub>-H<sub>2</sub>O mixtures. Because of the high acidity of sulfuric acid itself, relatively few substances are acids in this solvent. However, SO<sub>3</sub> does dissolve to form disulfuric acid, which is a slightly stronger acid than sulfuric acid.

$$SO_3 + H_2SO_4 \rightarrow H_2S_2O_7$$
 $SO_3 + H_2SO_7 \rightleftharpoons H^+ + HS_2O_7^-$ 
Aphydaeth 1 alegaeth 1 alegaeth 1 alegaeth 2 alegaeth 2

Anhydrous hydrogen fluoride self-ionizes to give the solvated proton and the bifluoride ion.

$$2HF \iff H^+ + HF_2^-$$

Hence strong fluoride acceptors such as antimony pentafluoride are acids in hydrogen fluoride,

$$SbF_5 + HF \longrightarrow H^+ + SbF_6^-$$

and proton acceptors such as water and nitric acid are bases in hydrogen fluoride,

$$H_2O + 2HF \implies H_3O^+ + HF_2^ HNO_3 + 2HF \implies H_2NO_3^+ + HF_2^-$$

If one wishes to have a protonic acid and its anion present in comparable amounts at equilibrium in an aqueous solution, the pK value of the acid must lie within, or near, the range 0 to 14. If the pK is much less than 0, the acid will be

<sup>&</sup>lt;sup>31</sup> R. J. Gillespie and E. A. Robinson, in "Non-aqueous Solvent Systems," T. C. Waddington, ed., pp. 117-210, Academic, London, 1965.




Figure 7.10 Effective pH ranges of various protonic solvents.

completely ionized even in a strongly acidic solution, and if the pK is much greater than 14, the acid will be completely nonionized even in a strongly basic solution. To have a measurable acid-anion equilibrium for p $K \ll 0$ , one must use a solvent that is less basic than water, such as sulfuric acid or acetic acid. To have a measurable acid-anion equilibrium for p $K \gg 14$ , one must use a solvent that is more basic than water, such as liquid ammonia. In Fig. 7.10, the effective pH ranges corresponding to aqueous solutions that can be achieved in several protonic solvents are shown graphically. By the "effective pH" of a nonaqueous solution we mean the pH of a hypothetical aqueous solution in which a dissolved test acid would have the same equilibrium acid-anion ratio as found in the nonaqueous solution. It can be seen that in a solvent such as formic acid one can differentiate the acidities of HCl (p $K \approx -6$ ) and HBr (p $K \approx -9$ ). On the other hand, in a solvent such as liquid ammonia, one can differentiate the acidities of PH<sub>3</sub> (p $K \approx 27$ ) and GeH<sub>4</sub> (p $K \approx 25$ ).

In aqueous solutions, the hydrogen-ion activity is closely proportional to the concentration of strong acid down to about pH 0 and closely proportional to the reciprocal of the concentration of strong base up to about pH 14. Beyond these pH limits, the hydrogen-ion activity and the effective pH change much more rapidly than one would calculate from changes in the concentration of strong acid or strong base. In such solutions, and even in completely nonaqueous solutions, it is possible to define an "acidity function" which is the effective aqueous pH. The acidity function  $H_0$  is defined in terms of a system buffered with a base B and its cationic conjugate acid BH+:

$$H_0 = pK_a + \log \frac{C_B}{C_{BH^+}}$$

<sup>32</sup> L. P. Hammett, "Physical Organic Chemistry," McGraw-Hill, New York, 1940.

Table 7.14 Compositions of some solutions with high  $-H_0$  and  $H_-$  values

Solution	$-H_0\dagger$	Solution H_‡
4% SbF, in HF	21.0	95% DMSO§, 5%
25% SbF <sub>5</sub> in HSO <sub>3</sub> F	21.0	EtOH; 10 <sup>-2</sup> M KOEt 20.6
7% SbF <sub>5</sub> · 3SO <sub>3</sub> in HSO <sub>3</sub> F	19.35	90% DMSO§, 10%
10% SbF, in HSO <sub>3</sub> F	18.94	EtOH; 10 <sup>-2</sup> M KOEt 19.68
HSO <sub>3</sub> F	15.07	80% DMSO§, 20%
H,S,O,	14.14	EtOH; 10 <sup>-2</sup> M KOEt 18.9°
100% H <sub>2</sub> SO <sub>4</sub>	11.93	15 M KOH (aqueous) 18.23
100% HF	11.0	10 M KOH (aqueous) 16.90
98% H <sub>2</sub> SO <sub>4</sub>	10.44	5 M KOH (aqueous) 15.44
90% H <sub>2</sub> SO <sub>4</sub>	8.92	and It of one present in such solutions
60% H <sub>2</sub> SO <sub>4</sub>	4.46	

† R. L. Gillespie, T. E. Peel, and E. A. Robinson, *J. Am. Chem. Soc.*, **93**, 5083 (1971); R. J. Gillespie and T. E. Peel, *J. Am. Chem. Soc.*, **95**, 5173 (1973); M. J. Jorgenson and D. R. Harrter, *J. Am. Chem. Soc.*, **85**, 878 (1963); G. A. Olah, G. K. S. Prakash, and J. Sommer, *Science*, **206**, 13 (1979).

‡ K. Bowden and R. Stewart, Tetrahedron, 21, 261 (1965); G. Yagil, J. Phys. Chem., 71, 1034 (1967).

§ DMSO = dimethyl sulfoxide.

where  $pK_a$  is the ionization constant of BH<sup>+</sup> and  $C_{BH^+}$  and  $C_B$  are the concentrations of BH<sup>+</sup> and B, respectively. The function  $H_-$  is defined in terms of a system buffered with a base B<sup>-</sup> and its neutral conjugate acid HB:

$$H_{-} = pK_a + \log \frac{C_{B^{-}}}{C_{HB}}$$

By appropriate choices of solvent and acid or base concentration, it is possible to prepare solutions having overlapping  $H_0$  or  $H_-$  ranges that collectively span an effective pH range from -21 to +21. The compositions and  $H_0$  or  $H_-$  values for some representative solutions are listed in Table 7.14.

Strongly acidic media such as solutions of SbF<sub>5</sub> in either HSO<sub>3</sub>F or HF have been used to prepare stable solutions of a variety of organic carbonium ions, oxonium ions, acyl cations, etc., which are too reactive to exist in less acidic solvents.<sup>33</sup> Some typical reactions follow.

<sup>33</sup> G. A. Olah, G. K. S. Prakash, and J. Sommer, *Science*, **206**, 13 (1979); G. A. Olah, D. G. Parker, and N. Yoneda, *Angew. Chem. Int. Ed.*, **17**, 909 (1978).

$$(CH_3)_3COOH + H^+ \longrightarrow (CH_3)_3COOH_2 \xrightarrow{H^+} CH_3$$
 $CH_3 \longrightarrow CH_3$ 
 $CH_3 \longrightarrow CH_3$ 

Unusual cations of the nonmetals can also be prepared in such solvents.<sup>34</sup> A blue solution of  $I_2$ <sup>+</sup> may be generated by the oxidation of  $I_2$  with  $S_2O_6F_6$  in  $HSO_3F$ :

$$2I_2 + S_2O_6F_2 \longrightarrow 2I_2^+ + 2SO_3F^-$$

Elemental sulfur, selenium, and tellurium give colored solutions when dissolved in a number of strongly acidic media. The species  $S_{16}^{2+}$ ,  $S_{8}^{2+}$ ,  $S_{4}^{2+}$ ,  $Se_{8}^{2+}$ ,  $Te_{4}^{2+}$ , and  $Te_{6}^{2+}$  are present in such solutions. Typical reactions are

$$2S_8 + S_2O_6F_2 \xrightarrow{HSO_3F} S_{16}^{2+} + 2SO_3F^-$$

$$8Se + 6H_2S_2O_7 \longrightarrow Se_8^{2+} + HS_3O_{10}^- + 5H_2SO_4 + SO_2$$

# ACIDS AND BASES IN APROTIC SOLVENTS

Some solvents do not self-ionize to any significant extent to give solvated protons. This category of "aprotic" solvents includes most hydrocarbons, ethers, and of course solvents containing no hydrogen such as bromine trifluoride and sulfur dioxide. A list of such solvents, and their physical properties, is given in Table 7.15. Obviously the Brönsted concept of acids and bases is inapplicable in these solvents. If an aprotic solvent undergoes self-ionization, the cation formed in the self-ionization is considered the acidic species, and the anion formed in the self-ionization is considered the basic species. For example, BrF<sub>2</sub>+ and BrF<sub>4</sub>- are the acidic and basic species, respectively, in bromine trifluoride.

$$2BrF_3 \Rightarrow BrF_2^+ + BrF_4^-$$

Thus antimony pentafluoride, which reacts with BrF3 as follows,

$$SbF_5 + BrF_3 \rightarrow BrF_2^+ + SbF_6^-$$

is an acid in BrF<sub>3</sub>. Potassium fluoride, which reacts as follows,

$$KF + BrF_3 \rightarrow K^+ + BrF_4^-$$

is a base in BrF<sub>3</sub>. When solutions of these reagents are mixed, a neutralization reaction occurs:

$$BrF_2^+ + BrF_4^- \implies 2BrF_3$$

In the case of aprotic solvents which do not self-ionize, acid-base reactions are best treated in terms of the very general Lewis acid-base theory, which we shall now discuss.

<sup>34</sup> R. J. Gillespie and M. J. Morton, *Quart. Rev.*, 1971, 553; R. J. Gillespie and J. Passmore, Acc. Chem. Res., 4, 413 (1971).

### LEWIS ACID-BASE THEORY

The Lewis acid-base theory is completely independent of solvent considerations. Indeed, many Lewis acid-base reactions proceed in the gas phase. In a Lewis acid-base reaction, a pair of electrons from one species is used to form a covalent bond to another species. The species that "donates" the electron pair is the base, and the species that "accepts" the electron pair is the acid. The reaction may be written

$$A + : B \rightarrow A - B$$

Sometimes the acid is referred to as an "electron acceptor" or an "electrophile" and the base is referred to as an "electron donor" or a "nucleophile." Many reactions involve the transfer of an acid from one base to another, or vice versa, or both transfers at once. In such cases the net reactions are written

$$B + A - B' \rightarrow B' + A - B$$

$$A + A' - B \rightarrow A' + A - B$$

$$A - B + A' - B' \rightarrow A - B' + A' - B$$

A few examples of some Lewis acids, bases, and the known adducts of these are listed in Table 7.16.

One of the difficulties of systematizing the relative basicities of Lewis bases is the fact that different trends in K,  $\Delta G^{\circ}$ , or  $\Delta H^{\circ}$  are obtained when different reference acids are used. For example, the complexing ability of the halide ions toward Al<sup>3+</sup> increases in the order  $I^- < Br^- < Cl^- < F^-$ . On the other hand, the order is  $F^- < Cl^- < Br^- < I^-$  for  $Hg^{2+}$ . A similar reversal can be seen in the heats of reaction of the acids  $I_2$  and  $C_6H_5OH$  with the bases  $(C_2H_5)_2O$  and  $(C_2H_5)_2S$ . The heat of reaction of  $I_2$  with  $(C_2H_5)_2S$  is greater than that with  $(C_2H_5)_2O$ , whereas the heat of reaction of  $C_6H_5OH$  with  $(C_2H_5)_2S$  is less than that with  $(C_2H_5)_2O$ . To resolve these problems, Pearson proposed the principle of hard and soft acids and bases. 36 A soft acid or base is one in which the valence electrons are easily polarized or removed, and a hard acid or base is one which holds its valence electrons tightly and is not easily distorted. The principle is: Hard acids prefer to coordinate to hard bases, and soft acids prefer to coordinate to soft bases. Tables 7.17 and 7.18 list some examples of acids and bases in the hard, soft, and borderline categories. The opposing trends in the reactivity of the halide ions toward Al3+ and Hg2+ are now easily rationalized. The Al3+ ion is a hard acid that prefers to bond to hard bases (such as F-), and the Hg<sup>2+</sup> ion is a soft acid that Prefers to bond to soft bases (such as I-). We can similarly explain the thermal data for  $I_2$ ,  $C_6H_5OH$ ,  $(C_2H_5)_2O$ , and  $(C_2H_5)_2S$ . Iodine and  $(C_2H_5)_2S$  interact relatively strongly because they are both soft, and  $(C_2H_5)_2O$ , and  $(C_2H_5)_2O$  interact strongly because they are both hard.

 <sup>&</sup>lt;sup>35</sup> R. J. Niedzielski, R. S. Drago, and R. L. Middaugh, J. Am. Chem. soc., 86, 1694 (1964).
 <sup>36</sup> R. G. Pearson, J. Am. Chem. Soc., 85, 3533 (1963); Science, 151, 172 (1966); Chem. Br., 3, 103 (1967); J. Chem. Educ., 45, 581, 643 (1968).

Table 7.15 Physical properties of some aprotic solvents†

Solvent	Formula	Melting point,	Boiling point, °C	Dielectric constant at 25°C	Viscosity 1000η
Sulfur dioxide Dinitrogen tetraoxide	SO <sub>2</sub> N <sub>2</sub> O <sub>4</sub>	-72.7 -11.2	-10.2 21.15	12.3 (22°C) 2.4 (18°C)	4.28 (-10°C) 
Arsenic trifluoride Iodine pentafluoride Bromine trifluoride	AsF <sub>3</sub> IF <sub>5</sub> BrF <sub>3</sub>	-8.5 9.6 8.8	63 98 127.6	5.7 (<-6°C) 36.2 (35°) 	21.9 (25°C) 22.2 (25°C)
Phosphorus trichloride Disulfur dichloride Arsenic trichloride Antimony trichloride Tin tetrachloride Iodine monochloride	PCl <sub>3</sub> S <sub>2</sub> Cl <sub>2</sub> AsCl <sub>3</sub> SbCl <sub>3</sub> SnCl <sub>4</sub> ICl	-91 -80 -18 73 -30.2 27.2	76.0 135.6 130.2 221 114.1 100	3.43 (25°C) 4.79 (15°C) 12.8 (20°C) 33.0 (75°C) 2.87 (20°C)	12.25 (20°C) 33 (95°C)  41.9 (28°C) 5.47 (-20°C)
Nitrosyl chloride Carbonyl chloride Thionyl chloride Phosphorus oxychloride Selenium oxychloride	NOCI COCI <sub>2</sub> SOCI <sub>2</sub> POCI <sub>3</sub> SeOCI <sub>2</sub>	-61.5 -104 -104.5 1.25 10.9	-5.4 8.3 79 105.3 176.4	19.7 (- 10°C) 4.3 (22°C) 9.0 (22°C) 13.9 (22°C) 46 (20°C)	11.5 (25°C)
Antimony tribromide Arsenic tribromide Iodine monobromide Mercury(II) bromide	SbBr <sub>3</sub> AsBr <sub>3</sub> IBr HgBr <sub>2</sub>	97 35 41 238	280 220 ~116 320	20.9 (100°C) 8.8 (35°C)  9.8	68.1 (100°C) 54.1 (35°C) 
Tin tetraiodide	SnI <sub>4</sub>	143.5 113.7	340 184.3	11.1 (118°C)	19.8 (116°C) 2.94 (25°C)
n-Hexane Isooctane Kerosene Benzene Toluene	$n-C_6H_{14}$ $iso-C_8H_{18}$ $\sim C_{12}H_{26}$ $C_6H_6$ $C_6H_6CH_3$ $o-C_6H_4CH_3$	-94.3 -111.3  5.5 -95 -25	69.0 117.2 210 80.1 110.6	1.90 ~ 1.94 (20°C) ~ 2.0 2.27 2.38 2.57 (20°C)	6.52 (20°C) 5.90 (20°C) 8.10 (20°C)

Carbon tetrachloride Chloroform Dichloromethane Ethylene chloride Tetrachloroethane Chlorobenzene Perfluoroheptane	CCl <sub>4</sub> CHCl <sub>3</sub> CH <sub>2</sub> Cl <sub>2</sub> CICH <sub>2</sub> CH <sub>2</sub> Cl Cl <sub>2</sub> CHCHCl <sub>2</sub> C <sub>6</sub> H <sub>3</sub> Cl n-C <sub>7</sub> F <sub>16</sub>	-22.8 -63.5 -96.7 -35.3 -43.8 -45.2	76.8 61.3 40.1 83.7 146.3 132 82.5	2.23 4.70 8.9 10.36  5.62	9.69 (20°C) 5.42 (25°C) 3.9 (30°C) 8.0 (20°C) 18.4 (15°C) 7.99 (20°C)  2.22 (25°C)
Diethyl ether Tetrahydrofuran	(C <sub>2</sub> H <sub>5</sub> ) <sub>2</sub> O QCH <sub>2</sub> CH <sub>2</sub> CH <sub>2</sub> CH <sub>2</sub>	-116.3 	65.4	7.39	7 7 5
1,2-Dimethoxyethane Diglyme Dioxane	CH <sub>3</sub> OCH <sub>2</sub> CH <sub>2</sub> OCH <sub>3</sub> CH <sub>3</sub> (OCH <sub>2</sub> CH <sub>2</sub> ) <sub>2</sub> OCH <sub>3</sub> QCH <sub>2</sub> CH <sub>2</sub> OCH <sub>2</sub> CH <sub>2</sub>	-69 -64 11.7	85.2 162.0 101.5	3.5-6.8	11 (20°C) 20 (20°C) 
Ethyl acetate Acetone	C <sub>2</sub> H <sub>5</sub> OCOCH <sub>3</sub> CH <sub>3</sub> COCH <sub>3</sub>	-83.6 -95.4	77.1 56.2	6.02 20.7	4.41 (25°C) 3.16 (25°C)
Acetonitrile Pyridine Nitromethane Nitrobenzene Formamide N-Methylformamide N-Methylformamide N-Methylacetamide Dimethylacetamide	CH <sub>3</sub> CN C <sub>5</sub> H <sub>5</sub> N CH <sub>3</sub> NO <sub>2</sub> C <sub>6</sub> H <sub>5</sub> NO <sub>2</sub> HCONH <sub>2</sub> HCONHCH <sub>3</sub> HCON(CH <sub>3</sub> ) <sub>2</sub> CH <sub>3</sub> CONHCH <sub>3</sub> CH <sub>3</sub> CON(CH <sub>3</sub> ) <sub>2</sub>	-45.7 -41.8 -28.5 5.7 2.55  -61 29.8 -20	81.6 115.5 101.2 210.9 193 111.2 153.0 206 166.1	36.2 12.3 38.6 (20°C) 34.6 109.5 182.4 36.7 178.9 (30°C) 37.8	3.45 (25°C) 9.45 (20°C) 6.08 (25°C) 20.3 (20°C) 37.6 (20°C) 16.5 (25°C) 7.96 (25°C) 38.85 (30°C) 9.2 (25°C)
Carbon disulfide Dimethyl sulfoxide Sulfolane Dimethyl carbonate Ethylene carbonate	CS <sub>2</sub> (CH <sub>3</sub> ) <sub>2</sub> SO (CH <sub>2</sub> ) <sub>4</sub> SO <sub>2</sub> CH <sub>3</sub> OCOOCH <sub>3</sub> QCH <sub>2</sub> CH <sub>2</sub> QCO	-111.6 18.55 28.37 5.0 	46.3 189.0 283 90.4 244 241.7	2.64 47.6 (23°C) 44.0 (30°C) 	3.76 (20°C) 19.8 (25°C) 98.7 (30°C)  25.3 (25°C)
Propylene carbonate Tri-n-butyl phosphate Hexamethylphosphoryltriamide	OCHCH <sub>3</sub> CH <sub>2</sub> OCO (n-C <sub>4</sub> H <sub>9</sub> O) <sub>3</sub> PO [(CH <sub>3</sub> ) <sub>2</sub> N] <sub>3</sub> PO	<-80 7.2	289 d. 235	30 (20°C)	35 (60°C)

<sup>†</sup> Reproduced with permission from W. L. Jolly, "The Synthesis and Characterization of Inorganic Compounds," pp. 100–101, Prentice-Hall, Englewood Cliffs, N.J., 1970.

Table 7.16 Some Lewis acids, bases, and their adducts

· 是一日 · 日 · 日 · 日 · 日 · 日 · 日 · 日 · 日 · 日 ·			Lewis bases		
Lewis acids	H- 9 5 7	OH-	NH <sub>3</sub>	Cl-	$C_6H_6$
H <sup>+</sup> B(CH <sub>3</sub> ) <sub>3</sub> SO <sub>3</sub> Ag <sup>+</sup> I <sub>2</sub>	H <sub>2</sub> B(CH <sub>3</sub> ) <sub>3</sub> H <sup>-</sup> HSO <sub>3</sub> <sup>-</sup>	H <sub>2</sub> O B(CH <sub>3</sub> ) <sub>3</sub> OH <sup>-</sup> HSO <sub>4</sub> - [AgOH] I <sub>2</sub> OH <sup>-</sup>	NH <sub>4</sub> <sup>+</sup> B(CH <sub>3</sub> ) <sub>3</sub> NH <sub>3</sub> NH <sub>3</sub> SO <sub>3</sub> Ag(NH <sub>3</sub> ) <sub>2</sub> <sup>+</sup> I <sub>2</sub> NH <sub>3</sub>	HCl SO <sub>3</sub> Cl <sup>-</sup> AgCl <sub>2</sub> <sup>-</sup> I <sub>2</sub> Cl <sup>-</sup>	[C <sub>6</sub> H <sub>7</sub> <sup>+</sup> ] B(CH <sub>3</sub> ) <sub>3</sub> · C <sub>6</sub> H <sub>6</sub>  AgC <sub>6</sub> H <sub>6</sub> <sup>+</sup> I <sub>2</sub> C <sub>6</sub> H <sub>6</sub>

Table 7.17 The classification of some Lewis acids†

Hard	Borderline	Soft
H+, Li+, Na+, K+  Be±+, Mg²+, Ca²+, Sr²+, Mn²+  Al³+, Sc³+, Ga³+, In³+, La³+  N³+, Cl³+, Gd³+, Lu³+, Cr³+  Co³+, Fe³+, As³+, CH₃Sn³+  Si⁴+, Ti⁴+, Zr⁴+, Th⁴+, U⁴+  Pu⁴+, Ce³+, Hf⁴+, WO⁴+, Sn⁴+  UO₂²+, (CH₃)₂Sn²+  VO²+, MoO³+, BeMe₂, BF₃  B(OR)₃, Al(CH₃)₃, AlCl₃  AlH₃, RPO₂+, ROPO₂+  RSO₂+, ROSO₂+, SO₃  I³+, I³+, Cl²+, Cré+, RCO+  CO₂, NC+  HX (hydrogen-bonding molecules)	Fe <sup>2+</sup> , Co <sup>2+</sup> , Ni <sup>2+</sup> Cu <sup>2+</sup> , Zn <sup>2+</sup> , Pb <sup>2+</sup> Sn <sup>2+</sup> , Sb <sup>3+</sup> , Bi <sup>3+</sup> , Rh <sup>3+</sup> Ir <sup>3+</sup> , B(CH <sub>3</sub> ) <sub>3</sub> , SO <sub>2</sub> NO <sup>+</sup> , Ru <sup>2+</sup> , Os <sup>2+</sup> R <sub>3</sub> C <sup>+</sup> , C <sub>6</sub> H <sub>5</sub> <sup>+</sup> , GaH <sub>3</sub>	Cu <sup>+</sup> , Ag <sup>+</sup> , Au <sup>+</sup> , Tl <sup>+</sup> , Hg <sup>+</sup> Pd <sup>2+</sup> , Cd <sup>2+</sup> , Pt <sup>2+</sup> , Hg <sup>2+</sup> CH <sub>3</sub> Hg <sup>+</sup> , Co(CN) <sub>3</sub> <sup>2-</sup> , Pt <sup>4+</sup> Tl <sup>3+</sup> , Tl(CH <sub>3</sub> ) <sub>3</sub> , BH <sub>3</sub> , Ga(CH <sub>3</sub> ) GaCl <sub>3</sub> , Gal <sub>3</sub> , InCl <sub>3</sub> RS <sup>+</sup> , RSe <sup>+</sup> , RTe <sup>+</sup> I <sup>+</sup> , Br <sup>+</sup> , HO <sup>+</sup> , RO <sup>+</sup> I <sub>2</sub> , Br <sub>2</sub> , ICN, etc. Trinitrobenzene, etc. Chloranil, quinones, etc. Tetracyanoethylene, etc. O, Cl, Br, I, N, RO, RO <sub>2</sub> M <sup>0</sup> (metal atoms) Bulk metals CH <sub>2</sub> , carbenes

<sup>†</sup> R. G. Pearson, J. Am. Chem. Soc., 85, 3533 (1963); Science, 151, 172 (1966); Chem. Br., 3, 103 (1967); J. Chem. Educ., 45, 581, 643 (1966).

Table 7.18 The classification of some Lewis bases†

Hard	Borderline	Soft
H <sub>2</sub> O, OH <sup>-</sup> , F <sup>-</sup> CH <sub>3</sub> CO <sub>2</sub> <sup>-</sup> , PO <sub>4</sub> <sup>3-</sup> , SO <sub>4</sub> <sup>2-</sup> Cl <sup>-</sup> , CO <sub>3</sub> <sup>2-</sup> , ClO <sub>4</sub> <sup>-</sup> , NO <sub>3</sub> <sup>-</sup> ROH, RO <sup>-</sup> , R <sub>2</sub> O NH <sub>3</sub> , RNH <sub>2</sub> , N <sub>2</sub> H <sub>4</sub>	C <sub>6</sub> H <sub>5</sub> NH <sub>2</sub> , C <sub>5</sub> H <sub>5</sub> N, N <sub>3</sub> <sup>-</sup> Br <sup>-</sup> , NO <sub>2</sub> <sup>-</sup> , SO <sub>3</sub> <sup>2-</sup> , N <sub>2</sub>	R <sub>2</sub> S, RSH, RS <sup>-</sup> I <sup>-</sup> , SCN <sup>-</sup> , S <sub>2</sub> O <sub>3</sub> <sup>2-</sup> , R <sub>3</sub> P, R <sub>3</sub> A (RO) <sub>3</sub> P CN <sup>-</sup> , RNC, CO C <sub>2</sub> H <sub>4</sub> , C <sub>6</sub> H <sub>6</sub> H <sup>-</sup> , R <sup>-</sup>

<sup>†</sup> R. G. Pearson, J. Am. Chem. Soc., **85**, 3533 (1963); Science, **151**, 172 (1966); Chem. Br., **3**, 103 (1967); J. Chem. Educ., **45**, 581, 643 (1968).

The principle of hard and soft acids and bases has many qualitative applications in inorganic chemistry. Because the hardness of an element usually increases with increasing oxidation state, to stabilize an element in a very high oxidation state, the element should be coordinated to hard bases, such as  $O^{2-}$ ,  $OH^-$ , and  $F^-$ . Thus iron(VI), silver(III), and platinum(VI) can be obtained in the compounds  $K_2FeO_4$ , AgO, and  $PtF_6$ , respectively. To stabilize an element in a low oxidation state, it should be coordinated to soft bases, such as CO and  $PR_3$ . Thus cobalt(-I) and platinum(0) are found in compounds such as  $Na[Co(CO)_4]$  and  $Pt[P(CH_3)_3]_4$ . In the series of compounds  $R_3SiI \rightarrow (R_3Si)_2S \rightarrow R_3SiBr \rightarrow R_3SiNC \rightarrow R_3SiCl \rightarrow R_3SiNCS \rightarrow R_3SiNCO \rightarrow R_3SiF$ , a given compound can be converted to any other on its right by refluxing it with the appropriate silver salt.<sup>37</sup> However, a compound cannot be converted in good yield to a compound on its left by this method. For example, the following reaction is irreversible:

Et<sub>3</sub>SiI + AgBr 
$$\rightarrow$$
 Et<sub>3</sub>SiBr + AgI

The soft silver ion prefers to bond to a relatively soft group, and the hard silicon

atom prefers to bond to a relatively hard group.

The qualitative concept of hard and soft acids and bases must be used with caution. If one does not take into account the *strengths* of Lewis acids and bases as well as their hardness or softness, wrong conclusions regarding the driving forces of acid-base reactions can be drawn. For example, consider the reaction

$$CHCl_3 \cdot NH_3 + B(CH_3)_3 \cdot C_6H_6 \implies CHCl_3 \cdot C_6H_6 + B(CH_3)_3 \cdot NH_3$$
 (7.1)

According to Tables 7.17 and 7.18 CHCl<sub>3</sub> and NH<sub>3</sub> are both hard, B(CH<sub>3</sub>)<sub>3</sub> is borderline, and C<sub>6</sub>H<sub>6</sub> is soft. Therefore one might predict that the reaction would go in the reverse direction. However, the reaction actually goes in the forward direction because of the very strong interaction between B(CH<sub>3</sub>)<sub>3</sub> and NH<sub>3</sub>. Obviously at least two parameters must be used to adequately characterize a Lewis acid or base

In Chap. 5 it was pointed out that the interaction of a proton with a Lewis base can be divided into two hypothetical parts: (1) the electrostatic interaction between the proton and the electronically frozen base molecule, and (2) the electronic relaxation, or flow of electron density toward the proton. This concept can be extended to the general interaction of Lewis acids with Lewis bases. Any such interaction can be broken up into an electrostatic part and a relaxation part. These two parts are referred to in the literature by a variety of terms. Thus the electrostatic interaction has been referred to as "the initial state interaction," "the frozen orbital potential," and "ionic interaction," and the relaxation part of the interaction has been referred to as "covalent bonding," "the final state interaction," "electron flow," and "polarization." Although there are some differences in the meanings of the expressions in each set, the expressions within each set are more or less interchangeable.

<sup>&</sup>lt;sup>37</sup> C. Eaborn, J. Chem. Soc., 3077 (1950); A. G. MacDiarmid, Prep. Inorg. React., 1, 165 (1964).

One way of quantitatively accounting for both the electrostatic and relaxation parts of acid-base interactions is by assigning two empirical parameters to each acid and each base and by equating the interaction energy of a given acid-base pair to a suitable algebraic function of the four parameters involved. For example, Drago et al.<sup>38</sup> have shown that the heat of reaction of an acid A and a base B to form an adduct AB can be calculated from the equation

$$-\Delta H^{\circ} = E_{A}E_{B} + C_{A}C_{B} \quad \text{kcal mol}^{-1}$$

where  $E_A$ ,  $E_B$ ,  $C_A$ , and  $C_B$  are empirical constants characteristic of the acid A and the base B. Values of these parameters are given in Tables 7.19 and 7.20 for a wide variety of Lewis acids and bases. The trends in the E parameters are more or less as expected for parameters which measure electrostatic character, and the trends in the C parameters are more or less as expected for parameters which measure covalent character. The parameters may be used to predict heats of adduct formation with an average error of 0.7 kcal mol<sup>-1</sup> or less. For example, we may use this method to calculate the heat of reaction 7.1. Using the appropriate data from Tables 7.19 and 7.20, we calculate  $\Delta H^\circ = -6.9$  kcal mol<sup>-1</sup> for the reaction as written.

<sup>38</sup> R. S. Drago and B. B. Wayland, *J. Am. Chem. Soc.*, **87**, 3571 (1965); R. S. Drago, *Chem. Br.*, **3**, 516 (1967); *Struct. Bonding (Berlin)*, **15**, 73 (1973); *J. Chem. Educ.*, **51**, 300 (1974), and references therein.

Table 7.19 Some selected acid parameters†

Acid	$C_A$	$E_A$
Iodine III	1.00	1.00
Iodine monochloride	0.830	5.10
p-tert-Butylphenol	0.387	4.06
p-Methylphenol	0.404	4.18 4.33
Phenol	0.442	4.17
p-Fluorophenol	0.446	4.34
p-Chlorophenol	0.478	4.42
m-Fluorophenol	0.506	4.48
m-Trifluoromethylphenol	0.530	2.04
tert-Butyl alcohol	0.300	5.93
Hexafluoroisopropyl alcohol	0.623	2.54
Pyrrole	0.295	9.88
Boron trifluoride	1.62	6.14
Boron trimethyl	1.70	16.9
Trimethylaluminum	1.43	13.3
Trimethylgallium	0.881	12.6
Triethylgallium	0.593	5.76
Trimethyltin chloride	0.0296	0.920
Sulfur dioxide	0.808	3.39
Bis(hexafluoroacetylacetonato)copper(II)	1,40	3.02
Chloroform	0.159	3,0

<sup>†</sup> R. S. Drago, J. Chem. Educ., 51, 300 (1974).

Table 7.20 Some selected base parameters†

Base	$C_B$	$E_B$
Pyridine	6.40	1.17
Ammonia	3.46	1.36
	5.88	1.30
Methylamine	8.73	1.09
Dimetriyianine		0.808
Trimethylamine	11.00	0.991
Triethylamine	1 34	0.886
Acetonitrile	2.58	1.32
Dimethylacetamide	1.74	0.975
Ethyl acetate	2.33	0.987
Acetone	3.25	0.963
Diethyl ether	2.38	1.09
p-Dioxane		0.978
Tetrahydrofuran	4.27	1.34
Difficinyl sulfoxide	2.03	0.339
Diethyl sulfide	OTOFI bise since 7.40 modernish to	0.341
Tetramethylene sulfide	7.90	1.34
Pyridine N-oxide	4.32	
Benzene	0.681	0.525
Mesitylene	2.19	0.574
2,2,6,6-Tetramethylpyridine N-oxyl	6.21	0.915

<sup>†</sup> R. S. Drago, J. Chem. Educ., 51, 300 (1974).

There is nothing inconsistent with a molecule acting both as a Lewis acid and a Lewis base. All that is required is an atom which can accept a pair of electrons and which has a lone pair of electrons. For example, SnCl<sub>2</sub> undergoes the following reactions in which it acts in turn as a Lewis acid and as a Lewis base:

$$SnCl_{2} \xrightarrow{Cl^{-}} SnCl_{3}^{-} \xrightarrow{PtCl_{4}^{2-}} Pt(SnCl_{3})_{5}^{3-}$$

$$SnCl_{2} \xrightarrow{N(CH_{3})_{3}} Cl_{2}SnN(CH_{3})_{3} \xrightarrow{BF_{5}} Sn$$

$$Cl$$

# PROBLEMS

\*7.1 The base-catalyzed exchange reaction of PH<sub>3</sub> and D<sub>2</sub>O may possibly proceed by a one-step process such as the following:

$$D_{2}O + PH_{3} + OD^{-} \rightarrow \begin{bmatrix} H \\ DOD \cdots P - H \cdots OD \\ H \end{bmatrix}^{\ddagger} \rightarrow DO^{-} + PH_{2}D + HOD$$

Consequently what may one say about the pK of PH<sub>3</sub>?

7.2 How do we know that phosphorous acid does not have the following structure?

- 7.3 Arrange the following aqueous acids in order of increasing acidity: HSO<sub>4</sub>-, H<sub>3</sub>O+, C<sub>2</sub>H<sub>3</sub>OH, H<sub>4</sub>SiO<sub>4</sub>, HSeO<sub>4</sub><sup>-</sup>, CH<sub>3</sub>GeH<sub>3</sub>, NH<sub>3</sub>, AsH<sub>3</sub>, HClO<sub>4</sub>, HSO<sub>3</sub>F.
- 7.4 According to the Branch and Calvin equation for estimating the pK of hydroxy acids, by what amount should the successive pK values of a polybasic acid differ?
- 7.5 Which of the following aqueous reactions would you expect to be the slowest? The fastest?

$$NH_4^+ \rightarrow NH_3 + H^+$$
  
 $NH_3 + OH^- \rightarrow H_2O + NH_2^-$   
 $HS^- \rightarrow H^+ + S^{2-}$   
 $HSO_4^- + OH^- \rightarrow H_2O + SO_4^{2-}$ 

- 7.6 Predict the pK of diamidophosphoric acid,  $HOPO(NH_2)_2$ .
- \*7.7 From the sublimation energy of ice (11.9 kcal mol<sup>-1</sup>) estimate the O—H ·
- \*7.8 Show that one might expect a significant fraction of the aqueous bisulfite ion to exist in the form of the HOSO<sub>2</sub>- isomer.
- 7.9 Explain why a solution of borax, Na<sub>2</sub>B<sub>4</sub>O<sub>7</sub> · 10H<sub>2</sub>O, is a good buffer solution.
- \*7.10 Because fluorine is more electronegative than chlorine, one might expect the boron atom in BF, to be more electron-deficient than that in BCl<sub>3</sub>. However, BCl<sub>3</sub> is a stronger acid toward N(CH<sub>3</sub>)
  - 7.11 Write equations for the net reactions which occur in the following cases:
    - (a) Aniline is added to a solution of potassium amide in liquid ammonia.
  - (b) Lithium nitride is added to a solution formed by the addition of acetic acid to excess liquid ammonia.
    - (c) NO<sub>2</sub>Cl is formed by passing HCl into a solution of nitric acid in concentrated sulfuric acid.
- (d) Boric acid is dissolved in sulfuric acid. (Six moles of dissolved species, including 2 mol of bisulfate ion, are formed per mole of boric acid.)
- 7.12 Explain how potassium acid phthalate can be a primary standard acid in water, and a primary standard base in anhydrous acetic acid.
- 7.13 What is the ammonium ion concentration in pure liquid ammonia?
- 7.14 Explain the fact that KOH is much more soluble in liquid ammonia containing water than in
- 7.15 Explain the fact that FeCl<sub>4</sub> is formed when FeCl<sub>3</sub> is dissolved in OP(OEt)<sub>3</sub>.
- 7.16 Which of the following reactions have equilibrium constants greater than 1 at ordinary temperature? tures? (All species may be assumed to be gaseous unless otherwise indicated.)
  - (a)  $R_3PBBr_3 + R_3NBF_3 \implies R_3PBF_3 + R_3NBBr_3$
  - (b)  $SO_2 + (C_6H_5)_3PHOC(CH_3)_3 \implies (CH_3)_3COH + (C_6H_5)_3PSO_2$
  - (c)  $\operatorname{AgCl}_2(aq) + 2\operatorname{CN}(aq) \Rightarrow \operatorname{Ag(CN)}_2(aq) + 2\operatorname{Cl}(aq)$ (d) MeOI + Et(CO)OMe  $\Rightarrow$  MeOOMe + Et(CO)I
- 7.17  $\Delta H^{\circ} = -3.9$  and -17.0 kcal mol<sup>-1</sup>, respectively, for the reactions

$$CHCl_3 + C_5H_5N \rightarrow C_5H_5NHCCl_3$$

and

Using these data and the E and C values for CHCl<sub>3</sub> and B(CH<sub>3</sub>)<sub>3</sub> from Tables 7.19 and 7.20, calculate  $E_a$  and  $C_B$  values for  $C_5H_5N$ .

- \*7.18 The heats of reaction of B(CH<sub>3</sub>)<sub>3</sub> with NH<sub>3</sub>, CH<sub>3</sub>NH<sub>2</sub>, (CH<sub>3</sub>)<sub>2</sub>NH, and (CH<sub>3</sub>)<sub>3</sub>N are 13.8, 17.6, 19.3, and 17.6 kcal mol<sup>-1</sup>, respectively. Can you explain why the value for (CH<sub>3</sub>)<sub>3</sub>N is out of line? 7.19 Both BH<sub>3</sub> and BF<sub>3</sub> form an adduct with (CH<sub>3</sub>)<sub>2</sub>NPF<sub>2</sub>. In one adduct, the boron atom is bonded to the nitrogen atom, and in the other, to the phosphorus atom. Predict and rationalize the structures of the adducts.
- \*7.20 Why are strongly acidic solvents used to prepare cationic species such as I<sub>2</sub><sup>+</sup> and Se<sub>8</sub><sup>2+</sup> and strongly basic solvents used to prepare anionic species such as S<sub>4</sub><sup>2-</sup> and Pb<sub>9</sub><sup>4-</sup>?
- 7.21 Cite other examples (besides those at the end of this chapter) of species which can act both as Lewis acids and Lewis bases.
- 7.22 On the basis of the parameters in Tables 7.19 and 7.20, predict (a) the relative order of the Lewis basicities of pyridine, dimethylamine, tetrahydrofuran, and diethyl sulfide with respect to the Lewis acid boron trimethyl, (b) the relative order of the Lewis acidities of  $I_2$ ,  $BF_3$ ,  $BMe_3$ , and  $SO_2$  with respect to the Lewis base acetonitrile.

# SOME THERMODYNAMIC AND KINETIC ASPECTS OF AQUEOUS REDOX CHEMISTRY

A chemist interested in carrying out a reaction in the laboratory requires two main kinds of information about the reaction: thermodynamic information and kinetic information. In this chapter, we will show how thermodynamics and kinetics can be used to systematize inorganic reactions, with particular emphasis on aqueous redox reactions. Of course it should be recognized that the principles can be applied to other types of reactions, to other solvent systems, and to systems with no solvent.

# THE USE OF THERMODYNAMIC DATA

The driving forces for chemical reactions are commonly expressed in the form of equilibrium constants or free-energy changes. However, the tabulation of such information for large numbers of related reactions is usually most efficiently accomplished not by tabulating the values of K or  $\Delta G^{\circ}$  for all the individual reactions, but by tabulating the free energies of formation of all the species involved in the various reactions. For example, one can write many thousands of reactions using as few as 100 different chemical species. Values of  $\Delta G^{\circ}_f$ , as well as  $\Delta H^{\circ}_f$  and  $S^{\circ}$ , are tabulated for various species in Appendix E.

It often happens that one or more of the  $\Delta G_f^\circ$  values required to calculate  $\Delta G^\circ$ 

for a reaction is unknown, but that the value of  $\Delta H^{\circ}$  for the reaction is known. In such cases an estimated value of  $\Delta S^{\circ}$  for the reaction can be very valuable. The ideal situation exists when the reaction is fairly symmetric, with species of similar complexity as reactants and products. For example, it would be a fairly good approximation to assume  $\Delta S^{\circ} = 0$  for the reaction

$$H_3PO_3 + H_3AsO_4 \longrightarrow H_3PO_4 + H_3AsO_3$$

and therefore  $\Delta H^{\circ}$  is a good approximation for  $\Delta G^{\circ}$  for this reaction. Probably  $\Delta S^{\circ}$  for this reaction differs from zero by no more than  $\pm 5$  cal deg<sup>-1</sup> mol<sup>-1</sup>, and therefore at room temperature  $\Delta H^{\circ}$  and  $\Delta G^{\circ}$  probably differ by no more than 1.5 kcal mol-1. On the other hand, it would be a very poor approximation to assume  $\Delta S^{\circ} = 0$  for the reaction

$$MnO_4^- + 5Fe^{2+} + 8H^+ \rightarrow Mn^{2+} + 5Fe^{3+} + 4H_2O$$

In this case, the highly charged Fe3+ ions have very negative entropies which are the principal cause of a very negative  $\Delta S^{\circ}$  for this reaction (-209.5 cal deg-1 mol<sup>-1</sup>). Hence for this reaction at 25°C,  $\Delta G^{\circ}$  is 62.5 kcal mol<sup>-1</sup> more positive than  $\Delta H^{\circ}$ 

When using chemical thermodynamic data, one must keep in mind the limitations of thermodynamics. Thermodynamic data give information only regarding the extent to which reactions can go, not regarding the rates at which they go. For example, although both of the following disproportionation reactions have equilibrium constants greater than 106, only the first proceeds at an appreciable rate under ordinary conditions:

$$2NO_2 + 2OH^- \rightarrow NO_2^- + NO_3^- + H_2O$$
 (fast)  
 $2N_2O \rightarrow N_2 + 2NO$  (slow)

The science, or art, of predicting the rates of chemical reactions is in a developmental stage. At present, often the best that can be done is to classify roughly certain classes of compounds as fast-reacting and others as slow-reacting. However, sometimes thermodynamic data are useful even in the absence of kinetic information. Thus, when thermodynamics tells us that a reaction cannot go, we are saved the trouble of trying the reaction.

Let us suppose that we wish to know whether hydrazine can be prepared by the oxidation of aqueous ammonia by nitric oxide. From a table of free energies of formation such as that in Appendix E, we could obtain the following data:

Species	$\Delta G_f^{\circ}$ (at 25°C). kcal mol <sup>-1</sup>
H <sub>2</sub> O( <i>l</i> )	-56.69
	30.6
$NH_3(aq)$	20.69
	-6.35

Thus we could calculate  $\Delta G^{\circ} = +49.0$  kcal mol<sup>-1</sup> and  $K = 1.2 \times 10^{-36}$  for the reaction

$$8NH_3(aq) + 2NO(g) \rightarrow 5N_2H_4(aq) + 2H_2O(l)$$

We would then realize that, under ordinary conditions, the reaction cannot proceed sufficiently to give an appreciable concentration of hydrazine.

However, one must be cautious in such applications of thermodynamics. Consider the reaction of a nonvolatile phase (or phases) to yield a volatile product (or products) for which  $\Delta G^{\circ} \gg 0$ . Reactions of this type often can be carried to completion by pumping on the reactants or by continuous sweeping of the nonvolatile phase with an inert carrier gas. An example of such a process is the dehydration of a solid compound in a desiccator. Even though the equilibrium dissociation pressure of water vapor over the compound may be far below 1 atm, it may be possible to dehydrate it completely in the desiccator, where the vapor is continuously removed from the gas phase by absorption by the desiccant Similarly, consider a reaction, for which  $\Delta G^{\circ} \gg 0$ , in which a gas reacts with a nonvolatile phase to yield a volatile product. Often such reactions can be carried to completion by sweeping the nonvolatile phase with the reactant gas, or by otherwise continuously removing the volatile product. An example of such a process is the synthesis of PtF<sub>6</sub> by the reaction of fluorine gas with a hot tungsten filament in a vessel with walls cooled by liquid nitrogen. The PtF6 formed at the high temperature is unstable with respect to the loss of F<sub>2</sub> to form PtF<sub>4</sub>. However, reasonable yields of the compound are obtained because convection currents in the reactor bring the PtF<sub>6</sub> in contact with the cold walls (where it freezes out) faster than it decomposes.

### Reduction Potentials<sup>2</sup>

Any oxidation-reduction (redox) reaction can be readily divided into two half-reactions—one in which an element undergoes oxidation and one in which an element undergoes reduction. We shall follow the convention of writing such half-reactions as reductions and shall measure their driving forces with reduction potentials, thus:

$$Na^{+} + e^{-} \rightarrow Na \qquad E^{\circ} = -2.71 \text{ V}$$

Of course there is no difficulty in applying the same methods, after taking account of the sign change, to oxidation potentials:

Na 
$$\to e^- + Na^+ E^\circ = +2.71 \text{ V}$$

Obviously, in order to use any potential, it is necessary to know whether it is an oxidation or reduction potential, and whether or not the above sign convention used. Particular care must be taken when using potentials from different sources. All the potentials cited in this chapter refer to 25°C.

<sup>&</sup>lt;sup>1</sup> B. Weinstock, J. G. Malm, and E. E. Weaver, *J. Am. Chem. Soc.*, **83**, 4310 (1961). <sup>2</sup> W. L. Jolly, *J. Chem. Educ.*, **43**, 198 (1966).

It should be remembered that the potentials are expressed in volts (a difference in electrical potential). Therefore a potential is a constant which does not change when the coefficients of the half-reaction are changed. Thus both of the following half-reactions have the same potential:

$$\frac{1}{2}I_2 + e^- \rightarrow I^- \qquad E^\circ = 0.536 \text{ V}$$
  
 $I_2 + 2e^- \rightarrow 2I^- \qquad E^\circ = 0.536 \text{ V}$ 

For simplicity, we shall hereafter omit the symbol V (for volt) in such expressions involving potentials.

#### The Use of Tabulated Potentials

Table 8.1 is a table of half-reactions and their standard potentials.<sup>3</sup> The reducing agents are listed in order of decreasing strength (and consequently the oxidizing agents are listed in order of increasing strength) from the top to the bottom of the table. An oxidizing agent should be able to oxidize all reducing agents lying above it in the table, and a reducing agent should be able to reduce all oxidizing agents lying below it in the table. However, because the potentials are "standard" potentials, this statement is strictly correct only when all the species are at unit activity. As will be shown later, exceptions to this rule can be effected by appropriate adjustment of product and reactant concentrations. Because from any pair of reduction potentials one can calculate the driving force for a complete, unique reaction, it is clear that a table of this sort summarizes an enormous amount of information in a small space. One calculates that a table of 100 reduction potentials would yield equilibrium constants for 4950 different reactions.

A tabulation of potentials like Table 8.1 is very handy when looking for oxidizing agents or reducing agents having a certain specified strength. However, a chemist often wishes to know whether a particular reaction can go, or what its equilibrium constant is. For such purposes it is more useful to have the half-reactions listed according to the elements whose oxidation states change.<sup>4</sup> Thus, if one wishes to know the driving force for the reaction

$$H_3AsO_3 + I_3^- + H_2O \rightarrow H_3AsO_4 + 3I^- + 2H^+$$

one looks under the arsenic potentials for

$$H_3AsO_4 + 2H^+ + 2e^- \rightarrow H_3AsO_3 + H_2O \quad E^\circ = 0.559$$

and under iodine for

$$I_3^- + 2e^- \rightarrow 3I^- E^\circ = 0.536$$

<sup>&</sup>lt;sup>3</sup> Most of the potentials given in this chapter are from W. M. Latimer, "Oxidation Potentials," 2d ed., Prentice-Hall, Englewood Cliffs, N.J., 1952.

Generally there is no ambiguity as to which elements change oxidation state. However, in the case of a half-reaction such as  $S_2O_8^{2-} + 2e^- \rightarrow 2SO_4^{2-}$  one might be justified in a double listing.

Table 8.1 The reduction potentials of some aqueous half-reactions

Acid solutions	G1 (100)	Basic solutions	はない
Couple	E°	Couple	E°
Na++e- → Na	-271	$M_{\rm P}(OH)$ + 2 $\rho^- \rightarrow M_{\rm P}$ + 2OH-	-2.69
$Mg^{2+} + 2e^- \rightarrow Mg$	-2.37	+ 36	-2.35
1	-1.66	1	-1.60
,	92.0-	1	-1.57
1	-0.50	1	-1.22
	-0.47	$2SO_3^{2-} + 2H_2O + 2e^- \rightarrow S_2O_4^{2-} + 4OH^-$	-1.12
	-0.14	1	-0.93
	80.0-	$HSnO_2 - + H_2O + 2e^- \rightarrow Sn + 3OH^-$	-0.91
	0.00	$2H_2O + 2e^- \rightarrow H_2(g) + 2OH^-$	-0.83
$HCOOH + 2H^+ + 2e^- \rightarrow HCHO + H_2O$	90.0	$AsO_4^{3-} + 3H_2O + 2e^- \rightarrow H_2AsO_3^{-} + 4OH^-$	19.0-
$S + 2H^+ + 2e^- \rightarrow H_2S$	0.14	$S + 2e^- \rightarrow S^{2-}$	-0.48
$Sn^{4+} + 2e^- \rightarrow Sn^{2+}$	0.15	6	-0.13
$SO_4^{2+} + 4H^+ + 2e^- \rightarrow H_2SO_3 + H_2O$	0.17	1	80.0-
$Fe(CN)_{s}^{3-} + e^{-} \rightarrow Fe(CN)_{s}^{4-}$	0.36	1	0.25
$I_3 - + 2e^- \rightarrow 3I^-$	0.54	$O_2(g) + 2H_2O + 4e^- \rightarrow 4OH^-$	0.40
$H_3AsO_4 + 2H^+ + 2e^- \rightarrow H_3AsO_3 + H_2O$	0.56	$10^{-} + H_2O + 2e^{-} \rightarrow I^{-} + 20H^{-}$	0.49
$O_2(g) + 2H^+ + 2e^- \rightarrow H_2O_2$	89.0	$MnO_4 - + 2H_2O + 3e^- \rightarrow MnO_2 + 4OH^-$	0.59
$Fe^{3+} + e^- \rightarrow Fe^{2+}$	0.77	$H_3IO_6^{2-} + 2e^- \rightarrow IO_3^- + 30H^-$	0.70
$NO_3^- + 4H^+ + 4e^- \rightarrow NO(g) + 2H_2O$	96.0	$BrO^- + H_2O + 2e^- \rightarrow Br^- + 2OH^-$	92.0
$Br_2 + 2e^- \rightarrow 2Br^-$	1.06	$HO_2 - + H_2O + 2e^- \rightarrow 30H^-$	0.88
$O_2(g) + 4H^+ + 4e^- \rightarrow 2H_2O$	E 0 1.23	$CIO^{-} + H_2O + 2e^{-} \rightarrow CI^{-} + 2OH^{-}$	68.0
$Cr_2O_7^{2-} + 14H^+ + 6e^- \rightarrow 2Cr^{3+} + 7H_2O$	1.33	$O_3(g) + H_2O + 2e^- \rightarrow O_2(g) + 2OH^-$	1.24
$Cl_2(g) + 2e^- \rightarrow 2Cl^-$	1.36	$S_2O_8^{2-} + 2e^- \rightarrow 2SO_4^{2-}$	2.01
$PbO_2 + 4H^+ + 2e^- \rightarrow Pb^{2+} + 2H_2O$	1.46		
$MnO_4^- + 8H^+ + 5e^- \rightarrow Mn^{2+} + 4H_2O$	1.51		
$H_5 IO_6 + H^+ + 2e^- \rightarrow IO_3 + 3H_2 O$	1.60		
$MnO_4 + 4H^+ + 3e^- \rightarrow MnO_2 + 2H_2O$	1.69		
$H_2O_2 + 2H^+ + 2e^- \rightarrow 2H_2O$	1.77 = 1.77		
4	2.01		
$O_3(g) + 2H^+ + 2e^- \rightarrow O_2(g) + H_2O$ $F_3(g) + 2e^- \rightarrow 2F^-$	2.07		

By subtracting the first half-reaction from the second, one gets the desired reaction. Whenever half-reactions are added or subtracted, one should not add or subtract the corresponding  $E^{\circ}$  values, but rather the appropriate number of electronvolts, or  $nE^{\circ}$  values (where n is the number of electrons appearing in a half-reaction). For the reaction under question,  $nE^{\circ} = 2(0.536 - 0.559) =$ -0.046. From this one can calculate  $\Delta G^{\circ}$  (in calories per mole) or K, using the The potentials for three half-reactions are plotted versus of the Fig. relations

$$-\Delta G^\circ = 23,060 nE^\circ$$
 and  $nE^\circ = 0.05916 \log K$   
 $\Delta G^\circ = 1060 \text{ cal mol}^{-1}$   
 $K = 0.17$ 

From these results one must not draw the conclusion that the reaction cannot proceed quantitatively in either direction. Indeed, there are volumetric methods of analysis based both on the quantitative oxidation of arsenious acid by triiodide and on the quantitative reduction of arsenic acid by iodide. These are accomplished by appropriately adjusting the hydrogen-ion concentration of the solu- $\frac{[I^-]^3[H_3AsO_4]}{[I_3^-][H_3AsO_3]} = \frac{0.17}{(10^{-7})^2} = 1.7 \times 10^{13}$ 

$$\frac{[I^{-}]^{3}[H_{3}AsO_{4}]}{[I_{3}^{-}][H_{3}AsO_{3}]} = \frac{0.17}{(10^{-7})^{2}} = 1.7 \times 10^{13}$$

and arsenious acid can be titrated with triiodide or vice versa. In 6 M HCl,

$$\frac{\text{[I-]}^3\text{[H}_3\text{AsO}_4\text{]}}{\text{[I}_3^-\text{][H}_3\text{AsO}_3\text{]}} \approx \frac{0.17}{6^2} \approx 5 \times 10^{-3} \qquad \text{(neglecting activity coefficients)}$$

and consequently arsenic acid can be quantitatively reduced by an excess of iodide. (The liberated triiodide can be titrated with thiosulfate.)

# Dependence of Potentials on pH

The general problem of the pH dependence of reduction potentials is of considerable. able importance. The potential of any half-reaction changes with the concentration of the species involved according to the Nernst equation,

$$E = E^{\circ} - \frac{0.05916}{n} \log Q$$

where Q has the same form as the equilibrium constant but is a function of the activities of the actual reactants and products and not those of the equilibrium state. If hydrogen ion or hydroxide ion appears in the half-reaction (and the corresponding ionic activity appears in Q), the potential will change with pH. Thus for the hydrogen-ion-hydrogen half-reaction,

$$H^+ + e^- \rightarrow \frac{1}{2}H_2 \qquad E^\circ = 0$$

we write

$$E = -0.05916 \log \frac{P_{\rm H_2}^{1/2}}{[\rm H^+]}$$

and for the oxygen-water half-reaction,

$$\frac{1}{2}O_2 + 2H^+ + 2e^- \rightarrow H_2O \quad E^\circ = 1.23$$

we write

$$E = 1.23 + 0.05916 \log ([H^+]P_{0,1}^{1/4})$$

The potentials for three half-reactions are plotted versus pH in Fig. 8.1. Theoretically no oxidizing agent whose reduction potential lies above the O<sub>2</sub>-H<sub>2</sub>O line, and no reducing agent whose reduction potential falls below the H<sup>+</sup>-H<sub>2</sub> line, can exist in aqueous solutions. Actually, for kinetic reasons, these lines can be extended about 0.5 V, and the dashed lines in Fig. 8.1 are more realistic boundaries for the region of stability of oxidizing and reducing agents in aqueous solutions.

One must take care to use reduction potentials only in the pH ranges for which they are valid. For example, the ferrous ion-iron reduction potential

$$Fe^{2+} + 2e^{-} \rightarrow Fe \quad E^{\circ} = -0.41$$

has little significance in alkaline solutions because the ferrous ion forms an essentially insoluble hydroxide. In order to calculate the appropriate potential for alkaline solutions one must know the solubility product for ferrous hydroxide  $(8 \times 10^{-16})$ . Note that by adding the Fe<sup>2+</sup> – Fe half-reaction to the reaction for the dissolution of ferrous hydroxide, we get the Fe(OH)2-Fe half-reaction:

$$\begin{array}{cccc} & \text{Fe}^{2+} + 2e^{-} & \rightarrow & \text{Fe} \\ & & \text{Fe}(\text{OH})_{2} & \rightarrow & \text{Fe}^{2+} + 2\text{OH}^{-} \\ \hline & \text{Fe}(\text{OH})_{2} + 2e^{-} & \rightarrow & \text{Fe} + 2\text{OH}^{-} \\ \end{array} \qquad \begin{array}{c} nE^{\circ} = -0.82 \\ nE^{\circ} = -0.89 \\ nE^{\circ} = -1.71 \end{array}$$

In the case of the Fe<sup>2+</sup>-Fe half-reaction,  $nE^{\circ}$  is simply obtained by multiplying -0.41 by 2. In the case of the reaction for the dissolution of Fe(OH)<sub>2</sub>,  $nE^{\circ}$  is




Figure 8.1 The H+-H2 and O2-H2O18 duction potentials as a function of pH.

obtained from the relation  $nE^{\circ} = 0.05916 \log K$ . One adds the electron volts (not the potentials!) for each step to obtain the electronvolts corresponding to the new half-reaction. The potential for the new half-reaction is then obtained by dividing by n, the number of electrons. Thus,  $E^{\circ} = -1.71/2 = -0.86$ .

### Reduction-Potential Diagrams

If an element can exist in several oxidation states, it is convenient to display the reduction potentials corresponding to the various half-reactions in diagrammatic form, as shown in the following diagrams for iron and oxygen.

One of the most important facts which can be learned from a reduction-potential diagram is which oxidation states, if any, are unstable with respect to disproportionation. If a given oxidation state is a stronger oxidizing agent than the next higher state, disproportionation can occur. (This is the situation when a reduction potential on the right is more negative than one on the left.) It will be noted that both Fe<sup>2+</sup> and Fe<sup>3+</sup> are stable with respect to disproportionation and that H<sub>2</sub>O<sub>2</sub> is unstable with respect to disproportionation. Thus the following reactions proceed spontaneously:

$$Fe + 2Fe^{3+} \rightarrow 3Fe^{2+}$$

$$2H_2O_2 \rightarrow 2H_2O + O_2$$

The latter reaction is very slow under ordinary conditions but rapid in the presence of certain catalysts.

Often species which are thermodynamically unstable with respect to dispro-Portionation are intermediates in oxidation-reduction reactions and are the cause of slow reactions. Hydrogen peroxide is such a species. Most oxidations by molecular oxygen proceed with intermediate formation of hydrogen peroxide.5 Thus, although any reducing agent with a reduction potential more negative than that of the  $O_2$ - $H_2O$  half-reaction (1.23 V) can theoretically be oxidized by  $O_2$ - $H_2O_2$ - $H_2O_3$ - $H_2O_3$ - $H_2O_3$ - $H_2O_3$ - $H_2O_3$ - $H_2O_3$ - $H_3O_3$ - $H_3O$ Oxygen, those with reduction potentials more positive than that of the  $O_2$ - $H_2O_2$ half-reaction (0.68 V) produce intermediates (including H<sub>2</sub>O<sub>2</sub>) of higher energy than the reactants. Therefore reactions of the latter type have high activation

Indeed, one-electron reducing agents (including many transition-metal ions) reduce oxygen to an even more even more unstable species, the superoxide ion,  $O_2^-$ . For a discussion of the mechanisms of such reactions reactions, see J. Wilshire and D. T. Sawyer, Acc. Chem. Res., 12, 105 (1979).

energies and proceed slowly. In agreement with this rule, bromide  $(Br_3^--Br_5^-, E^\circ = 1.05)$  is oxidized very slowly, and iodide  $(I_3^--I^-, E^\circ = 0.54)$  is oxidized

rapidly.

Sometimes it is not immediately obvious from an abbreviated reduction-potential diagram that a particular species is unstable with respect to disproportionation. Consider the diagram for phosphorus in basic solution (1 M OH<sup>-</sup>):

$$PH_3 \leftarrow \frac{-0.89}{} P_4 \leftarrow \frac{-2.05}{} H_2PO_2^- \leftarrow \frac{-1.57}{} HPO_3^{2-} \leftarrow \frac{-1.12}{} PO_4^{3-}$$

Hypophosphite (H<sub>2</sub>PO<sub>2</sub><sup>-</sup>) is stable with respect to disproportionation into phosphorus and phosphite. But if we consider the phosphine-hypophosphite half-reaction as shown in the more complete diagram,

$$PH_3 \leftarrow 0.89 \qquad P_4 \leftarrow -2.05 \qquad H_2PO_2 \leftarrow -1.57 \qquad HPO_3^2 \leftarrow -1.12 \qquad PO_4^3 \leftarrow -1.18$$

we see that hypophosphite is unstable with respect to the formation of phosphine and phosphite. This reaction takes place when solid hypophosphites are heated, but in hot aqueous solution the principal reaction is the reduction of water to give hydrogen:

$$H_2PO_2^- + OH^- \rightarrow HPO_3^{2-} + H_2$$

It is appropriate at this point to show how one calculates potentials when adding or subtracting two half-reactions to form a third half-reaction. As shown below, the phosphorus-phosphine and hypophosphite-phosphorus half-reactions may be added to give the hypophosphite-phosphine half-reaction

$$\frac{{}_{4}^{1}P_{4} + 3H_{2}O + 3e^{-} \rightarrow PH_{3} + 3OH^{-}}{H_{2}PO_{2}^{-} + e^{-} \rightarrow {}_{4}^{1}P_{4} + 2OH^{-}} \frac{nE^{\circ} = -2.67}{nE^{\circ} = -2.05}$$

$$\frac{H_{2}PO_{2}^{-} + 3H_{2}O + 4e^{-} \rightarrow PH_{3} + 5OH^{-}}{nE^{\circ} = -4.72}$$

We divide the sum of the electronvolts by the number of electrons in the new half-reaction to get the new potential. Thus,  $E^{\circ} = -4.72/4 = -1.18$ . It can be seen that the new potential is a weighted average of the other two.

One of the nicest applications of reduction-potential diagrams is the prediction of the products of reactions involving elements having several oxidation states. Let us consider the reactions of iodide with permanganate in acid solution. The pertinent diagrams are shown below.

$$I^{-} \stackrel{0.54}{\longleftarrow} I_{3}^{-} \stackrel{1.45}{\longleftarrow} HOI \stackrel{1.14}{\longleftarrow} IO_{3}^{-} \stackrel{\sim 1.7}{\longleftarrow} H_{5}IO_{6}$$

$$\downarrow \qquad \qquad \downarrow \qquad$$

In this case we may correctly assume that the reactions are "thermodynamically controlled," i.e., that equilibria are fairly rapidly achieved.<sup>6</sup> We notice that there are three species in these diagrams which are unstable toward disproportionation: HOI, Mn<sup>3+</sup>, and MnO<sub>4</sub><sup>2-</sup>. These are therefore eliminated from consideration. The Mn<sup>2+</sup>–Mn half-reaction is of no concern to us, because its reduction potential is far too negative for Mn to have any stability in acid solution. Therefore we may justifiably consider only the simplified diagrams

$$I^{-}$$
  $\stackrel{0.54}{\longleftarrow}$   $I_{3}^{-}$   $\stackrel{1.20}{\longleftarrow}$   $IO_{3}^{-}$   $\stackrel{\sim 1.7}{\longleftarrow}$   $H_{5}IO_{6}$ 
 $Mn^{2+}$   $\stackrel{1.239}{\longleftarrow}$   $MnO_{2}$   $\stackrel{1.69}{\longleftarrow}$   $MnO_{4}^{-}$ 

If the reaction between iodide and permanganate is carried out with iodide in excess (as when permanganate is added dropwise to a hydroiodic acid solution), then the products of the reaction must be compatible with the presence of iodide ion. Thus under these conditions iodate cannot be formed, because iodate would react with excess iodide to form triiodide. Similarly, manganese dioxide cannot be formed because it is capable of oxidizing iodide. The observed net reaction is

$$15I^{-} + 2MnO_{4}^{-} + 16H^{+} \rightarrow 5I_{3}^{-} + 2Mn^{2+} + 8H_{2}O$$

If the reaction is carried out with permanganate in excess (as when iodide is added dropwise to an acidic permanganate solution), the products of the reaction must be compatible with the presence of permanganate. Thus manganous ion cannot be formed, because it would react with permanganate to form manganese dioxide. The iodide would not be oxidized just to triiodide, because triiodide is capable of reducing permanganate. The fact that the  $H_5IO_6-IO_3^-$  and  $MnO_4^--MnO_2$  half-reactions have potentials of similar magnitude complicates the problem. It turns out that iodide is not cleanly oxidized to either iodate or periodic acid but to a mixture of these products:


$$I^{-} + 2MnO_{4}^{-} + 2H^{+} \rightarrow IO_{3}^{-} + 2MnO_{2} + H_{2}O$$
  
 $3I^{-} + 8MnO_{4}^{-} + 11H^{+} + 2H_{2}O \rightarrow 3H_{5}IO_{6} + 8MnO_{2}$ 


Notice that entirely different products are obtained when the reactant in excess is changed.

Reduction-potential diagrams for the more important elements that exist in several oxidation states are given in Table 8.2.

 $<sup>^6</sup>$  The oxidation of water by  $H_3IO_6$  and  $MnO_4^-$  is slow under ordinary conditions. The potentials for these oxidizing agents barely fall between the dashed lines of Fig. 8.1.


Table 8.2 Reduction-potential diagrams+







† Most of the potentials given in this chapter are from W. M. Latimer, "Oxidation Potentials," 2d ed., Prentice-Hall, Englewood Cliffs, N.J., 1952.

Table 8.2 (continued)





† Most of the potentials given in this chapter are from W. M. Latimer, "Oxidation Potentials," 2d ed., Prentice-Hall, Englewood Cliffs, N.J., 1952.



We have already point 25 potentials indicate iki , Englewood Cliffs, N.J. d ed., Prentice-Hall, E Potentials," 2d e "Oxidation M. Latimer, are relatively high conces given in this J. O. Échands, "Ino st Kinches of Inorganie P.

6.0

229

ganic Reactions, in Sphinson

#### MECHANISMS OF OXYANION REACTIONS7

We have already pointed out that, even if thermodynamic data such as reduction potentials indicate that a reaction has a large driving force, without kinetic information one cannot know whether or not the reaction proceeds at a reasonable rate. Let us consider oxidation-reduction reactions involving oxyanions such as BrO<sub>3</sub><sup>-</sup>, SO<sub>4</sub><sup>2-</sup> and OCl<sup>-</sup>. Most of these reactions involve the transfer of an oxygen atom (or oxygen atoms) from one atom to another. In the oxyanions, the oxygen atoms are held very tightly, and therefore direct transfer processes such as the following are very slow:

$$NO_2^- + OCl^- \rightarrow NO_3^- + Cl^-$$
  
 $ClO_3^- + I^- \rightarrow ClO_2^- + Ol^-$ 

Such reactions are usually acid-catalyzed. When one or two protons are attached to a coordinated oxide ion, the negative charge of the oxide ion is at least partly canceled and an  $OH^-$  ion or  $H_2O$  molecule can then leave the central atom of the oxyanion relatively easily. Consider the reaction of chlorate with a halide ion:

$$ClO_3^- + 6X^- + 6H^+ \rightarrow Cl^- + 3X_2 + 3H_2O$$

The rate law for this reaction is

Rate = 
$$k[ClO_3^-][X^-][H^+]^2$$

and the initial steps of the mechanism are believed to be as follows:

$$2H^{+} + ClO_{3}^{-} \rightleftharpoons H_{2}OClO_{2}^{+}$$
 (fast)  

$$X^{-} + H_{2}OClO_{2}^{+} \rightarrow XClO_{2} + H_{2}O$$
 (slow)  

$$XClO_{2} + X^{-} \rightarrow X_{2} + ClO_{2}^{-}$$
 (fast)

The ClO<sub>2</sub> ion is then reduced to Cl by a sequence of rapid reactions.

In the ClO<sub>3</sub><sup>-</sup>-Cl<sup>-</sup> reaction, if the intermediate ClClO<sub>2</sub> is allowed to reach a relatively high concentration, as by treating concentrated ClO<sub>3</sub><sup>-</sup> solution with concentrated HCl solution, a different reaction occurs, in which two ClClO<sub>2</sub> molecules interact to yield chlorine and chlorine dioxide:

$$O_2CICI + CICIO_2 \longrightarrow 2CIO_2 + CI_2$$

This mechanism has been shown to be consistent with experiments involving isotopically labeled chlorine. When labeled \*ClO<sub>3</sub><sup>-</sup> and ordinary HCl are used, all the labeling ends up in the \*ClO<sub>2</sub>, and none in the Cl<sub>2</sub>.<sup>8</sup>

Although the evidence for the species CIXO<sub>2</sub>, BrXO<sub>2</sub>, and IXO<sub>2</sub> in halate-ha-

8 H. Taube and H. Dodgen, J. Am. Chem. Soc., 71, 3330 (1949).

<sup>&</sup>lt;sup>7</sup> J. O. Edwards, "Inorganic Reaction Mechanisms," Benjamin, New York, 1964; A. G. Sykes, "Kinetics of Inorganic Reactions," Pergamon, New York, 1966; D. Benson, "Mechanisms of Inorganic Reactions in Solution," McGraw-Hill, London, 1968.

lide reactions is purely circumstantial, the compounds FClO<sub>2</sub>, FBrO<sub>2</sub>, and FIO<sub>2</sub> have actually been prepared and isolated using the following indicated processes.9

$$12KClO_3 + 20BrF_3 \longrightarrow 12KBrF_4 + 4Br_2 + 6O_2 + 12FClO_2$$

$$BrF_5 + 2Br_2 + 10O_3 \longrightarrow 5FBrO_2 + 10O_2$$

$$I_2O_5 + F_2 \xrightarrow{HF} 2FIO_2 + \frac{1}{2}O_2$$

It is conceivable that the first intermediate in the ClO<sub>3</sub>-X<sup>-</sup> reaction, H<sub>2</sub>OClO<sub>2</sub><sup>+</sup>, loses a water molecule before reaction with X<sup>-</sup>, but the kinetic data do not give information on this point. The rate law would be unchanged if the rate-determining step were

It is known that dehydrated intermediates of this type are involved in some reactions. For example, the nitration of an aromatic hydrocarbon by a solution of nitric acid in concentrated sulfuric acid probably proceeds as follows:

$$HNO_3 + H^+ \rightleftharpoons NO_2^+ + H_2O$$
 (fast)  
 $NO_2^+ + ArH \rightarrow ArNO_2 + H^+$  (slow)

The electrophilic  $NO_2^+$  ion attacks the  $\pi$  electron system of the hydrocarbon, with displacement of a proton to the solvent. The nitrosation of a secondary amine by nitrous acid is acid-catalyzed and is believed to proceed as follows:

$$HNO_2 + H^+ \implies NO^+ + H_2O \qquad K = 2 \times 10^{-7}$$
  
 $NO^+ + R_2NH \rightarrow R_2NNO + H^+ \qquad \text{(slow)}$ 

The NO+ can be detected in HNO<sub>2</sub>-H<sub>2</sub>SO<sub>4</sub>-H<sub>2</sub>O mixtures by its ultraviolet absorption spectrum. The exchange of <sup>18</sup>O between H<sub>2</sub><sup>18</sup>O and SO<sub>4</sub><sup>2-</sup> is acidcatalyzed and may involve the following mechanism:

$$2H^{+} + SO_{4}^{2-} \implies H_{2}SO_{4}$$
 $H_{2}SO_{4} \longrightarrow SO_{3} + H_{2}O$  (slow)
 $H_{2}^{18}O + SO_{3} \longrightarrow 2H^{+} + SO_{3}^{18}O^{2-}$  (fast)

The charge of the central atom of an oxyanion seems to be very important in determining reactivity: the lower the charge, the higher the reactivity. 10 Thus, rates for reactions of the chlorine oxyanions increase in the order ClO<sub>4</sub> <  $ClO_3 - ClO_2 - ClO$ . The rate of oxygen exchange with water increases in the order  $ClO_4^- < SO_4^{2-} < HPO_4^{2-} < H_2SiO_4^{2-}$ . The size of the central atom is also impact. important; the larger it is, the higher the reactivity. For example, iodate reactions

<sup>&</sup>lt;sup>9</sup> M. Schmeisser and K. Brändle, Adv. Inorg. Chem. Radiochem., 5, 41 (1963).

It should be remembered that, for a series of closely related species, atomic charge is a function of formal charge and of oxidation state.

are fast, chlorate reactions are slow, and bromate reactions are of intermediate rate.

Proof of the transfer of an oxygen atom from an oxidizing agent to a reducing agent has been obtained in the case of the reaction of nitrite with hypochlorous acid.<sup>11</sup> When <sup>18</sup>O-labeled HOCl was used, the <sup>18</sup>O ended up in the nitrate product:

$$NO_2^- + H^{18}OCl \rightarrow H^+ + NO_2^{18}O^- + Cl^-$$

The reaction may be looked upon as an S<sub>N</sub>2 attack of nitrite on the oxygen of HOCl, with displacement of chloride.

Sometimes the product formed when a species is oxidized depends on whether or not one uses a 1-equivalent oxidizing agent or a 2-equivalent oxidizing agent. Examples of 1-equivalent oxidizing agents are Fe<sup>3+</sup> and Ce<sup>4+</sup>, which undergo reduction by accepting one electron each. Examples of 2-equivalent oxidizing agents are Tl<sup>3+</sup> (which accepts two electrons to form Tl<sup>+</sup>) and IO<sub>5</sub> (which effectively accepts two electrons by loss of an oxygen atom). The oxidation of aqueous sulfur dioxide can proceed by two main paths: 12

$$SO_2 + H_2O \implies e^- + \frac{1}{2}S_2O_6^{2-} + H^+$$
  
 $SO_2 + 2H_2O \implies 2e^- + SO_4^{2-} + 4H^+$ 

The observed stoichiometries for various oxidizing agents are shown in Table 8.3. It can be seen that the 2-equivalent oxidizing agents almost invariably give sulfate as the only product and that the 1-equivalent oxidizing agents and the oxidizing agents which can act either as 1-equivalent or 2-equivalent generally give both sulfate and dithionate as products. It is interesting to note that the stoichiometry is completely independent of the reduction potential of the oxioxidants. These results can be explained by mechanisms in which the 2-equivalent oxidants take the S(IV) directly to S(VI),

and in which the 1-equivalent oxidants give an intermediate radical species which can either dimerize to give dithionate or lose another electron to give sulfate:

$$HSO_3^- \xrightarrow{-e^-} SO_3^- \longrightarrow \frac{1}{2}S_2O_6^{2-} + OUH$$
atter mechanism is undoubtedly as

The latter mechanism is undoubtedly oversimplified; oxidations by some transition-metal complexes probably involve intermediates in which the ·SO<sub>3</sub> - groups are stabilized by complexing with the metal atoms or with ligands.<sup>13</sup>

<sup>&</sup>lt;sup>11</sup> H. Taube, Rec. Chem. Prog. Kresge-Hooker Sci. Libr., 17, 25 (1956). <sup>12</sup> W. C. E. Higginson and J. W. Marshall, J. Chem. Soc., 447 (1957).

J. Veprek-Siska et al., Collect. Czech. Chem. Soc., 447 (1957).
 W. C. E. Higginson, J. Chem. Soc. Chem. Commun., 31, 1248, 3287 (1966); A. Brown and (1972).

Table 8.3 Stoichiometries of the oxidation of sulfur dioxide†

Oxidizing agent	Equivalents per SO <sub>2</sub> molecule
1-equivalent oxidants	3.7 × 10;
Ce4+	02411-011.27-1.44
Co3+	1.04-1.37
Fe <sup>3+</sup>	entrations are 2.1 cessed in molecules.
IrCl <sub>6</sub> 2-	1.2-1.87
Mo(CN) <sub>8</sub> 3-	1.94-2.00
Mn(H <sub>2</sub> P <sub>2</sub> O <sub>7</sub> ) <sub>3</sub> <sup>3</sup> -	~ 1.24
I- and 2-equivalent oxid	ants
	all of the princed had wender 1.84-1.95 arms of roll a
	It don't OLX to not use and 1.55-1.80 obtain mulesal
PtCl <sub>6</sub> <sup>2-</sup>	section profiles blookeses of he ~ 2.00 outglos oblinon.
VO <sub>2</sub> + Alast antibaseque	receiving the unit of the same as those for the services
2-equivalent oxidants	
I <sub>2</sub>	seed into a not soon to seed um hydroxide.
Br <sub>2</sub>	bios sinoldo suo 1 98_2 00 m m of babbi
Cl <sub>2</sub> dortulos	1.99-2.00
IO <sub>3</sub> -	LOZEN to nobulos sebesa de la 2.00 de obti boldous
	stand to solution aminals as 1.77-1.95 records of Na. 24
$H_2O_2$	Ozali to ~ 2.00
T]3+	~ 2.00

<sup>†</sup> W. C. E. Higginson and J. W. Marshall, J. Chem. Soc., 447 (1957); E. L. Stapp and D. W. Carlyle, *Inorg. Chem.*, 13, 834 (1974).

# The Landolt Clock Reaction of the Aller of the Control of the Cont

The reduction of iodate by bisulfite is a fascinating reaction that is often used as an entertaining lecture demonstration.<sup>14</sup> In acid solution iodate is reduced slowly by bisulfite to iodide.

$$IO_3^- + 3HSO_3^- \rightarrow I^- + 3HSO_4^-$$

lodate also reacts fairly rapidly with iodide to form iodine,

$$IO_3^- + 5I^- + 6H^+ \rightarrow 3I_2 + 3H_2O$$

but the liberated iodine is reduced very rapidly by bisulfite,

$$I_2 + HSO_3^- + H_2O \rightarrow 2I^- + HSO_4^- + 2H^+$$

The last reaction is so rapid that no iodine appears until all the bisulfite has been Oxidized. At that point, especially if a little starch is present, the solution suddenly becomes nearly opaque. The time required for the iodine to appear is a

<sup>&</sup>lt;sup>14</sup> H. Landolt, Chem. Ber., 18, 249 (1885); 19, 1317 (1886); 20, 745 (1887); J. A. Church and S. A. Dreskin, J. Phys. Chem., 72, 1387 (1968), and references therein.

function of concentrations and temperature, and the reaction may be used as a clock. The time T, in seconds at 23°C, is approximately given by the expression

$$T = \frac{3.7 \times 10^{-3}}{[IO_3^-][HSO_3^-]}$$

where the concentrations are expressed in molarities.

#### PROBLEMS

- 8.1 Write equations for the principal net reactions which occur in the following cases:
  - (a) A little potassium iodide is dissolved in a solution of KIO<sub>3</sub> in 6 M HCl.
- (b) Aqueous triiodide solution is added to excess cold sodium carbonate solution. (Potentials for half-reactions involving I<sub>3</sub><sup>-</sup> are practically the same as those for the corresponding half-reactions involving I2.)
  - (c) Cl<sub>2</sub>O is passed into a hot solution of sodium hydroxide.
  - (d) Iodine is added to an excess of aqueous chloric acid.
  - (e) Sodium hypophosphite is added to an excess of an acidic KMnO<sub>4</sub> solution.
  - (f) Arsine is bubbled into an excess of an acidic solution of Fe(NO<sub>3</sub>)<sub>3</sub>.
  - (g) A suspension of powdered sulfur in an alkaline solution of Na<sub>2</sub>SO<sub>3</sub> is boiled.
  - (h) Arsine is bubbled into a solution of H<sub>3</sub>AsO<sub>3</sub>. (i) K<sub>2</sub>FeO<sub>4</sub> is added to excess dilute nitric acid.
  - (j) A solution of Na<sub>2</sub>CrO<sub>4</sub> is added to an excess of a solution of V<sup>3+</sup> in dilute HClO<sub>4</sub>.
  - (k) Chlorine is passed into a cold NaOH solution.
  - (1) Air is bubbled through an Na<sub>2</sub>S solution until reaction ceases.
  - (m) Nitrogen dioxide is bubbled into an NaOH solution.
  - (n) Anhydrous H<sub>3</sub>PO<sub>3</sub> is heated in vacuo.
  - (o) An excess of powdered arsenic is added to an acidic solution of Ag+.
  - (p) Ferrous sulfate solution is added to excess alkaline hypochlorite solution.
  - (q) Mercurous nitrate solution is added to a solution of arsenious acid.
  - (r) Na<sub>2</sub>CrO<sub>4</sub> is added to an excess of a strongly acidic Mn<sup>2+</sup> solution. A solution of V3+ is added to excess Fe3+ solution.
  - (t) Tl(OH)<sub>3</sub> is added to excess HI solution.
- (u) Excess ozone is bubbled through a solution of Ru<sup>2+</sup>. 8.2 Show that the reduction potentials are consistent with the facts that the ruthenate ion, RuO<sub>4</sub><sup>2</sup>, is stable in 1 M OH<sup>-</sup>, even if the solution is boiled, whereas if the pH is lowered to about 12, disproportionation to RuO2 and RuO4 occurs.
- 8.3 Calculate the  $MnO_4$   $MnO_2$  reduction potential for pH = 7.
- **8.4** Calculate the  $HPO_3^{2-} P_4$  reduction potential for  $[OH^-] = 1 M$ .
- 8.5 Calculate the equilibrium constants for the following reactions:

$$4H^{+} + 2CI^{-} + MnO_{2} \rightarrow CI_{2} + Mn^{2+} + 2H_{2}O$$
 $O_{3}(g) + Xe(g) \rightarrow XeO_{3}(aq)$ 

\*8.6 The decomposition of Caro's acid (H<sub>2</sub>SO<sub>5</sub>) to oxygen and bisulfate follows the rate law: Rate  $k[HSO_5^-][SO_5^{2-}]$ . Two conceivable "mechanisms" for the reaction are indicated below. Explain how one of these could be eliminated by the use of 18O labeling.

- \*8.7 The rate of exchange of oxygen atoms between water and phosphate passes through a maximum at pH 5. Propose a plausible mechanism involving a reactive intermediate.
- 8.8 Number the following aqueous reactions in order of increasing rate in 1 M H<sup>+</sup> at room temperature.

other reason, or the solution to place surrous proceeds. For example, the

- (a)  $IO_3^- + 8I^- + 6H^+ \rightarrow 3I_3^- + 3H_2O$
- (b)  $BrO_3^- + 5Br^- + 6H^+ \rightarrow 3Br_2 + 3H_2O$ 
  - (c)  $CIO_4^- + 12I^- + 8H^+ \rightarrow 4I_3^- + CI^- + 4H_2O$
  - (d)  $HOI + 2I^- + H^+ \rightarrow I_3^- + H_2O$

### SOLVATED ELECTRONS

The electron is the simplest and most fundamental chemical species. We now know that it can exist in solution much like any other anion and that it can engage in a wide variety of reactions. First we will discuss the production of the aqueous electron and the methods used to study its very fast reactions with other aqueous species. Then we will study the remarkable metastable solutions of alkali metals in liquid ammonia, which allow us to use the ammoniated electron as a valuable reagent in synthetic chemistry. Finally we will consider alkali-metal anions, which are legitimate examples of alkali metals in the -1 oxidation state.

## THE HYDRATED ELECTRON'

When an aqueous solution is irradiated with x-rays, gamma rays, or accelerated electrons, water molecules are ionized as follows:

$$H_2O \xrightarrow{\text{high energy}} H_2O^+ + e^-$$

An ejected electron generally has a high energy which is rapidly dissipated by collisions in which electrons are knocked out of other water molecules. In about  $10^{-11}$  s the ejected electron reaches thermal equilibrium and becomes hydrated; we represent the hydrated species by  $e^-_{aq}$ . In the meantime  $H_2O^+$  is transformed into OH by the reaction

$$H_2O^+ + H_2O \rightarrow H_3O^+ + OH$$

<sup>1</sup> E. J. Hart, Acc. Chem. Res., 2, 161 (1969); E. J. Hart and M. Anbar, "The Hydrated Electron," Wiley-Interscience, New York, 1970; M. Anbar and P. Neta, Int. J. Appl. Radiat. Isot., 18, 493 (1967).

Hence the net ionization reaction is

$$2H_2O \rightarrow H_3O^+ + OH + e^-_{aq}$$

The radiation promotes some water molecules into highly excited electronic states. These excited water molecules decompose into H and OH radicals:

$$H_2O^* \rightarrow H + OH$$

Thus the irradiation of an aqueous solution gives H, OH, and  $e^{-}_{aq}$  as the major primary reactive species. These species may react with water, with themselves, or with other reagents in the solution to give various products. For example, the hydrated electron is known to react with  $H_2O_2$ ,  $O_2$ ,  $H^+$ , and  $NO_2^-$  as shown in the following reactions:

$$e^{-}_{aq} + H_2O_2 \rightarrow OH + OH^-$$
 (9.1)

$$e^{-}_{aq} + O_2 \rightarrow O_2^{-} \tag{9.2}$$

$$e^-_{\rm aq} + H^+ \rightarrow H$$
 (9.3)

$$e^{-}_{aq} + NO_{2}^{-} \rightarrow NO_{2}^{2-}$$
 (9.4)

Before 1960, many reduction reactions of this type were mistakenly ascribed to atomic hydrogen. In 1962 Czapski and Schwarz<sup>2</sup> reported data which proved that, in each of the four reactions above, the primary reducing species has a -1 charge and therefore probably is  $e^-_{aq}$ . They had no facilities for measuring the absolute rate constants for these reactions, but they were able to measure the ratios of rate constants by determining the relative yields of final products in systems in which two of the reactions were competing. They determined rate-constant ratios as a function of ionic strength and used the following Brönsted-Bjerrum equation<sup>3</sup> to evaluate the charge of the reducing species:

$$\log \frac{k}{k_0} = \frac{1.02 Z_a Z_b \mu^{1/2}}{1 + \mu^{1/2}}$$

In this equation k is the rate constant at ionic strength  $\mu$ ,  $k_0$  is the rate constant at infinite dilution, and  $Z_a$  and  $Z_b$  are the charges of the species involved in the second-order reaction. In Fig. 9.1,  $\log \left[ (k/k_0)_n/(k/k_0)_1 \right]$  is plotted versus  $\mu^{1/2}/(1+\mu^{1/2})$  for n=2,3, and 4 (i.e., for the rate constants of reactions 9.2, 9.3, and 9.4 relative to that for reaction 9.1). The points for reaction 9.2 form a line of zero slope corresponding to  $Z_aZ_b=0$ . Because the charge of the  $O_2$  molecule is zero, this result is expected. The points for reaction 9.3 form a line of -1 slope, as expected for  $Z_a$  and  $Z_b$  values of opposite sign. The points for reaction 9.4 form a line of +1 slope, as expected for  $Z_a=Z_b=-1$ . Thus the variation of the rate constants with ionic strength is consistent with a -1 charge for the reducing species in these reactions.

<sup>&</sup>lt;sup>2</sup>G. Czapski and H. A. Schwarz, *J. Phys. Chem.*, **66**, 471 (1962).

<sup>3</sup>A. A. Frost and R. G. Pearson, "Kinetics and Mechanism," 2d ed., pp. 150–153, Wiley, New York, 1961.




Figure 9.1 Plot of  $\log[(k/k_0)_n/(k/k_0)_1]$  versus  $\mu^{1/2}/(1 + \mu^{1/2})$ . Upper curve, n = 4; middle curve, n = 2; lower curve, n = 3. The ionic strength was varied with LiClO<sub>4</sub> (O), KClO<sub>4</sub> ( $\square$ ), NaClO<sub>4</sub> ( $\triangle$ ), and MgSO<sub>4</sub> (x). The closed circles represent no added salt other than reactants. [Reproduced with permission from G. Czapski and H. A. Schwarz, J. Phys. Chem., 66, 471 (1962). Copyright 1962 American Chemical Society.]

Although the hydrated electron decays very rapidly in aqueous solutions, it is possible to obtain its absorption spectrum by fast-scan spectrophotometry of solutions which have been exposed to an intense pulse of radiation. The absorption spectrum is shown in Fig. 9.2. Notice that  $e^{-}_{aq}$  has a broad absorption band at 715 nm, corresponding to a blue solution. By following the absorbance of  $e^{-}_{aq}$  as a function of time (during an interval of approximately 1 millisecond), it is




Figure 9.2 Absorption spectrum of  $e_{nq}$  (Adapted with permission from E. J. Hart and M. Anbar. "The Hydrated Electron," Wiley-Interscience, New York, 1970.)

Table 9.1 Rate constants of some e- reactions†

Reaction	Rate constant, $M^{-1}$ s <sup>-1</sup>
$e^{-}_{sq} + H_2O \rightarrow H + OH^-$	16
$e_{aq}^- + e_{aq}^- \xrightarrow{2H_2O} H_2 + 2OH^-$	$6.0 \times 10^{9}$
$e^{sq} + H \xrightarrow{H_2O} H_2 + OH^-$	$2.5 \times 10^{10}$
e <sup>-aq</sup> + OH → OH <sup>-</sup>	$3.0 \times 10^{10}$
$e^{-}_{aq} + H^{+} \rightarrow H$	$2.1 \times 10^{10}$
$e^{aq} + H_2O_2 \rightarrow OH + OH^-$	$1.2 \times 10^{10}$

† J. Hart, Acc. Chem. Res., 2, 161 (1969); E. J. Hart and M. Anbar,
"The Hydrated Electron," Wiley-Interscience, New York, 1970; M.
Anbar and P. Neta, Int. J. Appl. Radiat, Isot., 18, 494 (1967).

possible to study directly the kinetics of the reaction of  $e^{-}_{aq}$  with various species in the solution. The second-order rate constants for the reaction of  $e^{-}_{aq}$  with some representative species are given in Tables 9.1 and 9.2.

In alkaline solutions, hydrogen atoms are converted into hydrated electrons:

$$H + OH^- \rightarrow e^-_{aq} + H_2O$$

From the measured rate constants for this reaction  $(2.0 \times 10^7 \, M^{-1} \, \text{s}^{-1})$  and the reverse reaction  $(16 \, M^{-1} \, \text{s}^{-1})$  we can calculate the equilibrium constant

$$\frac{(e^{-}_{aq})}{(H)(OH^{-})} = K = \frac{k_f}{k_r} = \frac{2.0 \times 10^7}{16 \times 55.5} = 2.25 \times 10^4$$

Table 9.2 Rate constants of  $e^{-}_{aq}$  and H-atom reactions

Reduced species	k, M <sup>-1</sup> s <sup>-1</sup>		
	$e^{-}_{aq}$	H atom	
Ag+		THE PERSON NAMED IN	
Zn <sup>2+</sup>	$3.2 \times 10^{10}$	$1.1 \times 10^{10}$	
011	1 4 37 100	$<1.0 \times 10^{5}$	
O <sub>2</sub>	$5.2 \times 10^{10}$	$<1.0 \times 10^{5}$	
N <sub>2</sub> O		$1.9 \times 10^{10}$	
MnO <sub>4</sub> -	5.6 × 10°	~ 105	
Gd3+	$3.0 \times 10^{10}$	$2.6 \times 10^{10}$	
Eu <sup>3+</sup>			
CI-	$6.1 \times 10^{10}$		
C10-	< 105		
C <sub>6</sub> H <sub>6</sub>			
C <sub>6</sub> H <sub>10</sub>	$1.4 \times 10^{7}$	$1.1 \times 10^{9}$	
wat raday An Lin	<1.0 × 106	3 × 10°	

† E. J. Hart, Acc. Chem. Res., 2, 161 (1969); E. J. Hart and M. Anbar, "The Hydrated Electron," Wiley-Interscience, New York, 1970; M. Anbar and P. Neta, Int. J. Appl. Radiat. Isot., 18, 494 (1967).

By combining this with the ionization constant of water, we obtain  $K_a = 2.25 \times 10^{-10}$  for

$$H \rightleftharpoons H^+ + e^-_{aq}$$

Thus we have a measure of the acidity of the simplest possible aqueous acid!

The reactions of  $e^{-}_{aq}$  with H<sup>+</sup> and H<sub>2</sub>O to form atomic H are examples of a general reaction of  $e^{-}_{aq}$  with protonic acids:

$$e^-_{aq} + HX \rightarrow H + X^-$$

As one might expect, the rate constants for such reactions can be correlated with the acidities of the acids. Figure 9.3 shows a plot of  $\log k$  versus pK for various aqueous acids; it can be seen that these quantities are linearly related. Obviously the relatively low reactivity of  $e^{-}_{aq}$  with the water molecule (see Table 9.1) is related to the weak acidity of the water molecule.

In Table 9.2, rate constants for  $e^{-}_{aq}$  reactions can be compared with rate constants for the analogous atomic H reactions. Although atomic H is a powerful reducing agent,  $e^{-}_{aq}$  is stronger. This can be seen from the reduction potentials for these species.<sup>5</sup>

$$e^- + H^+ \rightarrow H \qquad E^\circ = -2.3 \text{ V}$$
 $e^- \rightarrow e^-_{\text{aq}} \qquad E^\circ = -2.8 \text{ V}$ 

<sup>4</sup> J. Rabani, Adv. Chem. Ser., 50, 242 (1965).

It should be remembered that in half-reactions of this type the symbol  $e^-$  stands for  $[\frac{1}{2}H_2 - H^+]$  and does not represent an electron of any type.




Figure 9.3 Plot of  $\log k$  for  $e^-_{aq}$  + HX reactions versus  $pK_a$  for HX. The k and  $pK_a$  values have been slightly corrected for statistical effects. The crosses refer to radiation data, the circles to photochemical data, and the square to a study of  $H_2O$  in ethylenediamine. (Reproduced with permission from J. Rabani, in "Solvated Electron," Advances in Chemistry Series, No. 50, p. 247, American Chemical Society, Washington, D.C., 1965.)

In general, the  $e^{-}_{aa}$  rate constants are greater than the corresponding atomic H rate constants, except in the case of reacting species which have no stable vacant orbitals to accept electrons. The  $e_{a0}^-$  reactions probably always involve the formation of intermediate species which correspond to the addition of a negative charge to the reacting species. High rate constants seem to be associated with the formation of stable intermediates, and relatively low rate constants with the formation of unstable intermediates. Thus the reaction with Zn<sup>2+</sup> is relatively slow because of the instability of Zn<sup>+</sup>, and Eu<sup>3+</sup> reacts much more rapidly than Gd<sup>3+</sup> because of the stability of Eu<sup>2+</sup> compared to Gd<sup>2+</sup>.

#### METAL-AMMONIA SOLUTIONS6

## Physical Characteristics

In contrast to water, which reacts rapidly with alkali metals to form hydrogen and the alkali-metal hydroxides, liquid ammonia reversibly dissolves the alkali metals and other electropositive metals to form metastable solutions containing ammoniated electrons. Metal-ammonia solutions have been extensively studied because of their unusual composition and because of their usefulness in inorganic and organic synthesis. We shall first discuss some of the physical characteristics of these solutions which give us insight to the microscopic structure of the solutions.

It is significant that the metals which are soluble in liquid ammonia are the electropositive metals with aqueous reduction potentials more negative than -2.5 V. Obviously, the factors which cause a metal to have a very negative reduction potential (high solvation energy for the ion, low ionization potential, and low sublimation energy) are the same as those which cause it to have a high solubility in ammonia. This observation is consistent with the concept that metal-ammonia solutions are electrolytic, i.e., that they contain ammoniated metal ions and electrons.

Dilute solutions of metals in ammonia are bright blue; the color is due to the short wavelength tail of a very broad and intense absorption band with a peak at approximately 1500 nm (1.5  $\mu$ m). This absorption spectrum is shown in Fig. 9.4. The fact that the spectra of the various metals are essentially identical proves that the that the absorption is due to a common species and strongly suggests that this species is the ammoniated electron. Further indication that the blue color is due to the to the ammoniated electron is found in the electrolytic behavior of metal-salt solutions. When a solution of a salt such as sodium bromide in liquid ammonia is electrolyzed with direct current using inert electrodes (e.g., platinum elec-

<sup>&</sup>lt;sup>6</sup>W. L. Jolly, Prog. Inorg. Chem., 1, 235 (1959); Solvated Electron, Adv. Chem. Ser., 50, 1-304 (65); J. L. L. Solvations, "Rutterworth, London, (1965); J. J. Lagowski and M. J. Sienko, eds., "Metal-Ammonia Solutions," Butterworth, London, 1970 (Supples 1970 (supplement to Pure and Applied Chemistry); W. L. Jolly, "Metal-Ammonia Solutions," Dowden, Hutchinson, and Ross, Stroudsburg, Pa., 1972.




Figure 9.4 Absorption spectrum of a dilute (10<sup>-4</sup> M) solution of a metal in liquid ammonia at -70°C.

trodes), a blue color appears in the region of the cathode. The electrode reaction may be written  $e^- \rightarrow e^-_{am}$ , where  $e^-_{am}$  stands for the ammoniated electron.

Metal-ammonia solutions are extremely good conductors of electricity; at all concentrations the equivalent conductances are greater than those found for any other known electrolyte in any known solvent. In Fig. 9.5 the equivalent conductances for Li, Na, and K are plotted against the negative logarithm of the molarity of the metal in the ammonia. In the very dilute region, the equivalent conductances approach a limiting value characteristic of the ions  $M^+_{am}$  and  $e^-_{am}$ . As the solutions are made more concentrated, the equivalent conductances decrease, as in the case of most electrolytic solutions, because of ionic association. However, at approximately 0.05 M the conductances reach a minimum




Figure 9.5 Equivalent conductances of metal-ammonia solutions at  $-33^{\circ}$ C versus the logarithm of dilution. (Reproduced with permission from D. M. Yost and H. Russell, Jr., "Systematic Inorganic Chemistry," Prentice-Hall, Englewood Cliffs, N.J., 1946.)

value. Further increase in concentration causes the conductances to increase rapidly until, in the saturated solutions, conductances comparable to those of metals are reached. These concentrated, highly conducting solutions are not blue, like the relatively dilute, electrolytic solutions, but rather bronze-colored. like a molten metal. Indeed, these metallike solutions have been likened to molten "expanded metals" in which ammoniated metal ions are held together by electrons. Further evidence for such a description is found in the fact that the metallike concentration regions correspond to NH<sub>3</sub>/metal ratios which are reasonable coordination numbers for the metal ions (e.g., in the case of Na, the metallike region ranges from NH<sub>3</sub>/Na  $\approx 5.5$  to NH<sub>3</sub>/Na  $\approx 10$ ).

The magnetic susceptibility of a very dilute metal-ammonia solution corresponds to that expected for a solution of ammoniated valence electrons with independent unpaired spins. In more concentrated solutions, the molar susceptibility decreases, as shown by the data in Table 9.3. Obviously spin pairing occurs

in the more concentrated solutions.

To explain the various physical phenomena, a model has been proposed for metal-ammonia solutions. It is believed that the ammoniated cations and ammoniated electrons are involved in aggregation equilibria of the following

$$M^{+}_{am} + e^{-}_{am} \rightleftharpoons (M^{+}_{am})(e^{-}_{am})$$
  
 $2M^{+}_{am} + 2e^{-}_{am} \rightleftharpoons (M^{+}_{am})_{2}(e^{-}_{am})_{2}$ 

The species  $(M_{am}^+)(e_{am}^-)$  and  $(M_{am}^+)_2(e_{am}^-)_2$  are obviously neutral and nonconductive species  $(M_{am}^+)(e_{am}^-)$ ducting; their formation accounts for the decrease in equivalent conductance with increasing concentration in the concentration region around  $10^{-2} M$ .  $(M_{am}^+)_2(e^-_{am})_2$  species is believed to be diamagnetic; its formation thus accounts for the decrease in magnetic susceptibility with increasing concentration in the same concentration region. In very concentrated solutions (> 1 M), there is not enough ammonia to adequately solvate the electrons; the solution may then be described as  $(M_{am}^+)e^-$ , i.e., as a molten expanded metal.

Table 9.3 Molar magnetic susceptibility of potassium solutions at -33°C†

M	
_	$\chi \times 10^6$
0.00341 0.00406	1268
0.00812	1240
0.0318	974
0.482	402
A TO STORING	29.9

<sup>†</sup> S. Freed and N. Sugarman, J. Chem. Phys., 11, 354 (1943).

#### Reactions

The ammoniacal electron is a very reactive species, widely used as a reagent in synthetic chemistry. We shall now briefly summarize the main types of reaction that the ammoniacal electron is known to undergo.

Many species react with metal-ammonia solutions simply by accepting electrons, without any bond breaking or extensive changes in geometry. Frequently the reactions serve as useful methods for the synthesis of reduced species. For example, manganate(VI), salts, hydronitrites, superoxides, and tetracyanonickelate(0) can be prepared as follows:

$$MnO_4^- + e^-_{am} \longrightarrow MnO_4^{2-}$$

$$NO_2^- + e^-_{am} \longrightarrow NO_2^{2-}$$

$$O_2 + e^-_{am} \longrightarrow O_2^-$$

$$Ni(CN)_4^{2-} + 2e^-_{am} \longrightarrow Ni(CN)_4^{4-}$$

A much larger class of metal-ammonia reactions is that in which the attacking electron causes a bond cleavage. For purposes of categorization, these reactions can be classified in terms of their overall stoichiometry, as shown in Fig. 9.6. The reaction paths of Fig. 9.6 are not necessarily indicative of the reaction mechanisms.

<sup>7</sup> J. Jander, "Anorganische und Allgemeine Chemie in Flüssigem Ammoniak," Interscience, New York, 1966; H. Smith, "Organic Reactions in Liquid Ammonia," Interscience, New York, 1963; W. L. Jolly, "Metal-Ammonia Solutions," Benchmark Papers in Inorganic Chemistry, Dowden, Hutchinson and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Stroudsburg, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, Pa., 1972; D. Nicholls, "Inorganic Chemistry in Liquid Ammonia" pp. 172, 205, Planton and Ross, nia," pp. 172-205, Elsevier, Amsterdam, 1979. or the decrease in magnetic susceptibility




Figure 9.6 General reactions of the ammoniacal electron involving bond cleavage. The most important general reactions are, III, and IV.

Addition of one electron usually goes according to general reaction I, in which one fragment of the bond cleavage effectively dimerizes:

$$NH_{3} + e^{-}_{am} \rightarrow \frac{1}{2}H_{2} + NH_{2}^{-}$$

$$NH_{4}^{+} + e^{-}_{am} \rightarrow \frac{1}{2}H_{2} + NH_{3}$$

$$GeH_{4} + e^{-}_{am} \rightarrow \frac{1}{2}H_{2} + GeH_{3}^{-}$$

$$C_{6}H_{5}I + e^{-}_{am} \rightarrow \frac{1}{2}C_{6}H_{5} - C_{6}H_{5} + I^{-}$$

The reaction of the electron with ammonia is extremely slow in clean, cold metal-ammonia solutions; indeed, if it were not so, metal-ammonia solutions would not be as valuable as they are. However, the reaction can be catalyzed by certain high-surface-area transition-metal compounds (e.g., iron rust and platinum black), and then the reaction serves as a useful synthesis of alkali-metal amides. The reaction of the electron with the ammonium ion is extremely fast and serves as a convenient way to destroy excess metal after completing a reduction with a metal-ammonia solution.

An example of general reaction II is found in the reaction of iodobenzene with excess ammoniated electrons:

$$2C_6H_5I + 3e^-_{am} \rightarrow C_6H_5 - C_6H_5 \cdot - + 2I^-$$

The  $C_6H_5$ — $C_6H_5$  ion is a typical aromatic radical anion; such species are highly colored and are readily formed by the reaction of polycyclic aromatic hydrocarbons with alkali metals. The odd electron occupies a highly delocalized  $\pi$  orbital of the hydrocarbon.

General reaction III, involving the formation of two anions, generally occurs when two electrons are added to a molecule:

$$Mn_2(CO)_{10} + 2e^-_{am} \longrightarrow 2Mn(CO)_5^ C_6H_5NHNH_2 + 2e^-_{am} \longrightarrow C_6H_5NH^- + NH_2^ R_3Ge-GeR_3 + 2e^-_{am} \longrightarrow 2GeR_3^-$$

Frequently one of the anions formed in a two-electron addition undergoes ammonolysis, corresponding to general reaction IV:

$$N_2O + 2e^-_{am} + NH_3 \longrightarrow N_2 + OH^- + NH_2^ NEt_4^+ + 2e^-_{am} + NH_3 \longrightarrow NEt_3 + C_2H_6 + NH_2^ RBr + 2e^-_{am} + NH_3 \longrightarrow Br^- + RH + NH_2^-$$

It happens that the amide ion formed in each of the latter three reactions reacts with the starting material to give the following side reactions:

$$N_2O + 2NH_2^- \rightarrow N_3^- + OH^- + NH_3$$

$$NEt_4^+ + NH_2^- \rightarrow NEt_3 + C_2H_4 + NH_3$$

$$RBr + NH_2^- \rightarrow RNH_2 + Br^-$$

General reaction V occurs in the reaction of aryl halides with the ammoniacal electron:

$$ArX + 3e^{-}_{am} + NH_3 \longrightarrow ArH \cdot - + X^- + NH_2^-$$

#### **Kinetics**

The kinetics of some of the reactions of metal-ammonia solutions have been studied, and in some cases the mechanisms of the reactions have been established.<sup>8,9</sup> One type of reaction which has been fairly thoroughly studied is the reaction of a weak protonic acid with the ammoniacal electron,

$$HA + e^-_{am} \longrightarrow \frac{1}{2}H_2 + A^-$$

In cases where the weak acid cannot initially react to form a radical anion (e.g., when HA = water, ethanol, and urea), the following mechanism appears to hold<sup>8,9</sup>:

$$HA + NH_3 \stackrel{1}{\rightleftharpoons} NH_4^+ + A^ NH_4^+ + e^-_{am} \stackrel{3}{\longrightarrow} \frac{1}{2}H_2 + NH_3$$
(9.5)

These reactions start out fairly rapidly with a simple first-order dependence on the weak acid and a zero-order dependence on sodium. As the reactions proceed, the rates drop markedly and become first-order in both the acid and sodium. The rates can be expressed quantitatively by the following rate law (derived from the above mechanism, assuming a steady state in NH<sub>4</sub>+):

$$-\frac{d(e^{-}_{am})}{dt} = \frac{k_1(HA)(e^{-}_{am})}{(k_2/k_3)(A^{-}) + (e^{-}_{am})}$$

## ALKALI-METAL ANIONS10

Alkali metals also dissolve (to form relatively unstable solutions) in certain ethers, low-molecular-weight amines, and hexamethyl phosphoryl triamide. These solutions have properties which indicate that they contain species distinctly different from those found in metal-ammonia solutions. For example, they have optical spectra with two types of absorption bands. One of these (an infrared band) is metal-independent and is assigned to the solvated electron. The other band (V band) has a peak position which depends on the metal and is assigned to the metal anion species, M<sup>-</sup>. Spectra for solutions of Cs, K, and Na in tetrahydrofuran are shown in Fig. 9.7. The ratio of the intensity of the V band to that of the infrared band depends on both solvent and metal. The less polar the solvent,

8 W. L. Jolly, in "Metal-Ammonia Solutions," J. J. Lagowski and M. J. Sienko, eds., pp. 167-181, Butterworth, London, 1970 (supplement to *Pure and Applied Chemistry*); Adv. Chem., 50, 27 (1965).

<sup>&</sup>lt;sup>9</sup> R. R. Dewald, *J. Phys. Chem.*, **79**, 3044 (1975); R. R. Dewald, R. L. Jones, and H. Boll, in "Electrons in Fluids," J. Jortner and N. R. Kestner, eds., pp. 473–478, Springer-Verlag, New York.

<sup>10</sup> J. L. Dye, J. Chem. Educ., 54, 332 (1977).




Figure 9.7 Spectra at 25°C of e-solv, Cs-, K-, and Na- in tetrahydrofuran. [Reproduced with permission from Dye, J. Chem. Educ., 54, 332 (1977).]

or the lower the atomic weight of the metal, the larger the ratio of the V-band intensity to the infrared band intensity. Evidence for the existence of alkali-metal anions is found in the following results.

1. Solutions with high V-band - infrared-band intensity ratios are diamagnetic, as expected for a spin-paired ground state for M-.

2. The solvent, metal, and temperature dependence of the V band is similar to that of the charge-transfer-to-solvent band of I- and similar to that expected for M-

3. When solutions containing Na<sup>+</sup> ions are subjected to an electron pulse from a linear accelerator, the rate of formation of the V band is second-order in  $e^-_{solv}$ ,

as expected for the formation of Na-.

4. The molar conductivity of sodium solutions decreases slowly with increasing concentration, as expected for a solute which forms ion pairs Na+Na- with a very large anion.

5. Although sodium is insoluble in 1,2-dimethoxyethane, sodium-potassium alloy dissolves to give equimolar Na and K, presumably as K<sup>+</sup> and Na<sup>-</sup>.

Alkali-metal cations form very stable complexes with complexing agents called "crown ethers" and "cryptands" that have structures such as the following:

The addition of a crown ether or cryptand (abbreviated C) to ethylamine, tetrahydrofuran, or a polyether greatly increases the solubility of alkali metals by shifting the following equilibrium to the right:

$$2M(s) \rightleftharpoons M^+ + M^-$$

The net reaction for the dissolution then becomes

$$2M(s) + C \implies MC^+ + M^-$$

Actual crystals of the "salt" [NaC+]Na- have been prepared by cooling an ethylamine solution of sodium and a cryptand. The crystal structure consists of alternate layers of NaC+ and Na- in a hexagonally packed arrangement. Obviously the -1 oxidation state of alkali metals is well established, and the M- species may have utility in synthetic chemistry as two-electron reducing agents.

# PROBLEMS

9.1 Hydrated electrons can be generated by ultraviolet irradiation of the aqueous I-ion:

$$1^- \xrightarrow{hv} 1 + e^-_{aq}$$
 and had by the first part of visits.

What is the overall net reaction for the ultraviolet irradiation of an aqueous HI solution?

- \*9.2 Which species would you expect to be more reactive toward  $e_{aq}^-$  (a)  $ClO_4^-$  or  $ClO^-$ ? (b)  $Cu^{2+}$  of  $Ni^{2+}$ ? (c)  $Fe(CN)_6^{4-}$  or  $Fe(CN)_6^{3-}$ ?
- 9.3 If a sodium-ammonia solution were electrolyzed by using direct current and inert electrodes, what would be the electrode reactions?
- \*9.4 A solvated electron in  $H_2O$  or  $NH_3$  is believed to occupy a cavity in the solvent, in which the protons of adjacent solvent molecules are oriented toward the electron in the cavity. Thus a solvated electron is situated in a potential well created by the polarization of solvent molecules. The information given in this chapter, what can you say about the relative sizes of the electron cavities in  $H_2O$  and  $NH_3$ ?
- 9.5 Write equations for the net reactions which occur when the following materials are added to a sodium-ammonia solution: (a) methylgermane; (b) iodine; (c) diethyl sulfide.
- \*9.6 In the reaction of a weak acid with a metal-ammonia solution (see mechanism 9.5), it is conceivable that atomic hydrogen is formed, which then either dimerizes  $(2H \rightarrow H_2)$  or reacts by the following sequence of rapid reactions:

$$H + e^-_{am} \rightarrow H^-$$
  
 $H^- + NH_3 \rightarrow H_2 + NH_2^-$   
 $NH_2^- + HA \rightarrow NH_2 + A^-$ 

In principle, could these two possibilities be distinguished kinetically?

9.7 Can you rationalize the shift in peak wavelength with a change in alkali metal in the absorption spectra of the M<sup>-</sup> species (Fig. 9.7)?

## BORON HYDRIDES AND THEIR DERIVATIVES

The boren hydrides and some of their physical

For many years the formulas and structures of the boron hydrides defied rationalization by conventional concepts of bonding. These compounds are beautiful examples of nonclassical, multicenter bonding, and the fact that they can be readily explained by simple molecular orbital (MO) theory is another proof of the power of that theory. The formulas and structures of the higher, polyhedral boron hydrides have been shown to conform to a simple rule based on the number of cluster electrons. This rule also has a molecular orbital basis and is widely applicable to all kinds of "cluster" compounds, including various polyanions and transition-metal cluster compounds (to be discussed in Chap. 16).

# SYNTHESES THE STATE OF THE STAT

Boron hydrides, or boranes, were first isolated and characterized by Alfred Stock and his coworkers in Germany. In the period from 1912 to 1930 they used vacuum-line techniques (most of which they devised themselves) to prepare  $B_2H_6$ ,  $B_4H_{10}$ ,  $B_5H_9$ ,  $B_5H_{11}$ ,  $B_6H_{10}$ ,  $B_{10}H_{14}$ , and many derivatives of these compounds. Further progress in the field was rather slow until, during World War II, Schlesinger's group at the University of Chicago developed easy methods for preparing NaBH<sub>4</sub> (sodium tetrahydroborate, usually called sodium borohydride), which is useful for the preparation of  $B_2H_6$  (diborane). Physical properties of some of the many boron hydrides which are now known are listed in Table 10.1.

A. Stock, "Hydrides of Boron and Silicon," Cornell University Press, Ithaca, N.Y., 1933.

H. I. Schlesinger and H. C. Brown, J. Am. Chem. Soc., 75, 219 (1953). Also see H. C. Brown, Science, 210, 485 (1980).

Table 10.1 The boron hydrides and some of their physical properties

NEU	Melting point, °C	Boiling point,	$\Delta H_f^\circ$ (at 25°C for gases) kcal mol <sup>-1</sup>
B <sub>2</sub> H <sub>6</sub>	-164.86	-92.84	7.5
$B_4H_{10}$	-120.8	16.1	CTY13.8 MOROS
B <sub>5</sub> H <sub>9</sub>	-46.75	58.4	15.0
B <sub>5</sub> H <sub>11</sub>	-123.2	65	22.2
B <sub>6</sub> H <sub>10</sub>	-63.2	108	19.6
B <sub>6</sub> H <sub>12</sub>	-83	90 00	
B <sub>8</sub> H <sub>12</sub>	~-20		
B <sub>8</sub> H <sub>18</sub>			
B <sub>9</sub> H <sub>15</sub>	2.6	0.8 mm at 28°C	
B <sub>10</sub> H <sub>14</sub>	99.5		ed 19 20 and the M
B <sub>10</sub> H <sub>16</sub>			2.0
B <sub>18</sub> H <sub>22</sub>	178.5		
iso-B <sub>18</sub> H <sub>22</sub>	1,0.5		
B <sub>20</sub> H <sub>16</sub>	199		

# The Synthesis of Boron Hydrides<sup>3,4</sup>

Diborane can be prepared by the reaction of a boron trihalide with a strong hydriding agent such as sodium tetrahydroborate or lithium aluminum hydridein an aprotic solvent. This synthesis is usually carried out with BF<sub>3</sub> and NaBH<sub>4</sub>in diglyme (the dimethyl ether of diethylene glycol):

$$3NaBH_4 + BF_3 \rightarrow 2B_2H_6 + 3NaF$$

A convenient laboratory synthesis involves the careful addition of NaBH<sub>4</sub> to concentrated H2SO4 or H3PO4:

$$2\text{NaBH}_4 + 2\text{H}_2\text{SO}_4 \rightarrow 2\text{Na}^+ + 2\text{HSO}_4^- + \text{B}_2\text{H}_6 + 2\text{H}_2$$

A synthetic method of potential industrial significance is the reduction of bond oxide with aluminum and hydrogen at high pressure in the presence of aluminum chloride catalyst:

$$B_2O_3 + 2Al + 3H_2 \xrightarrow{Al_5Cl_6} B_2H_6 + Al_2O_3$$

Several of the higher boron hydrides, B<sub>4</sub>H<sub>10</sub>, B<sub>5</sub>H<sub>9</sub>, B<sub>5</sub>H<sub>11</sub>, B<sub>6</sub>H<sub>10</sub>, and B<sub>10</sub>H<sub>14</sub>, can be prepared by the thermal decomposition of diborane. It is believed that the initial stages of the thermal decomposition involve the formation at low concentrations of high-energy intermediates such as BH<sub>3</sub>, B<sub>3</sub>H<sub>9</sub>, and B<sub>3</sub>H<sub>7</sub>. For example, the following mechanism has been as BH<sub>3</sub>, B<sub>3</sub>H<sub>9</sub>, and B<sub>3</sub>H<sub>7</sub>. ple, the following mechanism has been proposed for the formation of tetraborane:

<sup>4</sup> R. W. Parry and M. K. Walter, Prep. Inorg. React., 5, 45 (1968).

<sup>&</sup>lt;sup>3</sup> E. L. Muetterties, ed., "The Chemistry of Boron and Its Compounds," Wiley, New York, 1967;
"Muetterties and W. H. Knoth, "Polyhed at D. E. L. Muetterties and W. H. Knoth, "Polyhedral Boranes," Dekker, New York, 1968.




Figure 10.1 Structures of some boron hydrides and borane anions. Boron atoms are represented by the shaded balls; hydrogen atoms by the smaller, unshaded balls.

$$\begin{array}{rcl} B_{2}H_{6} & \rightleftharpoons & 2BH_{3} \\ B_{2}H_{6} + BH_{3} & \rightleftharpoons & B_{3}H_{9} \\ B_{3}H_{9} & \rightleftharpoons & B_{3}H_{7} + H_{2} \\ B_{3}H_{7} + B_{2}H_{6} & \rightarrow & B_{4}H_{10} + BH_{3} \end{array}$$

The same higher hydrides, as well as  $B_8H_{12}$ ,  $B_9H_{15}$ , and  $B_{10}H_{16}$ , can be prepared by the appropriate treatment of lower hydrides with an electric discharge. For other preparative procedures, the review by Parry and Walter<sup>5</sup> should be consulted. The structures of several boron hydrides are illustrated in Fig. 10.1.

# The Synthesis of Borane Anions

In Chap. 6 we briefly discussed the synthesis of the tetrahydroborate ion,  $BH_4^-$ , and the octahydrotriborate ion,  $B_3H_8^-$ . A large number of higher borane anions are known; these have been prepared mainly by two general methods. The first method, the "BH condensation method," consists of the effective addition of BH groups to borane anions by treatment with diborane or other sources of BH

groups. The general mechanism is believed to involve a sequence of steps in which  $BH_3$  groups are added and  $H_2$  molecules are lost. This sort of process is undoubtedly involved in the synthesis of  $B_3H_8^-$  from  $BH_4^-$  and diborane:

$$BH_4^- + [BH_3] \implies B_2H_7^-$$
  
 $B_2H_7^- + [BH_3] \rightarrow B_3H_8^- + H_2$ 

Similar mechanisms have been postulated for the synthesis of the anions  $B_n H_n^{2-}$ , where n ranges from 6 to 12. The second method for preparing higher borane anions, specifically the  $B_n H_n^{2-}$  ions, is the pyrolysis of salts of lower borane anions. The particular product obtained is highly dependent on the temperature, the cation, and the solvent (if any). Some useful conversions are indicated in the following:

$$\begin{array}{cccc} (CH_3)_4NB_3H_8 & \xrightarrow{\Delta} & (CH_3)_3NBH_3 + [(CH_3)_4N]_2B_{10}H_{10} + [(CH_3)_4N]_2B_{12}H_{12} \\ \\ CsB_3H_8 & \xrightarrow{\Delta} & Cs_2B_9H_9 + Cs_2B_{10}H_{10} + Cs_2B_{12}H_{12} \\ \\ CsB_3H_8 & \xrightarrow{traces\ of\ ether} & Cs_2B_{12}H_{12} \\ \end{array}$$

$$(C_2H_5)_4NBH_4 \xrightarrow{\Delta} [(C_2H_5)_4N]_2B_{10}H_{10}$$

All the  $B_n H_n^{2-}$  anions have boron frameworks corresponding to highly symmetric polyhedra. The octahedral and icosahedral structures of B<sub>6</sub>H<sub>6</sub><sup>2-</sup> and  $B_{12}H_{12}^{2-}$ , respectively, are shown in Fig. 10.1. It should be noted that the boron atom frameworks of the neutral boranes in Fig. 10.1 are essentially polyhedral fragments. Indeed, the larger boranes and their derivatives are usually classified in terms of their structural relationships to polyhedra. A "closo" borane (e.g., B<sub>6</sub>H<sub>6</sub><sup>2-</sup> or B<sub>12</sub>H<sub>12</sub><sup>2-</sup>) has framework atoms at the vertices of a polyhedron which has all equilateral, or nearly equilateral, triangular faces (i.e., a deltahedron). A "nido" borane is formally derivable from a closo borane by the removal of one framework BH group and the addition of two protons and two hydrogen atoms to the resulting open face. Both B<sub>5</sub>H<sub>9</sub> (formally derivable from B<sub>6</sub>H<sub>6</sub><sup>2-</sup>) and B<sub>10</sub>H<sub>14</sub> (formally derivable from B<sub>11</sub>H<sub>11</sub><sup>2-</sup>) are nido boranes. An "arachno" borane is formally derivable from a closo compound by the removal of two framework atoms. Thus B<sub>4</sub>H<sub>10</sub> (formally derivable from B<sub>6</sub>H<sub>6</sub><sup>2-</sup>) is an arachno borane. relatively rare "hypho" boranes are formally derivable from closo compounds by the removal of three framework atoms and have even more opened-out structures than the arachno boranes. The anion  $B_5H_{12}^-$  (related to  $B_8H_8^{2-}$ ) is an example of a hypho borane.7

<sup>&</sup>lt;sup>6</sup> R. W. Rudolph, Acc. Chem. Res., 9, 446 (1976).

<sup>&</sup>lt;sup>7</sup> R. J. Remmel, H. D. Johnson, I. S. Jaworiwsky, and S. G. Shore, *J. Am. Chem. Soc.*, 97, 5395 (1975).

## The Synthesis of Carboranes

A boron-hydrogen compound in which carbon atoms occupy structural sites similar to those occupied by boron atoms is called a "carborane." The most important carborane synthesis is that of 1,2-B<sub>10</sub>C<sub>2</sub>H<sub>12</sub>, which is isoelectronic with the  $B_1H_1^2$  ion. The reactions involved in the synthesis follow:

$$B_{10}H_{14} + 2Et_{2}S \xrightarrow{n-Pr_{2}O} B_{10}H_{12}(Et_{2}S)_{2} + H_{2}$$

$$B_{10}H_{12}(Et_{2}S)_{2} + C_{2}H_{2} \xrightarrow{n-Pr_{2}O} B_{10}C_{2}H_{12} + H_{2} + 2Et_{2}S$$

The second step involves the insertion of the two carbon atoms of acetylene into the B<sub>10</sub>H<sub>12</sub> framework, yielding the icosahedral 1,2-B<sub>10</sub>C<sub>2</sub>H<sub>12</sub> framework, with the carbon atoms occupying adjacent positions on the icosahedron. When this compound is heated, rearrangement occurs to the 1,7 and 1,12 isomers, in which the carbon atoms occupy positions separated by one and two boron atoms, respectively.

## STRUCTURE AND BONDING8,9

Three-Center Bonding The boron hydrides, borane anions, and carboranes have extraordinary structures. Some of these structures are shown in Fig. 10.1. It should be noted that the framework atoms of the larger molecules form the vertices of either a regular polyhedron or a polyhedral fragment. Compounds of this type have fascinated chemists not only because of their unusual structures and reactions but also because simple valence bond theory cannot account for their bonding. It is easy to understand why BH<sub>3</sub> is a reactive species; there are only six valence electrons in the compound, and it is impossible for the boron atom to achieve a complete valence octet. However, even the stable dimer, diborane, lacks enough electrons to permit conventional bonding as in ethane. The key to the bonding of diborane is found in the fact that two of the hydrogen atoms form bridges between the two boron atoms. These B—H—B bridges in diborane are examples of "threecenter bonds," in which a bonding pair of electrons holds together three atoms. In our previous discussions of valence bond theory, we have considered only two-center bonds," in which bonding electrons hold together two atoms. By including the three-center bond concept in valence bond theory, we can write Octet-satisfying structures for the boron hydrides and their derivatives. The

B-H-B bridge is usually represented by the structure B

<sup>8</sup> See footnote 3.

W. N. Lipscomb, "Boron Hydrides," Benjamin, New York, 1963.

other type of three-center bond which is encountered in boron hydrides is the

B—B—B bond, usually represented by the structure B

B. In carboranes one must consider analogous B—B—C or B—C—C bonds.

Three-center bonding is easily accommodated by simple MO theory. In fact, in Chap. 4 we have already considered the MOs in linear and triangular  $H_2$ , which are analogous to the MOs in the "open" B-H-B bond and the "closed" B-B-B bond. When two of the three atoms (the "end" atoms) do not interact (that is,  $\beta_{13}=0$ ), the energy levels are, in order of increasing energy,  $\alpha+\sqrt{2}\beta$ ,  $\alpha-\sqrt{2}\beta$ . When all three atoms interact equally with one another, the energy levels are  $\alpha+2\beta$ ,  $\alpha-\beta$ . Because there must be a continuous change in the MO energy levels as the interaction between the end atoms ( $\beta_{13}$ ) increases from zero to  $\beta_{12}$ , we can draw a correlation diagram, as shown in Fig. 10.2. It can be seen that, whether the bonding is closed and completely symmetric (as in the B-B-B bonding of  $B_{12}H_{12}^{2-}$ ) or somewhere between open and closed (as in the B-H-B bonding of  $B_{2}H_{6}$ ), the lowest MO, which accepts the two valence electrons, has definite bonding character.

To describe the bonding of a boron compound satisfactorily, the following criteria must be fulfilled:

- The total number of valence electrons must equal twice the number of bonds, including both two- and three-center bonds.
- 2. Each boron atom must use four orbitals and must achieve a complete octet of valence electrons.
- 3. The bonding must be consistent with the observed structure of the molecule and with an approximately tetrahedral disposition of bonds to each boron

<sup>10</sup> See Prob. 4.2 and its answer in the back of the book.




Figure 10.2 Energy levels for the three center bond as a function of  $\beta_{13}/\beta_{13}$ , where  $\beta_{12} = \beta_{23}$ . The "open" bond prevails at  $\beta_{13}/\beta_{12} = 0$ , and the symmetric "closed" bond at  $\beta_{13}/\beta_{12} = 1$ .

It is useful to express the first two of these rules in the form of topological equations. For the case of a species of formula  $B_bH_h^q$ , where q is the net charge, let  $\alpha$  represent the number of two-center bonds and  $\beta$  the number of three-center bonds. Rule 1 corresponds to

$$\alpha + \beta = \frac{1}{2}(3b + h - q)$$

Rule 2 corresponds to equating the total number of two- and three-center connections to the number of atomic orbitals, or

$$2\alpha + 3\beta = 4b + h$$

Solving for  $\alpha$  and  $\beta$ , we obtain

$$\alpha = \frac{1}{2}(b + h - 3q) \tag{10.1}$$

$$\beta = b + q \tag{10.2}$$

If the numbers of two- and three-center bonds in the proposed bonding for a species  $B_b H_h^q$  correspond to Eqs. 10.1 and 10.2, we can be sure that rules 1 and 2 are satisfied.<sup>11</sup> We shall presently describe, for several boranes, bonding assignments which are consistent with rules 1 to 3. A shorthand scheme for describing borane bonding, devised by Lipscomb, amounts to listing four numbers (s, t, y, and x), defined as follows.<sup>12</sup>

s = the number of B - H - B bonds

t = the number of B—B—B bonds


y = the number of B—B bonds

x = the number of BH<sub>2</sub> groups plus twice the number of BH<sub>3</sub> groups

Hereafter we shall give the appropriate *styx* numbers when discussing the bonding in particular boranes.

First let us consider the tetrahydroborate ion,  $BH_4^-$ . The bonding in this simple species can be described by using classical valence bond theory because, according to Eq. 10.2,  $\beta = 1 - 1 = 0$ . Clearly rule 3 is satisfied because the species is tetrahedral and the boron uses four  $sp^3$  hybrid orbitals.

Next we shall consider diborane,  $B_2H_6$ . From Eqs. 10.1 and 10.2 we obtain  $\alpha = 4$  and  $\beta = 2$ , consistent with the bonding




<sup>&</sup>quot;Lipscomb (op. cit., chap. 2) has devised a similar, but more complicated set of topological


<sup>&</sup>lt;sup>12</sup> If we assume that each boron atom in a species  $B_bH_{h}^{\sigma}$  is bonded to at least one terminal hydrogen atom (by a B-H bond), then it can be easily shown that the *styx* parameters are related to  $\alpha$ ,  $\beta$ , and b as follows:  $\alpha - b = x + v$ :  $\beta = s + t$ .

This bonding topology, corresponding to the *styx* numbers 2002, requires that the bridging hydrogens lie in a plane perpendicular to the plane of the other atoms, as shown in Fig. 10.1.

Now let us consider tetraborane,  $B_4H_{10}$ , for which we calculate  $\alpha = 7$  and  $\beta = 4$ . The 4012 bonding shown below is consistent with these parameters and fits the observed structure of the molecule.




In the case of pentaborane-9,  $B_5H_9$ ,  $\alpha = 7$  and  $\beta = 5$ . The 4120 bonding assignment, which follows, is consistent with these parameters and with the structure shown in Fig. 10.1:



This molecule has the shape of a square pyramid. Inasmuch as the four basal boron atoms are actually equivalent, the bonding must be described as a resonance hybrid of the four bonding structures corresponding to permutation of the two B—B bonds and the B—B—B bond. Pentaborane-9 is the simplest boron hydride which uses all the possible types of two- and three-center bonds.

Finally we shall discuss the bonding in the closo octahedral anion  $B_6H_6^{2-in}$  terms of two- and three-center bonds. For this species, we calculate  $\alpha = 9$  and  $\beta = 4$ . From Fig. 10.1 we see that each boron atom is bonded to a terminal hydrogen atom by a two-center B—H bond; hence the octahedral  $B_6$  framework must be held together by three two-center bonds and four three-center bonds. One of many possible permutations of this 0430 bonding, consistent with approximations.

imately tetrahedral bonding to the boron atoms, is shown in the following structure:



Obviously there are many resonance structures which one can write for this ion. One of the intriguing aspects of the polyhedral  $B_n H_n^{2-}$  ions is the fact that they all have a -2 charge. Neutral B<sub>n</sub>H<sub>n</sub> molecules would be consistent with valence bond theory: Each molecule would have n B—H bonds and n B—B—B bonds (that is,  $\alpha = \beta = n$ ). The nonexistence of neutral molecules can be rationalized by the fact that the number of resonance structures that can be written for a  $B_nH_n^{2-}$  ion is always greater than that for the corresponding  $B_nH_n$  neutral mole-Cule. 13 Positive  $B_nH_n$  ions are unacceptable because they would not have enough valence electrons. Equations 10.1 and 10.2 yield the impossible result for q > 0that the number of two-center bonds would be less than the number of B—H bonds and that the number of three-center bonds would be greater than the number of boron atoms. Finally if we rule out charges more negative than -2(-4, -6, etc.) because of the destabilization caused by charge repulsion, we complete a rationalization of the charge on the  $B_nH_n^{2-}$  ions. <sup>14,15</sup> To obtain a more rigorous explanation of the stability of the -2 charge of these species and to avoid the awkwardness of writing many resonance structures to explain the bonding in these species, we must go to simple MO theory.

# MO Theory of Clusters16

Let us assume that we have n cluster atoms at the vertices of a regular deltahedron. dron. The four valence orbitals on each vertex atom may be divided into one external sp hybrid orbital, two equivalent tangential p orbitals, and one internal radial sp hybrid orbital, two equivalent tangential p orbitals,  $\sigma$  bond to an external orbital. The external orbital is used to form a  $\sigma$  bond to an external orbital are external hydrogen atom or group. The tangential orbitals and internal orbital are

20, 563 (1981); A. J. Stone and M. J. Alderton, *Inorg. Chem.*, 21, 2297 (1982).

<sup>&</sup>lt;sup>13</sup> I. R. Epstein and W. N. Lipscomb, *Inorg. Chem.*, **10**, 1921 (1971), app. II.

By simple valence bond considerations, it can be shown that q must equal -2 for the unknown  $g_{0nal}$  by  $g_$ trigonal bipyramidal B<sub>3</sub>H<sub>3</sub><sup>9</sup>. See Prob. 10.6. <sup>16</sup> R. B. King and D. H. Rouvray, *J. Am. Chem. Soc.*, **99**, 7834 (1977); A. J. Stone, *Inorg. Chem.*, 563 (100).




Figure 10.3 The orbitals used by a polyhedral vertex atom in cluster bonding.

used to bond the cluster atoms together. This orbital arrangement is shown in Fig. 10.3.

Pairwise interaction of the 2n tangential orbitals in the "surface" bonding of the polyhedron leads to n bonding and n antibonding orbitals. The n internal p hybrid orbitals overlap at the center of the polyhedron to generate one strongly bonding orbital and n-1 nonbonding or antibonding orbitals. Thus the cluster contains n+1 bonding orbitals. Upon filling these bonding orbitals with electrons, we obtain a total of 2n+2 cluster electrons. Thus we have rationalized the so-called 2n+2 rule of polyhedral clusters. Clearly any  $B_nH_n^q$  species conforms to the rule if q=-2; the boron atoms contribute 2n electrons to the cluster, and the -2 charge accounts for the other two electrons.

It is not necessary that the n vertex atoms be boron atoms, or that they be identical. Thus the closo carboranes  $C_2B_{n-2}H_n$  (n=5 to 12), which are isoelectronic and isostructural with the  $B_nH_n^{2-}$  ions, also follow the 2n+2 rule. Nido arachno molecules, such as  $B_5H_9$ ,  $B_6H_{10}$ , and  $B_3C_3H_7$ , have 2n+4 framework electrons; electrons; and hypho molecules, such as  $B_5H_{11}$ , and  $B_7C_2H_{13}$ , have 2n+6 framework framework electrons. (In all cases n is the number of framework atoms.) It is framework electrons as the closo compounds to which they are structurally usually does not change the number of framework electrons; the resulting polyhecloso polyhedron).

Exceptions to the 2n + 2 rule are found in boron halide clusters. Although polyhedral ions of the type  $B_nCl_n^{2-}$  and  $B_nBr_n^{2-}$ , which follow the 2n + 2 rule, are well established, various neutral 2n clusters such as  $B_9Cl_9$  and  $B_nBr_n$  (n = 7 to 10), and even a few examples of 2n + 1 radical anions of the type  $B_9X_9^-$  have been

<sup>&</sup>lt;sup>17</sup> K. Wade, *Chem. Commun.*, 792 (1971); R. E. Williams, *Inorg. Chem.*, **10**, 210 (1971); R. W. Rudolph and W. R. Pretzer, *Inorg. Chem.*, **11**, 1974 (1972); R. W. Rudolph, *Acc. Chem. Res.*, **9**, 446 (1976).

<sup>&</sup>lt;sup>18</sup> E. H. Wong and R. M. Kabbani, *Inorg. Chem.*, **19**, 451 (1980); N. A. Kutz and J. A. Morrison, *Inorg. Chem.*, **19**, 3295 (1980).

prepared and characterized. As far as has been determined, these species all have closo polyhedral structures. The stability of these highly electron-deficient species has been rationalized by assuming halogen  $\pi$  donation to the cluster MOs. 19

#### METALLOCARBORANES AND METALLOBORANES<sup>20,21</sup>

Treatment of 1,2-B<sub>10</sub>C<sub>2</sub>H<sub>12</sub> with ethoxide ion in ethanol at 70°C causes a degradation corresponding to the deletion of a B+ ion from the molecule:

$$B_{10}C_2H_{12} + OC_2H_5^- + 2C_2H_5OH \rightarrow B_9C_2H_{12}^- + B(OC_2H_5)_3 + H_2$$

The B<sub>9</sub>C<sub>2</sub>H<sub>12</sub> ion can be deprotonated by a strong base to give the "open" B<sub>9</sub>C<sub>2</sub>H<sub>11</sub><sup>2-</sup> ion pictured in Fig. 10.4. The latter ion can react with various transition-metal ions or organo transition-metal ions to form complexes in which the metal atom completes the icosahedron. For example,

$$4B_9C_2H_{11}^{2-} + 3Co^{2+} \rightarrow Co + 2Co(B_9C_2H_{11})_2^{-}$$

The structure of the  $Co(B_9C_2H_{11})_2^-$  ion is shown in Fig. 10.5. Each atom in each of the two icosahedra contributes three orbitals to the icosahedral framework bonding. Each icosahedron receives 2 electrons from the Co- group, 22 18 electrons from nine BH groups, and 6 electrons from two CH groups. Thus 26 electrons are available per icosahedron, in agreement with the 2n + 2 rule.

Reaction of B<sub>5</sub>H<sub>9</sub> with Fe(CO)<sub>5</sub> at 220°C gives 10 to 20 percent yields of B<sub>4</sub>H<sub>8</sub>Fe(CO)<sub>3</sub>, which has a B<sub>5</sub>H<sub>9</sub> structure in which the apex BH group has been replaced by an Fe(CO)<sub>3</sub> group, as shown in Fig. 10.6a.<sup>23</sup> Reaction of a mixture of  $B_5H_9$  and  $Fe(CO)_5$  with LiAlH<sub>4</sub> gives  $\sim 1$  percent yields of  $B_3H_7Fe_2(CO)_6$  which,

N. N. Greenwood, C. G. Savory, R. N. Grimes, L. G. Sneddon, A. Davison, and S. S. Wreford, J. Chem. Soc. Chem. Commun., 718 (1974).





Figure 10.4 Skeletal structure of the B<sub>9</sub>C<sub>2</sub>H<sub>11</sub><sup>2-</sup> ion. (Reproduced with permission from E. L. Muetterties and W. H. Knoth, "Polyhedral Boranes," Dekker, New York, 1968.)

<sup>&</sup>lt;sup>19</sup> For an MO discussion, see M. E. O'Neill and K. Wade, *Inorg. Chem.*, 21, 461 (1982).

<sup>20</sup> See footnote 3.

<sup>&</sup>lt;sup>21</sup> M. F. Hawthorne and G. B. Dunks, *Science*, **178**, 462 (1972).

Transition-metal atoms in such cluster compounds acquire valence shells containing 18 electrons, corresponding to rare-gas configurations. The Co- ion has 10 valence electrons; 8 more are obtained by sharing from other cluster atoms. The 6 framework orbitals provided by the cobalt atom require 12 electrons. Since 8 of these are provided by other atoms, 4 (or 2 per cluster) are provided by the Co-itself.



similarly, has a  $B_5H_9$  structure in which the apex BH group and one of the basal BH groups have been replaced by Fe(CO)<sub>3</sub> groups, as shown in Fig. 10.6b.<sup>24</sup> In these ferraboranes, each Fe(CO)<sub>3</sub> group contributes three orbitals and two electrons to the bonding (just as a BH group does); thus both compounds have the same number of framework electrons (14) as  $B_5H_9$  and may be considered nido clusters. The 2n + 2 rule and the relationships between framework structure and the number of framework electrons have been useful guides in the synthesis of these and other boron cluster compounds.<sup>25</sup> In Chap. 16 we shall discuss

# OTHER MAIN-GROUP CLUSTER COMPOUNDS

transition-metal cluster compounds in more detail.

The 2n + 2 rule appears to be generally applicable to clusters containing maingroup elements. In these clusters, atoms which have no substituents are assumed

E. L. Andersen, K. J. Haller, and T. P. Fehlner, J. Am. Chem. Soc., 101, 4390 (1979).
 R. W. Rudolph, Acc. Chem. Res., 9, 446 (1976).




Figure 10.6 The structures of ferraboranes. (a) B<sub>4</sub>H<sub>8</sub>Fe(CO)<sub>3</sub>; (b) B<sub>3</sub>H<sub>7</sub>Fe<sub>2</sub>(CO)<sub>6</sub>. (Reproduced with permission from N. N. Greenwood et al., J. Chem. Soc. Chem. Commun., 718 (1974), and from E. L. Andersen, K. J. Haller, and T. P. Fehlner, J. Am. Chem. Soc., 101, 4390 (1979), Copyright 1979 American Chemical Society.)




Figure 10.7 The structures of some nonmetal cluster ions. (a) The tricapped trigonal prism structure of Ga 2. Note that this structure of  $Ge_2^{2-}$ . (b) The monocapped archimedean antiprism structure of  $Ge_2^{4-}$ . Note that this structure has one has one vertex less than the closo bicapped archimedean antiprism. (c) The trigonal prism structure of Te 4. of Te, 4. (Reproduced with permission from C. H. E. Belin, J. D. Corbett, and A. Cisar, J. Am. Chem. Soc., 99, 7163 (1977), and from R. C. Burns et al., Inorg. Chem., 18, 3086 (1979), Copyright 1977 and 1979 American Chemical Society.)

to have one lone pair of electrons each, directed outward from the surfaces of the clusters. For example, Ge<sub>9</sub><sup>2</sup>- has a tricapped trigonal prism structure (Fig. 10.7a), a closo structure corresponding to 20 framework electrons. On the other hand, Geo4- has a nido configuration based on a bicapped archimedean antiprism.26 (See Fig. 10.7b.) The cation Te<sub>6</sub><sup>4+</sup>, with 20 framework electrons, has a trigonal prism structure<sup>27</sup> (Fig. 10.7c), which may be considered a hypho structure related to the tricapped trigonal prism structure that would presumably be adopted by hypothetical Te<sub>9</sub>16+. The rather complicated structure of the As<sub>11</sub>3- anion (with 36 framework electrons) has been rationalized by looking upon it as a 17-vertex polyhedron from which 6 vertices have been deleted.28


#### **PROBLEMS**

10.1 Draw three possible structures for the B<sub>3</sub>H<sub>8</sub> ion, showing any three-center bonds clearly. Which structure do you think is more plausible? Give the styx numbers for all three structures. 10.2 Draw a plausible structure for B<sub>3</sub>C<sub>2</sub>H<sub>5</sub>. How many bonds of each type (B—H, B—B, C—H,


B-B-B, B-H-B, B-B-C, B-C-C) are there?

10.3 In a polyhedral anion of formula B<sub>n</sub>H<sub>n</sub><sup>2-</sup>, how many B—B bonds and how many B—B—B bonds are there?

\*10.4 At least two different mechanisms have been proposed for the isomerization of 1,2-B<sub>10</sub>C<sub>2</sub>H<sub>11</sub>. One involves the rotation of triangular faces of the icosahedron (e.g., a B<sub>2</sub>C face). A second involves the conversion of two adjacent triangular faces into a square face, followed by conversion into two



A cube octahedron intermediate, or activated complex, has been proposed for the latter mechanism



Show that the first mechanism can explain the formation of the 1,7 and 1,12 isomers, but that the second mechanism cannot account for the formation of the 1,12 isomer.

<sup>&</sup>lt;sup>26</sup> C. H. E. Belin, J. D. Corbett, and A. Cisar, J. Am. Chem. Soc., 99, 7163 (1977).

<sup>&</sup>lt;sup>27</sup> R. C. Burns, R. J. Gillespie, W. C. Luk, and D. R. Slim, *Inorg. Chem.*, 18, 3086 (1979). <sup>28</sup> C. H. E. Belin, J. Am. Chem. Soc., 102, 6036 (1980).

10.5 Sketch and label an MO energy level diagram for the bonding of the bridging hydrogens in  $B_2H_6$ . Assume that the boron atoms lie on the z axis and that the bridging hydrogen atoms lie on the x axis, and make the approximation that the bridging hydrogen atoms interact only with the  $2p_x$  orbitals of the boron atoms.

\*10.6 Using the valence bond method and the topological rules outlined on page 255, show that the only acceptable value of q for  $B_5H_5^q$  is -2, corresponding to 2n + 2 framework electrons.


10.7 Rationalize the fact that  $C_2B_9H_{11}^{2-}$ , formed by the reduction of polyhedral  $C_2B_9H_{11}$ , has an open, polyhedral fragment structure.

10.8 Propose topologically acceptable styx numbers for the species B<sub>5</sub>H<sub>12</sub>-, B<sub>6</sub>H<sub>10</sub>, and B<sub>6</sub>H<sub>12</sub>.

10.9 Predict the structure of As<sub>6</sub><sup>2-</sup>.

10.10 Explain the fact that the proton nmr spectrum of  $(CCH_3)_6^{2+}$  shows two peaks with a 5:1 intensity ratio. Propose a plausible structure for the  $(CH)_5^+$  ion.

10.11 Reaction of  $[(CH_3)_2C_2B_4H_4]_2$ FeH<sub>2</sub> with  $B_5H_9$  gives, among other things,  $(CH_3)_4C_4B_{11}H_{11}$ . The structure shown below has been proposed for the  $C_4B_{11}$  cluster of this molecule. Rationalize this structure in terms of electron counting, and show how you count the cluster electrons.



CLASSIFICATION OF BONDS AND CRYSTALS

## THE SOLID STATE

Up to this point, practically all of the chemical species we have discussed have been molecules or ions—either in the gas or liquid phase, or in solution. We have said very little about solid compounds. In this chapter, in which we discuss the solid state, you will find that you are familiar with most of the principles used. However, you will find it necessary to employ a talent that you probably have not used much before: you will be required to visualize relatively complex three-dimensional structures. Some people can do this much more easily than others. Fortunately this ability "to think in three dimensions" can be improved by practice with structural models, and it is strongly recommended that you obtain access to a good model-building kit or at least a large set of balls. Then you will be chapter.

# CLASSIFICATION OF BONDS AND CRYSTALS

Bonding between atoms may be classified into the following types:

 Covalent. This is the type of bonding which we have principally discussed thus far in this book. Covalent bonding is generally described in terms of electron pairs which are shared by the bonded atoms.

<sup>&</sup>lt;sup>1</sup> A. F. Wells, "Structural Inorganic Chemistry," 4th ed., Oxford University Press, London, 1975; C. Kittel, "Introduction to Solid State Physics," 5th ed., Wiley, New York, 1976.

- 2. Ionic. This is the bonding caused by the electrostatic (coulombic) attraction between oppositely charged atoms or ions. In the limit of pure ionic bonding between atoms, each ion would be spherically symmetric and there would be no shared electrons.
- 3. Van der Waals. This bonding, sometimes referred to as London dispersion forces, corresponds to the relatively weak interaction which occurs between atoms and molecules caused by instantaneous dipole-induced dipole interactions. Even in species which have no permanent dipole moment, instantaneous dipoles arise because of momentary asymmetry in electron distribution. These instantaneous dipoles induce dipoles in adjacent species. In other words, the electrons in separate species tend to synchronize their movements to minimize electron-electron repulsion and to maximize electron-nucleus attraction. Van der Waals forces increase rapidly with molecular volume and with the number of polarizable electrons. They are the principal forces holding together the atoms in solid argon and are the principal intermolecular forces in solid CCl4 and I2.

4. Metallic. This type of bonding holds together regular lattices of electron-deficient atoms, or groups of atoms, such as in metals and alloys. The characteristic feature of metallic bonding is that the bonding electrons are delocalized

over the entire crystal.

It might appear that the best way of classifying solids would be in terms of the types of bonds between the atoms, i.e., covalent, ionic, van der Waals, and metallic. However, bonds which are purely of one type or another are rare, and in most crystals there are bonds of more than one type. Figure 11.1 illustrates how covalent, ionic, and metallic bonding mix together even in simple compounds and shows that the bonding in most compounds cannot be cleanly classified into any one of these groups. It is more useful to classify solids in terms of their




Figure 11.1 Classification of compounds according to the degree of covalent, ionic, and metallic character in the bonding.

structural features, and we shall now show how it is possible to roughly classify crystals in the following four categories: (1) crystals containing finite, discrete complexes, (2) crystals containing infinite one-dimensional complexes, (3) crystals containing infinite two-dimensional complexes, and (4) crystals consisting of infinite three-dimensional complexes.

## Crystals Containing Finite Complexes at vd booting extraction base amount

This category includes most solid compounds of the nonmetals in which the molecules are held together by van der Waals or dipole-dipole forces. In the case of atoms (for example, Ne, Ar, Kr, and Xe) and molecules with approximately spherical shapes (for example, HCl, H2S, and SiF4), the so-called close-packed structures and the body-centered cubic structure are generally found. The close-packed structures may be understood by reference to Fig. 11.2. When identical spheres are packed together as closely as possible on a plane surface, they are arranged as shown, with each sphere touching six others. An exactly similar layer of spheres can be laid on top of this layer, so that the spheres of the second layer rest in depressions of the first layer. When a third layer is placed on the second layer, there are two choices: The spheres may be placed in the depressions directly over the first-layer spheres or in the depressions which lie over depressions in the first layer. The two simplest sequences of layers may be indicated ABAB . . . (called "hexagonal close packing") or ABCABC . . . (called "cubic close packing" or "face-centered cubic packing"). In each case each sphere touches 12 others, and the fraction of space occupied by spheres is 0.7405. Sketches of spheres packed in these two ways are shown in Fig. 11.3.

The body-centered cubic structure is illustrated in Fig. 11.3. In the case of molecular crystals, this type of packing is less common, probably because the packing is slightly less efficient than in the close-packed structures. (The fraction of space occupied by spheres is 0.68.) Unfortunately there does not appear to be any simple rationale for predicting the type of packing in molecular crystals. Thus, although the *molecular* structures of Se<sub>4</sub>N<sub>4</sub> and S<sub>4</sub>N<sub>4</sub> are practically identical, the packing of Se<sub>4</sub>N<sub>4</sub> is approximately body-centered cubic, whereas that of S<sub>4</sub>N<sub>4</sub> is almost cubic close-packing.<sup>2</sup> Very subtle changes in van der Waals

<sup>&</sup>lt;sup>2</sup> H. Bärnighausen, T. von Volkmann, and J. Jander, Acta Crystallogr., 21, 571 (1966).




Figure 11.2 Two adjacent layers of close-packed spheres. Notice that there are two ways of placing a third layer. If the spheres in the third layer are directly over those of the first layer, the packing is hexagonal close packing. Otherwise the packing is cubic close packing.




Figure 11.3 Arrangement of spheres in hexagonal close packing (left) and cubic close packing (right). (Adapted with permission from L. Pauling, "The Nature of the Chemical Bond," 3d ed., Cornell University Press, Ithaca, N.Y., 1960.)

bonding and electron-electron repulsions may be the determining factors in changes in crystal structure.

The packing of nonspherical or dipolar molecules generally deviates from the undistorted close-packed and body-centered cubic structures. The packing diagrams of two rather complicated molecules [an iron(III) complex of N-(2-phenylethyl)salicylaldimine and chloride,³ and pentacarbonyl(tetraphosphorus trisulfide)molybdenum⁴] are shown in Figs. 11.5 and 11.6, respectively. Inasmuch as these molecules are not spherically symmetric, it is necessary to specify their angular orientations as well as their positions when describing the packing.

<sup>3</sup> J. A. Bertrand, J. L. Breece, and P. G. Eller, *Inorg. Chem.*, **13**, 125 (1974).

<sup>4</sup> A. W. Cordes, R. D. Joyner, R. D. Shores, and E. D. Dill, *Inorg. Chem.*, **13**, 132 (1974).




Figure 11.4 Body-centered cubic structure. This type of packing is found for the atoms in various metals and for the molecules in the crystals of many molecular compounds [e.g., SiF<sub>4</sub>, N<sub>4</sub>(CH<sub>2</sub>)<sub>6</sub>, and MoAl<sub>12</sub>].




Figure 11.5 Packing diagram of Fe(SANE)<sub>2</sub>Cl. [SANE = N-(2-phenylethyl)salicylaldimine.] The asymmetric units are linked into loose "dimers." Carbon atoms are represented by open circles; other atoms by filled circles. [Reproduced with permission from J. A. Bertrand et al., Inorg. Chem., 13, 125 (1974). Copyright 1974 American Chemical Society.]




Figure 11.6 Projection of the crystal packing of Mo(CO)<sub>5</sub>P<sub>4</sub>S<sub>3</sub>. [Reproduced with permission from A. W. Cordes et al., Inorg. Chem., 13, 132 (1974). Copyright 1974 American Chemical Society.]

### Crystals Containing Infinite One-Dimensional Complexes

The simplest examples of one-dimensional complexes in the solid state consist of infinite linear molecules held together in lattices by van der Waals bonds. The SiS<sub>2</sub> structure consists of SiS<sub>4</sub> tetrahedra which share edges to form long chains, as shown in Fig. 11.7. In palladium(II) chloride, PdCl<sub>2</sub>, infinite chains are built of planar PdCl<sub>4</sub> groups sharing opposite edges, as shown in Fig. 11.8. In elemental tellurium, the atoms are joined in the form of infinite helical chains. Similar helical chains exist in the "metallic" form of selenium and the fibrous form of sulfur. The fibrous sulfur structure is illustrated in Fig. 11.9.

Many crystals contain anionic chains held together by cations. For example, the complex KCu(CN)<sub>2</sub> has a spiral polymeric anion in which each Cu(I) atom is bound to two carbon atoms and one nitrogen atom:

Silicate chain ions are found in the two large classes of minerals, the "pyroxenes," and the "amphiboles." The former [including enstatite, MgSiO<sub>3</sub>; diopside,




Figure 11.7 Structure of SiS<sub>2</sub>. Small circles represent silicon atoms; large circles sulfur atoms.




Figure 11.8 Structure of PdCl<sub>2</sub>.




Figure 11.9 Structure of fibrous sulfur. (Adapted with permission from L. Pauling, "The Nature of the Chemical Bond," 3rd ed., Cornell University Press, Ithaca, N.Y., 1960.)




Figure 11.10 Silicon-oxygen anionic chains in pyroxenes (a) and amphiboles (b). (Reproduced with permission from A. F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford, 1962.)

CaMg(SiO<sub>3</sub>)<sub>2</sub>; jadeite, NaAl(SiO<sub>3</sub>)<sub>2</sub>; and spodumene, LiAl(SiO<sub>3</sub>)<sub>2</sub>] contain simple chains of tetrahedral SiO<sub>4</sub> groups connected by shared oxygen atoms, as shown in Fig. 11.10a. The latter [including tremolite, Ca<sub>2</sub>Mg<sub>5</sub>(OH)<sub>2</sub>(Si<sub>4</sub>O<sub>11</sub>)<sub>2</sub>, and arfved-sonite, Na<sub>3</sub>Mg<sub>4</sub>Al(OH)<sub>2</sub>(Si<sub>4</sub>O<sub>11</sub>)<sub>2</sub>] contain double chains in which one-half of the SiO<sub>4</sub> groups are joined to two adjacent groups by shared oxygen atoms, and one-half are joined to three adjacent groups by shared oxygen atoms, as shown in Fig. 11.10b.

### Crystals Containing Infinite Two-Dimensional Complexes

Structures in which layers are held together by van der Waals or weak covalent bonds are found in elemental arsenic and graphite (Fig. 11.11) and in CdCl<sub>2</sub>, MoS<sub>2</sub>, CrCl<sub>3</sub>, and HgI<sub>2</sub> (Fig. 11.12).

The graphite structure differs from the other layer structures in that the atoms of each layer are coplanar. The large distance between layers (3.35 Å) compared with the C—C distance of 1.42 Å in the layers indicates very weak bonding between layers, thus allowing the layers to slide easily over one another, giving graphite its valuable lubricating properties. In the common hexagonal graphite structure, the atoms of alternate layers lie above one another, and the repeat distance perpendicular to the layers is 6.70 Å. In Fig. 11.11c, it can be seen that







Figure 11.11 Layer structures of arsenic (a) and hexagonal graphite (b). (c) Relative alignments of adjacent layers in graphite. See text.










Figure 11.12 Structures of some simple MX<sub>2</sub> and MX<sub>3</sub> layers. Small circles represent metal atoms in the plane of the paper; large circles, the X atoms which lie in planes above and below that of the metal atoms. The layers are CdCl<sub>2</sub> (a), MoS<sub>2</sub> (b), CrCl<sub>3</sub> (c), and Hgl<sub>2</sub> (d). (Reproduced with permission from A. F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford, 1962.)

there are two different ways in which adjacent layers can be symmetrically drawn with solid lines the symbol A, and the other two dashed-line layers the layers  $ABABAB \dots$ ,  $ACACAC \dots$ , or  $BCBCBC \dots$ , all of which are the stacking order  $ABCABC \dots$ , in which every third layer is superposed. It is interesting that in hexagonal graphite there are two crystallographically different equivalent.

Structures with layers which are held together by hydrogen bonds are found in

Crystals Containing Infinite Three-Dimension.





Figure 11.13 Structure of a silicon-aluminum-oxygen sheet. Oxygen atoms lying above the Si(Al) atoms (small black circles) are drawn more heavily. (Reproduced with permission from A. F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford, 1962.)

various hydroxy compounds, such as aluminum hydroxide, Al(OH)<sub>3</sub>. The arrangement of Al and O atoms in this compound is similar to that of the Cr and Cl atoms in CrCl<sub>3</sub>, shown in Fig. 11.12c; hydrogen bonds link together the oxygen atoms of adjacent layers. In boric acid (Fig. 7.6) hydrogen bonds hold together the atoms within each layer.

Examples of anionic layers held together by cations are found in certain aluminosilicates such as the hexagonal form of  $CaAl_2Si_2O_8$ . This compound contains silicon-aluminum-oxygen sheets of the type shown in Fig. 11.13. Such sheets are joined together in pairs by oxygen atoms to form double layers of empirical composition  $(AlSiO_4)_n^{n-}$ . These double layers are held together by calcium ions as shown in Fig. 11.14. The micas have related structures.



Si(Al) of Ha bris warm books o scolo

O O man as translations of wars resistant


Ca2+

Figure 11.14 Side view of the structure of hexagonal CaAl<sub>2</sub>Si<sub>2</sub>O<sub>8</sub>, showing the double layers, interleaved with Ca<sup>2+</sup> ions. (Reproduced with permission from A. F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford, 1962.)


### Crystals Containing Infinite Three-Dimensional Complexes

Metals, which we shall discuss separately in Chap. 12, have three-dimensional frameworks which generally can be described in terms of one of the following types of atomic structures: hexagonal close packing, cubic close packing, and body-centered cubic.

A wide variety of three-dimensional framework structures have been observed for compounds. In the case of simple compounds having the general formula  $M_m X_x$ , where X is a relatively large atom, most observed structures consist of close-packed arrangements of the X atoms, with the M atoms occupying the holes. There are two types of holes in a close-packed structure: tetrahedral and octahedral. The hole formed by the following arrangement of spheres is a tetrahedral hole:



The hole formed by the following arrangement of spheres is an octahedral hole:



By examination of Fig. 11.2 it can be seen that the number of tetrahedral holes is equal to twice the number of close-packed spheres and that the number of octahedral holes is equal to the number of close-packed spheres.

In Table 11.1 are listed some common structures based on close packing. Let us consider the NaCl structure. The chlorine atoms are arranged in a cubic close-packed array, and all the octahedral holes are occupied by sodium atoms. The octahedral holes have a cubic close-packed arrangement, and so the NaCl lattice may be considered as two interpenetrating cubic close-packed lattices. The conventional representation of the NaCl lattice is shown in Fig. 11.15a, arrangements of the two sets of equivalent atoms. Many MX compounds have the NaCl crystal structure. These include most of the alkali-metal halides and many metal oxides, sulfides, carbides, nitrides, and phosphides.

Five other structures based on close-packed X atoms are illustrated in Fig. 11.16. In fluorite (CaF<sub>2</sub>), the calcium atoms have a cubic close-packed arrangement, with all the tetrahedral holes occupied by fluorine atoms. Each calcium

Table 11.1 Structures based on close packing of X atoms

		oles occupied atoms	Type of close pa	Coordina- tion number		
Formula	Tetrahedral	Octahedral	hcp	сср	M	X
M <sub>2</sub> X	1	0	ė.	F <sub>2</sub> Ca (fluorite)	4	8
M <sub>3</sub> X <sub>2</sub>	1	0		$Zn_3P_2$ $O_3Mn_2$	4	6
MX	0	1	NiAs	NaCl	6	6
13	1/2	0	ZnS (wurtzite)	ZnS (zinc blende)	4	4
M <sub>2</sub> X <sub>3</sub>	0	2/3	α-Al <sub>2</sub> O <sub>3</sub> (corundum)	100	6	4
189	1	0	$\beta$ -Ga <sub>2</sub> S <sub>3</sub>	γ-Ga <sub>2</sub> S <sub>3</sub>	4	N.
MX <sub>2</sub>	0	$\frac{1}{2}$	CdI <sub>2</sub> TiO <sub>2</sub> (rutile)	CdCl <sub>2</sub> TiO <sub>2</sub> (anatase)	6	3
adios bus	(a) splete (b)	o dose paolo s	β-ZnCl <sub>2</sub>	HgI <sub>2</sub> γ-ZnCl <sub>2</sub> SiS <sub>2</sub> OCu <sub>2</sub> α-ZnCl <sub>2</sub>	4	2
MX <sub>3</sub>	0	1/3	BiI <sub>3</sub>	CrCl <sub>3</sub>	6	2
RICHUEN	ALVINO F	ngonal phon	Al <sub>2</sub> Br <sub>6</sub>	kei neighbors an	4 / 12	2
MX <sub>4</sub>	N A STATE OF THE S	M is a tropic	SnI <sub>4</sub>	y many MX com	4	1
MX <sub>6</sub>	d forms of 0 l	of the or sta	named after one by systematic ren	α-WCl <sub>6</sub>	6 11	1 sits

atom has eight nearest-neighbor fluorine atoms at the corners of a cube, and each fluorine atom has four nearest-neighbor calcium atoms at the corners of a letrahedron. A number of difluorides, dioxides, and disilicides have the fluorite structure. In the so-called anti-fluorite structure, the positions occupied by the cations and anions of the fluorite structure are interchanged. The anti-fluorite structure is adopted by most of the alkali-metal oxides and sulfides.

In nickel arsenide, the arsenic atoms have the hexagonal close-packed arnickel atom is octahedral holes occupied by nickel atoms. Thus each
nickel atom is octahedrally coordinated by arsenic atoms, and each arsenic atom




Figure 11.15 Conventional NaCl structure (a), cubic close packing of spheres (b), and another representation of the NaCl structure (c). [From W. Barlow, Z. Kristallogr., 29, 433 (1898).]

has six nickel neighbors at the corners of a trigonal prism. The NiAs structure is adopted by many MX compounds in which M is a transition metal and X is Sn, As, Sb, S, Se, or Te.

The rutile structure is named after one of the crystal forms of TiO<sub>2</sub>. This structure can be obtained by systematic removal of one-half of the nickel atoms from nickel arsenide, followed by a slight distortion of the arsenic atoms from hexagonal close packing. The rutile structure consists of chains of MX<sub>6</sub> octahedra, in which each octahedron shares a pair of opposite edges and which are further linked by sharing corners to form a three-dimensional structure in which each M atom has six X neighbors and each X atom has three coplanar M neighbors. Many dioxides and difluorides have the rutile structure, and many compounds of the type ABX<sub>4</sub>, A<sub>2</sub>BX<sub>6</sub>, etc., have rutile-like structures in which the metal atoms are either randomly or regularly distributed in the M sites.

Zinc sulfide is found in two crystal modifications, one called zinc blende (based on cubic close-packed sulfur atoms) and the other wurtzite (based on hexagonal close-packed sulfur atoms). In each structure, the zinc atoms occupy half of the tetrahedral holes, and both the zinc and sulfur atoms have four

tetrahedral nearest neighbors. Although many MX compounds (such as ZnO, SiC, CuCl, AlP, and InAs) adopt wurtzite or zinc-blende structures, even more compounds having two or more different metal atoms are known which adopt structures related to the ZnS structures. Thus BeSiN<sub>2</sub> has a wurtzite-type structure, and Cu<sub>2</sub>FeSnS<sub>4</sub> has a zinc-blende-like structure. Diamond has a zinc-blende-type structure, in which both the Zn and S sites are occupied by carbon




Figure 11.16 Structures of fluorite  $(CaF_2)$  (a), rutile  $(TiO_2)$  (b), nickel arsenide (NiAs) (c), zinc blende (ZnS) (d), and wurtzite (ZnS) (e). (Reproduced with permission from A. F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford, 1962.)




Figure 11.17 The β-cristobalite structure of SiO<sub>2</sub> idealized. In fact, the Si—O—Si bond angles are not 180°, but close to 144°. Compare with the zinc-blende structure. (Reproduced with permission from A. F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford 1962.)

atoms. Silicon, germanium, and gray tin also crystallize in the diamond structure. A rare hexagonal form of diamond (wurtzite-type structure) was discovered in meteorites and has been synthesized in the laboratory. Ordinary ice has a occupied by oxygen atoms. As shown in Fig. 7.3, the hydrogen atoms lie approximately on the lines connecting the oxygen atoms, 1.01 Å from one oxygen atom and 1.75 Å from the other. The short O—H bonds are randomly distributed, but with the restriction that at any given time only two H atoms are close to any one O atom. The high-temperature form of silica (cristobalite) has a oxygen atoms near the midpoints of the lines connecting the silicon atoms (Fig. 11.17).

It should be noted that Table 11.1 includes several structures which do not fit strictly into the category of infinite three-dimensional networks. For example, one-sixth of the tetrahedral holes occupied by aluminum atoms in such a way that adjacent pairs of tetrahedral holes are occupied. Thus, pairs of bromine atoms on discrete molecules of the following type:

An important structure for compounds of the type MX, which does not correspond to a close packing for either the M or X atoms, is the cesium chloride structure, shown in Fig. 11.18. Each atom has eight nearest neighbors, as in the body-centered cubic structure.

There are many ionic compounds of the type  $M_m X_x$  in which M, X, or both M and X are replaced by complex ions. When the complex ions are approximately spherical, the spatial arrangement of the ions is often the same as in one of the

<sup>&</sup>lt;sup>5</sup> R. E. Hanneman, H. M. Strong, and F. P. Bundy, Science, 155, 955 (1967).




Figure 11.18 The CsCl structure.

symmetric structures which we have discussed. For example, [Co(NH<sub>3</sub>)<sub>6</sub>]I<sub>2</sub> and [Mg(NH<sub>3</sub>)<sub>6</sub>]I<sub>2</sub> adopt the fluorite (CaF<sub>2</sub>) structure, and K<sub>2</sub>PtCl<sub>6</sub> and K<sub>2</sub>SnCl<sub>6</sub> adopt the anti-fluorite structure (i.e., a fluorite-like structure in which anions occupy the Ca<sup>2+</sup> positions and cations occupy the F<sup>-</sup> positions). The structure of [Ni(H<sub>2</sub>O)<sub>6</sub>][SnCl<sub>6</sub>] is a slightly deformed version of that of CsCl. Polyatomic ions can attain effective spherical symmetry by rapid free rotation or random orientation. Such behavior is often found in salts containing the ions NH<sub>4</sub>+, NO<sub>3</sub>-, CN-, and SH-.

Salts containing polyatomic ions sometimes adopt structures similar to the corresponding simple  $M_m X_x$  compounds but of lower symmetry because of the





Figure 11.19 Sections through the structures of NaCl and CaC2, showing the relationship of the packing. (Reproduced with permission from A. F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford, 1962.)






Figure 11.20 The CaCO<sub>3</sub> and NaCl structures similarly oriented. (Reproduced with permission from A.F. Wolle, 1962) A.F. Wells, "Structural Inorganic Chemistry," 3d ed., Clarendon Press, Oxford, 1962.)

nonspherical shapes of the ions. For example, the structure of calcium carbide,  $CaC_2$ , is essentially that of NaCl, but the structure is distended in the direction along which the  $C_2^{2-}$  ions are aligned, as shown in Fig. 11.19. Calcite,  $CaCO_3$ , also has a structure like that of NaCl but elongated along a threefold axis, as shown in Fig. 11.20. When one of the complex ions is very large and irregularly shaped, and the counter-ion is small, the structure is usually determined by the packing of the large ions, the counter-ions fitting in the interstices.

# THE EFFECT OF RADIUS RATIO AND CHARGE ON STRUCTURE

There is no sharp dividing line between ionic and covalent bonding. The ionic character of a bond increases with increasing electronegativity difference between the atoms. Thus the bonding in solid NaCl is principally ionic, and that in diamond is completely covalent. However, in compounds such as ZnO and AgBr, the bonding is intermediate in character. An abrupt change in a physical property in a series of compounds has often been mistakenly ascribed to an abrupt change in the ionic character of the bonding. For example, consider the melting points of the fluorides of the second-row elements:

NaF	MgF <sub>2</sub>	AlF <sub>3</sub>	SiF <sub>4</sub>	PF <sub>5</sub>	SF <sub>6</sub>
988°C	1266℃	1291°C (sublimes)	-90°C	-94°C	-50°C
			BOAT THE SECOND	SHARE IN THE	al when we

The enormous change in melting points between AIF<sub>3</sub> and SiF<sub>4</sub> is not due to a marked change in ionic character (the electronegativities of Al and Si are 1.5 and 1.8 respectively) but rather to a change from an infinite lattice structure in which each aluminum is coordinated to six fluorine atoms to a lattice of discrete SiF<sub>4</sub> molecules held together by van der Waals bonds

In most saline halides (i.e., halides with infinite three-dimensional ionic the number of halide ions that could be bound to the metal ion is greater than discrete molecule. Generally a halide will exist in the form of molecules only positive atom equals the maximum coordination number of the electropositive atom for that halogen. A halide  $MX_n$  will have a three-dimensional crystal lattice number greater than n. Obviously the radius ratio of the atoms is the critical possible values of the ratio  $r_M/r_X$  for various types of coordination of X atoms when combined with atomic or ionic radii, should be useful for predicting cause atomic and ionic radii are not well-defined, constant quantities. However,

Table 11.2 Allowed values of  $r_{\rm M}/r_{\rm X}$  for various types of coordination

Coordination number	Type of coordination	Minimum value of $r_M/r_X$		
2	Linear	0		
3	Triangular planar	0.155		
4	Tetrahedral	0.225		
6	Square planar   Octahedral	0.414		
8	Square antiprismatic	0.645		
8	CsCl structure	0.732		
12	Cubooctahedral	1.000		

by using, for example, a consistent set of ionic radii such as those deduced by Pauling from crystal structure data (Table 11.3), it is possible to observe a correlation of the calculated radius ratios with the observed coordination numbers in crystals. The  $r_{\rm M}/r_{\rm X}$  values for metals in various oxide lattices and in various halides are listed with the corresponding observed coordination numbers

Table 11.3 Pauling ionic radii (in angstroms)†

Ag+	1.26	Fe <sup>2+</sup>	0.76	Pb4+	0.84
A 3+	0.50	Fe <sup>3+</sup>	0.64	P <sup>3-</sup>	2.12
As3-	2.22	Ga+	1.13	P5+	0.34
As <sup>5+</sup>	0.47	Ga <sup>3+</sup>	0.62	Pd <sup>2+</sup>	0.86
Au+ B <sup>3+</sup>	1.37	Ge <sup>2+</sup>	0.93	Ra <sup>2+</sup>	1.40
Ba <sup>2+</sup>	0.20	Ge <sup>4+</sup>	0.53	Rb+	1.48
Be <sup>2+</sup>	1.35	H-	1.40	S <sup>2-</sup>	1.84
Br	0.31	Hf4+	0.81	Sb <sup>3-</sup>	2.45
C+	1.95	Hg <sup>2+</sup>	1.10	Sc3+	0.81
C4+	2.60	1-000 900	2.16	Se <sup>2</sup>	1.98
Ca2+	0.15	In+	1.32	Sr <sup>2+</sup>	1.13
Cd2+	0.99	In <sup>3+</sup>	0.81	Sn <sup>2+</sup>	1.12
Ce3+	0.97	K <sup>+</sup>	1.33	Sn <sup>4+</sup>	0.71
Ce4+	1.11	La <sup>3+</sup>	1.15	Te <sup>2-</sup>	2.21
CI-	1.01	Li+	0.60	Ti <sup>2+</sup>	0.90
C <sub>0</sub> 2+	1.81	Lu3+	0.93	Ti <sup>3+</sup>	0.76
C <sub>0</sub> 3+	0.74	Mg <sup>2+</sup>	0.65	Ti <sup>4+</sup>	0.68
Cr2+	0.63	Mn <sup>2+</sup>	0.80	Tl+	1.40
Cr3+	0.84	Mn³+	0.66	Tl <sup>3+</sup>	0.95
CLe+	0.69	Mo <sup>6+</sup>	0.62	U3+	1.11
Cs+	0.52	N3-	1.71	U <sup>4+</sup>	0.97
Cu+	1.69	N5+	0.11	V2+	0.88
Cu2+	0.96	Na+	0.95	V3+	0.74
Eu2+	0.70	NH <sub>4</sub> +	1.48	V <sup>4+</sup>	0.60
Eu3+	1.12	Ni <sup>2+</sup>	0.72	Y3+	0.93
F	1.03	Olan O2- Souley	1.40	Zn <sup>2+</sup>	0.74
_	1.36	Pb2+	1.20		

<sup>†</sup> L. Pauling, "The Nature of the Chemical Bond," 3d ed., Cornell University Press, Ithaca, N.Y.,

Table 11.4 Radius ratios and coordination numbers in oxides and halides

	Oxide	lattices			tors of coordinal	
-pt-l		Commonly observed	Migated etc	Halides		
Cation	$r_{\rm M}/r_{\rm O}$	coordination nos.	Salt	$r_{\rm M}/r_{\rm X}$	Coordination no	
B <sup>3+</sup>	0.14	3, 4	MgI <sub>2</sub>	0.30	6	
Be <sup>2+</sup>	0.22	4	MgBr <sub>2</sub>	0.33	6	
Si <sup>4+</sup>	0.29	4	MgCl <sub>2</sub>	0.36	6	
Al3+	0.36	4, 6	CaI <sub>2</sub>	0.46	6	
Ge <sup>4+</sup>	0.38	4, 6	MgF <sub>2</sub>	0.48	6	
Li <sup>+</sup>	0.43	4	CaBr <sub>2</sub>	0.51	6	
Mg <sup>2+</sup>	0.46	6	SrI <sub>2</sub>	0.52	>6	
Ti4+	0.48	6 000	CaCl <sub>2</sub>	0.55	6	
Zr <sup>4+</sup>	0.57	6	SrBr <sub>2</sub>	0.58	>6	
Sc3+	0.58	6	Bal,	0.58		
Na <sup>+</sup>	0.68	6	SrCl <sub>2</sub>	MINE STREET	>6	
Ca <sup>2+</sup>	0.71	8 2 (LII side I)	BaBr <sub>2</sub>	0.62	The state of the s	
Ce4+	0.72	tins with the obest 8 1		0.69	>6	
K <sup>+</sup>	0.95	9	CaF <sub>2</sub>	0.73	WINDLESS IN THE	
Cs+	1.21	12	BaCl <sub>2</sub>	0.75	>6 7 11 21 11	
		Carlo de la Superioria	SrF <sub>2</sub>	0.83	minus har 8 des a	
		A SALE SALE SALES	BaF <sub>2</sub>	0.99	8	

for the metals in these compounds in Table 11.4. It can be seen that  $r_{\rm M}/r_{\rm X}$  values at the border lines between various coordination numbers are in approximate agreement with the theoretical  $r_{\rm M}/r_{\rm X}$  values of Table 11.2.

The Pauling ionic radii of Table 11.3 are useful for qualitative comparisons of rough quantitative estimations of interionic distances, but serious errors can be made if the values are used indiscriminately. One factor which influences the effective radius of an ion in a crystal is the coordination number. Other things being equal, an increase in coordination number causes the valence electrons to be shared among more bonds; hence the covalent character of the bonds is reduced and the effective ionic radius increases. For example, the interionic distance in TICl is 3.15 Å when the crystal has the NaCl structure (coordination number 6) and 3.32 Å when it has the CsCl structure (coordination number 8). Of course, even though the interionic distance increases on going to the structure with a higher coordination number, the packing efficiency increases. Thus the density of TICl is 6.37 g cm<sup>-3</sup> in the NaCl structure and 7.07 g cm<sup>-3</sup> in the CsCl structure. In the case of some transition-metal ions, another factor influencing ionic radius is the spin state: the greater the spin, the greater the ionic radius. The reason for this relationship between spin and effective ionic radius will be discussed in Chap. 18. Shannon<sup>6</sup> has prepared a table of effective ionic radii in which, for a given metal ion, separate values are listed for various coordination

<sup>&</sup>lt;sup>6</sup> R. D. Shannon, Acta Crystallogr., A32, 751 (1976).




Figure 11.21 Average principal quantum number of valence shells versus electronegativity difference for MX compounds. Open circles correspond to tetrahedral structures; solid structures correspond to octahedral structures. [From E. Mooser and W. B. Pearson, Acta Crystallogr. 12, 1015 (1959).]

numbers and, when appropriate, for high- and low-spin states. Ionic radii from his compilation are given in Appendix F.

The radius ratio of two atoms is related to the electronegativity difference between the atoms. In general, the greater the electronegativity difference between M and X, the greater the value of  $r_{\rm M}/r_{\rm X}$ . Thus it is not surprising that Mooser and Pearson<sup>7</sup> observed that, if the average principal quantum number of the valence shells of M and X is held constant, a transition from tetrahedral coordination to octahedral coordination occurs when the electronegativity difference exceeds a particular value. In Fig. 11.21, the average principal quantum number is plotted against the electronegativity difference for a large number of compounds of type MX. It can be seen that a fairly sharp boundary separates the tetrahedral structures (open circles) from the octahedral structures (solid circles).

Striking evidence that the effective radius of an ion depends on the nature of its counter-ion is given in Table 11.5, which lists the interionic distances for AgX and NaX compounds having the NaCl crystal structure. If we make the completely arbitrary assumption that the X<sup>-</sup> radius is constant on going from AgY to NaX, then we conclude that Ag<sup>+</sup> is larger than Na<sup>+</sup> when  $X^- = F^-$ , but that Na<sup>+</sup> is larger than  $Ag^+$  when  $X^- = Cl^-$ ,  $Br^-$ , or  $PF_6^-$ . These results can be rationalized by recognizing that  $Ag^+$  is a much "softer" ion than  $Na^+$  and that it forms much more covalent (relatively short) bonds with polarizable ions such as Cl-, Br-, and PF<sub>6</sub>.

Pauling<sup>8</sup> proposed several rules for predicting the types of anion-cation coordination in stable ionic lattices containing more than two kinds of ions. His first rule says, in effect, that the charge on a given anion should be canceled by its share of the charges on the cations to which it is coordinated. Thus an oxide ion

<sup>&</sup>lt;sup>7</sup>E. Mooser and W. B. Pearson, Acta Crystallogr., 12, 1015 (1959). L. Pauling, "The Nature of the Chemical Bond," 3d ed., Cornell University Press, Ithaca, N.Y.,

Table 11.5 A comparison of Ag+ and Na+ in NaCl-type structures

Compound	M—X distance,
AgF NaF	2.47 2.31
AgCl NaCl	2.77
AgBr NaBr	2.89
AgPF <sub>6</sub> NaPF <sub>6</sub>	3.76 3.80

will be stable if it is coordinated to any of the following combinations of cations:

Two tetrahedral Si<sup>4+</sup> ions, as in many silicates  $(2 = \frac{4}{4} + \frac{4}{4})$ 

One tetrahedral Si<sup>4+</sup> ion and two octahedral Al<sup>3+</sup> ions, as in topaz, Al<sub>2</sub>SiO<sub>4</sub>F<sub>2</sub>  $(2 = \frac{4}{4} + \frac{3}{6} + \frac{3}{6})$ us ratio of two atoms is related to the elect-

One tetrahedral Si4+ ion and three octahedral Mg2+ ions, as in olivine, Mg2SiO4  $(2 = \frac{4}{4} + \frac{2}{6} + \frac{2}{6} + \frac{2}{6})$  and X a

One tetrahedral Si4+ ion and two tetrahedral Be2+ ions, as in phenacite, Be2SiO4  $(2 = \frac{4}{4} + \frac{2}{4} + \frac{2}{4})$ . The second of the se

Pauling's second rule is concerned with the number of anions simultaneously coordinated to two different cations, i.e., with the sharing of polyhedron vertices, edges, and faces. The rule states that shared edges, and especially shared faces, decrease the stability of a structure. The effect is greatest for cations of high charge and low coordination number and is caused by the increased electrostatic repulsion between cations. In agreement with this rule, SiO<sub>4</sub> tetrahedra tend to share only vertices with one another and with other polyhedra. However, in compounds in which the bonding is relatively covalent and in which the atomic charges are lower, exceptions to this second rule occur. Thus we have seen, in Fig. 10.7, how SiS<sub>4</sub> tetrahedra share edges in SiS<sub>2</sub> to form infinite chains,

Pauling's third rule, which also has an electrostatic basis, states that in a crystal containing different cations, those with high charge and low coordination number tend not to occupy polyhedra which share vertices or edges with each other. The highly charged cations tend to be as far apart from one another as

### LATTICE ENERGY A SUBSTICE MANAGEMENT OF THE STATE OF THE

used only for ensuals having a particular charge type. The Madelul The energy required to break up a crystal into infinitely separated ions is called the  $M_m X_x(s) \rightarrow m M^{z_M}(g) + x X^{z_N}(g)$ lattice energy U:

$$M_m X_x(s) \rightarrow m M^{z_M}(g) + x X^{z_X}(g)$$

If the bonding in the crystal were completely ionic, the lattice energy could be calculated from the ionic charges and the geometric arrangement of the ions in the lattice. It is convenient to express this theoretical electrostatic lattice energy  $U_e$  as a function of the stoichiometric numbers m and x, the ionic charges  $z_{\rm M}$  and  $z_{\rm X}$ , the closest interionic distance r, and a geometric factor called the reduced Madelung constant, M':

$$U_e = -M' \frac{z_{\rm M} z_{\rm X}(m+x)e^2}{2r}$$

In the case of a salt for which m = x = 1, the quantity M' - 1 is essentially a measure of the stabilization in the crystal lattice relative to that in a simple ion pair. (M' = 1 for an ion pair.) Values of M' for various crystal structures are given in Table 11.6. Values for many other structures are given in the literature.9 It can be seen that M' has essentially the same magnitude (namely  $\sim 1.7$ ) for all the crystal structures listed, showing that the lattice stabilization is of comparable magnitude for these structures. 10 Most texts quote the Madelung constants  $\mathcal{M}$  or M, which are related to M' by the equations given in Table 11.6. When these Madelung constants are used, the theoretical electrostatic lattice energy must be calculated by the following equations: of sodium chlouds (Similar calcula

$$U_e = -M \frac{z_{\rm M} z_{\rm X} e^2}{r}$$

<sup>9</sup> Q. C. Johnson and D. H. Templeton, J. Chem. Phys., 34, 2004 (1961). D. H. Templeton, J. Chem. Phys., 23, 1826 (1955).

Table 11.6 Values of Madelung constants for several crystal structures

CHORDING SEG	e attributed to repulsi	Conventional Madelung constants				
Crystal structure	Reduced Madelung constant, M'	$\mathcal{M} = \left(\frac{m+x}{2}\right)M'$	$M = \frac{z_{\rm M} z_{\rm X}(m+x)}{2} M'$			
CsCl	1.7476	1.7476	1.7476			
ZnS (zinc blende)	1.7627	1.7627	1.7627			
ZnS (wurtzite)	1.6381	1.6381	6.5522			
	1.6413	1.6413	6.5653			
	1.6796	2.5194	5.0388			
Al <sub>2</sub> O <sub>3</sub> (corundum)	1.6053	2.4080	19.264			
	1.6688	4 172	25.031			

Inasmuch as a Madelung constant of type M contains the  $z_M z_X$  factor, it can be used only for crystals having a particular charge type. The Madelung constants M' and M are more generally useful because they can be applied to crystals of any charge type. Thus M' = M = 1.7476 for any compound of type  $M^{n+}X^{n-}$  which has the sodium chloride structure (for example, MnO), whereas M = 1.7476 when n = 1 and M = 6.9902 when n = 2.

There is no experimental method known for directly measuring lattice energies. However, it is possible to obtain "experimental" values of lattice energies from appropriate thermodynamic data. Thus the lattice energy of a salt such as NaCl can be calculated as the sum of the energies of the following reactions, whose sum corresponds to the dissociation of the crystal into gaseous ions.

$$NaCl(s) \rightarrow Na(s) + \frac{1}{2}Cl_2(g) -\Delta H_f^s(NaCl) = 98.3 \text{ kcal mol}^{-1}$$
 $Na(s) \rightarrow Na(g)$ 
 $S(Na) = 25.6 \text{ kcal mol}^{-1}$ 
 $\frac{1}{2}Cl_2(g) \rightarrow Cl(g)$ 
 $\frac{1}{2}D(Cl_2) = 29.1 \text{ kcal mol}^{-1}$ 
 $Na(g) \rightarrow Na^+(g) + e^-(g)$ 
 $I(Na) = 118.5 \text{ kcal mol}^{-1}$ 
 $U(NaCl) = -\Delta H_f^s(NaCl) + S(Na) + \frac{1}{2}D(Cl_2) + I(Na) - EA(Cl)$ 
 $= 188.1 \text{ kcal mol}^{-1}$ 

Each of the energy terms involved in the summation has been evaluated by a separate physical chemical method; hence we may consider the sum 188.1 kcal mol<sup>-1</sup> as the experimental lattice energy of sodium chloride. (Similar calculations can be carried out for other salts using the heats of formation of solids given in Appendix E, the heats of formation of gaseous atoms in Table 3.12, the c.) It is interesting to compare the experimental value of *U* for NaCl with the theoretical electrostatic value. From the observed interionic distance in crystal-line NaCl (2.814 Å) we calculate.

$$U_e = \frac{1.7476 \times (4.803 \times 10^{-10})^2 \times 1.4394 \times 10^{13}}{2.814 \times 10^{-8}} = 206.2 \text{ kcal mol}^{-1}$$
discrepancy of 18.1 kcal mol discrepancy of 18.1 kcal mol

The discrepancy of 18.1 kcal mol<sup>-1</sup> may be attributed to repulsions between the electron clouds of adjacent ions in the lattice. These repulsions may be approximately accounted for by the use of the relation

$$U = U_e \left( 1 - \frac{\rho}{r} \right) \tag{11.1}$$

where  $\rho$  is a constant, approximately 0.31 Å. In the case of the alkali-metal halides, lattice energies calculated by this equation are accurate to about  $\pm 2$  percent.

The factor for converting ergs per molecule to kilocalories per mole is  $1.4394 \times 10^{13}$ .

Table 11.7 Comparison of experimental and calculated lattice energies†

Salt	$U_{\rm exp},$ kcal mol $^{-1}$	$U_{ m calcd},$ kcal $ m mol^{-1}$	ogo 🛕	
CaF <sub>2</sub>	628.0	615.9	12.1	
Cal <sub>2</sub>	494.2	436.5	57.7	
BaF <sub>2</sub>	561.0	551.8	9.2	
BaI <sub>2</sub>	446.6	423.5	23.1	

† T. E. Brackett and E. B. Brackett, *J. Phys. Chem.*, **69**, 3611 (1965).

In Table 11.7, experimental values of lattice energies and lattice energies calculated from Eq. 10.1 are listed for several alkaline-earth halides. It can be seen that the agreement is fairly good for the fluorides and poor for the iodides (especially for CaI<sub>2</sub>, for which the experimental value is 13.2 percent greater than the calculated<sup>12</sup> value). The reason for the poor agreement is undoubtedly the neglect, in the calculation, of the polarizabilities of the ions. A large ion, such as the iodide ion, is much more easily distorted in an electric field (i.e., more easily polarized) than a small ion, such as the fluoride ion. (Values of some ionic polarizabilities are given in Table 11.8.) The soft iodide ion, when coordinated to the small, doubly charged calcium ion, is strongly polarized, and the interaction of the induced moment with the charge of the calcium ion increases the bonding energy beyond that expected for spherically symmetric ions. The explanation of

<sup>12</sup> T. E. Brackett and E. B. Brackett, *J. Phys. Chem.*, **69**, 3611 (1965).

Table 11.8 Ionic polarizabilities†

lon	$\alpha, \dot{A}^3$	Ion	$\alpha$ , $\dot{A}^3$
Li+ Na+	0.0	CI-	3.00
K+	0.21	Br	4.13
Rb+	0.97	and the adoles	6.18
Cs+	1.47	OH-	2.0
Mg2+	2.36	NO <sub>3</sub> -	3.78
Ca2+	0.18	IO <sub>3</sub> -	6.18
Sr2+	0.7	ClO <sub>4</sub> -	4.16
Ba2+	0.84	SO <sub>4</sub> <sup>2</sup> -	3.81
0H,+	1.63	O2-11	2.8
NH <sub>4</sub> +	1.2	noo S2- oldon	9.0
-	1.7 0.84	HS-	5.3

Polarizabilities calculated from molar refractions (in mainly data of Böttcher from R. J. W. Le Fèvre, Adv. Phys. 98, Chem., 3, 1 (1965).

the enhanced stability of CaI<sub>2</sub> in terms of polarization is essentially equivalent to ascribing a large covalent contribution to the bonding. Thus we see that the estimation of lattice energies by Eq. 11.1 for relatively covalent compounds such as ZnS and InSb would be almost hopeless.

The reader may verify, from data in Appendix E, that  $\Delta H_f^\circ$  for the alkali-meta fluorides decreases from CsF to LiF, whereas  $\Delta H_f^\circ$  for the alkali-metal iodide increases from CsI to LiI. To understand the reason for these different trends, its helpful to consider the relation

$$\Delta H_f^{\circ} = S(M) + \frac{1}{2}D(X_2) + I(M) - EA(X) - U(MX)$$

The only terms on the right side of this equation that change on going from CsX to LiX are S(M), I(M), and U(MX), each of which increases. Inasmuch as the trend in  $\Delta H_f^o$  is determined by the trend in S(M) + I(M) - U(MX), whether or not  $\Delta H_f^o$  increases or decreases, is determined by the relative rates of change of S(M) + I(M) and U(MX). Obviously the trend in  $\Delta H_f^o$  for the fluorides is established by the trend in U(MF), which exceeds the trend in S(M) + I(M), and the trend in  $\Delta H_f^o$  for the iodides is established by the trend in S(M) + I(M), which exceeds the trend in U(MI). The reason for the relatively small trend in U(MI) is the fact that the interionic distance r is principally determined by the larger iodide ion. Hence the energy does not increase markedly. On going from CsF to LiF, the fractional change in r is relatively great; consequently the lattice energy increases markedly.

# APPLICATION OF THE ISOELECTRONIC PRINCIPLE

Compounds of elements which have similar electronegativities and polarizabilities often have the same type of structure if the average number of valence electrons per atom is the same. A large class of isostructural compounds, known zinc blende). These compounds, have diamond-like structures (wurtzite or atom. Examples of such compounds containing group III—group V combinations are BN, AIP, GaAs, and InSb. Group II—group VI combinations are ZnSe ternary compounds, such as CuInTe<sub>2</sub> and ZnGeAs<sub>2</sub>, have diamond-like structures which can be rationalized on this basis

In a binary compound of elements whose electronegativities are quite different, the electropositive (metallic) element generally transfers its electrons to the transferred to give each nonmetal atom a noble-gas configuration, the nonmetal anions may share electrons with each other in the same way as in the corresponding isoelectronic nonmetal. For example, in MgB<sub>2</sub>, the B<sup>-</sup> ions form planar an anionic lattice having the germanium structure. In LiGa and CaGa<sub>2</sub>, the gallium atoms form form anionic puckered layers as in elemental arsenic. (Note, however, that in




Figure 11.22 Schematic two-dimensional analogs of the regular structure of a crystal (a) and the semirandom network of a glass (b).

 $CaC_2$  the carbon atoms form diatomic anions,  $C_2^{2-}$ , isoelectronic with  $N_2$ .) And in LiAs the arsenic atoms form anionic spiral chains as in elemental selenium.

#### GLASSES

A glass is a material, formed by cooling from the normal liquid state, which has undergone no discontinuous change such as crystallization but which has become more rigid through an increase in viscosity. It is commonly assumed that a liquid has become a glass when its shear viscosity exceeds about 10<sup>13</sup> poise. Glasses, like ordinary liquids, have crystallographic order only over a range of one or two interatomic spacings. A crude representation of the difference between a crystal and a corresponding glass is shown in Fig. 11.22. The x-ray diffraction pattern of a glass or liquid shows only one or two diffuse rings—completely different from the sharp rings of powdered crystals. Although the word "glass" is usually associated with silicates, ceramics, and related nonmetallic materials, it has been discovered that very fast cooling (~ 10<sup>6</sup> deg s<sup>-1</sup>) of certain molten alloys can yield metallic materials that are rigid and have liquidlike molecular structures. These metallic glasses have exceptional strength, corrosion resistance, and ease of magnetization 13

## PROBLEMS

II.1 From the heat of formation of ammonium chloride, NH<sub>4</sub>Cl, and estimated lattice energies,  $\frac{1347 \text{ Å}}{\text{A}}$  gas-phase proton affinity of ammonia. (NH<sub>4</sub>Cl has the CsCl structure, with  $r_{\text{N-Cl}} = \frac{1}{3}$ 

<sup>&</sup>lt;sup>13</sup> J. J. Gilman, Science, 208, 856 (1980).

- 11.2 From the heat of formation of BaO and other information, estimate the heat of the reaction  $O(g) + 2e^{-g}(g) \rightarrow O^{2-g}(g)$ . How reliable do you think your estimate is?
- 11.3 Estimate the heat of formation of CaCl(s). Do you think CaCl(s), if prepared, would be a stable compound? Explain.
- 11.4 In the compound MX3, if all the M atoms are equivalent and all the X atoms are equivalent what are the possible coordination numbers for each atom?
- \*11.5 Calculate the minimum radius ratio for trigonal prismatic sixfold coordination, as in MoS<sub>2</sub> (see Fig. 11.12b).
- 11.6 Give the formula of a beryllium silicon nitride (containing equal numbers of Be and Si atoms) that would be expected to have a diamond-like crystal structure.
- \*11.7 The second ionization potential of Mg is approximately twice the first, and the conversion of 0 to O2- is endothermic, whereas the conversion of O to O- is exothermic. Nevertheless we formulate MgO as Mg2+O2- rather than as Mg+O-. Why? What simple experiment would show the latter formulation to be unrealistic?
- 11.8 Some salts can be prepared with either a CsCl structure or an NaCl structure. Which structure would you expect to be preferred at high pressures? Why?
- \*11.9 The cation-to-anion distances for several compounds having the NaCl structure are listed

MgO	2.10 Å	MgS	2.60 Å	MgSe	2.73 Å
MnO	2.24 Å	MnS	2.59 Å	MnSe	2.73 Å

How can you explain these data? Calculate the radius of the S2- ion from these data.

- \*11.10 Imagine a CsCl-type structure from which half of the M atoms are removed in such a way that each X atom has four tetrahedral cation neighbors. What is this well-known MX2 structure?
- \*11.11 Boron nitride, BN, has a graphite-like layer structure in which the layers have an eclipsed alignment, with B and N atoms alternating both in the bonds of each layer and in the direction perpendicular to the layers. Can you rationalize the difference between this structure and that of
- 11.12 What is the C—C bond order in graphite? Is the C—C distance of graphite (1.42 Å) consistent with that of harmone (1.40 Å). with that of benzene (1.40 Å), in which the C—C bond order is 1.5?
- \*11.13 Calculate the fraction of space occupied by spheres packed in (a) the diamond structure and (b) the simple cubic structure (i.e., the NaCl-like structure in which all the atoms are identical). How can structure in which all the atoms are identical. you rationalize the existence of elements with the diamond structure and the nonexistence of elements with the simple cubic structure?
- 11.14 For a compound MX<sub>2</sub> in which all the M atoms are tetrahedrally coordinated and equivalent describe conceivable structures. Which all the M atoms are tetrahedrally coordinated and equivalent describe conceivable structures which are (a) one-dimensional (chain), (b) two-dimensional (layer) and (c) three-dimensional (chain), (b) two-dimensional (layer) and (c) three-dimensional. Give a known example for each structure type.
- 11.15 All the alkaline-earth oxides except BeO have the NaCl structure. How and why does BeO differ? differ?

## TWELVE

**METALS** 

Most of the elements in the periodic table are metals. In this chapter we will show how the physical properties of these elements, and of the compounds formed by the reaction of these elements with one another (alloys), can be systematized in terms of electron configurations. Then we will discuss the very important class of materials known as metallic compounds—i.e., compounds, containing nonmetallic elements, which have the physical properties (especially the electrical properties) of metals. An understanding of the material in the preceding chapter on the solid state is essential to an understanding of the topics in this chapter.

## **BONDING ENERGIES AND STRUCTURES**

Metals have very characteristic physical properties, including the following: (1) high reflectivity (often called metallic luster); (2) high electrical conductivity, which decreases with increasing temperature; (3) high thermal conductivity; and (4) malleability and ductility. Many of a metal's properties, such as chemical reactivity, hardness, strength, melting point, and boiling point, can be correlated with the strength with which the atoms of the metal are held together. This bonding strength is most simply measured by the energy required to break up the metal into gaseous atoms, i.e., the atomization energy. As one might expect, metals with low atomization energies generally are soft and have low melting points, and metals with high atomization energies generally are hard and have high melting points. In Table 12.1 we have listed the heats of atomization and melting points of the metals in a periodic-table arrangement. In the case of the

Table 12.1 Heats of atomization† (in kilocalories per mole at 25°C) and melting points (in degrees Celsius) of the metals

Li 38.1	Be 77.5					J. De y	A LIVER	1000	MUNICIPA	1 10	- 100 000
180°	1283°										
Na 25.6 97.5°	Mg 35.0 650°	Al 78.7 660°									
X 21.3 63.4°	Ca 42.6 850°	Sc 90.3 1539°		V 123 1730°	Cr 95 1900°	Mn 67.7 1247°	99.3	Co 101.7 1493°	Ni 102.9 1455°		Zn 31.2 420°
Rb 19.3 38.8°	Sr 39.5 770°		Zr 144.5 1852°	Nb 175.2 2487°	Mo 157.6 2610°	Tc 158	Ru 155.8	Rh	Pd 90.0	Ag 68.1	Cd 26.7
Cs 18.2 28.7°	Ba 43.5 704°		Hf 148.5 2300°	Ta 187 2997°	W 205.5 3380°	Re 185.4 3150°	Os 188.6	Ir 160.3 2454°	Pt 134.9	Δ11	Hg‡ 15.3

<sup>†</sup> L. Brewer, Lawrence Berkeley Laboratory Report LBL-3720 Rev., May 4, 1977.

nontransition metals (groups I to III), the atomization energies increase from left to right. This trend continues for two or three positions into the transition series, in periods 3, 4, and 5. The trend is strong evidence that metallic bonding energy is directly related to the number of valence electrons. Sodium, with a single 3s electron, can form only one electron-pair bond per atom. This bond is equally distributed in fractional bonds to the neighboring atoms in the lattice, and we can crudely represent the metal as a resonance hybrid of structures such as the

The magnesium atom, with the 3s<sup>2</sup> electron configuration, can be "prepared" for covalent bonding by promotion to the 3s3p configuration, with two unpaired electrons. Thus a magnesium atom can distribute two bonds to its neighbors in the lattice. The energetics of the situation may be illustrated as follows:

Mg(g) 
$$(3s3p)$$

Mg(g)  $(3s^2)$ 
 $-98 \text{ kcal mol}^{-1}$ 
 $(49 \text{ kcal mol}^{-1} \text{ per bond})$ 

Mg(s) (metallic state)

The aluminum atom, with the  $3s^23p$  ground state, can be promoted to the  $3s3p^2$  state, and it can form three bonds per atom in the metal lattice. Further increase in the number of bonds per atom occurs as we move from a group III metal such as scandium into the transition-metal series, where d electrons are involved in the bonding. However, because of the pairing of d electrons and the increased promotion energies, the number of bonds per atom eventually drops off.

We may now state the first rule of Engel and Brewer. The bonding energy of a metal or alloy depends on the average number of unpaired electrons per atom available for bonding. Low-lying excited electron configurations with more unpaired electrons than the ground-state configuration may be important if the bonding energy from the additional electron-pair bonds compensates for the

promotion energy.

The second rule of Engel and Brewer is concerned with the crystal structures of metals: The crystal structure depends on the average number of s and p orbitals per atom involved in bonding, i.e., upon the average number of unpaired s and p electrons in the atoms in their "prepared-for-bonding" state. When the number of bonding s, p electrons is less than or equal to 1.5, the body-centered cubic (bcc) structure is observed. When the number of bonding s, p electrons is between 1.7 and 2.1, the hexagonal close-packed (hcp) structure is observed. When the number of s, p electrons is in the range 2.5 to 3.2, the cubic close-packed (ccp) structure is observed. Of course, when the number of s, p electrons is near 4, a nonmetallic diamond-like structure is found.

A remarkable feature of the second rule is that it relates metal structure only to the number of unpaired s and p electrons in the prepared-for-bonding state. In fact one can restate the second rule in terms of the number of p electrons: 1, 2, 3, and 4 s, p electrons are equivalent to 0, 1, 2, and 3 p electrons. In either case, although the number of unpaired d electrons is relevant with respect to atomization energy, it is irrelevant with respect to structure. The dependence of structure on the number of p electrons probably follows from the fact that, compared to s orbitals and d orbitals, p orbitals are highly directional in character. However, there does not yet appear to be a simple explanation for the particular structures observed.

In Table 12.2 we have listed the observed crystal structures of the metals. As predicted by the second rule, the alkali metals all have the bcc structure. However, of the alkaline-earth metals, only beryllium and magnesium rigorously obey the rule by having only the hcp structure. The bcc structure shown by calcium, strontium, and barium can be explained by the general rule that the relative importance of d orbitals increases with atomic number. Thus, in these cases, excitation to an (n-1)dns state is energetically favored over excitation to an nsnp state. Unfortunately, there does not seem to be any simple explanation for the ccp structures shown by calcium and strontium. The bcc and hcp structures shown by scandium, yttrium, and lanthanum (in contrast to the normal

L. Brewer, Science, 161, 115 (1968); in "Electronic Structure and Alloy Chemistry of the Transition Elements," P. A. Beck, ed., pp. 221–235, Interscience, New York, 1963.

Table 12.2 Crystal structures of metals†

The structures are listed in order of temperature stability, with the room-temperature structure lowest.

Li bcc	Be hcp					curs as	o arou	oom-tem	rod to a	elmun	od/ m
Na bcc	Mg hcp	Al ccp									
K bcc	Ca bcc ccp	Sc bcc hcp	Ti bcc hcp	V bcc	Cr bcc	Mn bcc ccp β	Fe bcc ccp bcc	Co ccp hcp	Ni ccp	Cu	Zn hcp
Rb bcc	Sr bcc hcp	Y bcc hcp	Zr bcc hcp	Nb bcc	Mo bcc	Tc hcp	Ru hcp	Rh	Pd ccp	Ag ccp	Cd hcp
Cs bcc	Ba bcc	La bcc ccp hcp	Hf bcc hcp	Ta bcc	W bcc	Re hcp	Os hcp	Ir ccp	Pt ccp	Au ccp	

<sup>†</sup> L. Brewer, Science, 161, 115 (1968).

ccp structure of aluminum) can be explained in terms of d-orbital participation, as in the cases of calcium, strontium, and barium. In fact, the bcc structure shown by the first four members of each transition series can be explained by assuming that each atom is prepared for bonding by achieving a  $d^{v-1}s$  valence electron configuration (where v is the number of valence electrons).

As we move immediately to the right of chromium, molybdenum, and tungsten, the added electrons are generally put into p orbitals to maintain the addition of electrons, d electrons are paired and eventually the bonding is due only to s, p orbitals. In copper, silver, and gold, the prepared electronic state is reach zinc and cadmium, the d electrons are held too tightly to be easily prostructure and two bonds per atom. When we moted, and the prepared electronic state is  $d^{10}sp$ , corresponding to the hcp atomization energies are qualitatively in accord with these bonding descriptions.

The Engel-Brewer rules can be readily applied to alloys.<sup>2</sup> The metals of the first half of a transition series, which have fewer than five d electrons in their configuration is achieved. This fact and the second rule lead to the conclusion valence electrons is less than 6.5, corresponding to the prepared electron configuration  $d^5s^1p^{0.5}$ . On this basis we predict the maximum solubilities of metals such

<sup>&</sup>lt;sup>2</sup> L. Brewer, Science, **161**, 115 (1968); Acta Metal., **15**, 553 (1967); L. Brewer and P. R. Wengert, Metal. Trans., **4**, 83 (1973).

Table 12.3 Maximum solubilities (in mole percentages) of some metals in the bcc phase of tungsten mouse in supplied that the supplied of the supplied to the s

Metal	Predicted solubility	Observed solubility
Re	50	35-43
)s	25	10-20
lr .	16.7	10-15
t rev isi	12.5	4-10

as Re, Os, Ir, and Pt in the bcc phase of tungsten to be that mole fraction corresponding to 6.5 valence electrons per atom. The predicted and observed mole fractions are given in Table 12.3. Although the agreement is far from perfect, it shows that qualitative and even semiquantitative predictions can be made by using the Engel-Brewer rules.

Another, related, application of the rules is the prediction of the effect of small additions of alloying metals upon the relative stability of two crystal structures.3 From Table 12.2 we see that Ti, Zr, and Hf can have either a bcc structure (corresponding to configuration  $d^3s$ ) or an hcp structure (corresponding to configuration  $d^2sp$ ). Addition of d-electron-rich metals to the right of these metals favors d-orbital bonding and thus stabilizes the bcc structure. The addition of metals containing no d electrons stabilizes the hcp structure because that structure will suffer less by a reduction in the amount of d-orbital bonding. All the experimental data available confirm these predictions of the effects of alloying on the relative stabilities of the bcc and hcp structures.

Brewer has shown that the alloying of d-electron-poor metals such as Zr, Nb, Ta, and Hf with d-electron-rich metals such as Re, Ru, Rh, Ir, Pt, and Au yields extremely stable alloys.<sup>3</sup> For example, if platinum is heated with ZrC (one of the most stable carbides known), the alloy ZrPt<sub>3</sub> and graphite are formed.

$$ZrC + 3Pt \xrightarrow{\Delta} ZrPt_3 + C$$

These interactions of "electron-deficient" and "electron-rich" transition metals may be considered an extension of Lewis acid-base reactions.

# Hume-Rothery Compounds<sup>4</sup>

The importance of the average number of s, p valence electrons in the correlation of allows. of alloy composition with structure was recognized long ago by Hume-Rothery. The phase diagrams of a large class of binary alloys, e.g., those of copper and silver

<sup>&</sup>lt;sup>3</sup> Brewer and Wengert, op. cit.

<sup>&#</sup>x27;H. J. Emeléus and J. S. Anderson, "Modern Aspects of Inorganic Chemistry," 3d ed., pp. 507-510, Van Nostrand, New York, 1960.

with the zinc family of metals or the aluminum family of metals, show a wide variety of phases. Three of these phases, called Hume-Rothery compounds, have structures which may be associated with certain electron/atom ratios. The first phase, having the  $\beta$ -brass structure (a bcc-type structure), corresponds to an s, p electron/atom ratio of 3:2. Examples of such phases are CuZn, AgCd, Cu<sub>3</sub>Al, Cu<sub>3</sub>Sn, and NiAl. (In these and the following examples, Cu and Ag must be considered as  $d^{10}s$  metals, and Ni must be considered a  $d^{10}$  metal.) The second phase, having the  $\gamma$ -brass structure (a complex cubic structure), corresponds to an s, p electron/atom ratio of 21:13. Examples are Cu<sub>5</sub>Zn<sub>8</sub>, Ag<sub>5</sub>Hg<sub>8</sub>, Cu<sub>9</sub>Al<sub>4</sub>, Cu<sub>31</sub>Sn<sub>8</sub>, and Ni<sub>5</sub>Zn<sub>21</sub>. The third phase, having the  $\varepsilon$ -brass structure (an hcp-type structure), corresponds to an s, p electron/atom ratio of 7:4. Examples are CuZn<sub>3</sub>, AgCd<sub>3</sub>, and Cu<sub>3</sub>Sn.

It can be seen that the  $\beta$ -brass type of alloys and the  $\varepsilon$ -brass type of alloys are in accord with the Engel-Brewer rule relating s, p electrons to structure. However, the reader may question the apparently ad hoc assignment of one s, p electron to Cu, Ag, and Au, and no s, p electrons to transition elements such as Ni, Pt, Co, and Fe. Each of these metals, in the pure state, has a prepared-for-bonding electron configuration of  $d^5sp^2$ ,  $d^6sp^2$ ,  $d^7sp^2$ , or  $d^8sp^2$ , corresponding to the ccp structure. However, when any one of these metals is diluted sufficiently with a metal such as zinc (with prepared-for-bonding configuration  $d^{10}sp$ ), the number of d orbitals available for bonding is reduced so much that there is no advantage in promotion




Figure 12.1 The Cu – Zn phase diagram. (From L. V. Azároff, "Introduction to Solids," pp. 294–297. McGraw-Hill, New York, 1960.)

to these excited states, and the metals then have, in effect, prepared-for-bonding electron configurations with more of the d orbitals filled. The limiting electron configurations for such metals are  $d^8$ ,  $d^9$ ,  $d^{10}$ , and  $d^{10}s$ .

To show the typical complexity of the phase diagrams of such systems, the Cu-Zn phase diagram is given in Fig. 12.1. As can be seen from this diagram,

there are other phases besides the Hume-Rothery phases in this system.

#### BAND THEORY5

# Electrical Conductivity

When two lithium atoms are brought together, the 2s atomic orbital levels are split into two levels, corresponding to the 2s\sigma bonding molecular orbital (MO) and the 250\* antibonding MO, as shown in Fig. 12.2. If six lithium atoms were brought together to form a cluster, the atomic orbitals would be split into six MOs, ranging in character from completely bonding to completely antibonding, as shown in Fig. 12.3. When a very large number (say Avogadro's number) of lithium atoms are brought together to form a regular array, as in the normal bcc metal, the resulting energy levels are so closely spaced that they form an essentially continuous energy band, as shown in Fig. 12.4. The bottom of the band is a bonding level and the composed of as level, and the top of the band is an antibonding level. The band is composed of as many levels as there are atoms, and each level can hold two electrons of opposite spin. Inasmuch as each lithium atom furnishes one valence electron, the band is exactly half-filled. Another way of depicting energy bands is in the form of a density of state. density-of-states diagram, as shown in Fig. 12.5. Here the number of electrons that can be conthat can be accommodated in a narrow range of energy is plotted as a function of energy. Cross-hatching is used to indicate the filled portion of a band.

The individual levels of a band correspond to MOs which extend throughout

<sup>&</sup>lt;sup>5</sup> C. A. Wert and R. M. Thomson, "Physics of Solids," McGraw-Hill, New York, 1964; C. Kittel, "Introduction to Solid State Physics," 5th ed., Wiley, New York, 1976.




Figure 12.2 Interaction of the 2s orbilithium atoms. The dashed line inditernuclear distance in the Li<sub>2</sub> molecular distance di




Figure 12.3 The molecular orbitals resulting from interaction of the 2s orbitals of six lithium atoms. The relative positions of the six levels depend on the arrangement of the atoms in the cluster.




Figure 12.4 The valence band in lithium metal shown as a function of the internuclear distance. The dashed line indicates the equilibrium internuclear distance in the actual metal.




Figure 12.5 Density of states as a function of energy for the valence band of a metal such as lithium. The vertical line, which marks the boundary between the filled and empty parts of the band at 0 K, corresponds to the Fermi energy. At a finite temperature, this boundary is fuzzy, as shown.

the metal lattice. The valence electrons can be thought of as moving throughout electrons moving in one direction as in another. For example, in a horizontal to the number of electrons moving to the left is equal double density-of-states diagram of Fig. 12.6a, in which points above the horizontal axis refer to left-moving electrons, and points below the horizontal axis refer to





Figure 12.6 Density-of-states diagrams for electrons moving to the left (upper curves) and to the right (lower curves). (a) The diagram for a metal wire in the absence of an electric field. (b) The diagram for a metal wire subjected to an electric field; + at the left end, and - at the right end.

right-moving electrons. If we apply an electric field to the wire, so that the left side is positively charged relative to the right side, the energy of the left-moving electrons is reduced and the energy of the right-moving electrons is increased, as shown by the diagram of Fig. 12.6b, in which the two bands are shifted relative to one another. The electrons fill up the lowest available energy levels, resulting in more electrons moving to the left than to the right and a net electric current.

When the temperature of a metal is increased, lattice irregularities become more pronounced because of increased atomic vibrations. These irregularities scatter the electrons, thus reducing the electrical conductivity. This effect of temperature on conductivity may also be explained in terms of MO theory. In a highly regular metal, the electron orbitals extend for great distances through the lattice, and the electrons are highly mobile because of the delocalization. The introduction of irregularities increases the amount of localized bonding and hence decreases the conductivity.

The electrical conductivity of a filled band is zero because, in such a band, the number of electrons moving in one direction must always be equal to the number moving in the opposite direction. Even though application of an electric field can shift the relative positions of the left-moving and right-moving bands on the energy scale, because each band is full it is impossible for electrons to spill out of the higher-energy band into the lower-energy band. For this reason one might expect an alkaline-earth metal such as calcium, which has a filled valence s shell in the free atomic state, to be a nonconductor. However, at the interatomic distances found in this metal, the valence s and p bands overlap, as shown in Fig. 12.7. Consequently the density-of-states diagram is as shown in Fig. 12.8, and the metal exhibits typical metallic electrical conductivity.

An "experimental" density-of-states diagram for a metal can be obtained by photoelectron spectroscopy. The metal is prepared with a clean surface in an ultrahigh vacuum (<10<sup>-9</sup> torr) and is irradiated with monochromatic photons.






Figure 12.7 The valence band of an alkaline-earth metal such as calcium. The dashed line indicates the equilibrium internuclear distance in the actual metal

A plot of the number of emitted electrons per absorbed photon versus kinetic energy has approximately the shape of the density-of-states diagram, assuming that the yield of electrons is proportional to the electron population. Figure 12.9 shows the observed photoemission energy distributions for copper for five different photon energies. The shapes of the curves differ because the relative cross sections of the electrons in the band are a function of photon energy and electron

About two dozen metallic elements, and many alloys, have been shown to exhibit superconductivity. That is, the electrical resistances become zero when the metals are cooled below characteristic transition temperatures (e.g., 1.19 K for Al, 5.30 K for V). The theory of superconductivity is exceedingly complex, and a discussion will not be attempted here. Suffice it to say that the phenomenon is

<sup>6</sup> D. E. Eastman, in "Electron Spectroscopy," D. A. Shirley, ed., p. 487, North-Holland, Amstern 1972 dam, 1972




Figure 12.8 Density of states as a function of energy for an alkalineearth metal such as calcium.




Figure 12.9 Photoemission energy distributions for Cu. (Reproduced with permission from D. E. Eastman, in the Land Amsterdam, 1972.) Eastman, in "Electron Spectroscopy," D. A. Shirley, ed., p. 487, North-Holland, Amsterdam, 1972.)

caused by a second-order interaction between electrons and the vibrating lattice, involving the condition of involving pairs of electrons. The theory is discussed in several recent texts.<sup>7-9</sup>

The density-of states diagram for an insulator looks like that in Fig. 12.10, in which the high-energy empty band corresponds to nonbonding or antibonding

R. Dalven, "Introduction to Applied Solid State Physics," Plenum, New York, 1980.

<sup>7</sup> Kittel, op. cit.

<sup>&</sup>lt;sup>8</sup>L. Solymar and D. Walsh, "Lectures on the Electrical Properties of Materials," 2d ed., Oxford liversity Den. University Press, London, 1979.




Figure 12.10 Density of states as a function of energy for an insulator.

Sometimes it is possible to convert such a material into a metallic conductor by the application of high pressure (for example, 100 kbars). From Fig. 12.11 it can be seen that, if the interatomic distance is sufficiently reduced by increased pressure, the bands will overlap, yielding a density-of-states diagram similar to that of calcium (Fig. 12.8). In Table 12.4 the electrical resistivities of the elements of the first long row of the periodic table are listed. The metals with partially filled d bands generally have higher resistivities than other metals such as K. Ca. Cu. and Zn. This greater resistivity is probably due to the fact that the d orbitals are somewhat "inner" orbitals and do not overlap as effectively as s and p orbitals. Consequently the valence electrons are relatively "localized" in narrow bands and do not hop from one atom to another as rapidly as they would if they occupied broader s or p bands. The very high resistivities of Ge and Se are expected in view of the nonresonating covalent structures of these elements. However, the low resistivity of As is remarkable in view of its structure (Fig. 11.11a). Apparently the bonding valence band and a higher antibonding band are so broad that they overlap and permit metallic conductivity.




Figure 12.11 The valence bands of an insulator which can be converted into a metal by high pressure.

Table 12.4 Electrical resistivities at 22°C† of the elements of the first long row of the periodic table resistivities at 22°C† of the elements of the first long row of

Element	Resistivity, $\mu\Omega$ cm	Element	Resistivity $\mu\Omega$ cm
Kin of ovincion al	7.19	Co	5.00
Ca	3.35	Ni	5.80
Sc Ti	46.8	Cu Cu	7.04 1.70
	43.1 2 Dongue at	Zn 195Wied noite	5.92
Coregase. Wasy	19.9	Ga morrel a lo	14.8
nal energy of (r)	12.9 W B 310 E	Ge off sedown	~108
Mn verene sen	srioxo 136 elemente	As	29
Fe all y stranger	9.8	Se	~1011

<sup>†</sup> D. E. Gray, ed., "American Institute of Physics Handbook," 3d ed., McGraw-Hill, New York, 1972.

# rentle (bond and my level believed in the content of the content o

Some substances have permanent magnetic moments even in the absence of applied magnetic fields and are called "ferromagnetic." Only a few elements are ferromagnetic: Fe, Co, Ni, and several lanthanides. A density-of-states diagram for the 3d and 4s shells of Fe, Co, or Ni would look something like that shown in Fig. 12.12. Here the upper diagram corresponds to electrons with their spins oriented one way (say "up"), and the lower diagram corresponds to electrons with




Figure 12.12 Density-of-states diagrams for a ferromagnetic transition metal. The upper bands correspond to electrons with spins "up"; the lower bands correspond to electrons with spins "down." The points marked Cu indicate the Fermi energy of copper, for which there is no relative displacement of the bands.

their spins oriented the opposite way (say "down"). The remarkable thing about these metals is that the two bands are spontaneously displaced so that they are unequally filled. Thus more electrons are aligned one way than in the opposite way, and the metal has a permanent magnetic moment. The thermal energy of the crystal tends to misalign the electronic spins and to bring the density-of-states bands together. Obviously energy is required to displace the bands relative to one another as shown in Fig. 12.12. It is believed that the source of this energy is the exchange interaction between neighboring aligned spins. (See Chap. 1.) Raising the temperature of a ferromagnet causes the magnetization to decrease. When the temperature reaches the Curie temperature, at which the thermal energy of the crystal tending to bring the bands together equals the exchange energy, the magnetization is zero. At temperatures above the Curie temperature (1043, 1404, and 631 K for Fe, Co, and Ni, respectively) the metal is no longer ferromagnetic.

Metals which are ferromagnetic have high densities of states at the Fermi energy (i.e., the energy corresponding to the highest filled level in the band). Thus many electrons change their spin direction (and yield exchange energy) for a small displacement of the bands. For ordinary metals, the density of states at the Fermi energy is lower and the energy required to displace the bands is not compensated by the exchange energy. For example, in copper metal the levels are filled to a point where the density of states is very low (see Fig. 12.12); consequently this metal is not ferromagnetic. The reason for the high density of states in Fe, Co, and Ni is the fact that the 3d atomic orbitals are somewhat interior orbitals which do not overlap strongly with those on other atoms in the lattice; thus the 3d bands for these metals are narrow.

Magnetic data for alloys of the metals in the vicinity of Fe, Co, and Ni in the periodic table show that the number of aligned spins per atom,  $N_{\rm B}$ , is a continuous function of the average number of electrons per atom. In Fig. 12.13 it can be seen that the maximum number of aligned spins per atom is 2.4, a value achieved by an Fe-Co alloy. For some unknown reason, when the constituent metals of the alloy differ in atomic number by more than two units, the points deviate markedly from the curve.

On an ultramicroscopic scale, all the electronic spins of a ferromagnetic material are aligned in the same direction. However, in different regions called "domains" (with linear dimensions in the range  $\sim 10^{-4}$  to  $\sim 10^{-1}$  cm), the directions of magnetization can be different. Thus the net magnetic moment of a macroscopic ferromagnetic crystal can be near zero because of cancelation of the moments of the individual magnetic domains. A pattern of domains with approximately zero resultant magnetic moment is shown in Fig. 12.14. The net magnetic moment of a sample can increase under the influence of an applied magnetic field by two independent processes: (1) In weak applied fields, the volumes of domains favorably oriented in the field can increase at the expense of adjacent domains unfavorably oriented. (2) In strong fields, the direction of

<sup>10</sup> Wert and Thomson, loc. cit.




Figure 12.13 The number of aligned spins per atom as a function of the average number of electrons per atom. (From C. A. Wert and R. M. Thomson, "Physics of Solids," McGraw-Hill, New York, 1964.)

magnetization within a domain can rotate toward alignment with the field. The first process involves the shifting of the boundaries between domains. The change in spin direction does not occur suddenly across a sharp boundary, but rather gradually over a boundary hundreds of atoms thick, as shown schematically in Fig. 12.15. Because the shifting of domain boundaries is not a completely reversible process, the magnetization of a ferromagnetic material shows hysteresis, as seen in the magnetization curve of Fig. 12.16. The coercive force is the field  $H_c$  required to reduce the induction to zero. It may range from 20,000 gauss




Figure 12.14 A ferromagnetic domain pattern on a single crystal face of nickel. (Adapted from Kittel, "Introduction to Solid State Physics," 5th ed., p. 485, Wiley, New York, 1976.)




Figure 12.15 Schematic diagram of the boundary between two magnetic domains. Actual boundaries are hundreds of atoms thick. By the gradual turning of the spins within the boundary, the boundary can move in response to an applied magnetic field.




Figure 12.16 A magnetic hysteresis loop. The arrows indicate the direction of the change in magnetic field. The coercive force,  $H_c$ , is the field required to bring the induction to zero; the remanence,  $B_r$ , is the value of the magnetic induction at zero applied field.

in a high-stability Fe-Pt magnet to 0.004 gauss in a Supermalloy pulse transformer

#### METALLIC COMPOUNDS

There are numerous binary compounds of transition metals and relatively electronegative elements which show metallic character, at least by virtue of their high electrical conductivity with a negative temperature coefficient. These include some very hard, high-melting, and chemically inert borides, carbides, nitrides, oxides, and sulfides. These compounds may be looked upon as three-dimen-

Table 12.5 Properties of some metallic carbides and nitrides†

Compound	Density, g cm <sup>-3</sup>	Melting point, °C	Electrical resistivity, $\mu\Omega$ cm	Superconducting below, K
TiC	4.93	2940	68	1.15
VC	5.36	2684	60	<1.2
Cr <sub>3</sub> C <sub>2</sub>	6.68	1810	Tybe 75 add one de	M/W <1.2 Um sitting
ZrC	6.46	3420	42 mortage	
NbC	7.78	3613	35	11.1
Mo <sub>2</sub> C	9.18	2520	71	2.78
MoC	9.15	2600		2.70
HfC —	12.3	3820	37	<1.2
TaC	14.48	3825	25	9.7
WC	15.7	2720	19	1.28
ThC	10.64	2625	25	1.20
ThC <sub>2</sub>	8.65	2655	30	
UC	13.63	2650	40	
UC <sub>2</sub>	11.86	~2500	90	
ΓiN	5.43	2950	25	4.8
VN	6.10	2350	85	7.5
CrN	6.14	1080d	640	None
ZrN	abin 7.3	2980	21	9
NbN	8.47	2630d	78	15.2
Mo <sub>2</sub> N	9.46	790d		5.0
HfN	14.0	3330	33	or to Hamming on
-TaN	14.3	2950d	128	mon 1.8 The same
-TaN	15.6	2950d	amote muribas vel	17.8
ThN	11.9	2820	20	
JN	14.4	2800	176	

<sup>† &</sup>quot;Kirk-Othmer Encyclopedia of Chemical Technology," 3d ed., vol. 4, pp. 490-505, Wiley-Interscience, New York; R. Kieffer and P. Ettmayer, *High Temp. High Pressures*, 6, 253 (1974).

sional cationic metal lattices, held together by metallic bonding, with interspersed anions. In most cases the compounds are markedly variable in composition. For example, in the case of niobium nitride, four different phases have been identified, having N/Nb ratios of 0.4 to 0.5, 0.8 to 0.9, 0.95, and 1.00. One of the highest-melting substances known is the reaction product of a 4:1 mixture of TaC and ZrC, which melts at 4215 K. Some metallic compounds become superconducting at temperatures well above the highest superconducting temperature for a pure metal (9.46 K for Nb). For example, NbC, TaN, and Nb<sub>3</sub>Ge have transition temperatures of 11.1, 15.2, and 22.3 K, respectively. The properties of some metallic carbides and nitrides are listed in Table 12.5.

Most metallic carbides are prepared by the powder metallurgical reaction between the metal or metal oxide and carbon. <sup>12</sup> An intimate pulverized mixture

<sup>11</sup> Emeléus and Anderson, loc. cit.

<sup>&</sup>lt;sup>12</sup> S. Windisch and H. Nowotny, in "Preparative Methods in Solid State Chemistry," P. Hagenmuller, ed., pp. 533-562, Academic, New York, 1972.

of the reactants is heated in an induction or resistance furnace, usually to a temperature of at least 1500°C. For example, Cr<sub>3</sub>C<sub>2</sub> can be prepared at 1800°C by the following reactions:

$$3Cr + 2C \longrightarrow Cr_3C_2$$

$$3Cr_2O_3 + 13C \longrightarrow 2Cr_3C_2 + 9CO$$

Metallic nitrides which are thermodynamically stable with respect to the elements can be prepared by reaction of the metals with nitrogen or ammonia. For example,

$$Ti + \frac{1}{2}N_2 \xrightarrow{1200^{\circ}C} TiN$$

$$4Fe + 2NH_3 \xrightarrow{500^{\circ}C} 2Fe_2N + 3H_2$$

Some nitrides can be prepared by reaction of a metal halide with ammonia, thus<sup>13,14</sup>

$$CrCl_3 + 4NH_3 \xrightarrow{800^{\circ}C} CrN + 3NH_4Cl$$

The tungsten bronzes are a group of nonstoichiometric bronze-like compounds of general formula  $M_xWO_3$ , where 0 < x < 1 and where M can be an alkali metal, barium, lead, thallium, copper, silver, or a lanthanide. Sodium tungsten bronzes,  $Na_xWO_3$  (0.32 < x < 0.93), can be made by the high-temperature reduction of sodium tungstate,  $Na_2WO_4$ , with a wide variety of reducing agents. The structure may be considered to be a  $WO_3$  network in which holes are randomly occupied by sodium atoms. Each sodium atom furnishes an electron to a band formed by overlap of the tungsten 5d orbitals with the oxygen atomic orbitals. Because this band is only partially filled, the compound exhibits metallic conductivity. Some of the properties of sodium tungsten bronzes are listed in Table 12.6.

It is possible to prepare materials of the type  $WO_{3-x}F_x$  by replacing some of the oxygen atoms of  $WO_3$  by fluorine atoms. <sup>16</sup> The materials for which 0.17 < x < 0.66 are analogous to tungsten bronzes; the extra electrons introduced by the fluorine atoms partially fill the valence band and cause the materials to be good conductors.

# "One-Dimensional" Metallic Compounds

Many compounds are known which contain extended chains of metal atoms or chains of metal clusters. These structural features are often found in transition-metal halides or chalcogenides with low nonmetal/metal ratios.<sup>17</sup> Thus

<sup>&</sup>lt;sup>13</sup> G. Brauer, "Handbook of Preparative Inorganic Chemistry," vol. 2, Academic, New York, 1965.

<sup>&</sup>lt;sup>14</sup> R. Kieffer and P. Ettmayer, *High Temp. High Pressures.* **6**, 253 (1974). <sup>15</sup> E. Banks and A. Wold, *Prep. Inorg. React.* **4**, 237 (1968).

<sup>&</sup>lt;sup>16</sup> A. W. Sleight, *Inorg. Chem.*, **8**, 1764 (1969); C. E. Derrington et al., *Inorg. Chem.*, **17**, 977 (1978).

<sup>&</sup>lt;sup>17</sup> For a review on halides of this type, see J. D. Corbett, Acc. Chem. Res., 14, 239 (1981).

Table 12.6 Properties of Na, WO, crystals†

X	Color	Phase	Lattice parameter,‡ $a_0$ , Å
0.37	Blue	Tetragonal	SHAR HAR
0.40	Blue	Tetragonal	
0.44	Blue	Cubic	3.821
0.56	Violet	Cubic	3.831
0.58	Violet	Cubic	3.832
0.65	Red	Cubic	3.838
0.70	Orange	Cubic	3.842
0.81	Yellow	Cubic	3.851

† E. Banks and A. Wold, Prep. Inorg. React., 4, 237 (1968).

‡ The lattice parameter of a cubic crystal is the "repeat distance,"

i.e., the side dimension of the unit cell.

NaMo<sub>4</sub>O<sub>6</sub>, formed by heating a mixture of Na<sub>2</sub>MoO<sub>4</sub>, MoO<sub>2</sub>, and Mo,<sup>18</sup> contains anionic chains of the repeating unit Mo<sub>4</sub>O<sub>6</sub><sup>-</sup>. These chains contain Mo<sub>6</sub> octahedra sharing opposite edges, with oxygen atoms forming bridges between molybdenum atoms in the same and adjacent chains, as shown in Fig. 12.17. Similar chains of octahedral metal clusters exist in the compounds  $Sc_5Cl_8$ , which is better represented by the formula  $(ScCl_2^+)$   $(Sc_4Cl_6^-)$ , and  $Sc_5Cl_3^{-18a}$ 

When liquid mercury is treated with a solution of AsF<sub>5</sub> in SO<sub>2</sub>, golden crystals of Hg<sub>3</sub>AsF<sub>6</sub> are formed.<sup>19</sup> This compound contains infinite chains of mercury atoms in a lattice of AsF<sub>6</sub><sup>-</sup> ions, as shown in Fig. 12.18. The Hg—Hg distance

18a See footnote 17, page 308.

<sup>&</sup>lt;sup>19</sup> D. Brown, B. D. Cutforth, C. G. Davies, R. J. Gillespie, P. R. Ireland, and J. E. Vekris, Can. J. Chem., 52, 791 (1974).




Figure 12.17 View of one cluster chain in NaMo<sub>4</sub>O<sub>6</sub>. [Reproduced with permission from C. C. Torardi and R. McCarley, J. Am Chem. Soc., 101, 3963 (1979 Copyright 1979 American Chaical Society.]

<sup>&</sup>lt;sup>18</sup> C. C. Torardi and R. E. McCarley, J. Am. Chem. Soc., 101, 3963 (1979).




Figure 12.18 A view of the Hg<sub>3</sub>AsF<sub>6</sub> structure, showing chains of Hg atoms (circles) running through the lattice of AsF<sub>6</sub> ions (octahedra). [Reproduced from D. Brown, B. D. Cutforth, C. G. Davis, R. J. Gillespie, P. R. Ireland, and J. E. Vekris, Can. J. Chem., 52, 791 (1974).]

and the spacing of the  $AsF_6^-$  ions are not commensurate with the formula  $Hg_3AsF_6$ , but rather with the composition  $Hg_{2.86}AsF_6$ . This anomaly can be explained either by assuming that the compound is indeed nonstoichiometric (with an average oxidation state of mercury of 1/2.86 = 0.35) or by assuming that the compound is stoichiometric ( $Hg_3AsF_6$ ), with vacancies randomly distributed among 4.7 percent of the  $AsF_6^-$  sites in the lattice.<sup>20</sup>

An interesting class of one-dimensional conducting solids can be prepared by partial oxidation of the tetracyanoplatinate complex,  $Pt(CN)_4^{2-}$ , either electrolytically or with chlorine or bromine.<sup>21</sup> These compounds contain square planar  $Pt(CN)_4^{n-}$  ions stacked such that the platinum  $5d_{2^2}$  orbitals overlap, as shown in Fig. 12.19. The formulas and properties of some of these compounds are given in Table 12.7. The unoxidized platinum(II) compound,  $K_2Pt(CN)_4 \cdot 3H_2O$ , is a nonconductor of electricity. Its platinum oxidation state is integral (+2), and the

Table 12.7 Properties of some tetracyanoplatinates†

Complex	Pt oxidation state	Pt—Pt distance, Å	Color	Conductivity Ω <sup>-1</sup> cm <sup>-1</sup>
Pt metal $K_2Pt(CN)_4 \cdot 3H_2O$ $K_2Pt(CN)_4Br_{0,3} \cdot 3H_2O$ $K_2Pt(CN)_4Cl_{0,32} \cdot 3H_2O$ $K_{1,75}Pt(CN)_4 \cdot 1.5H_2O$ $Cs_2Pt(CN)_4(HF_2)_{0,39}$	0 +2 +2.3 +2.32 +2.25 +2.39	2.775 3.50 2.89 2.88 2.96 2.83	Metallic White Bronze Bronze Bronze Gold	9.4 × 10 <sup>4</sup> 5 × 10 <sup>-7</sup> 4-830 ~ 200 ~80

<sup>†</sup> J. S. Miller and A. J. Epstein, *Prog. Inorg. Chem.*, **20**, 1 (1976); G. D. Stucky, A. J. Schultz, and J. M. Williams, *Ann. Rev. Mater. Sci.*, **7**, 301 (1977).

<sup>&</sup>lt;sup>20</sup> A. J. Schultz, J. M. Williams, N. D. Miro, A. G. MacDiarmid, and A. J. Heeger, *Inorg. Chem.*, 646 (1978).

<sup>&</sup>lt;sup>21</sup> J. S. Miller and A. J. Epstein, *Prog. Inorg. Chem.*, 20, 1 (1976).

$$N \equiv C$$
 $N \equiv C$ 
 $N$ 

Figure 12.19 The stacking of planar  $Pt(CN)_4$  groups in partially oxidized  $K_2Pt(CN)_4 \cdot 3H_2O$  complexes. Note the overlapping of the  $d_{22}$  orbitals and the staggering of the cyano groups. [Reproduced with permission from J. S. Miller and A. J. Epstein, Prog. Inorg. Chem., 20, 1 (1976).]

Pt—Pt separation is so great that there is no significant bonding between Pt(CN)<sub>4</sub> groups. However, in the oxidized compounds the Pt—Pt separations are almost as short as in platinum metal itself, and the compounds are electrically conducting. The electrical conductivity arises from partial filling of one-dimensional bands.

Polysulfur nitride,  $(SN)_x$ , is remarkable because it is a polymeric metal which contains no metal atoms.<sup>22</sup> It is prepared by the spontaneous polymerization of  $S_2N_2$  at temperatures between 0°C and room temperature, whereby shiny metallic fiber bundles are formed. The crystals contain parallel chains of alternating S and N atoms with approximately coplanar atoms in the following configuration:

<sup>&</sup>lt;sup>22</sup> M. M. Labes, P. Love, and L. F. Nichols, *Chem. Rev.*, 79, 1 (1979).

Although all the sulfur atoms and all the nitrogen atoms in these chains are stereochemically equivalent, there are two markedly different N—S distances. A valence bond representation of the chains requires that they be considered resonance hybrids:

$$\begin{array}{c|c}
N_{-} & S^{+} & S^{+} \\
N_{-} & S^{+} & N_{-} & N_{-}
\end{array}$$

The conductivity of (SN)<sub>x</sub> is about  $4 \times 10^3 \ \Omega^{-1} \ \text{cm}^{-1}$  at room temperature, increasing by a factor of 200 to 250 on cooling to liquid helium temperature. In 1975, it was found that (SN)<sub>x</sub> becomes superconducting below 0.26 K.<sup>23</sup> This discovery stimulated both extensive work on sulfur-nitrogen compounds and attempts to prepare other superconducting compounds of nonmetals.

# "Two-Dimensional" Metallic Compounds

The electrical resistivity of graphite (see Fig. 11.11b) in the direction perpendicular to the layers is 0.3 to 0.5  $\Omega$  cm at 50 K and 0.15 to 0.25  $\Omega$  cm at room temperature. The magnitude and temperature coefficient of this resistivity is characteristic of a semiconductor. However, in a direction parallel to the layers, the resistivity is much lower:  $2 \mu\Omega$  cm at 10 K and 40  $\mu\Omega$  cm at room temperature. This latter resistivity is almost as low as that found for typical metals, and graphite is often referred to as a semimetal.24 The semimetallic behavior of graphite can be explained by the density-of-states diagram. The Fermi level occurs at a low minimum in the band, in the region where a filled band and an empty band barely overlap. Because of the low density of states at the Fermi surface, the application of an electric field does not cause as much net electron flow as in the case of a typical metal, in which the Fermi surface is situated in a region with a high density of states.

The layers of the graphite structure are so widely separated and so weakly held together that many molecules and ions can penetrate the "galleries" between layers and form so-called intercalates or layered interstitial compounds. Most of the stable graphite intercalates are essentially salts in which the graphite layers have had electrons either removed or added. Changing the number of valence

<sup>&</sup>lt;sup>23</sup> R. L. Greene, G. B. Street, and L. J. Suter, *Phys. Rev. Lett.*, **34**, 577 (1975).

<sup>&</sup>lt;sup>34</sup> A. K. Holliday, G. Hughes, and S. M. Walker, in "Comprehensive Inorganic Chemistry," vol. 1, pp. 1259-1294, Pergamon, Oxford, 1973.

electrons in graphite causes a shift of the Fermi surface away from the density-ofstates minimum and a consequent increase in electrical conductivity.

Among the first layer-structure intercalates to be discovered were the graphite-alkali metal compounds, which are readily prepared by direct reaction of the metals with graphite. The most metal-rich compositions which have been obtained are C<sub>8</sub>M for potassium, rubidium, and cesium, C<sub>6</sub>Li for lithium, and C<sub>64</sub>Na for sodium.<sup>25</sup> In C<sub>8</sub>M compounds, the carbon layers are exactly superimposed (not offset as in graphite) and are separated by about 5.5 Å (compared with 3.35 Å in graphite itself). The metal atoms form regular triangular nets between the carbon layers, with metal atoms centered between hexagonal C<sub>6</sub> rings. One extra valence electron has been added for every eight carbon atoms in the carbon layers.

A much larger number of graphite intercalates are known in which the carbon layers are believed to be positively charged. The most thoroughly studied of these are graphite bisulfates, formed by treatment of graphite with a mixture of sulfuric and nitric acids. The most bisulfate-rich composition achieved is  $C_{24}^{+}HSO_4^{-}\cdot 2H_2SO_4$ . Although many graphite intercalates are known in which it appears that neutral molecules have intercalated, recent work indicates that in most (if not all) of these cases the graphite is oxidized. Thus, although  $AsF_5$  reacts with graphite to form a highly conducting compound of empirical formula  $C_8AsF_5$ , the actual intercalated species appear to be  $AsF_6^-$  and  $AsF_3$ . That is, the graphite is oxidized according to the following equation:

$$3AsF_5 + 24C \longrightarrow C_{24}^{2+}(AsF_6^{-})_2 \cdot AsF_3$$

Intercalation will not occur with species which do not have oxidizing power themselves unless an oxidizing agent is present during the reaction. Thus graphite is not intercalated by  $GeF_4$  alone but is intercalated by  $GeF_4$ -fluorine mixtures to yield, at the intercalation limit,  $C_{12}GeF_{5-6}$ , which is in equilibrium with gaseous fluorine.<sup>27</sup>

25 Holliday, Hughes, and Walker, op. cit.

<sup>26</sup> E. M. McCarron and N. Bartlett, *J. Chem. Soc. Chem. Commun.*, 404 (1980); N. Bartlett, B. McQuillan, and A. S. Robertson, *Mater. Res. Bull.*, 13, 1259 (1978).

<sup>27</sup> E. M. McCarron, Y. J. Grannec, and N. Bartlett, J. Chem. Soc. Chem. Commun., 890 (1980).




Figure 12.20 Layer structure of TiS<sub>2</sub>. Atoms intercalate between the layers held together by van der Waals bonding.

Titanium disulfide, in common with several other transition-metal disulfides, has a layered structure (Fig. 12.20). Because it is a metallic conductor and can be readily intercalated with metallic lithium, TiS2 has received considerable attention as a possible electrode material in rechargeable batteries.28 If TiS2 is made one electrode in an electrolytic cell with a second electrode of lithium metal and a solution of a lithium salt in an aprotic polar solvent such as dioxolane as electrolyte, the reactions which occur spontaneously in the shorted cell are as follows.

$$\begin{array}{cccc} \text{Li} & \longrightarrow & \text{Li}^+ + e^- & \text{at anode} \\ \text{Li}^+ + \frac{1}{x} \, \text{TiS}_2 + e^- & \longrightarrow & \frac{1}{x} \, \text{Li}_x \text{TiS}_2 & \text{at cathode} \\ \\ \hline & \text{Li} + \frac{1}{x} \, \text{TiS}_2 & \longrightarrow & \frac{1}{x} \, \text{Li}_x \text{TiS}_2 & \text{overall reaction} \end{array}$$

The process is reversible; by applying a reverse potential to the cell, the TiS<sub>2</sub> can be deintercalated. Because of the low equivalent weight of lithium, a battery of this type would have possible application in electric automobiles.

#### **PROBLEMS**

- \*12.1 The compression of a transition metal by application of pressure improves the overlap of the valence d orbitals and increases the bonding ability of the d orbitals relative to that of the s and p orbitals. Predict the effect of pressure on the relative stabilities of the bcc and hcp structures of zirconium and the bcc and ccp phases of iron.
- 12.2 Why would you expect an increase in temperature to stabilize a bcc structure relative to an hcp
- \*12.3 How would you expect the electrical conductivity of a solid-solution alloy (e.g., an alloy of Cu
- 12.4 What are the structure types (bcc, hcp, ccp, or diamond-like) of the following alloys: CuBe, Ag<sub>5</sub>Cd, AgMg, Ag<sub>5</sub>In<sub>3</sub>, Cu<sub>3</sub>Ge, FeAl, and InSb?
- 12.5 Give the empirical formulas (or approximate composition ranges) that might be expected for five solid phases in the Ag-Al phase diagram. For each phase, predict the crystal structure type.
- 12.6 Arrange the following materials in order of hardness: Cs, Na, C(diamond), W, Al, Fe, Mg. 12.7 Can a tantalum crucible be used in the melting of (a) Sr, (b) Re, (c) Pt?
- \*12.8 Why are none of the metals of the second and third transition series ferromagnetic?
- \*12.9 The densities of the lanthanide metals change gradually from 6.19 g cm<sup>-3</sup> for La to 9.84 for Lu, except for Eu and Yb, which have low densities of 5.24 and 6.98, respectively. Explain.
- 12.10 What species probably occupy the galleries in the graphite intercalate C<sub>12</sub>GeF<sub>5-6</sub>?
- \*12.11 Using the information that in C<sub>8</sub>K the C—C bond distance is 1.42 Å and that the metal atoms form regular triangular nets between the carbon layers, calculate the distance between K atoms in each
- 12.12 Why does the Pt-Pt distance decrease oxidizing K2Pt(CN)4 · 3H2O to K2Pt(CN)4Br03 · 3H2O?
- <sup>28</sup> M. S. Whittingham and R. R. Chianelli, J. Chem. Educ., 57, 569 (1980); D. W. Murphy and P. A. Christian, Science, 205, 651 (1979).

- \*12.13 What fraction of the energy band formed by the overlap of the  $p\pi$  orbitals of the S and N atoms of  $(SN)_x$  is filled with electrons?
- 12.14 Without referring to any data, list the following metals in order of increasing melting point: K, Cr, Co, W, Li, Zn.
- 12.15 Without referring to any data, indicate the structure types (bcc, hcp, ccp, or diamond-like) of the following metals: Ge, Rb, Cu, Cr, Mg, Al, Cd, Pd.
- 12.16 Although iron metal is ferromagnetic, a typical iron nail does not act as a magnet (e.g., it does not attract iron filings). Explain.

## THIRTEEN

## SEMICONDUCTORS1

There is no question that semiconductors are important solid-state materials. Almost everyone has heard of them and knows something about their technical application. In this chapter we will briefly describe the electrical properties of semiconductors (here your understanding of the solid state and band theory will be valuable), and we will discuss the chemistry involved in the manufacture of semiconductors and in various semiconductor devices.

A semiconductor is a crystal with a narrow energy gap between a filled valence band and a conduction band. If the crystal were cooled to absolute zero, the conduction band would be empty and the material would be a perfect nonconductor. However, at ordinary temperatures some electrons are thermally excited from the valence band to the conduction band, enough to give the material an electrical conductivity between that of a metal and that of an insulator. (Typical room-temperature resistivities of metals, semiconductors, and insulators are 5,  $5 \times 10^7$ , and  $10^{23} \, \mu\Omega$  cm, respectively.) The conductivity of a semiconductor is proportional to the number of electrons in the conduction band, which in turn is proportional to the Boltzmann factor  $e^{-E_g/RT}$ , where  $E_g$  is the energy gap. Consequently the conductivity of a semiconductor increases exponentially with increasing temperature.

The semiconducting material of greatest commercial importance is elemental silicon. If one were able to prepare a perfectly pure crystal of silicon, the small number of electrons in the conduction band at any given temperature would equal the number of positive "holes" in the valence band. Both conduction

<sup>&</sup>lt;sup>1</sup> C. A. Wert and R. M. Thomson, "Physics of Solids," McGraw-Hill, New York, 1964; L. V. Azaroff, "Introduction to Solids," McGraw-Hill, New York, 1960; C. Kittel, "Introduction to Solid State Physics," 5th ed., Wiley, New York, 1976.




Figure 13.1 Schematic drawing of silicon, showing the negative-electron and positive-hole current carriers which give rise to a small intrinsic conductivity in the pure element.

electrons and holes contribute to electrical conductivity. The electrons travel through the interstices of the lattice, and the holes jump from one bond to another, as crudely illustrated in Fig. 13.1. The countercurrent motion of conduction electrons and valence holes in an applied field constitutes the "intrinsic" semiconductivity of the crystal. Generally even highly purified silicon contains enough impurity atoms to increase the semiconductivity far above the hypothetical intrinsic semiconductivity. For example, let us suppose that a minute fraction of the silicon atoms are randomly replaced by atoms containing more than four valence electrons each, such as arsenic atoms. Because the crystal must remain essentially electrically neutral, each arsenic atom contributes an electron which can enter the conduction band. The principal conducting species in the sample of silicon would be the negative electrons, and such a material is called an n-type (for "negative") semiconductor. A schematic illustration of this type of semiconductor and the corresponding density-of-states diagram are shown in Fig. 13.2. At absolute zero, the extra electrons introduced by the arsenic atoms would be localized around the arsenic atoms (which have + 1 formal charges), but at ordinary temperatures, many of them would be excited to the conduction band. The energy gap between the donor level and the conduction band is the energy required to break an interstitial electron completely away from an arsenic atom




Figure 13.2 Schematic drawing of n-type silicon, and the corresponding density-of-states diagram.




Figure 13.3 Schematic drawing of p-type silicon, and the corresponding density-of-states diagram.

Now suppose that a very small fraction of the atoms in a crystal of silicon were replaced by atoms containing *fewer* than four valence electrons each, such as boron atoms. The principal conducting species in the material would be positive valence holes, as shown in Fig. 13.3, and such a material is called a *p*-type (for "positive") semiconductor. At absolute zero, the positive holes introduced by the impurity boron atoms would be localized around the boron atoms (which would have negative formal charges), whereas at finite temperatures many of these holes would be excited so that they would be free to hop among the silicon-silicon bonds and thus to carry electric current. In the density-of-states diagram of Fig. 13.3, the energy gap between the valence band and the acceptor level is the minimum energy required to force a normal valence electron to neutralize a hole next to a boron atom, so that the boron atom is bonded by single bonds to four silicon atoms. In effect, holes are excited to the left into the valence band.

Silicon which is to be used in semiconductors must first be highly purified. Crude silicon (~98 percent pure) is generally produced by heating quartz rock and carbon above 1800°C in an electric-arc furnace.<sup>2</sup>

$$SiO_2 + C \xrightarrow{\Delta} CO_2 + Si$$

This silicon has about 20 million times more impurity than can be tolerated. It can be purified by converting it to trichlorosilane with hydrogen chloride, carefully distilling the trichlorosilane, and then decomposing it to give purified silicon. The chemical reactions involved are

3HCl + Si 
$$\frac{350^{\circ}\text{C}}{\text{higher}}$$
 SiHCl<sub>3</sub> + H<sub>2</sub>

If necessary, this silicon can then be further purified by zone refining.<sup>3</sup> In this process a rod of the element is melted near one end, and, by moving the furnace, the short melted zone is moved slowly to the other end of the rod. Because

<sup>&</sup>lt;sup>2</sup> Chem. Eng. News, 46 (Nov. 30, 1970).

W. G. Pfann, "Zone Melting," Wiley, New York, 1966.

impurities are more soluble in the melt than in the solid, they concentrate in the melt and are carried to one end of the rod. After the process is repeated several times, the impure end is removed.

Sometimes semiconductors can be purified by gas-phase thermal transport processes.<sup>4</sup> For example, germanium can be purified by placing it in one end of an evacuated tube with a small amount of iodine and then heating the tube so that the end containing the impure germanium is at 500°C and the other end is at 350°C. The iodine reacts with the germanium to form vapors of GeI<sub>4</sub> and GeI<sub>2</sub>. Soon a steady state is reached in which the following reaction takes place continuously, as written, in the high-temperature zone, and the reverse reaction takes place in the initially empty, low-temperature zone.

$$Ge(s) + GeI_4(g) = \frac{500^{\circ}C}{350^{\circ}C} = 2GeI_2(g)$$

Thus germanium is transported from one end of the tube to the other, leaving impurities behind.

Purified silicon and germanium crystals can be converted into *n*-type or *p*-type semiconductors by high-temperature diffusion of the appropriate impurity elements ("dopants") into the crystals. Arsenic and phosphorus are often used for *n*-type semiconductors, and boron and aluminum are often used for *p*-type semiconductors.

#### BAND GAPS

The band gap of a semiconductor is the energy difference between the top of the valence band and the bottom of the conduction band. Values of the band gap in various substances are listed in Table 13.1.

<sup>4</sup> H. Schäfer, "Chemical Transport Reactions," Academic, New York, 1963; also in "Preparative Methods in Solid State Chemistry," P. Hagenmuller, ed., p. 251, Academic, New York, 1972.

Table 13.1 Band gaps of some semiconductors

Compound	$E_{g}$ , at 0 K, eV	Compound	$E_g$ , at 0 K, eV
α-Sn	0.0	CdTe	1.6
InSb	0.2	Se	1.8†
PbTe	0.2	Cu <sub>2</sub> O	2.2
Te Transfer	0.3	InN	2.4
PbS	0.3	CdS	2.6
InAs	0.4	ZnSe	2.8
ZnSb	0.6	GaP	2.88
Ge	0.7	ZnO	3.4
GaSb	0.8	SrTiO <sub>3</sub>	3.4
Si	1.1	ZnS	3.9
InP	1.3	AIN	4.6
GaAs	1.5	Diamond	5.4
The Diff	Clemina J many	BP	6.0

The binding energies associated with impurities are much smaller than the band gaps. For example, the energy required to excite an electron away from a phosphorus atom impurity in silicon to the conduction band is about 0.044 eV. Similarly, the energy required to excite a hole from an aluminum atom impurity in silicon to the valence band is about 0.057 eV. These excitation energies may be compared with the band gap, 1.1 eV.

### DEFECT SEMICONDUCTORS<sup>5</sup>

Many compounds are semiconductors because they are nonstoichiometric. For example, when compounds such as NaCl, KCl, LiH, and  $\delta$ -TiO are subjected to high-energy radiation or are heated with an excess of their constituent metals, the compounds become deficient in the electronegative elements and their compositions may be represented by the general formula  $MY_{1-x}$ , where x is a small fraction. The crystal lattice of such a compound has anion vacancies, each of which is usually occupied by an electron. Such electron-occupied holes are called "F centers." The electron of an F center can be thermally excited to a conduction band, thus giving rise to n-type semiconduction.

Another class of n-type semiconductor are those compounds which contain excess interstitial metal atoms and whose compositions correspond to the formula  $M_{1+x}Y$ . The compounds ZnO, CdO,  $Cr_2O_3$ , and  $Fe_2O_3$  show this type of structural defect. The interstitial metal atoms are readily ionized, allowing their valence electrons to enter a conduction band and leaving interstitial metal ions. When a defect oxide of this type is heated in oxygen, its room-temperature conductivity decreases because of the loss of some of the interstitial metal atoms by oxidation.

Compounds which are deficient in metal ions, of general formula  $M_{1-x}Y$ , are p-type semiconductors. This type of semiconductor can be found in  $Cu_2O$ , FeO, NiO,  $\delta$ -TiO, CuI, and FeS. Electrical neutrality is maintained in these compounds, in spite of cation vacancies, by the presence of metal ions of higher oxidation state. Thus the phase  $Fe_{0.95}O$  is more precisely represented by the formula  $Fe^{II}_{0.85}Fe^{III}_{0.10}O$ . Electrical conductivity is achieved by the hopping of valence electrons from lower-oxidation-state metal ions to higher-oxidation-state metal ions. However, because the Fe(III) ion concentration is much lower than the Fe(II) ion concentration, the effective migrating unit is a positive hole in a metal ion and the conductivity is of the p type. The energy gap for this type of semiconductor corresponds to the energy required to move a positive hole away from the vicinity of a cation vacancy, where it is electrostatically held. When a defect oxide of this type is heated in oxygen, its room-temperature conductivity increases because of oxidation of some of the metal ions and the consequent increase in positive-hole concentration.

<sup>&</sup>lt;sup>5</sup> H. J. Emeléus and J. S. Anderson, "Modern Aspects of Inorganic Chemistry," 3d ed., Van Nostrand, New York, 1960.

#### CONTROLLED-VALENCE SEMICONDUCTORS6

Defect semiconductors are generally difficult to obtain with large deviations from stoichiometry. Hence only limited variations in electrical properties are possible. In addition, compositions are difficult to reproduce exactly. These difficulties can be overcome by the use of "controlled-valence" semiconductors, first prepared by Verwey and his coworkers.

For example, consider the material formed by heating an intimate mixture of NiO and a small amount of Li<sub>2</sub>O in air at 1200°C. Oxygen is absorbed, and a single phase of composition Li<sub>2</sub>Ni<sub>1-2</sub>O is formed:

$$\frac{x}{2} \operatorname{Li_2O} + (1 - x)\operatorname{NiO} + \frac{x}{4} \operatorname{O_2} \rightarrow \operatorname{Li_xNi_{1-x}O}$$

Inasmuch as Li<sup>+</sup> and Ni<sup>2+</sup> ions have similar radii, Li<sup>+</sup> ions can substitute for Ni<sup>2+</sup> ions in the lattice. One Ni<sup>3+</sup> ion is formed for every Li<sup>+</sup> ion introduced to preserve electrical neutrality. The resulting compound can be represented more precisely by the expanded formula  $\text{Li}_x \text{Ni}^{\text{III}}_x \text{Ni}^{\text{II}}_{1-2x} O$ . The positive holes in the Ni<sup>2+</sup> ions (i.e., the Ni<sup>3+</sup> ions) can move from one nickel ion to another and thus give rise to *p*-type semiconduction. By simply controlling the ratio of lithium to nickel, the electrical conductivity can be varied at will. The conductivity of pure NiO is about  $10^{-10} \, \Omega^{-1} \, \text{cm}^{-1}$ , whereas the compound in which 10 percent of the nickel atoms have been replaced by lithium atoms has a conductivity of about  $1 \, \Omega^{-1} \, \text{cm}^{-1}$ .

Mixed-valence systems can also be obtained with compounds having the perovskite structure such as barium titanate, BaTiO<sub>3</sub>. (This compound consists of a ccp lattice of Ba<sup>2+</sup> and O<sup>2-</sup> ions in which the octahedral holes surrounded exclusively by O<sup>2-</sup> ions are occupied by Ti<sup>4+</sup> ions.) If a small number of the barium ions are replaced by + 3 ions such as lanthanum ions, a corresponding number of Ti<sup>4+</sup> ions must be reduced to Ti<sup>3+</sup>, forming the system La<sub>x</sub>Ba<sub>1-x</sub>Ti<sup>III</sup><sub>x</sub>Ti<sup>IV</sup><sub>1-x</sub>O<sub>3</sub>. This material exhibits *n*-type semiconductivity.

Compounds of the type  $\text{Li}_x \text{Mn}_{1-x} \text{O}$  are semiconducting, but they cannot be made by heating a mixture of  $\text{Li}_2 \text{O}$  and MnO in air, because MnO is easily oxidized in air at high temperatures. In this case, the reaction is carried out in a sealed container, and the oxygen is introduced in the form of lithium peroxide:

$$\frac{x}{2}\operatorname{Li}_{2}O_{2} + (1-x)\operatorname{MnO} \rightarrow \operatorname{Li}_{x}\operatorname{Mn}_{1-x}\operatorname{O}$$

#### APPLICATIONS

Semiconductors have innumerable practical applications which contribute to our high standard of living. We shall describe just four applications: the photovoltaic

<sup>&</sup>lt;sup>6</sup> W. D. Johnston, *J. Chem. Educ.*, **36**, 605 (1959); P. E. Snyder, *Chem. Eng. News*, 102 (Mar. 13, 1961).




Figure 13.4 Energy level diagram for a *p-n* junction, showing band bending and the creation of an electron-hole pair upon absorption of a photon with energy equal to or greater than the band gap.

cell, the photoelectrolytic cell, the rectifier, and the insulated-gate field-effect transistor. Typically these devices involve a semiconductor crystal which is p-type in one part and n-type in another. The boundary region is called a p-n junction and has interesting electrical properties. Such a crystal can be made, for example, by allowing small amounts of boron to diffuse into one side of a slice of n-type silicon at high temperatures. If properly doped, the crystal will then be p-type on one side and n-type on the other, with a region within the slice where the two types of silicon meet: the p-n junction.

At the p-n junction, a few electrons are transferred from the n-type semiconductor to the p-type semiconductor, causing a partial depletion of charge carriers in both phases near the junction. This charge transfer equalizes the Fermi levels and causes band bending (i.e., an electric-field gradient) near the junction, as shown in Fig. 13.4.

#### The Photovoltaic Cell7

Let us suppose that a *p-n* junction is irradiated with light. If the photon energy equals or exceeds the band gap, electron-hole pairs will be formed in the irradiated region, as indicated in Fig. 13.4. Because of the band bending, the electrons will migrate toward the bulk of the *n*-type semiconductor and the holes will migrate toward the bulk of the *p*-type semiconductor. Thus the *n*-type region will achieve a negative potential relative to the *p*-type region. If the *n*-type and *p*-type regions are electrically connected to an external circuit, a current will flow as long as the junction is irradiated. Obviously such a crystal can be used as a kind of battery whose energy is derived from light. One of the aims of solid-state chemists is to

<sup>7</sup> Wert and Thomson, op. cit.

prepare efficient cells of this type economically enough to permit their use in harnessing solar energy.

#### The Photoelectrolytic Cell

When an n-type semiconductor is immersed in a solution containing a suitable redox couple  $A^+/A$ , a few electrons near the surface of the semiconductor react with the oxidizing agent of the couple,  $A^+$ , and thus deplete the semiconductor surface region of charge carriers and cause a bending of the bands as shown in Fig. 13.5. Absorption at the interface of a photon with energy greater than the band gap promotes an electron to the conduction band and creates a hole in the valence band. Because of the band bending, the electron and hole spontaneously separate; the electron  $e^-$  moves toward the bulk of the semiconductor, and the hole  $(h^+)$  remains at the interface. If the reduction potential of the solution is low enough, the electron-transfer reaction

$$A + h^+ \longrightarrow A^-$$

occurs at the interface. The excited electron can move through a wire connected to the semiconductor to a nonphotoactive electrode where an oxidized species, B<sup>+</sup>, can be reduced:

$$B^+ + e^- \longrightarrow B$$

This combination of n-type semiconductor and inert electrode immersed in the solution comprises a photoelectrochemical cell<sup>8</sup> in which light promotes the reaction

$$A + B^+ \longrightarrow A^+ + B$$

<sup>8</sup> A. J. Bard, *Science*, **207**, 139 (1980); M. S. Wrighton, *Acc. Chem. Res.*, **12**, 303 (1979); M. S. Wrighton, *Chem. Eng. News*, 29 (Sept. 3, 1979). Also see "Photoeffects at Semiconductor-Electrolyte Interfaces," A.C.S. Symposium Series, No. 146, American Chemical Society, Washington, D.C., 1981.




Figure 13.5 Energy level diagram for an *n*-type semiconductor in contact with a solution containing the A<sup>+</sup>/A redox couple. Photon absorption creates an electron-hole pair.

If the A/A+ and B+/B couples are H<sub>2</sub>O/O<sub>2</sub> and H+/H<sub>2</sub> couples, Installation

$$H_2O \implies \frac{1}{2}O_2 + 2H^+ + 2e^{-\frac{1}{2}O_2}$$
 $2H^+ + 2e^- \implies H_2$ 

He Photoelectroly and 1

the net cell reaction will be the photoelectrolysis of water to H<sub>2</sub> and O<sub>2</sub>:

$$H_2O \longrightarrow H_2 + \frac{1}{2}O_2$$
 we have A/A signor substitution

In fact, this reaction has been carried out using photoelectrolytic cells involving the semiconductor SrTiO<sub>3</sub>. Because the band gap of SrTiO<sub>3</sub> is about 3.4 V, it is necessary to use ultraviolet light with such cells. The ultraviolet light is converted fairly efficiently (about 25 percent) to storable energy in the form of hydrogen and oxygen. Unfortunately, because sunlight consists mainly of visible light, the device has very low efficiency (about 1 percent) for converting solar energy into hydrogen and oxygen. Practical solar photoelectrolysis requires the development of semiconductors that can use visible light efficiently and that have long-term stability under photoelectrolysis conditions. Some fluorine-doped oxide semiconductors show promise for such applications. Thus TiO2-xFx (where  $x \approx 0.002$ ) and WO<sub>3-x</sub>F<sub>x</sub> (where  $x \approx 0.01$ )<sup>10</sup> are *n*-type semiconductors which have photoelectrolytic properties superior to those of the corresponding defect semiconductors, TiO<sub>2-x</sub> and WO<sub>3-x</sub>.

The concepts learned from photoelectrolytic cells with semiconductor electrodes have been used to design relatively economical systems in which aqueous suspensions of semiconductor particles are used for similar purposes. In a typical system, n-type SrTiO<sub>3</sub> powder with platinum dispersed on the surface of the particles has been used. 11 Each particle is essentially a short-circuited photoelectrolytic cell in which the semiconductor electrode and counter-electrode have been brought into contact. (See Fig. 13.6.) Irradiation of such particle suspen-

<sup>9</sup> S. N. Subbarao, Y. H. Yun, R. Kershaw, K. Dwight, and A. Wold, *Inorg. Chem.*, 18, 488 (1979). <sup>10</sup> C. E. Derrington, W. S. Godek, C. A. Castro, and A. Wold, *Inorg. Chem.*, 17, 977 (1978).




Figure 13.6 Representation of SrTiO<sub>3</sub>-Pt particle and the corresponding energy level diagram. When an aqueous suspension of such particles is irradiated with ultraviolet light, water is electrolyzed into hydrogen and oxygen.

sions still involves the electron/hole formation and surface oxidation and reduction reactions found in cells, but without external current flow. The Pt-SrTiO<sub>3</sub> system, when irradiated with ultraviolet light, has been shown to effect the decomposition of water into hydrogen and oxygen, the hydrogen forming at the platinum surface and the oxygen forming at the SrTiO<sub>3</sub> surface. Unfortunately, just as in the corresponding photoelectrolytic cell process, the system has a low solar efficiency.

#### The Rectifier

Let us suppose that a voltage is applied across a p-n junction so that the p-type region is positive relative to the n-type region. In the p-type region, holes will migrate toward the junction, and in the n-type region electrons will migrate toward the junction. At the junction, the holes and electrons will be essentially annihilated. That is, the migrating electrons of the *n*-type region will drop down into the valence-shell vacancies of the p-type region. The migration of holes and electrons can continue indefinitely; i.e., a current will flow as long as the voltage is applied. Now let us suppose that the voltage is reversed so that the p-type region is negative relative to the n-type region. In the p-type region, holes will migrate away from the junction, and in the n-type region, electrons will migrate away from the junction. Thus, in the region of the junction, the current carriers will be depleted and no current can flow. Actually, current can flow under these conditions if the voltage is high enough. It is necessary to supply enough energy to excite an electron from the valence band of the p-type region all the way up to the conduction band so that the electron can cross the barrier into the n-type region. Obviously a p-n junction can serve as a rectifier for converting alternating current into direct current, as long as the voltage is not too high.

#### The Insulated-Gate Field-Effect Transistor<sup>12</sup>

This type of transistor, also called a "metal oxide semiconductor" (MOS) transistor, can be understood by reference to Fig. 13.7. When the gate voltage  $(V_g)$  is zero, no current flows from the source to the drain because these n-type regions are insulated from each other by p-type silicon. The excess electrons are indicated by dots, and the holes are indicated by circles. When a positive voltage is applied to the gate, holes are driven away from the interface of the silicon dioxide and the silicon under the gate. With a sufficiently high gate voltage, a very thin region of the silicon under the gate is changed from p type to n type. This inverted region is called an n channel and provides a conduction path for electrons between the source and the drain. Thus the gate voltage controls the magnitude of the current. Devices of this type can be made microscopically small and allow the miniaturization of integrated circuits. MOS circuits are widely used in computers and pocket calculators.

<sup>12</sup> W. C. Hittinger, Sci. Am., 229, 48 (August 1973), 100 (Manual Property of August 1973), 110 (Manual Property of August 1973)




Figure 13.7 Cross section of an enhancement-type MOS transistor. The black regions correspond to Al metal, the white regions to  $SiO_2$ , the regions with black dots to n-type Si, and the regions with open circles to p-type Si. (a) The source and drain are insulated from each other. (b) Sufficiently high voltage has been applied to the gate to create an n-type channel between the source and the drain.

#### AMORPHOUS SEMICONDUCTORS13

When crystalline silicon is doped with phosphorus atoms, the geometric constraints of the crystal force the phosphorus atoms to occupy silicon sites so that they are obliged to bond tetrahedrally. Thus the phosphorus atom acquires a positive formal charge, and the extra valence electron is held weakly nearby at an energy level slightly below that of the bottom of the conduction band. However, when an amorphous or glassy sample of silicon is doped with phosphorus, the situation is different. There are no geometric constraints, and the amorphous silicon has a high concentration of "dangling bonds" which can be used to bond to the entering phosphorus atoms. Thus by breaking only one Si—Si bond and using one dangling bond, a phosphorus atom can bond trigonally, as shown below.

Thus phosphorus doping of ordinary amorphous silicon does not alter the conductivity. However, if the doping is carried out in the presence of hydrogen (either by exposure to hydrogen gas during the doping or by using amorphous silicon formed by the decomposition of silane), it is possible to form an *n*-type

semiconductor. It has been suggested that the hydrogen ties up the dangling bonds as SiH groups and thereby forces the impurity atoms to bond tetrahedrally. It appears that the economic breakthrough necessary to achieve the large-scale generation of electric power from solar energy may come about through the use of relatively cheap amorphous silicon rather than through the development of cheaper methods of making crystalline silicon devices.

Chalcogenide glasses, such as compounds of selenium or tellurium and arsenic, are photoconductive and thus find application in xerography and television. Doping is not necessary to achieve photoconductivity in these materials; the pure materials contain positively and negatively charged sites which can trap electrons and holes, respectively. The positively charged sites are believed to be trivalent chalcogen atoms at branching points in the chalcogen chains. The negatively charged sites are believed to be monovalent chalcogen atoms which terminate chains and side chains.<sup>14</sup> These two sites are illustrated below.

Optical excitation promotes an electron to the conduction band and creates a hole in the valence band. The electron is trapped near a positive site at an energy level slightly below the bottom of the conduction band, and the hole is trapped near a negative site at an energy level slightly above the top of the valence band. This situation constitutes the semipermanent photoconductive state.

#### THE PHOTOGRAPHIC LATENT IMAGE15

The silver halides, which have formed the basis of the photographic process since about 1835, are not semiconductors. However, now that we have discussed various aspects of solid-state chemistry, including conduction bands, interstitial ions, and photoionization, the reader is prepared to understand the theories of

<sup>&</sup>lt;sup>14</sup> M. Kastner, D. Adler, and H. Fritzsche, Phys. Rev. Lett., 37, 1504 (1976).

<sup>&</sup>lt;sup>15</sup> C. E. K. Mees and T. H. James, eds., "The Theory of the Photographic Process," 3d ed., Macmillan, New York, 1966; T. H. James, ed., "The Theory of the Photographic Process," 4th ed., Macmillan, New York, 1977.

latent image formation in photographic emulsions. A photographic emulsion consists of a suspension, in gelatin, of microscopic crystals of a silver halide (usually silver bromide) or a mixture of silver halides. Exposure of the emulsion to a small amount of light causes a change in the crystals (latent image formation) such that subsequent reduction to silver by a reducing agent (developer) is greatly accelerated.

Silver bromide in the dark has only a very low conductivity at normal temperatures, and a negligible conductivity at temperatures below  $-200^{\circ}$ C. This low dark conductivity is due to the migration of interstitial silver ions. When a crystal of silver bromide is illuminated, there is an immediate increase in conductivity, which occurs even at low temperatures. This photoconductivity is due to the ejection of valence electrons from bromide ions in the AgBr lattice:

$$Br^{-}(lattice) + hv \longrightarrow Br(lattice) + e^{-}(conduction band)$$

Many of the conduction electrons back-react with bromine atoms to re-form bromide ions. However, some of the conduction electrons are at least temporarily trapped in portions of the crystal of lower energy level than the rest of the crystal. Specks of silver sulfide on the silver bromide grain surfaces, which were formed during digestion of the AgBr-gelatin emulsion, are believed to be efficient electron traps.

Most of the prevalent theories of latent image formation involve both the migration of interstitial silver ions and the production and trapping of photoelectrons. According to the Gurney-Mott<sup>16</sup> mechanism, an electron is captured by a trapping center, where it is temporarily localized. A silver ion can migrate to this center and combine with the trapped electron to form an atom. The atom is not stable but can decompose into a silver ion and a free electron, causing the cycle to start anew. However, during its lifetime the silver atom can trap a second electron, and, if the second electron remains trapped until the arrival of a second silver ion, a two-atom cluster forms. The minimum-sized cluster corresponding to a stable latent image speck is believed to consist of three or four silver atoms.<sup>17</sup> Specks of silver of this size or greater, on the silver halide crystal surface, can catalyze the subsequent action of a developer. The Gurney-Mott mechanism is represented by the following equations, in which  $e^-$  stands for a conduction electron and Ag<sup>+</sup> stands for an interstitial silver ion.

$$trap + e^- \implies e^-/trap$$
 $e^-/trap + Ag^+ \implies Ag/trap$ 
 $Ag/trap + e^- \implies Ag^-/trap$ 
 $Ag^-/trap + Ag^+ \implies Ag_2/trap$ 
 $etc.$ 

<sup>&</sup>lt;sup>16</sup> R. W. Gurney and N. F. Mott, Proc. R. Soc. London Ser. A. 164, 151 (1938).

<sup>&</sup>lt;sup>17</sup> For a discussion of the electronic and structural properties of Ag<sub>3</sub> clusters and ions, see H. Basch, J. Am. Chem. Soc., 103, 4657 (1981).

A modification of this theory, proposed by Mitchell,  $^{18}$  differs in the order of the  $e^-$  and  $Ag^+$  trapping, as shown in the following mechanism.

$$trap + Ag^{+} \rightleftharpoons Ag^{+}/trap$$
 $Ag^{+}/trap + e^{-} \rightleftharpoons Ag/trap$ 
 $Ag/trap + Ag^{+} \rightleftharpoons Ag_{2}^{+}/trap$ 
 $Ag_{2}^{+}/trap + e^{-} \rightleftharpoons Ag_{2}/trap$ 
etc.

#### **PROBLEMS**

- 13.1 Estimate the longest wavelength of light which can generate a current in a silicon photovoltaic cell.
- \*13.2 Predict the effect on the electrical conductivity of adding iron to an  $\text{Li}_x \text{Ni}_{1-x} \text{O}$  semiconductor (to form  $\text{Li}_x \text{Fe}_y \text{Ni}_{1-x-y} \text{O}$ ). Explain.
- 13.3 Indicate the type of semiconduction (n or p) shown by the following materials: (a) Zn-doped GaAs, (b)  $In_{1+x}As_{1-x}$ , where  $x \le 1$ , (c) x-ray-irradiated KCl, (d)  $Li_{0.05}Cu_{0.05}O$ , (e) WO<sub>2.999</sub>.
- 13.4 Categorize the following materials, on the basis of their electrical conductivities, as metallic, semiconducting, or insulating: Bi, AlF<sub>3</sub>, CdS, CuZn, NaHCO<sub>3</sub>, InP, CeS, Os, Na<sub>0.5</sub>WO<sub>3</sub>, P<sub>4</sub>.
- 13.5 Compare the electrical conductivities of germanium crystals containing (a) 0.1 ppm of As, (b) 0.1 ppm of As and 0.05 ppm of Al, (c) 0.1 ppm of As and 0.1 ppm of Al, (d) 1 ppm of Al.
- \*13.6 Using a simple thermodynamic argument, explain why, in the thermal transport of germanium by iodine, the germanium is transported from the higher temperature zone to the lower temperature zone, rather than vice versa.
- \*13.7 Laser emission can occur at a p-n junction if a dc voltage is applied across the junction. In the case of gallium arsenide, the light is emitted in the near infrared at about 8400 Å, with the exact wavelength tunable by variation of temperature or pressure. State and explain the direction of the wavelength shift with increasing pressure. Would you expect the GaP laser to emit at a shorter or longer wavelength than the GaAs laser? Explain.
- \*13.8 Propose a mechanism for the development of a photographic emulsion, involving electron transfer from the developing agent and the silver latent image speck.
- 13.9 What magnitude band gap would be suitable for a photoelectrolytic cell designed to operate efficiently in sunlight at a wavelength of  $\sim 5500 \text{ Å}$ ?
- \*13.10 Without reference to any data, arrange the following materials in order of increasing band gap: CdS, CdSe, InSb, GaSb, diamond,  $\alpha$ -Sn.
- \*13.11 When an electrode of *p*-type indium phosphide in an acidic aqueous solution of V<sup>3+</sup> is irradiated with sunlight, the V<sup>3+</sup> is reduced to V<sup>2+</sup> with 11.5 percent solar conversion efficiency.<sup>19</sup> Sketch the valence and conduction bands and acceptor level in the region of the electrode surface and indicate the mechanism of the photoelectrolytic process.

<sup>19</sup> A. Heller, B. Miller, and F. A. Thiel, *Appl. Phys. Lett.*, **38**, 282 (1981).

<sup>&</sup>lt;sup>18</sup> J. W. Mitchell, *Rep. Prog. Phys.*, **20**, 433 (1957); *J. Photogr. Sci.*, **5** 49 (1957). Also see Mees and James, op. cit.

#### CHAPTER FOURTEEN

# INTRODUCTION TO TRANSITION-METAL CHEMISTRY

The remaining chapters in this book cover the chemistry of transition-metal compounds. By transition metal we mean any one of the elements that has a partly filled d shell in one of its commonly occurring oxidation states. The "inner" transition metals, which are characterized by partly filled f shells, will only occasionally be discussed. The transition-metal compounds have certain characteristic properties which make it convenient, if not necessary, to study them separately from the compounds of the main-group elements. We have already pointed out, in Chap. 12, that the transition metals are hard, strong, high-melting metals which form alloys with one another and with other metals and which have high electrical and thermal conductivities. Other characteristic properties which we shall later discuss are (1) each transition metal generally has several readily accessible oxidation states; (2) the compounds are often colored; (3) many of the compounds are paramagnetic; (4) the metal ions are often obtained in the form of complexes with a wide variety of ligands; and (5) the compounds often have catalytic properties.

## OXIDATION STATES

The multiplicity of oxidation states shown by most transition metals is due to the ability of these elements to lose a variable number of d electrons. For example, in aqueous solution, vanadium exists in the +2, +3, +4, and +5 oxidation states, corresponding to the electron configurations  $d^3$ ,  $d^2$ ,  $d^1$ , and  $d^0$ , respectively. Consequently the aqueous chemistry of vanadium consists, to a large extent, of

the oxidation-reduction reactions of vanadium. These types of reactions may be understood and predicted with the aid of the following reduction-potential diagram.

The fact that the vanadium reduction potentials gradually become more positive from left to right in this diagram indicates that the species  $V^{2+}$ ,  $V^{3+}$ , and  $VO^{2+}$  are stable with respect to disproportionation. A striking demonstration can be carried out by the addition of excess zinc pellets to a solution of  $(VO_2)_2SO_4$  in dilute sulfuric acid. The originally yellow solution successively turns green, blue, green, and, finally, violet as the vanadium is reduced stepwise from  $VO_2^+$  to  $\bar{V}^{2+}$ . The  $Fe^{3+}$ ,  $Fe^{2+}$  potential is 0.77 V; consequently the addition of  $Fe^{2+}$  to an acidic solution of  $VO_2^+$  reduces the vanadium to  $VO^{2+}$ , and no further. The  $Sn^{2+}$ , Sn potential is -0.14 V; thus tin reduces  $VO_2^+$  cleanly to  $V^{3+}$ . The  $Zn^{2+}$ , Zn potential is -0.76 V, and, as we have indicated, zinc reduces  $VO_2^+$  to  $V^{2+}$ .

The reduction-potential diagrams given in Chap. 8 can be likewise used to interpret the oxidation-reduction reactions of other transition metals.

#### COLORS and any sense bearing which are removed within service control of

The colors of transition-metal compounds are usually attributable to electronic transitions involving d orbitals. These transitions are of two main types. In one type, the "d-d transition," an electron is transferred between orbitals that have predominantly metal d-orbital character. In this type of transition, there is little shift of electron density from any atom to another. In the other type of transition, the "charge-transfer transition." an electron is transferred from a molecular orbital centered mainly on the ligands (or a ligand) to one centered mainly on the metal atom, or vice versa. In this type of transition, the atomic charges in the initial and final states are appreciably different. As a rough rule of thumb, d-d transitions give pale colors, and charge-transfer transitions give dark colors.

# 

A substance which has no unpaired electrons is "diamagnetic"; i.e., it is repelled by a magnetic field. On the other hand, a substance with unpaired electrons is generally "paramagnetic" and shows the opposite behavior: When it is placed in a magnetic field gradient, it is attracted toward the region of greater field strength with a force proportional to the field strength times the field gradient. An applied magnetic field causes the electron spins to become somewhat ordered so that they are oriented favorably with respect to the field. In a "ferromagnetic" substance at low temperature, there is a spontaneous cooperative interaction between spins of

the unpaired electrons such that they are all aligned and the substance has a high net magnetic moment. In an "antiferromagnetic" substance at low temperature, half of the electron spins are aligned one way and half are aligned the opposite way, so that the substance not only has no magnetic moment but also does not exhibit paramagnetic behavior in a magnetic field. The cooperative spin alignments of both ferromagnetic and antiferromagnetic substances become disordered as the temperature is increased, and at sufficiently high temperatures (i.e., above the Curie temperature of a ferromagnetic substance, and above the Néel temperature of an antiferromagnetic substance), the substances become paramagnetic.

In our study of electron configurations in Chap. 1, we saw that free transitionmetal ions frequently have unpaired d electrons. Many compounds contain these ions with electron configurations which are relatively unperturbed, at least with respect to the number of unpaired d electrons. Hence many transition-metal compounds show one of the types of magnetism just described.

### COMPLEXES

Transition metals have a much more diverse and interesting chemistry than, say, the alkali metals. In the case of transition metals in high oxidation states, this difference arises partly because the highly charged ions can electrostatically strongly bind a wide variety of negative or polar ligands. In the case of transition metals in low oxidation states, the difference arises because of the presence of electrons in the metal d orbitals. These d electrons can become involved in the bonding and permit the formation of complexes which cannot be formed in the case of the "hard" alkali-metal ions. Thus, much of the chemistry of the transition metals is the chemistry of complexes, or coordination compounds.

The term "coordination compound" is usually applied to any compound containing molecules or ions in which metal atoms are surrounded by other atoms or groups. Thus both CH<sub>3</sub>Mn(CO)<sub>5</sub> and K<sub>3</sub>[Fe(CN)<sub>6</sub>] are considered coordination compounds. Metal-containing molecules and ions are often called "complexes" or, in the case of ions, "complex ions." In fact, the term "complex ion" is even applied to ions in which the central atom is a nonmetal, such as BCl<sub>4</sub> and PF<sub>6</sub>. However, neutral nonmetallic species such as SiBr<sub>4</sub> and SF<sub>6</sub> are usually simply referred to as molecules rather than as coordination compounds or complexes.

#### CATALYSIS

Most industrially important reactions are carried out with the aid of catalysts, and the catalysts are usually transition metals or transition-metal compounds. For example, the Haber process for the synthesis of ammonia from nitrogen and

hydrogen involves an iron-iron oxide catalyst. The oxidation of ammonia to nitric oxide (which is used in the synthesis of nitric acid) is catalyzed by a platinum or platinum-rhodium catalyst. The Ziegler-Natta polymerization of ethylene and propene is catalyzed by a mixture of TiCl<sub>4</sub> and Al(C<sub>2</sub>H<sub>5</sub>)<sub>3</sub>. Many biologically important reactions take place with the aid of proteins in which transition-metal atoms play important roles. For example, a cobalt atom lies at the heart of the vitamin B<sub>12</sub> coenzymes. Iron atoms are importantly involved in the hemoglobin of blood and in the ferredoxins of the photosynthetic process. Both molybdenum and iron are contained in nitrogen-fixing enzymes.

The transition-metal atoms in catalysts act as sites for holding the reacting species in conformations favorable for reaction and act as sources of, or sinks for, electrons. These functions are obviously aided by the abilities of transition metals to form complexes and to undergo oxidation-reduction reactions.

#### COORDINATION GEOMETRY

In the following paragraphs we shall discuss the commonly observed geometrical arrangements of ligand donor atoms in complexes. For convenience, we shall classify these structures in terms of the coordination numbers of the metal atoms

#### **Coordination Number 2**

Although this coordination number is found in high-temperature, gas-phase species such as MgCl<sub>2</sub>(g), it is rather unusual for ordinary, stable complexes. It is found principally in some of the complexes of the ions Cu<sup>+</sup>, Ag<sup>+</sup>, Au<sup>+</sup>, and Hg<sup>2+</sup>, each of which has a ground-state  $d^{10}$  electron configuration. Typical examples of such complexes are Cu(NH<sub>3</sub>)<sub>2</sub>+, AgCl<sub>2</sub>-, Au(CN)<sub>2</sub>-, and HgCl<sub>2</sub>. All such complexes are linear; i.e., the ligand-metal-ligand bond angle is 180°. As a rough approximation, we may describe the bonding as a consequence of the overlap of  $\sigma$ orbitals of the ligands with sp hybrid orbitals of the metal atom. However, a metal d orbital is probably involved in the bonding to some extent. Let us assume that the bonds lie on the z axis of the metal atom and that a small amount of the nonbonding electron density of the metal  $d_{z^2}$  orbital is shifted to the metal s orbital. In this case the metal orbitals used in bonding would not be simple sp. hybrid orbitals but rather hybrid orbitals with 50 percent p<sub>2</sub> character, a small amount of  $d_{z^2}$  character, and the remainder s character. A pair of electrons would occupy a hybrid nonbonding metal orbital, principally of  $d_{x}$  character with a little s character. This type of hybridization would shift some nonbonding electron density away from the regions between the metal and the ligands and thus would be energetically favored. www.gailbalant.estatouras studibalances function gaves

are illustrated to show the gradual transition from CdCL\* (which has almost the

L. E. Orgel, "An Introduction to Transition-Metal Chemistry: Ligand-Field Theory," 2d ed., pp. 69-71, Wiley, New York, 1966. Carrier and Carrier by Markey Carrier and Property of the Proper

#### **Coordination Number 3**

This coordination number is rare among metal complexes. Most crystalline compounds of stoichiometry MX<sub>3</sub> have structures in which the coordination number of M is greater than 3. For example, CrCl<sub>3</sub> has an infinite layer lattice in which each Cr atom is coordinated to six Cl atoms (see Fig. 11.12c). In CsCuCl<sub>3</sub> each Cu atom is coordinated to four Cl atoms in infinite anionic chains: —Cl—CuCl<sub>2</sub>—Cl—CuCl<sub>2</sub>. And AuCl<sub>3</sub> really exists as planar Au<sub>2</sub>Cl<sub>6</sub> molecules in which each Au atom is bonded to two bridging Cl atoms and two terminal Cl atoms. Coordination number 3 is occasionally encountered in complexes with extremely bulky ligands and, in the case of a few d<sup>10</sup> metal complexes, even with ligands that are not very bulky. Some well-established examples are KCu(CN)<sub>2</sub> (see page 269), [(CH<sub>3</sub>)<sub>3</sub>S<sup>+</sup>][HgI<sub>3</sub><sup>-</sup>], Cr{N[Si(CH<sub>3</sub>)<sub>3</sub>]<sub>2</sub>}<sub>3</sub>, Fe{N[Si(CH<sub>3</sub>)<sub>3</sub>]<sub>2</sub>}<sub>3</sub>, {Cu[SC(NH<sub>2</sub>)<sub>2</sub>]<sub>3</sub>}Cl, [Cu(SPPh<sub>3</sub>)<sub>3</sub>]ClO<sub>4</sub>, and Pt(PPh<sub>3</sub>)<sub>3</sub>. In all these cases the metal atom and the three directly coordinated ligand atoms are coplanar.

#### **Coordination Number 4**

This is a very important coordination number, for which two limiting configurations are commonly observed, "tetrahedral" and "square planar." In Chap. 3 it was pointed out that 4-coordinate non-transition-element complexes in which the central atom has no lone-pair electrons (such as BeCl<sub>4</sub><sup>2-</sup>, BF<sub>4</sub><sup>-</sup>, ZnCl<sub>4</sub><sup>2-</sup>, SnCl<sub>4</sub>, and AlF<sub>4</sub><sup>-</sup>) are almost always tetrahedral. The same geometry is also generally found for 4-coordinate transition-element complexes in which the central atom or ion does *not* have a *d*<sup>8</sup> electron configuration. Thus species such as Co(CO)<sub>4</sub><sup>-</sup>, Ni(CO)<sub>4</sub>, FeCl<sub>4</sub><sup>-</sup>, CoCl<sub>4</sub><sup>2-</sup>, MnO<sub>4</sub><sup>-</sup>, VO<sub>4</sub><sup>3-</sup>, and FeO<sub>4</sub><sup>2-</sup> are tetrahedral. When the central atom has a *d*<sup>8</sup> configuration, one sometimes finds tetrahedral geometry, but, more commonly, square planar geometry. Examples of *d*<sup>8</sup> tetrahedral complexes are NiCl<sub>4</sub><sup>2-</sup>, NiBr<sub>4</sub><sup>2-</sup>, NiCl<sub>3</sub>OPPh<sub>3</sub>, and Co(I) and Ni(II) complexes that have ligands with bulky substituents. Examples of *d*<sup>8</sup> square planar complexes are IrCl(CO)(PEt<sub>3</sub>)<sub>2</sub>, Ni(CN)<sub>4</sub><sup>2-</sup>, PdCl<sub>4</sub><sup>2-</sup>, Pt(NH<sub>2</sub>CH<sub>2</sub>CH<sub>2</sub>NH<sub>2</sub>)<sub>2</sub><sup>2+</sup>, AgF<sub>4</sub><sup>-</sup>, Au<sub>2</sub>Cl<sub>6</sub>, and [Rh(CO)<sub>2</sub>Cl]<sub>2</sub>. The last two complexes have bridging chlorine atoms which are shared by the two 4-coordinate metal atoms.

#### **Coordination Number 5**

The structures of 5-coordinate complexes lie between two limiting geometries: trigonal bipyramidal and square pyramidal. These limiting structures are not markedly different, as can be seen by examination of Fig. 14.1. The conversion of one structure into the other requires a relatively slight distortion. In Fig. 14.2, seven different 5-coordinate structures, including two nonmetallic compounds, are illustrated to show the gradual transition from CdCl<sub>5</sub><sup>3-</sup> (which has almost the ideal trigonal bipyramid structure) to Ni(CN)<sub>5</sub><sup>3-</sup> (which, in one of its forms, has almost the ideal square pyramid structure). Several of the intermediate structures are almost equally well described as distorted trigonal bipyramids or as




Figure 14.1 The distortion of a trigonal bipyramid to a square pyramid. [Reproduced with permission from E. L. Muetterties and L. J. Guggenberger, J. Am. Chem. Soc., 96, 1748 (1974). Copyright 1974 American Chemical Society.]

distorted square pyramids. To eliminate such ambiguity, Muetterties and Guggenberger<sup>2</sup> proposed the specification of dihedral angles of the polyhedron as an objective way to describe the shape of a 5-coordinate compound. Dramatic proof of the fact that the various conformations from trigonal bipyramidal to square pyramidal have comparable energies is provided by the compound [Cr(NH<sub>2</sub>CH<sub>2</sub>NH<sub>2</sub>)<sub>3</sub>][Ni(CN)<sub>5</sub>] · 1.5H<sub>2</sub>O, which contains two types of Ni(CN)<sub>5</sub><sup>3-</sup> ions: One has the geometry of a regular square pyramid, and the other has a geometry practically midway between that of a trigonal bipyramid and a square pyramid.<sup>3</sup>

<sup>2</sup> E. L. Muetterties and L. J. Guggenberger, *J. Am. Chem. Soc.*, **96**, 1748 (1974). <sup>3</sup> K. N. Raymond, P. W. R. Corfield, and J. A. Ibers, *Inorg. Chem.*, **7**, 1362 (1968).

CdCl<sub>5</sub><sup>3-</sup> P(C<sub>6</sub>H<sub>5</sub>)<sub>5</sub> Co(C<sub>6</sub>H<sub>7</sub>NO)<sub>5</sub><sup>2+</sup> Ni(CN)<sub>5</sub><sup>3-</sup>

Figure 14.2 The 5-coordinate structures found in seven different species. The structures range from almost ideal trigonal bipyramidal to almost ideal square pyramidal. [Reproduced with permission from E. L. Muetterties and L. J. Guggenberger, J. Am. Chem. Soc., 96, 1748 (1974). Copyright 1974 American Chemical Society.]

Sb(C6H5)5

Ni(CN),3-


Nb(NC5H10)5

Further evidence for a small energy difference between trigonal bipyramidal and square pyramidal configurations is the ease with which the axial and equatorial ligands of trigonal bipyramidal complexes are scrambled. These ligands do maintain their stereochemical integrity long enough to allow structure determinations by diffraction methods and vibrational spectroscopic studies, but in some cases the axial and equatorial sites exchange at a rate such that these sites cannot be distinguished by nmr (which has a time scale<sup>4</sup> typically around 10<sup>-3</sup> s). For example, the <sup>13</sup>C nmr spectrum of Fe(CO)<sub>5</sub> shows only one resonance.<sup>5</sup> It is generally believed that the scrambling of the axial and equatorial sites occurs by the so-called Berry mechanism, which has already been discussed in terms of the stereochemical nonrigidity of PF<sub>5</sub> (Chap. 3).<sup>6</sup> In this mechanism, the square planar configuration is believed to be an intermediate or activated complex. Stereochemical nonrigidity, with consequent easy scrambling of ligands, is a relatively common feature of discrete complexes which have low activation energy routes between alternative geometries.<sup>7</sup>

Caution must be used when interpreting stoichiometric data as evidence for coordination number 5. Thus Cs<sub>3</sub>CoCl<sub>5</sub> contains the anions CoCl<sub>4</sub><sup>2-</sup> and Cl<sup>+</sup>, Tl<sub>2</sub>AlF<sub>5</sub> contains infinite chain anions of the type —F—AlF<sub>4</sub>—F—AlF<sub>4</sub>—, and Co(NH<sub>2</sub>CH<sub>2</sub>CH<sub>2</sub>NHCH<sub>2</sub>CH<sub>2</sub>NH<sub>2</sub>)<sub>2</sub>Cl<sub>2</sub> contains the 6-coordinate ions Co(NH<sub>2</sub>CH<sub>2</sub>CH<sub>2</sub>NHCH<sub>2</sub>CH<sub>2</sub>NH<sub>2</sub>)<sub>2</sub><sup>2+</sup> and the 4-coordinate ions CoCl<sub>4</sub><sup>2-</sup>.

#### **Coordination Number 6**

This is the commonest and most important coordination number for transition-metal complexes. The geometry usually corresponds to six coordinated atoms at the corners of an octahedron or a distorted octahedron. The regular octahedron, shown in the following sketch,



is a highly symmetric polyhedron. The reader can probably recognize the existence of six twofold rotational axes, four threefold rotational axes, three


<sup>&</sup>lt;sup>4</sup> We loosely refer to the minimum lifetime a species must have in order that a characteristic nmr spectrum be observed (related to the nmr frequency) as the nmr "time scale."

<sup>&</sup>lt;sup>5</sup> F. A. Cotton, A. Danti, J. S. Waugh, and R. W. Fessenden, J. Chem. Phys., 29, 1427 (1958).


<sup>&</sup>lt;sup>6</sup> For a historical survey of early work on stereochemical nonrigidity, see F. A. Cotton, J. Organomet. Chem., 100, 29 (1975).

<sup>&</sup>lt;sup>7</sup> J. P. Jesson and E. L. Muetterties, in "Dynamic Nuclear Magnetic Resonance Spectroscopy," L. Jackman and F. A. Cotton, eds., p. 253, Academic, New York, 1975.


fourfold rotational axes, three mirror planes of one type, six of another type, and a center of symmetry. (See Chap. 2 for a discussion of symmetry elements.) One common type of distortion of the octahedron, "tetragonal" distortion, involves either elongation or contraction of the octahedron along one of the fourfold symmetry axes, as shown below.



Another type of distortion, "trigonal" distortion, involves either elongation or contraction along one of the threefold symmetry axes, as shown below, to form trigonal antiprisms.



Very rarely one finds a 6-coordinate complex with trigonal prismatic geometry:



This geometry is unusual probably because repulsions between the coordinated atoms are greater than in the antiprismatic geometry which would be obtained if one rotated one triangular face 60° relative to the other.

It should be noted that, although a hexacoordinate complex of formula  $MA_6$  can have a regular octahedral geometry ( $O_h$  symmetry), complexes of the type  $MA_5B$ ,  $MA_4B_2$ , etc., cannot have  $O_h$  symmetry. In such mixed-ligand complexes, the ligands generally are not even at the corners of regular octahedra. Nevertheless, we usually refer to such complexes as octahedral complexes. Only when distortions from octahedral symmetry are great do we describe the structures differently. For example, the hexacoordinate iron compound  $H_2Fe(CO)_4$  has  $C_{2\nu}$  symmetry, and, although it has approximate octahedral structure, it can also be described as having the structure of a bicapped tetrahedron, in which the hydride ligands are positioned over two faces of an  $Fe(CO)_4$  tetrahedron. Of course, similar remarks regarding the loss of symmetry in complexes with more than one kind of ligand apply to other coordination numbers as well.

#### **Coordination Number 7**

Coordination numbers higher than 6 in discrete complexes are most commonly found for second- and third-row transition metals, lanthanides, and actinides. Coordination number 7 is relatively uncommon; it has been found with three limiting geometries: the pentagonal bipyramid, the monocapped octahedron, and the trigonal prism with one of its rectangular faces capped. Examples of pentagonal bipyramidal geometry are ReF<sub>7</sub>, V(CN)<sub>7</sub><sup>4-</sup>, Mo(CN)<sub>7</sub><sup>5-</sup>, UO<sub>2</sub>F<sub>5</sub><sup>3-</sup>, and NbOF<sub>6</sub><sup>3-</sup>. Examples of capped octahedra are Mo(CO)<sub>3</sub>(PEt<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub> and W(CO)<sub>4</sub>Br<sub>3</sub><sup>-</sup>, and examples of capped trigonal prisms are NbF<sub>7</sub><sup>2-</sup> and Mo(CNR)<sub>7</sub><sup>2+</sup>.

#### **Coordination Number 8**

Cubic coordination is almost never found in discrete complexes. However, 8-coordinate complexes often have the geometry of a square antiprism, which is

<sup>8</sup> M. G. B. Drew, Prog. Inorg. Chem., 23, 67 (1977).




Figure 14.3 The square antiprism (a) and the dodecahedron (b). Note that, whereas all the vertices of the square antiprism are equivalent, the dodecahedron contains two types of vertices (A and B).




Figure 14.4 The coordination Th[i-PrN(O)C(O)t-Bu]4 consists essentially of two interpenetrating tetrahedra. This geometry minimizes repulsions between the tert-butyl groups, which are situated at one end of each bidentate ligand. [Reproduced with permission from W. L. Smith and K. N. Raymond, J. Am. Chem. Soc., 103, 3341 (1981). Copyright 1981 American Chemical Society.]

obtained by rotating one face of a cube 45° relative to the opposite face. Another commonly found geometry is that of the dodecahedron, which may be looked upon as a combination of an elongated tetrahedron and a flattened tetrahedron. The square antiprism and the dodecahedron are illustrated in Fig. 14.3. These configurations have very similar energies, and, in the case of octacyano complexes such as Mo(CN)<sub>8</sub><sup>3- or 4-</sup> and W(CN)<sub>8</sub><sup>3- or 4-</sup>, either geometry can be obtained in solids by appropriate choice of the cation. For example, the Mo(CN)<sub>3</sub><sup>3</sup>ion is square antiprismatic in Na<sub>3</sub>Mo(CN)<sub>8</sub>·4H<sub>2</sub>O and dodecahedral in  $[N(n-C_4H_9)_4]_3Mo(CN)_8$ .

The eight coordinated oxygen atoms of the thorium hydroxamate Th[i-PrN(O)C(O)t-Bu]<sub>4</sub> are situated approximately at the corners of a cube. The geometry of this complex can be rationalized in terms of the asymmetry of the ligands, which have isopropyl groups at one end and relatively large tert-butyl groups at the other end. It appears that repulsions between the tert-butyl groups cause the four C—O oxygen atoms to be as far apart as possible, i.e., at the corners of a tetrahedron. The N-O oxygen atoms cap the faces of the tetrahedron and

thus form the approximately cubic geometry, as shown in Fig. 14.4.

#### **Higher Coordination Numbers**

Nine-coordinate complexes, such as Nd(H<sub>2</sub>O)<sub>9</sub><sup>3+</sup> and ReH<sub>9</sub><sup>2-</sup>, have geometries corresponding to a tricapped trigonal prism, as illustrated in Fig. 14.5. It appears that there are no examples of the capped square antiprism geometry in discrete ML<sub>9</sub> complexes.<sup>10</sup> Coordination numbers 10 to 12 are occasionally found in complexes of lanthanide and actinide elements but, in view of their rarity, are not very important. Twelve-coordination generally involves the formation of a distorted icosahedral geometry, either with six bidentate ligands, as in Ce(NO<sub>2</sub>)<sub>6</sub><sup>2</sup>-. or with four tridentate ligands, as in Zr(BH<sub>4</sub>)<sub>4</sub>, Hf(BH<sub>4</sub>)<sub>4</sub>, Np(BH<sub>4</sub>)<sub>4</sub>, and Pu(BH<sub>4</sub>)<sub>4</sub>. The structure of these borohydrides is illustrated in Fig. 14.6.

<sup>9</sup> W. L. Smith and K. N. Raymond, J. Am. Chem. Soc., 103, 3341 (1981).

<sup>&</sup>lt;sup>10</sup> L. J. Guggenberger and E. L. Muetterties, J. Am. Chem. Soc., 98, 7221 (1976).




Figure 14.5 The geometry of a 9-coordinate complex such as ReH<sub>9</sub><sup>2-</sup>. The ligands are at the vertices of a trigonal prism which has been capped on each of its rectangular faces.




Figure 14.6 The structure of the borohydrides of zirconium, hafnium, neptunium, and plutonium:  $M(BH_4)_4$ . The  $BH_4$  groups are tetrahedrally arranged, and the 12 coordinated hydrogen atoms are at the corners of a distorted icosahedron.

# The Relative Prevalence of Coordination Numbers 4, 6, 8, and 12

Coordination numbers of 4, 6, 8, and 12 are more common than coordination numbers of 5, 7, 9, 10, and 11, both in the solid state and in discrete complexes. It is easy to understand why these coordination numbers are common in solids, inasmuch as close-packed atoms have a coordination number of 12 and form

Table 14.1 Parameters proportional to bond distance and total bond energy in ML, complexes

Coordination	Optimum	de" ligand (b	n/d	$\Delta(n/d)$
no., n	figure	shood d mall		$\Delta n$
3 mar toylerone	Triangle	1.155	2.60	0.67
4	Tetrahedron	1.225	3.27	0.07
5	Trigonal bipyramid†	1.414	3.54	0.70
6	Octahedron	1.414	4.24	0.76
7	Monocapped octahedron	1.592	4.40	0.16
8	Square antiprism	1.645	4.86	0.40
9	Tricapped trigonal prism	1.732	5.20	0.34
10	Bicapped square antiprism	1.85	5.41	0.21
12	Icosahedron	1.902	6.31	0.45

<sup>†</sup> The tetragonal pyramid has the same value of d, etc.

both tetrahedral and octahedral holes, and the fluorite and cesium chloride structures involve coordination number 8. However, it is not as obvious why these same coordination numbers are also relatively prevalent in discrete ML. complexes. If the M-L bonds are assumed to be ionic (i.e., "bond energies" inversely proportional to the M-L distance), the preference for the common coordination numbers can be shown to be a simple matter of energetics. In Table 14.1 are given the M-L distances, d, corresponding to various coordination numbers, n, assuming that the ligand atoms are spheres of unit radius that touch each other and the atom M. The tabulated quantities n/d are thus proportional to the total bond energies of the ML<sub>n</sub> complexes, and the quantities  $\Delta(n/d)/\Delta n$ measure the increases in total bond energy accompanying unit increases in coordination number. It can be seen that, if a complex with a coordination number of 3, 5, or 7 were to increase its coordination number by 1, or if a complex with a coordination number of 10 were to increase its coordination number by 2, there would be a relatively large gain in bond energy that might more than compensate for the increase in interligand repulsion. On the other hand, if a complex with a coordination number of 5, 7, or 9 were to decrease its coordination number by 1, there would be a relatively small loss in bond energy that might be more than compensated by the decrease in interligand repulsion. Thus the  $\Delta(n/d)/\Delta n$  values in Table 14.1 show that complexes with coordination numbers other than 4, 6, 8, and 12 would be expected to lose or gain ligands relatively easily and thus to be relatively rare. of the annual late of the annual manual lines and

#### LIGANDS

The ligands of a complex may be classified by the way in which they are coordinated to the central metal atom. A "monodentate" ligand is one which is attached to the metal atom by a bond from only one atom (the donor atom) of the

ligand. Ligands such as H-, F-, Cl-, O2-, PR3, H2O, CH3-, OR-, and CO are monodentate. (The asterisks indicate the donor atoms of the polyatomic ligands.) A "polydentate" ligand (bidentate, tridentate, etc.) is one which can be attached to the metal atom by bonds from two or more donor atoms. Examples of bidentate ligands are ethylenediamine, NH2CH2CH2NH2 (which can coordinate through two nitrogen atoms and is often represented by the symbol "en"), and o-phenylenebis(dimethylarsine),

(which can coordinate through two arsenic atoms and is often represented by the symbol "diars").

### Complexes of Monodentate Ligands

Simple metal cations in aqueous solution, usually represented by formulas such as Mn2+, Fe3+, and Zn2+, are actually hydrated species which are better represented by formulas which indicate how many water molecules are directly coordinated to the metal atoms, e.g., Mn(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, Fe(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, and Zn(H<sub>2</sub>O)<sub>4</sub><sup>2+</sup>. 11 Treatment of such aqueous species with solutions containing appropriate monodentate ligands such as NH3 and Br can cause displacement of water molecules by the ligands:

$$Zn(H_2O)_4^{2+} + 4NH_3 \implies Zn(NH_3)_4^{2+} + 4H_2O$$
  
 $Fe(H_2O)_6^{3+} + Br^- \implies Fe(H_2O)_5Br^{2+} + H_2O$ 

Often abbreviated equations, such as the following, are written, but it should be remembered that water molecules play an important part in the reactions.

$$Zn^{2+} + 4NH_3 \Rightarrow Zn(NH_3)_4^{2+}$$
  
 $Fe^{3+} + Br^- \Rightarrow FeBr^{2+}$ 

When complexation of a metal ion takes place, it is often possible to detect the formation of a series of complexes, corresponding to the stepwise coordination of ligands to the metal ion. For example, in the case of the nickel ion, six different ammonia complexes are formed. The relative concentrations of the six complexes depend on the concentration of free ammonia and can be calculated from the equilibrium constants of the following reactions. 12 visually and an analysis

$$Ni^{2+} + NH_3 \implies NiNH_3^{2+} \log K = 2.72$$

12 A. E. Martell and R. M. Smith, "Critical Stability Constants," vols. 1-4, Plenum, New York, 1974-1977; the data for Ni2+ and NH3 are for 25°C and zero ionic strength.

For many non-transition-metal ions, e.g., Ag+, Zn2+, Cd2+, Hg2+, and Ga3+, the coordination number in aqueous solution is not known with certainty. See F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., p. 153, Wiley, New York, 1967.

$$NiNH_3^{2+} + NH_3 \implies Ni(NH_3)_2^{2+} \quad \log K = 2.17$$
 $Ni(NH_3)_2^{2+} + NH_3 \implies Ni(NH_3)_3^{2+} \quad \log K = 1.66$ 
 $Ni(NH_3)_3^{2+} + NH_3 \implies Ni(NH_3)_4^{2+} \quad \log K = 1.12$ 
 $Ni(NH_3)_4^{2+} + NH_3 \implies Ni(NH_3)_5^{2+} \quad \log K = 0.67$ 
 $Ni(NH_3)_5^{2+} + NH_3 \implies Ni(NH_3)_6^{2+} \quad \log K = 0.03$ 

It can be seen that the log K values decrease steadily as the number of coordinated ammonia molecules increases. This sort of trend is fairly generally observed and, in this case, is probably due to the steady buildup of negative charge on the nickel atom as ammonia molecules are coordinated. However, consider the following complexation constants for the chloride complexes of mercuric ion.<sup>13</sup>

$$Hg^{2+} + Cl^{-} \iff HgCl^{+} \qquad \log K = 6.74$$
 $HgCl^{+} + Cl^{-} \iff HgCl_{2} \qquad \log K = 6.48$ 
 $HgCl_{2} + Cl^{-} \iff HgCl_{3}^{-} \qquad \log K = 0.9$ 
 $HgCl_{3}^{-} + Cl^{-} \iff HgCl_{4}^{2-} \qquad \log K = 1.0$ 

In this case, the driving force for complexation drops off enormously after the disubstituted complex forms. The break in the sequence of  $\log K$  values at  $\operatorname{HgCl}_2$  is probably associated with a change in geometry. The species  $\operatorname{HgCl}_2$  is linear, whereas  $\operatorname{HgCl}_2^{2-}$  is tetrahedral. The data illustrate the strong tendency for  $d^{10}$  metal ions to form linear, 2-coordinate complexes.

Not all coordination compounds are as readily prepared as the nickel-ammonia complexes and the mercuric-chloride complexes. For example, cobalt(III) complexes are usually synthesized by the oxidation of aqueous cobalt(II) with oxygen or hydrogen peroxide in the presence of the ligands. Thus when air is bubbled vigorously through a solution containing cobalt(II), ammonia, ammonium ion, and suspended activated charcoal, good yields of the hexaamminecobalt(III) ion are obtained:

$$4\text{Co(NH}_3)_6^{2+} + \text{O}_2 + 4\text{NH}_4^+ \rightarrow 4\text{Co(NH}_3)_6^{3+} + 2\text{H}_2\text{O} + 4\text{NH}_3$$

A method for preparation of the remarkable complex Ru(NH<sub>3</sub>)<sub>5</sub>N<sub>2</sub><sup>2+</sup>, in which the ruthenium atom is coordinated to five ammonia molecules and to one end of a molecule of nitrogen, is schematically represented as follows.

<sup>&</sup>lt;sup>13</sup> Martell and Smith, loc. cit.; the data for Hg<sup>2+</sup> and Cl<sup>-</sup> are for 25°C and ionic strength 0.5.

The hexacoordinate chromium(0) complex Cr(CO)<sub>5</sub>PMe<sub>3</sub> can be prepared by the following sequence.

$$CrCl_3 \xrightarrow{Na} Cr(CO)_6 \xrightarrow{I^-} Cr(CO)_5I^-$$
high pressure

 $Cr(CO)_5PMe_3$ 

This route has the advantage of giving only the monosubstituted phosphine complex, Cr(CO)<sub>5</sub>PMe<sub>3</sub>. Direct reaction of PMe<sub>3</sub> and Cr(CO)<sub>6</sub> gives mono-, di-, and trisubstitution and is more difficult to control.

Frequently monodentate ligands are simultaneously coordinated to more than one metal atom and act as bridges between the metal atoms. (Obviously a complex with bridging ligands must be "polynuclear"; i.e., it must contain more than one metal center.) For example, when the pH of a  $VO_4^{3-}$  solution is reduced to a value below  $\sim 13$ , various polyvanadate ions form, in which tetrahedral  $VO_4$  groups form chains by sharing oxygen atoms. The simplest of these species is the divanadate ion,  $V_2O_7^{4-}$ :

Hydrolysis of the ferric ion not only involves the formation of FeOH<sup>2+</sup> and Fe(OH)<sub>2</sub><sup>+</sup>, but also at least one dinuclear species:

$$2\text{Fe}^{3+} + 2\text{OH}^- \implies \text{Fe}_2(\text{OH})_2^{4+} \qquad K \approx 10^{25}$$
  
or  $\text{Fe}_2\text{O}^{4+} + \text{H}_2\text{O}$ 

Notice that the reaction quotient is (complex)(Fe<sup>3+</sup>)<sup>-2</sup>(OH<sup>-</sup>)<sup>-2</sup> whether the complex is formulated as Fe<sub>2</sub>(OH)<sub>2</sub><sup>4+</sup> or Fe<sub>2</sub>O<sup>4+</sup>. Hence aqueous equilibrium data cannot be used to determine the nature of the bridging in this complex. Although the complex may consist of two hydroxide ions bridging two Fe(H<sub>2</sub>O)<sub>4</sub><sup>3+</sup> groups, magnetic and spectroscopic studies<sup>14</sup> suggest that it probably consists of an oxide ion bridging between two Fe(H<sub>2</sub>O)<sub>5</sub><sup>3+</sup> groups. Other examples of complexes containing bridging monodentate ligands, shown in Fig. 14.7, are Co<sub>4</sub>(CO)<sub>12</sub> (which contains three CO groups that bridge across Co—Co bonds), Rh<sub>6</sub>(CO)<sub>16</sub> (in which four CO groups occupy triply bridging positions over four of the triangular faces of the octahedron), and Au<sub>2</sub>Cl<sub>6</sub> (with two bridging chloride ions). More unusual examples, in which ligands occupy central positions in metal clusters, are shown in Fig. 14.8. In the volatile complex Be<sub>4</sub>O(O<sub>2</sub>CCH<sub>3</sub>)<sub>6</sub>, a central oxygen atom is surrounded tetrahedrally by four beryllium atoms, and in




Figure 14.7 Some complexes with bridging monodentate ligands. (a) Co<sub>4</sub>(CO)<sub>12</sub>; (b) Rh<sub>6</sub>(CO)<sub>16</sub>; (c) Au<sub>2</sub>Cl<sub>6</sub>.




Figure 14.8 Complexes with atoms inside metal clusters. (a)  $Be_4O(O_2CCH_3)_6$ , with only three of the acetate groups shown, for clarity; (b)  $HCo_6(CO)_{15}^-$ , with an "internal" hydrogen atom.

HCo<sub>6</sub>(CO)<sub>15</sub><sup>-</sup>, the hydrogen atom is situated in the center of the metal octahedron.<sup>15</sup>

### Polydentate Ligands

Some of the more important polydentate ligands, and the abbreviations used to represent them in formulas, are listed in Table 14.2. A number of simple ligands, not listed in this table, can be either monodentate or bidentate; these include  $SO_4^{2-}$ ,  $CO_3^{2-}$ ,  $NO_3^{-}$ , and  $CH_3CO_2^{-}$ , which can coordinate through one or two oxygen atoms. The complex formed by the coordination of a polydentate ligand to a metal atom is called a "chelate complex"; several such complexes are illustrated schematically in Fig. 14.9.

The term "chelate effect" refers to the apparent enhanced stability of a chelate complex compared to that of a complex with similar ligand donor groups but no rings. For example, consider the conversion of Cd(NH<sub>2</sub>CH<sub>3</sub>)<sub>4</sub><sup>2+</sup> to Cden<sub>2</sub><sup>2+</sup>:

$$Cd(NH_2CH_3)_4^{2+} + 2en \implies Cden_2^{2+} + 4CH_3NH_2$$

Because the equilibrium constant<sup>16</sup> for this reaction is  $1.2 \times 10^4$ , we might conclude that the reaction intrinsically has a large driving force. However, in a sense, this large driving force is fictitious, because the magnitude of the equilibrium constant depends on the arbitrary choice of the standard state for the solutes (conventionally, the 1 m solution). It has been pointed out that, if the standard state for solutes is taken to be the hypothetical mole fraction unity state, the driving force for chelation reactions of this type largely disappears.<sup>17</sup> In the case of an aqueous solution, unit molality corresponds to a mole fraction of 1/55.5; hence for the cited reaction, the equilibrium constant becomes  $1.2 \times 10^4 \times (1/55.5)^2$ , or 3.9. In other words, chelation reactions proceed primarily because they are generally carried out in dilute solutions; their driving force increases with increasing dilution because of the mass action effect. It is significant that the enthalpies of chelation reactions of the type we are discussing (in which the nature

<sup>&</sup>lt;sup>17</sup> A. W. Adamson, J. Am. Chem. Soc., 76, 1578 (1954).




Figure 14.9 Schematic representations of chelates. (a) A complex with three bidentate ligands, such as  $Co(en)_3^{3+}$ ; (b) meridional chelation of a tridentate ligand; (c) facial chelation of a tridentate ligand; (d) the chelation of a tetradentate ligand such as NTA<sup>3-</sup>. Notice that, in all these cases, adjacent donor atoms of a ligand are coordinated cis to one another.

<sup>15</sup> D. W. Hart et al., Angew. Chem. Int. Ed., 18, 80 (1979).

<sup>16</sup> Martell and Smith, loc. cit.

of the ligand donor groups remains approximately constant) are generally small. This fact again emphasizes that the apparent free-energy change is mainly determined by  $T\Delta S^{\circ}$ , the value of which depends on the choice of standard state.

 $\beta$ -Diketones, e.g., acetylacetone, can be readily deprotonated to form mononegative anions with delocalized  $\pi$  electrons. By chelation with a metal ion, very stable six-membered rings can be formed by these ligands:

When the coordination number of the metal ion is twice its charge, it is possible to prepare neutral  $\beta$ -diketonates, such as Be(acac)<sub>2</sub> and Cr(hfa)<sub>3</sub>, which are volatile and soluble in organic solvents. Bidentate ligands frequently act as bridges between metal atoms. For example, the addition of acetate to a solution of a chromium(II) salt precipitates Cr<sub>2</sub>(OAc)<sub>4</sub> · 2H<sub>2</sub>O, in which the two chromium atoms are linked together by the four bridging acetate ions:

$$H_2O$$
 $CH_3$ 
 $CH_3$ 

This is one member of a large family of compounds (differing in the metal atoms, the carboxylate groups, and the axial monodentate ligands) with metal-metal bonding.<sup>18</sup>

Most hexacoordinate complexes with three bidentate ligands have structures which are intermediate between trigonal antiprismatic and trigonal prismatic. That is, the twist angle (defined in Fig. 14.10) generally lies between 0°, corresponding to the trigonal prism, and 60°, corresponding to the trigonal antiprism. Various factors are believed to be important in determining the geometry in such

<sup>&</sup>lt;sup>18</sup> For further discussion, see pp. 370–372.

Table 14.2 Some polydentate ligands and their abbreviations

Name 1 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	Formula	Denticity†	Abbreviation
Ethylenediamine	H <sub>2</sub> NCH <sub>2</sub> CH <sub>2</sub> NH <sub>2</sub>	2	en R
2,2'-Bipyridine		2	bipy
1,10-Phenanthroline		2	phen
o-Phenylenebis(dimethylarsine)	AsMe <sub>2</sub> AsMe <sub>2</sub>		diars
1,2-Bis(diphenylphosphino)ethane	$CH_2-P(C_6H_5)_2$ $CH_2-P(C_6H_5)_2$	the thread of a poly all such a such	diphos
Acetylacetonate	O O-      CH <sub>3</sub> CCH <sub>2</sub> CCH <sub>3</sub>	2	acac-
Hexafluoroacetylacetonate	O O-       CF,CCH <sub>2</sub> CCF,	2 113	hfa-

Salicylaldiminate	O-	sal-
8-quinolinate		"oxinate"
Oxalate	-O <sub>2</sub> CCO <sub>2</sub> -	OX <sup>2-</sup>
Terpyridine (tridentate)		terpy
Diethylenetriamine (tridentate)	CH <sub>2</sub> CH <sub>2</sub> NH <sub>2</sub> NH CH <sub>2</sub> CH <sub>2</sub> NH <sub>2</sub>	dien
Triethylenetetramine (tetradentate)	N(CH <sub>2</sub> CH <sub>2</sub> NH <sub>2</sub> ) <sub>3</sub>	tren
Nitrilotriacetate (tetradentate)	N(CH <sub>2</sub> CO <sub>2</sub> ) <sub>3</sub> <sup>3-</sup>	NTA <sup>3-</sup>
Ethylenediaminetetraacetate (hexadentate)	-O <sub>2</sub> CCH <sub>2</sub> CH <sub>2</sub> CO <sub>2</sub> - NCH <sub>2</sub> CH <sub>2</sub> N CH <sub>2</sub> CO <sub>2</sub> - 6 CH <sub>2</sub> CO <sub>2</sub> -	EDTA4-

CH=NR

<sup>†</sup> Number of donor atoms.




Figure 14.10 View down the threefold axis of a tris(bidentate ligand) complex.

complexes. One important factor is the "bite" distance of the ligand, i.e., the distance between the two donor atoms of the same chelate. 19,20 As the ratio of the bite distance to the metal – donor atom distance decreases, the twist angle tends to decrease. (See Fig. 14.11.) This correlation of twist angle with bite distance can be rationalized in terms of ligand-ligand repulsion energies. A set of tris-chelate

<sup>19</sup> D. L. Kepert, Inorg. Chem., 11, 1561 (1972); Prog. Inorg. Chem., 23, 1 (1977).

<sup>20</sup> A. Avdeef and J. P. Fackler, Jr., Inorg. Chem., 14, 2002 (1975).




Figure 14.11 Plot of the ratio of the ligand bite distance to the metal—donor atom distance versus the twist angle. Group A: nitrogen ligands ( $\triangle$ ), oxygen ligands ( $\bigcirc$ ), sulfur and selenium ligands ( $\triangle$ ), acac-type ligands ( $\bigcirc$ ). Group B: dithiolate ligands and Se analogs ( $\square$ ). [Adapted with permission from A. Avdeef and J. P. Fackler, Inorg. Chem., 14, 2002 (1975). Copyright 1975 American Chemical Society.]

complexes having rather distinctive properties (represented as open squares in Fig. 14.11) are those with dithiolate ligands of the following type (or the selenium analogs):

Some of these complexes have essentially perfect trigonal prismatic geometry  $(\phi = 0^{\circ})$ . Special electronic factors are probably responsible for these unusual structures.<sup>21</sup>

### Pi Complexes

Many olefins, aromatic species, and other  $\pi$ -bonded systems can function as ligands in which the  $\pi$ -bonded atoms coordinate to metal atoms. Ethylene, benzene, the allyl anion  $(C_3H_5^-)$ , the cyclopentadienide ion  $(C_5H_5^-)$ , and the cycloheptatriene (tropylium) cation  $(C_7H_7^+)$  are important examples of such ligands. For example, the trichloro(ethylene)platinate(II) ion is readily synthesized by displacing one of the chloride ions from  $PtCl_4^{2-}$  by ethylene:

$$PtCl_4^{2-} + C_2H_4 \longrightarrow Pt(C_2H_4)Cl_3^- + Cl^-$$

The  $\pi$ -allyl complex  $C_3H_5Mn(CO)_4$  is prepared by the following sequence:

Note that the conversion of the intermediate  $\sigma$ -allyl complex (which has only one Mn—C bond) to the  $\pi$ -allyl complex is accompanied by the loss of a CO molecule from the complex. Bis(cyclopentadienyl) iron ("ferrocene") can be prepared by treating an iron(II) halide with the cyclopentadienide ion:

$$C_5H_6 \xrightarrow{\text{KOH}} C_5H_5^- \xrightarrow{\text{FeCl}_2} \text{Fe}(C_5H_5)_2$$

The structures of the three  $\pi$ -bonded organometallic compounds just discussed are shown in Fig. 14.12.

Pi complexes differ from chelate complexes in two important respects: (1) The coordinated atoms of the ligand are coplanar and bonded together as a chain or ring, with the metal atom situated on one side of the plane; (2) the number of metal-ligand bonding electron pairs provided by the ligand (or the effective number of coordination sites occupied by the ligand) is less than the number of coordinated atoms. Thus ethylene in effect occupies one of the square planar





Figure 14.12 Structures of three  $\pi$ -bonded organometallic compounds. (a) Pt(C<sub>2</sub>H<sub>4</sub>)Cl<sub>3</sub><sup>-</sup>; (b) C<sub>3</sub>H<sub>5</sub>Mn(CO)<sub>4</sub>; (c) Fe(C<sub>5</sub>H<sub>5</sub>)<sub>2</sub>, ferrocene.

coordination sites in  $Pt(C_2H_4)Cl_3^-$ ; the  $\pi$ -allyl group occupies two of the octahedral sites in  $\pi$ - $C_3H_5Mn(CO)_4$ , and the two  $C_5H_5^-$  ions in  $Fe(C_5H_5)_2$  in effect occupy six octahedral coordination sites. The details of the bonding in such compounds will be discussed in later chapters.

Even hetero  $\pi$ -bonded species can form  $\pi$  complexes with transition metals.<sup>22</sup> For example, pyrrole can be deprotonated to form the pyrrolide anion, analogous to the  $C_5H_5^-$  ion. The pyrrolide anion reacts with a metal carbonyl halide to form a  $\sigma$  complex which may then be converted via loss of two CO ligands into the corresponding  $\pi$  complex, as shown in the following scheme.


We have seen examples in which the allyl group is attached to a metal atom by either one or three carbon atoms and in which the pyrrolide ion is attached by either one or five atoms. There are many other examples of variations in the mode of bonding of  $\pi$  ligands. It is interesting that the  $C_7H_7^+$  ligand can coordinate either seven, five, three, or one carbon atom to a metal atom, as in the following examples:

<sup>22</sup> K. H. Pannell, B. L. Kalsotra, and C. Parkanyi, *J. Heterocyclic Chem.*, **15**, 1057 (1978). A review on heterocyclic  $\pi$  complexes.



Cotton<sup>23</sup> devised the "hapto" nomenclature to describe in a simple way the various possible modes of bonding between metals and  $\pi$  systems. Based on this nomenclature, the C<sub>7</sub>H<sub>7</sub>-metal coordination in C<sub>7</sub>H<sub>7</sub>Mo(CO)<sub>3</sub>+ is called "heptahapto" (n<sup>7</sup>) coordination, that in C<sub>7</sub>H<sub>7</sub>Mn(CO)<sub>3</sub> is called "pentahapto" (n<sup>5</sup>) coordination, etc. The formulas for these complexes can be modified to express these modes of bonding as follows:  $(\eta^7 - C_7 H_7) Mo(CO)_3^+$ ,  $(\eta^5 - C_7 H_7) Mn(CO)_3$ , etc. In Ti(C<sub>5</sub>H<sub>5</sub>)<sub>4</sub>, two of the cyclopentadienyl groups are pentahapto and two are monohapto, as shown in Fig. 14.13. The proton nmr spectrum of this compound, shown in Fig. 14.14, undergoes marked changes as the temperature is changed.24 At temperatures around -30°C two peaks, corresponding to the  $\eta^5$ -C<sub>5</sub>H<sub>5</sub> and  $\eta^1$ -C<sub>5</sub>H<sub>5</sub> groups, are seen. The fact that only one peak is observed for the monohapto groups indicates that an intramolecular rearrangement of each monohapto ring occurs rapidly enough to make the protons equivalent on the

<sup>23</sup> F. A. Cotton, J. Am. Chem. Soc., 90, 6230 (1968).






Figure 14.13 Structure of Ti(C5H5)4. Notice that two of the rings are σ-bonded, through one carbon atom (monohapto), and that two of the rings are  $\pi$ -bonded, through five carbon atoms (pentahapto).




Figure 14.14 The pmr spectrum of  $Ti(C_5H_5)_4$  at several temperatures. The X corresponds to  $(C_5H_5)_3$  TiClimpurity. [Reproduced with permission from J. L. Calderon, F. A. Cotton, B. G. DeBoer, and J. Takats, J. Am. Chem. Soc., 92, 3801 (1970). Copyright 1970 American Chemical Society.]

time scale of the nmr experiment (roughly, 10<sup>-3</sup> s). If the sample temperature is raised above 40°C, the two nmr peaks merge to form a single band. This behavior is ascribed to an increase in the rate of a scrambling process in which the two types of rings interchange their roles, so as to make all the protons equivalent on the nmr time scale.

### **ISOMERISM**

Around the turn of the century, Alfred Werner explained many of the chemical and physical properties of a large number of complexes by means of his revolu-

Table 14.3 Properties of platinum(IV) complexes of ammonia and chloride

Old formula	Relative molar conductivity of aqueous solution	No. of isomers known	Werner's formula
PtCl <sub>4</sub> · 6NH <sub>3</sub>	523	"HM"	[Pt(NH <sub>3</sub> ) <sub>6</sub> ]Cl <sub>4</sub>
PtCl <sub>4</sub> · 5NH <sub>3</sub>	404	1/ 10	[Pt(NH <sub>3</sub> ) <sub>5</sub> Cl]Cl <sub>3</sub>
PtCl <sub>4</sub> · 4NH <sub>3</sub>	228	2	[Pt(NH <sub>3</sub> ) <sub>4</sub> Cl <sub>2</sub> ]Cl <sub>2</sub>
PtCl <sub>4</sub> · 3NH <sub>3</sub>	97	2	[Pt(NH <sub>3</sub> ) <sub>3</sub> Cl <sub>3</sub> ]Cl
PtCl <sub>4</sub> · 2NH <sub>3</sub>	0	2	$[Pt(NH_3)_2Cl_4]$
PtCl <sub>4</sub> · KCl · NH <sub>3</sub>	108	1	K[Pt(NH <sub>2</sub> )Cl <sub>5</sub> ]
PtCl <sub>4</sub> · KCl · NH <sub>3</sub>	256	1 5	K <sub>2</sub> [PtCl <sub>6</sub> ]

by the data in Table 14.3. Werner proposed that, in each of these seven compounds, the platinum +4 ion is strongly coordinated to six ligands and that, in those cases in which the resulting complex has a net charge, the counter-ions (Cl<sup>-</sup> or K<sup>+</sup>) are not directly coordinated to the platinum. The formulas given in the fourth column, in which the formulas of the complexes are written inside brackets, readily explain the relative electrical conductivity data of the second column. As expected, the molar conductivity increases with the number of ions in the formula and is zero for the neutral complex Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>4</sub>.


# Cis-Trans Isomerism

The number of isomers, given in column 3 of Table 14.3, was explained by Werner by postulating that the six ligands of each complex are attached to the platinum atom at the vertices of an imaginary octahedron around the platinum atom. Thus, in the complex  $Pt(NH_3)_4Cl_2^{2+}$ , the two chlorine atoms can be either at adjacent (cis) positions of the octahedron, as in the following representations:

$$H_3N$$
 $Pt$ 
 $H_3N$ 
 $Pt$ 
 $H_3N$ 
 $Pt$ 
 $NH_3$ 
 $NH_3$ 
 $NH_3$ 


<sup>&</sup>lt;sup>25</sup> A. Werner, Z. Anorg. Chem., 3, 267 (1893); A. Werner, "Neuere Anschauungen auf der Gebiete der Anorganischen Chemie," Friedrich Vieweg, Brunswick, Germany, 1905; G. B. Kauffman, "Classics in Coordination Chemistry, Part I, The Selected Papers of Alfred Werner," Dover, New York, 1968.

or at opposite (trans) positions, as in the following representations:




In a completely analogous way the isomerism of Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>4</sub> can be explained in terms of cis and trans configurations of the coordinated NH<sub>3</sub> molecules.

One of the isomers of Pt(NH<sub>3</sub>)<sub>3</sub>Cl<sub>3</sub><sup>+</sup> has the structure in which the three NH<sub>3</sub> molecules are cis to one another and the three Cl atoms are cis to one another,




and the other isomer has the structure in which two NH<sub>3</sub> molecules are trans to one another and two Cl atoms are trans to one another, making the structure in which two NH<sub>3</sub> molecules are trans to




The former, "facially" coordinated, structure has one threefold rotational axis of symmetry, whereas the latter, "meridionally" coordinated, structure has one twofold rotational axis of symmetry.

Cis-trans isomerism is also found in square planar complexes. For example, two types of Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub> are known, having the following structures:



#### **Optical Isomerism**

A complex is optically active if its structure cannot be superimposed on its mirror image. For example, consider the complex *cis*-Co(en)<sub>2</sub>(NO<sub>2</sub>)<sub>2</sub><sup>+</sup>, which can exist in either of the following configurations:



It should be noted that each structure is the mirror image of the other and that the structures are not superimposable. Consequently they are optical isomers. The usual method for the synthesis of cis-Co(en)<sub>2</sub>(NO<sub>2</sub>)<sub>2</sub>+ yields a product containing equal amounts of these isomers, i.e., a racemic mixture which does not rotate polarized light. The isomers cannot be separated by the usual techniques for separating other types of isomers (e.g., cis and trans isomers) because the optical isomers have essentially the same physical<sup>26</sup> and chemical properties, at least in systems which contain no other optically active species. However, optical isomers do interact differently with optically active species, and such specific interactions form the basis of methods for separating optical isomers. For example, if a solution containing the isomers of Co(en)<sub>2</sub>(NO<sub>2</sub>)<sub>2</sub>+ is treated with potassium antimonyl-(+)-tartrate, the [(-)-cis-Co(en)<sub>2</sub>(NO<sub>2</sub>)<sub>2</sub>][(+)-SbOC<sub>4</sub>H<sub>4</sub>O<sub>6</sub>] combination (which is only slightly soluble) precipitates as crystals, leaving the (+)-cis-Co(en)<sub>2</sub>(NO<sub>2</sub>)<sub>2</sub>+ isomer in solution.

### Linkage Isomerism

Some ligands, called "ambidentate" ligands,<sup>27</sup> can bond to a metal atom through more than one type of donor atom. This flexibility leads to "linkage isomerism," first discovered by Jörgensen in 1894.<sup>28</sup> He characterized the nitrito and nitro isomers of the complex having the formula Co(NH<sub>3</sub>)<sub>5</sub>NO<sub>2</sub><sup>2+</sup>. In the red nitritopentaamminecobalt(III) ion, the nitrite ion is coordinated through one of its oxygen atoms; thus, Co—O—N . In the yellow nitropentaammineco-

balt(III) ion, the nitrite ion is coordinated through its nitrogen atom; thus,

Co-N. The nitrito isomer is prepared by treatment of 
$$Co(NH_3)_5H_2O^{3+}$$
 with

<sup>&</sup>lt;sup>26</sup> Of course, optical isomers rotate the plane of polarized light in opposite directions.

<sup>&</sup>lt;sup>27</sup> A. H. Norbury and A. I. P. Sinha, Quart. Rev., 24, 69 (1970).

<sup>&</sup>lt;sup>28</sup> S. M. Jörgensen, Z. Anorg. Chem., 5, 169 (1894).

a cold, buffered HNO<sub>2</sub>-NO<sub>2</sub>-solution. The reaction is believed to proceed by the following mechanism:<sup>29</sup>

$$\begin{array}{c} \text{Co(NH}_3)_5\text{H}_2\text{O}^{3+} + \text{OH}^- & \stackrel{\text{fast}}{\Longrightarrow} & \text{Co(NH}_3)_5\text{OH}^{2+} + \text{H}_2\text{O} \\ \\ 2\text{HNO}_2 & \stackrel{\text{fast}}{\Longrightarrow} & \text{N}_2\text{O}_3 + \text{H}_2\text{O} \\ \\ \text{Co(NH}_3)_5\text{OH}^{2+} + \text{N}_2\text{O}_3 & \longrightarrow & \begin{bmatrix} (\text{NH}_3)_5\text{Co} - \text{O} - \text{H} \\ \text{O} - \text{N} - \text{O} \text{NO} \end{bmatrix} \\ \\ \downarrow & \downarrow & \downarrow & \downarrow \\ \text{(NH}_3)_5\text{Co} - \text{ONO}^{2+} + \text{HONO} \end{array}$$

The nitrito complex, when heated, rearranges by an intramolecular process to the more stable nitro complex. The nitrite ion can coordinate in three other ways, as shown below.

All three of these types of coordination are found in the complex Ni<sub>3</sub>(3-methylpyridine)<sub>6</sub>(NO<sub>2</sub>)<sub>6</sub>, which has the following structure.<sup>30</sup>

Another ambidentate ligand, the thiocyanate ion (SCN<sup>-</sup>), can bond to metal atoms through the sulfur atom or the nitrogen atom. Soft metal ions such as Pd<sup>2+</sup> and Hg<sup>2+</sup> usually form sulfur-bonded thiocyanate complexes, whereas relatively hard metal ions such as Cr<sup>3+</sup> and Fe<sup>2+</sup> form nitrogen-bonded thiocyanate complexes. In a few cases, e.g., Pdbipy-(NCS)<sub>2</sub> and Pdbipy(SCN)<sub>2</sub>, linkage isomers have been prepared. The nature of the bonding in such isomers can be readily determined by infrared spectroscopy. The C—S stretching vibration falls in the range 690 to 720 cm<sup>-1</sup> for M—SCN bonding, and in the range 780 to 860 cm<sup>-1</sup> for M—NCS bonding.

In principle, the cyanide ion, CN-, is an ambidentate ligand, but there are no

<sup>&</sup>lt;sup>29</sup> J. L. Burmeister and F. Basolo, Prep. Inorg. React., 5, 1 (1968).

<sup>30</sup> D. M. L. Goodgame, M. A. Hitchman, and D. F. Marsham, J. Chem. Soc. (A), 259 (1971).




Figure 14.15 One-eighth of the unit cell of prussian (Turnbull's) blue. For simplicity, the alkali-metal ions and water molecules are omitted. Each iron atom is octahedrally coordinated.

known stable discrete complexes with metal - NC bonding.31 However, there are many examples of solids in which the cyanide ion bridges between metal ions, the carbon atom to one metal ion and the nitrogen atom to another. For example. practically all chemists know that treatment of aqueous Fe3+ with hexacvanoferrate(II), Fe(CN)<sub>6</sub><sup>4-</sup>, yields a blue precipitate called "prussian blue" and that treatment of aqueous Fe2+ with hexacyanoferrate(III), Fe(CN)63-, yields a blue precipitate called "Turnbull's blue." These precipitates are actually identical; the empirical formula is  $Fe_4[Fe(CN)_6]_3 \cdot xH_2O(x = 14 \text{ to } 16)$ , i.e., "ferric ferrocyanide." The structure (shown in part in Fig. 14.15) consists of a simple cubic array of alternating Fe(II) and Fe(III) atoms, with the cyanide ions bridging thus: Fe(II)—CN—Fe(III). Of course, a perfect cubic array of this type would have equal numbers of Fe(II) and Fe(III) atoms, inconsistent with the formula. X-ray and neutron diffraction data<sup>32</sup> indicate that one-fourth of the Fe<sup>II</sup>(CN),<sup>4-</sup> groups are randomly vacant. Six molecules of water are coordinated to Fe(III) at empty nitrogen sites; thus the average composition of each Fe(III) coordination unit is Fe<sup>III</sup>(NC)<sub>4.5</sub>(OH<sub>2</sub>)<sub>1.5</sub>. Approximately eight additional water molecules are present either as isolated molecules at the centers of the unit cell octants or as water molecules connected by hydrogen bonds to the coordinated ones.

In stable transition-metal carbonyls, the carbonyl group is always attached through the carbon atom (at least whenever CO functions as a monodentate ligand). However, in studies33 of the cocondensation of Au atoms with a large excess of CO at 6 to 10 K, spectroscopic data suggest the formation of isocarbonyl(carbonyl)gold, COAuCO. The normal isomer, OCAuCO, was formed when Au and CO were cocondensed in rare-gas matrices.

# STRUCTURAL REORGANIZATION

The fact that it is possible to isolate and to characterize structural isomers of the types that we have discussed (cis-trans, optical, and linkage) indicates that the

<sup>&</sup>lt;sup>31</sup> Metastable Co(CN)<sub>6</sub>NC<sup>3-</sup> and Cr(H<sub>2</sub>O)<sub>5</sub>NC<sup>2+</sup> have been prepared. See J. Halpern and S. Nakamura, J. Am. Chem. Soc., 87, 3002 (1965); J. P. Birk and J. H. Espenson, J. Am. Chem. Soc., 90, 1153 (1968).

<sup>&</sup>lt;sup>32</sup> A. Ludi et al., *Inorg. Chem.*, **16**, 2704 (1977); **19**, 956 (1980).

<sup>33</sup> D. McIntosh and G. A. Ozin, Inorg. Chem., 16, 51 (1977).

bonds between the metal atoms and ligands in these isomers are not rapidly broken and re-formed under ordinary conditions. If the ligand-to-metal bonds did dissociate rapidly, equilibrium would be rapidly achieved and it would be possible to isolate only the thermodynamically stable isomer (or mixture, in the case of optical isomers). Rapid interconversion of isomers is found in many complexes. For example, aluminum(III) forms a trisacetylacetonato complex,  $Al(C_5H_7O_2)_3$ , which undoubtedly consists of a mixture of (+) and (-) optical isomers. However, because of the rapid interconversion of these isomers, nobody has thus far succeeded in separating them. Obviously the prediction of the relative kinetic stabilities of coordination compounds is an important problem, one which we shall take up in Chap. 19.

#### **PROBLEMS**

- \*14.1 Plot, on one graph, separate curves showing the concentrations of Hg<sup>2+</sup>, HgCl<sup>+</sup>, etc., as functions of log (Cl<sup>-</sup>) for an aqueous system 0.1 *M* in mercury(II). What can you conclude about the relative stabilities of the complexes?
- \*14.2 In crystalline AgO, half of the silver atoms are linearly coordinated to two nearest-neighbor oxygen atoms and half are coordinated to four nearest-neighbor oxygen atoms in a square planar configuration. Explain.
  - 14.3 Predict the structures of the following discrete complexes: OsO<sub>4</sub>, VOCl<sub>3</sub>, Pt(NH<sub>3</sub>)<sub>4</sub><sup>2+</sup>, Ag(NH<sub>3</sub>)<sub>2</sub><sup>+</sup>, Pt(PPh<sub>3</sub>)<sub>4</sub>, Nb<sub>2</sub>Cl<sub>10</sub>, Cr<sub>2</sub>O<sub>7</sub><sup>2-</sup>, Ru<sub>4</sub>F<sub>20</sub>.
  - **14.4** Draw all the possible isomers (including optical) for each of the following complexes. (Be careful not to draw the same structure twice.) (a)  $Co(en)_2(H_2O)Cl^{2+}$ , (b)  $Co(NH_3)_3(H_2O)ClBr^+$ , (c)  $Pt(NH_3)(NH_2OH)(NO_2)(C_3H_4N)^+$ .
  - 14.5 Which type of octahedral distortion would you expect in Co(en)<sub>3</sub><sup>3+</sup>? In trans-Co(NH<sub>3</sub>)<sub>4</sub>Cl<sub>2</sub><sup>+</sup>?
- \*14.6 The <sup>13</sup>C nmr spectrum of an aqueous solution of Mo(CN)<sub>8</sub><sup>4-</sup> shows only one peak. What may one conclude about the structure of the aqueous complex ion?
- 14.7 How many isomers are possible for the complexes (a)  $MX_4Y_2$  and  $MX_3Y_3$ , assuming trigonal prism geometry, (b)  $MX_6Y_2$ , assuming square antiprism geometry, and (c)  $MX_6Y_2$ , assuming dodecahedron geometry?
- \*14.8 Suggest experimental techniques for determining whether  $C_7H_7Mo(CO)_2C_5H_5$  has the structure  $(\eta^7-C_7H_7)Mo(CO)_2(\eta^1-C_5H_5)$  or  $(\eta^3-C_7H_7)Mo(CO)_2(\eta^5-C_5H_5)$ , aside from an x-ray structure determination. Explain how you would interpret the experimental data.
- \*14.9 Platinum(II) forms a 4-coordinate complex with one molecule of mesostilbenediamine,

and one molecule of isobutylenediamine.

It is possible to resolve the complex into optically active isomers. Show that this result proves that the complex does not have tetrahedral geometry and that the result is consistent with square planar geometry.

14.10 Sketch three different trigonal bipyramidal structures for (Me<sub>2</sub>PCH<sub>2</sub>PMe<sub>2</sub>)<sub>2</sub>FeCO and identify the optical isomers. Do the same for square pyramidal.

# THE BONDING IN COORDINATION COMPOUNDS

Chemists have found that two approaches are particularly valuable for describing the bonding in transition-metal complexes: the "electrostatic ligand-field" approach and the molecular orbital (MO) approach. These methods are fundamentally quite different; the first assumes essentially pure ionic interactions between the central metal ion and the surrounding ligand atoms or anions, and the second assumes the formation of covalent bonds between the central metal atom and surrounding ligands. Yet, as we shall see, these apparently contradictory methods lead to electronic energy level diagrams which are remarkably similar. Although the MO approach gives a more realistic and more widely applicable picture of bonding, the qualitative results of the simpler electrostatic ligand-field theory are completely adequate for many purposes.

In this chapter we describe both approaches, using only a few examples to illustrate their application. In subsequent chapters we shall consider in detail various physical and chemical properties of transition-metal compounds, using one or the other of these bonding approaches as a basis for systemization.

# **ELECTROSTATIC LIGAND-FIELD THEORY**

Let us consider the bonding in transition-metal complexes from a very simple electrostatic point of view. We may consider an octahedral complex as a metal

The pure electrostatic approach, first expounded by Bethe in 1929, is sometimes referred to as "crystal-field theory," and the expression "ligand-field theory" is sometimes reserved for a modification in which certain physically unrealistic features of the model are corrected for. However, the expression "crystal-field theory" has misleading connotations, and "electrostatic ligand-field theory" is much more descriptive.

ion surrounded by either six negative ions or six dipolar groups with their negative ends pointing toward the metal ion. These ligands occupy the vertices of an imaginary octahedron. It is completely arbitrary how we align the cartesian coordinates of the metal ion with respect to the six ligands; for convenience, we suppose that the ligands lie exactly on the x, y, and z axes of the metal atom, as shown in Fig. 15.1. In view of the spatial configurations of the five metal d orbitals (see Fig. 1.9), which are degenerate in the free atom or ion, it is obvious that these d orbitals are no longer degenerate in the octahedral electric field of the ligands. In the complex, the lobes of the  $d_{yy}$ ,  $d_{yz}$ , and  $d_{yz}$  orbitals are directed between the ligands, and the lobes of the  $d_{zz}$  and  $d_{yz\rightarrow yz}$  orbitals are directed toward the ligands. Thus the five d orbitals are split by the octahedral field into two groups: a triply degenerate group composed of the  $d_{xy}$ ,  $d_{xz}$ , and  $d_{yz}$  orbitals (which are labeled by the group-theoretical symbol  $t_{2p}$ ) and a doubly degenerate group composed of the  $d_{z^2}$  and  $d_{x^2-y^2}$  orbitals (labeled by the symbol  $e_g$ ). From Fig. 1.9, it should be obvious that, in an octahedral environment, the  $t_{2g}$  orbitals are equivalent, but it is not obvious that the  $e_g$  orbitals are equivalent; however, this equivalence becomes apparent when one recognizes that the  $d_{zz}$  orbital is a kind of hybrid of the  $d_{z^2-x^2}$  and  $d_{z^2-v^2}$  functions.

The d electrons of the metal ion would obviously prefer to occupy the  $t_{2g}$  set of orbitals than the  $e_g$  set of orbitals. That is, the  $e_g$  energy level lies above the  $t_{2g}$ energy level. Figure 15.2 is a plot of the energies of the d orbitals of a metal atom as a function of the distribution of six negative charges on a spherical shell surrounding the atom. The left side of the diagram corresponds to a uniform distribution of the six charges on the spherical shell; the right side corresponds to placing the negative charges at octahedral positions. Because the total energy of the d-orbital system is independent of the way the negative charges are distributed on the sphere, the "center of gravity" of the energy levels remains constant. Hence the  $e_g$  level is raised 1.5 times as much as the  $t_{2g}$  level is lowered. If we call the total octahedral-field splitting  $\Delta_o$ , then the relative energies of the  $e_g$  and  $t_{2g}$ levels are  $\frac{3}{5}\Delta_o$  and  $-\frac{2}{5}\Delta_o$ , respectively.<sup>2</sup>

<sup>2</sup> In some literature,  $\Delta_o$  is referred to as 10Dq.






Figure 15.1 Octahedral arrangement of negative ligands around a metal ion.



Charge distribution around ion

Figure 15.2 Splitting of d-orbital energies in an octahedral field.

Let us now consider a tetrahedral complex. For convenience, we shall consider the ligands to occupy tetrahedral corners of a cube positioned so that the cartesian coordinates of the metal atom pass through the centers of the cube faces, as shown in Fig. 15.3. The lobes of the  $d_{xy}$ ,  $d_{xz}$ , and  $d_{yz}$  orbitals are directed toward the midpoints of the cube edges, at an angle of 35.3° with respect to the ligands. The lobes of the  $d_{z^2}$  and  $d_{x^2-y^2}$  orbitals are directed toward the cube faces and bisect the angles between pairs of ligands, thus making an angle of 54.7° with the ligands. Calculations show that electrons in the  $d_{z^2}$  and  $d_{x^2-y^2}$  orbitals are repelled less by the ligands than are electrons in the  $d_{xy}$ ,  $d_{xz}$ , and  $d_{yz}$  orbitals. As a result, we obtain a splitting of the d-orbital energies into two levels, as shown in Fig. 15.4. The energy of the triply degenerate  $t_2$  set is raised  $\frac{2}{5}\Delta_t$ , and the energy of the double degenerate e set is lowered  $\frac{2}{5}\Delta_t$ . Calculations show that, if the metal-ligand distances are maintained constant,  $\Delta_t = \frac{4}{9}\Delta_e$ ; this relation is qualita-






Figure 15.4 Splitting of d-orbital energies in a tetrahedral field.

tively predictable from the fact that the total negative charge of four ligands is less than that of six ligands.

It is interesting to consider the effect on the d-orbital energy levels of a tetragonal elongation of an octahedral complex. If we pull out the ligands on the z axis and push in the ligands on the x and y axes so as to maintain the total coulomb energy constant, the  $d_{z^2}$  and  $d_{x^2-y^2}$  orbitals are no longer equivalent, and their energies diverge, as shown in Fig. 15.5. Similarly, the  $d_{xy}$  orbital is no longer equivalent to the  $d_{xz}$  and  $d_{yz}$  orbitals, and its energy is raised relative to that of the latter orbitals. In the limit of a square planar configuration, reached when the axial ligands have been completely withdrawn, the  $d_{x^2-y^2}$  orbital definitely has the highest energy, but the relative energies of the other orbitals depend on quantitative properties of the metal ion and ligands. Theoretical calculations and experi-




Figure 15.5 Splitting of d-orbital energies in a tetragonally distorted octahedral field and in a square planar field.

mental data indicate that the energy of the  $d_{32}$  orbital becomes comparable to that of the  $d_{xz}$  and  $d_{yz}$  orbitals in square complexes of Co(II), Ni(II), and Cu(II), as shown in Fig. 15.5.

It should be pointed out that the separations between the energy levels in Figs. 15.2, 15.4, and 15.5 are generally of the order of only a few electronvolts. These energy differences are relatively small compared to typical total interaction energies between positively charged metal ions and negatively charged ligands. For example, the energy required to dissociate completely the coordinated water molecules from the metal ion in a complex such as Fe(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup> (in the gas phase) is of the order of magnitude of 40 eV.3

# MOLECULAR ORBITAL THEORY

We have seen that, by application of electrostatic ligand-field theory, we predict that the d-orbital energies of a transition-metal ion are split into two or more levels when the ion is subjected to a nonspherical electrostatic field such as it would experience in a coordination compound. Before discussing the various chemical ramifications of such orbital splitting, it will be useful to consider an entirely different approach to the bonding in transition-metal compounds, viz., MO theory, to show that the MO approach leads essentially to the same qualitative results. The MO approach is more realistic than the purely electrostatic approach and can explain several phenomena that cannot be explained by the electrostatic approach.

Let us apply simple MO theory to the  $\sigma$  bonding of a regular octahedral complex. The metal atom has, in its valence shell, five d orbitals, an s orbital, and three p orbitals. Each of the six equivalent ligand atoms contributes an atomic orbital, or a hybrid atomic orbital, to the  $\sigma$ -bonding system. We are concerned with how these 15 orbitals combine to form MOs. The combination of ligand orbitals which has the same symmetry as, and can interact with, the metal s orbital to yield a bonding MO and an antibonding MO is represented by the following group orbital wave function,4

$$\phi(a_{1g}) = \frac{1}{\sqrt{6}} (\sigma_1 + \sigma_2 + \sigma_3 + \sigma_4 + \sigma_5 + \sigma_6)$$

where  $\sigma_1$ ,  $\sigma_2$ , etc., stand for the ligand atomic orbital wave functions. This ligand combination is pictured in Fig. 15.6. The ligand-orbital combination which can

<sup>&</sup>lt;sup>3</sup> F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., pp. 80-85, Wiley, New York, 1967.

<sup>&</sup>lt;sup>4</sup> The coefficient  $1/\sqrt{6}$  is the "normalization constant," the value of which is determined by the requirement that the wave function be normalized. It has been assumed that S = 0. The coefficients of the other wave functions discussed in this paragraph are similarly calculated normalization constants.




Figure 15.6 Combination of ligand  $\sigma$  orbitals which can interact with the metal s orbital.

interact with the metal  $d_{z^2}$  orbital is represented by the following function,

$$\phi(e_g) = \frac{1}{2\sqrt{3}} (2\sigma_5 + 2\sigma_6 - \sigma_1 - \sigma_2 - \sigma_3 - \sigma_4)$$

and is pictured in Fig. 15.7. The ligand-orbital combination which can interact with the metal  $d_{x^2-\nu^2}$  orbital is represented as follows,

$$\phi(e_g) = \frac{1}{2}(\sigma_1 - \sigma_2 + \sigma_3 - \sigma_4)$$

and is pictured in Fig. 15.8. The combinations suitable for interacting with the metal p orbitals are given in the following functions:

$$\phi(t_{1u}) = \frac{1}{\sqrt{2}} (\sigma_1 - \sigma_3) \quad \text{for } p_x$$

$$\phi(t_{1u}) = \frac{1}{\sqrt{2}} (\sigma_2 - \sigma_4) \quad \text{for } p_y$$

$$\phi(t_{1u}) = \frac{1}{\sqrt{2}} (\sigma_5 - \sigma_6) \quad \text{for } p_z$$

These combinations are shown in Fig. 15.9. The metal  $d_{xz}$ ,  $d_{xy}$ , and  $d_{yz}$  orbitals have no net overlap with the ligand  $\sigma$  orbitals, and therefore these d orbitals, which




Figure 15.7 Combination of ligand  $\sigma$  orbitals which can interact with the metal  $d_{z^2}$  orbital.




Figure 15.9 Combinations of ligand  $\sigma$  orbitals which can interact with the metal p orbitals.

have  $t_{2g}$  symmetry, are nonbonding. The energy level diagram for the MOs which arise from the interactions which we have just described is shown in Fig. 15.10. The transition-metal valence s and p orbitals lie above the valence d orbitals in this diagram (rather than below, as in the free metal atom) because in a complex the metal atom generally has a positive charge, and the positive charge causes the





Figure 15.10 Molecular orbital energy level diagram for an octahedral complex with only  $\sigma$  bonding.


relative energies of the orbitals to approach those of a hydrogen-like atom.<sup>5</sup> Thus in a metal ion from the first transition series, the energies of the 4s and 4p orbitals lie above those of the 3d orbitals. Notice that the separation between the  $t_{2g}$  and  $e_g^*$  levels is identified with  $\Delta_o$ . Each ligand contributes 2 electrons to the MOs; these 12 electrons can be used to fill the bonding  $a_{1g}$ ,  $t_{1u}$ , and  $e_g$  MOs. The metal ion contributes as many valence electrons as it possesses. Thus an octahedral complex of a  $d^1$  metal ion, such as  $\text{Ti}(H_2O)_6^{3+}$ , has one electron in one of the nonbonding  $t_{2g}$  orbitals. An octahedral complex of a  $d^8$  metal ion, such as  $\text{Ni}(H_2O)_6^{2+}$ , has six electrons in the  $t_{2g}$  orbitals and two unpaired electrons in the  $e_g^*$  orbitals. Completely analogous descriptions of the d electrons are possible, using the energy level diagram of Fig. 15.2 based on electrostatic ligand-field theory.

#### Pi Bonding

The bonding of H<sup>-</sup> is entirely  $\sigma$ -donor bonding, and that of NH<sub>3</sub> and CH<sub>3</sub><sup>-</sup> is principally  $\sigma$ -donor bonding. Therefore the bonding of such ligands to metal atoms can be adequately described by an energy level diagram like that in Fig. 15.10, in which  $\pi$  bonding is ignored. However, ligands such as Cl<sup>-</sup>, O<sup>2-</sup>, and CO<sub>3</sub><sup>2-</sup>, when engaged in  $\sigma$  bonding to metal atoms, have electrons in essentially nonbonding  $p\pi$  orbitals of the donor atoms which can interact with appropriate  $d\pi$  orbitals of the metal atoms. Similarly, ligands such as CN<sup>-</sup>, CO, and NO<sup>+</sup> have empty antibonding  $\pi^*$  orbitals which can interact with metal  $d\pi$  orbitals. In fact, it is believed that ligands such as CF<sub>3</sub><sup>-</sup> and PF<sub>3</sub> also have empty orbitals which can interact with metal  $d\pi$  orbitals. In the case of CF<sub>3</sub><sup>-</sup>, it has been proposed that the empty orbitals are the antibonding  $\sigma^*$  orbitals of the C—F bonds, and in the case of PF<sub>3</sub>, it has been proposed that the empty orbitals are the valence-shell d orbitals of phosphorus and the  $\sigma^*$  orbitals of the P—F bonds. All the  $\pi$ -type interactions which we have described are schematically indicated in the following sketches.



<sup>&</sup>lt;sup>8</sup> See p. 13.



 $d\pi$ - $\sigma^*$ , as in M—CF<sub>3</sub> and M—PF<sub>3</sub>

In an ML<sub>6</sub> complex in which each ligand donor atom has two  $\pi$  orbitals that can interact with the metal orbitals, the ligand  $\pi$  orbitals may be combined into four group orbitals of symmetry  $t_{1g}$ ,  $t_{2g}$ ,  $t_{1u}$ , and  $t_{2u}$ . The  $t_{1g}$  and  $t_{2u}$  combinations are nonbonding because there are no metal orbitals having these symmetries, and the  $t_{1u}$  combinations are essentially nonbonding because the metal p orbitals, which have this symmetry, are engaged in strong  $\sigma$  bonding with the ligands. However, the  $t_{2g}$  combinations can interact significantly with the metal  $t_{2g}$  orbi-




Figure 15.11 Energy level diagram showing the interaction of the  $t_{2g}$  d orbitals with filled  $\pi$  orbitals of the ligands. The nonbonding ligand  $\pi$  orbitals are not shown. Notice that the interaction tends to decrease  $\Delta_n$ .






Figure 15.12 Energy level diagram showing the interaction of the  $t_{2g}d$  orbitals with empty  $\pi$  orbitals of the ligands. The ligand  $\pi$ -orbital combinations of other symmetries are not shown. Notice that the interaction tends to increase  $\Delta_o$ .

tals. Two types of interaction are possible, differing as to whether the ligand  $\pi$  orbitals are filled and of lower energy than the metal  $t_{2g}$  orbitals, or empty and of higher energy than the metal  $t_{2g}$  orbitals. The first type of interaction, such as found in MnCl<sub>6</sub><sup>4-</sup>, is illustrated in the energy level diagram of Fig. 15.11. Notice that, in this case, the  $p\pi$ - $d\pi$  interaction causes a decrease in  $\Delta_o$ . The second type of interaction, such as found in Fe(CN)<sub>6</sub><sup>4-</sup>, is illustrated in the energy level diagram of Fig. 15.12. In this case, the  $d\pi \rightarrow p\pi$  back bonding causes an increase in  $\Delta_o$ . Such back bonding serves to transfer electrons from the metal atom (which would be excessively negative in the absence of back bonding) to the ligand. The combination of  $\sigma$  donor bonding and  $\pi$  back bonding involved in the coordination of species such as CN<sup>-</sup>, CO, N<sub>2</sub>, etc., is often referred to as "synergic bonding." The  $\sigma$  basicity of N<sub>2</sub> is much too low to account for the strength of the many transition-metal – N<sub>2</sub> bonds that are known. However, the combination of  $\sigma$  and  $\pi$  bonding is remarkably strong, perhaps because it does not require a large net interatomic transfer of charge.

The bonding of a transition-metal atom to an olefin can be similarly described in terms of a combination of a  $\sigma$  olefin  $\rightarrow$  metal bond and a  $\pi$  metal  $\rightarrow$  olefin bond, as indicated in the following sketches:



It is also acceptable to assume that the two metal d orbitals involved in the bonding form two equivalent hybrid orbitals and to describe the bonding as analogous to that in cyclopropane:



# The Metal-Metal Bond<sup>6</sup>

Metal-metal bonding occurs in many transition-metal binuclear complexes in which the metal atoms are close enough to allow interaction of their d orbitals. It

<sup>&</sup>lt;sup>6</sup> W. C. Trogler, *J. Chem. Educ.*, **57**, 424 (1980); F. A. Cotton, *Acc. Chem. Res.*, **11**, 225 (1978); M. H. Chisholm and F. A. Cotton, *Acc. Chem. Res.*, **11**, 356 (1978).




Figure 15.13 Energy level diagrams for the orbitals derived from the metal d orbitals of dinuclear metal complexes, showing the effects of the ligands. The bonding M—L and M—X orbitals are not shown

is helpful to consider first the bonding in a bare  $M_2$  molecule. If the M—M bond axis is taken as the z axis, the d orbitals will be split more or less as indicated in the first energy level diagram of Fig. 15.13. The  $d_{z^2}$  orbitals on the atoms will combine to form a bonding  $\sigma$  MO and an antibonding  $\sigma^*$  MO. The  $d_{xz}$  and  $d_{yz}$  orbitals, which are physically indistinguishable, will combine to form two degenerate bonding  $\pi$  MOs and two degenerate antibonding  $\pi^*$  MOs. The  $d_{x^2-y^2}$  and  $d_{xy}$  orbitals on the two atoms overlap each other with all four lobes to form  $\delta$  MOs, i.e., MOs each of which has two nodal planes containing the M—M axis. Therefore degenerate pairs of bonding  $\delta$  MOs and antibonding  $\delta^*$  MOs will form. Because orbital overlap increases in the order  $\delta < \pi < \sigma$ , the bonding-antibonding separation increases in the same order, as indicated in Fig. 15.13.

When ligands are introduced along the  $\pm x$  and  $\pm y$  axes, such that these axes are in the eclipsed configuration ( $D_{4h}$  symmetry<sup>7</sup>), the  $\delta_{x^2-y^2}$  orbitals are strongly destabilized by  $\sigma$  interactions with the ligands. Although the relative positions of the orbitals depend on the ligands and metals, an energy level diagram like the second one in Fig. 15.13 is expected. Note that the bonding M—L orbitals are

 $<sup>^{7}</sup>$  See Chap. 2 for a discussion of symmetry and group-theoretical symbols such as  $D_{4h}$  and  $D_{4d}$ .

not shown in the figure. Complexes with two  $d^4$  metal atoms, such as  $\text{Re}_2\text{Cl}_8^{2-}$  and  $\text{Mo}_2\text{Cl}_8^{4-}$ , generally have  $D_{4h}$  geometry and have short quadruple  $M \equiv M$  bonds, corresponding to the electron configuration  $\sigma^2\pi^4\delta^2$ . The  $\delta$ -bonding electrons are not very tightly bound, and it is possible to prepare metal-metal bonded compounds in which the  $\delta$  orbitals are empty. Examples of such  $M \equiv M \sigma^2\pi^4$  triple bonding are found in the complexes  $\text{Mo}_2(\text{HPO}_4)_4^{2-}$  and  $\text{Re}_2(\text{C}_3\text{H}_5)_4$ . Because the antibonding  $\delta^*$  orbital is not far above the bonding  $\delta$  orbital, electrons may be placed in it to give the  $\sigma^2\pi^4\delta^2\delta^{*2}$  configuration. This kind of triple bond, in which the  $\delta$  bonding cancels the  $\delta^*$  antibonding, is found in  $\text{Re}_2\text{Cl}_4(\text{PR}_3)_4$ . Even further addition of antibonding electrons can take place, each antibonding pair causing a decrease in bond order. In  $\text{Rh}_2(\text{O}_2\text{CR})_4$ , for example, there are 14 metal valence electrons and only a single bond,  $\sigma^2\pi^4\delta^2\delta^{*2}\pi^{*4}$ .

In complexes of the type  $M_2L_8X_2$ , in which X ligands are introduced along the z axis, the  $\sigma$  donor orbitals of the X ligands interact with the  $\sigma$  and  $\sigma^*$  M—M orbitals. Two bonding M—X orbitals are formed, and the energies of the  $\sigma$  and  $\sigma^*$  M—M orbitals are raised, as shown in the third energy level diagram of Fig. 15.13. To the extent that the  $\sigma$  M—M orbital becomes involved in M—X bonding, the M—M bond is weakened. Thus  $Cr_2^{4+}$  complexes without axial ligands have very short Cr—Cr bonds (<2.0 Å), whereas those with axial ligands have relatively long Cr—Cr bonds (2.2 to 2.5 Å). In fact, the shorter the Cr— $X_{axial}$  distance in the latter compounds, the longer the Cr—Cr distance.

In staggered  $M_2L_8X_2$  complexes ( $D_{4d}$  symmetry), the  $\sigma$  and  $\pi$  orbitals are the same as in the corresponding eclipsed complexes. However, the two  $\delta_{x^2-y^2}$  orbitals (antibonding M—L orbitals) become equivalent, and the two  $d_{xy}$  orbitals also become equivalent and essentially nonbonding as indicated in the fourth energy level diagram of Fig. 15.13. This set of MOs can easily accommodate 10 d electrons, but in the case of a species such as  $Mn_2(CO)_{10}$ , which has a  $D_{4d}$  structure and 14 d electrons, it would apparently be necessary to put four electrons into strongly antibonding  $\pi^*$  orbitals. We can rationalize the existence of  $Mn_2(CO)_{10}$  by recognizing that the strong  $\pi$ -acceptor CO ligands lower the energies of the d orbitals with appropriate symmetry, especially the  $\pi$ ,  $\pi^*$ , and  $\delta_n$  orbitals. Thus we obtain the fifth energy level diagram of Fig. 15.13, which can accommodate all 14 d electrons of  $Mn_2(CO)_{10}$  in low-lying MOs, corresponding to an Mn—Mn single bond.


An important class of triply bonded species are those of the type  $X_3M \equiv MX_3$ , exemplified by  $Mo_2(NMe_2)_6$  and  $W_2(NEt_2)_4Cl_2$ . In these compounds the trigonally disposed ligands raise the energy of both  $\delta$  orbitals, leaving only  $\sigma$  and  $\pi$  bonding. In the absence of  $\delta$  bonding, the repulsions between ligands on the two metal atoms lead to a staggered ligand configuration for all  $X_3M \equiv MX_3$  molecules.

# WEAK- AND STRONG-FIELD COMPLEXES

An octahedral complex having 4, 5, 6, or 7 d electrons can have either of two ground-state electron configurations. In a weak field, the maximum number of

electrons are unpaired, as indicated by the following energy level diagrams:

These configurations are referred to as "high-spin." In a strong field, the energy gap  $\Delta_o$  is greater than the energy required to pair electrons in the same orbital and the  $t_{2g}$  level is filled as far as possible, as shown by the following diagrams:



These configurations are referred to as "low-spin."

Many of the physical and chemical properties of low-spin complexes are markedly different from those of high-spin complexes. For example, the effective radius of the metal atom, the magnetic properties of the complex, the redox reactivity of the complex, the substitution lability of the complex, the geometric distortions of the complex, the optical absorption spectrum of the complex, and the strengths of the metal-ligand bonds are all factors which are a function of whether or not the complex is low-spin or high-spin. In succeeding chapters, we shall discuss these factors in relation to electron configurations.

In tetrahedral complexes,  $\Delta_i$  is never great enough to convert a high-spin configuration into a low-spin configuration; in other words, all tetrahedral complexes are "weak-field."

#### PROBLEMS

- 15.1 Sketch the d-orbital energy level diagrams for complexes of the following type: (a) 2-coordinate, linear; (b) 5-coordinate, trigonal bipyramidal; (c) 5-coordinate, square pyramidal, with the metal atom in the basal plane.
- 15.2 Rationalize the fact that  $\Delta_o$  increases in the order  $CrCl_6^{3-}$ ,  $Cr(NH_3)_6^{3+}$ ,  $Cr(CN)_6^{3-}$ .
- 15.3 Rationalize the fact that  $\Delta_o$  increases in the order  $Co(H_2O)_6^{2+}$ ,  $Co(H_2O)_6^{3+}$ ,  $Rh(H_2O)_6^{3+}$ .
- 15.4 Assuming that  $d\pi \rightarrow p\pi$  back bonding occurs to the fullest possible extent in Fe(CN)<sub>6</sub><sup>4-</sup>, use valence bond theory to estimate the average bond orders of the Fe—C and C—N bonds. What are the formal charges of the atoms?
- 15.5 Show that the complex  $Pt(C_2H_4)Cl_3^-$ , shown in Fig. 14.12a, can be looked upon as a square planar complex or, somewhat unrealistically, as a trigonal bipyramidal complex.
- 15.6 Which electron configuration of a  $d^5$  transition-metal complex, the high-spin or low-spin configuration, would you expect to be favored by the application of high pressure?
- \*15.7 Why are the ReCl<sub>4</sub> groups of the complex Re<sub>2</sub>Cl<sub>8</sub><sup>2-</sup> in the eclipsed configuration rather than staggered?
- \*15.8 Explain why IrCl<sub>6</sub><sup>2-</sup> has only one unpaired electron. Also explain the fact that the esr spectrum

#### 374 CHAPTER 15: THE BONDING IN COORDINATION COMPOUNDS

of  $IrCl_6^{2-}$  is split into a multiplet by the nuclear moments of the chlorine atoms, showing that the electron spin density is delocalized onto the chlorine atoms.

15.9 Sketch the combination of chlorine p orbitals in the xy plane of MnCl<sub>6</sub><sup>4-</sup> which has the symmetry of the manganese  $d_{xy}$  orbital.

15.10 Would you expect the metal-metal bond to lengthen, shorten, or remain about the same on going from (a)  $Mo_2(SO_4)_4^{4-}$  to  $Mo_2(SO_4)_4^{3-}$  and (b)  $Tc_2Cl_8^{3-}$  to  $Tc_2Cl_8^{2-}$ ?

\*15.11 The gas-phase Mo<sub>2</sub> molecule is believed to have a sextuple bond. How can this be, in view of the d-orbital energy level diagram in Fig. 15.13?

### THE 18-ELECTRON RULE

Now that we have discussed the theoretical aspects of the bonding in transition-metal coordination compounds, it is appropriate to introduce simple electron-counting rules, which can be justified using molecular orbital theory, for predicting the structures and formulas of these compounds. First we will discuss the 18-electron rule as applied to relatively simple complexes. Then we will apply a combination of the 2n+2 rule (covered in Chap. 10) and the 18-electron rule to metal cluster compounds. Finally we will show that the concept of oxidation state, applied to transition-metal compounds, is not always as straightforward as one might think.

In Chap. 3 we discussed the basis and application of the Lewis octet theory. The theory ascribes special stability to an electron configuration in which each non-transition-element atom achieves a number of valence electrons equal to that of a rare-gas atom, i.e., 8 valence electrons. Because transition-metal atoms have five d orbitals in addition to one s and three p orbitals in their valence shells, extension of the Lewis theory to transition-metal compounds corresponds to ascribing special stability to an electron configuration in which each transition-metal atom achieves 18 valence electrons. Thus we have the 18-electron rule (alias the rare-gas, nine orbital, or effective atomic number rule). This rule is not rigorously followed by some transition-metal compounds; in fact, Mitchell and Parish¹ pointed out that transition-metal compounds fall into three groups.

The first group consists of compounds with weak ligand fields. The 18-electron rule plays no part in determining the electron configuratons of these compounds. Thus, in the case of octahedral complexes with low  $\Delta$  values, there is

P. R. Mitchell and R. V. Parish, J. Chem. Educ., 46, 811 (1969).

essentially no restriction (except the Pauli restriction) on the number of electrons which can occupy the nonbonding  $t_{2g}$  and weakly antibonding  $e_g^*$  orbitals. In principle, the number of valence electrons can range from 12 to 22. Some examples of such complexes are given in Table 16.1. It can be seen that all these examples involve first-row transition elements in low or medium oxidation states, with no strongly back-bonding ligands such as CO, olefins, or arenes. Notice that, although  $Mn(CN)_6^{3-}$  is low-spin, it does not conform to the 18-electron rule.

The second group consists of compounds with relatively high  $\Delta$  values but with ligands which do not engage in strong back bonding. In octahedral complexes of this type, there is essentially no restriction on the number of nonbonding  $t_{2g}$  electrons, but because of the high energy of the  $e_g^*$  orbitals, electrons are forbidden to occupy these orbitals. Therefore the number of valence electrons can range only from 12 to 18. Some examples are given in Table 16.2. It can be seen that all the examples are second- and third-row transition-metal complexes, which have higher  $\Delta$  values than the corresponding first-row metal complexes. There are no well-established complexes of these heavier metals with more than 18 valence electrons.

The third group consists of compounds with high  $\Delta$  values and ligands which strongly back-bond. These compounds fairly rigorously conform to the 18-electron rule. In octahedral complexes of this type, the  $t_{2g}$  orbitals are bonding, and therefore it is energetically favorable for these orbitals to be completely filled. Obviously the 18-electron rule is most useful as a predictive guide for compounds of this category, particularly for  $\pi$ -bonded organometallic and carbonyl compounds. Some simple examples are given in Table 16.3.

Complexes with  $d^8$  metal atoms sometimes have 18 valence electrons and sometimes only 16 valence electrons. The 18-electron complexes are found when the ligands are strongly back-bonding and can remove much of the electron

Table 16.1 Octahedral complexes with relatively low  $\Delta$  values

oved amote li allada consile Complex	No. of <i>d</i> electrons provided by metal ion	Total no. of valence electrons on metal atom
TiF <sub>2</sub> 2-201811 0	feuration in which each	ascribing special ambility to an electro 21con
VCl <sub>6</sub> <sup>2</sup> -oupsis	Thus we have the 18-	metal atom actieves 18 valence electr6hs.
$V(C_2O_4)_3^{3-}$	T /2 or redroma elemon	alias the rare-gas, nine orbital, or effect 11e at
Cr(NCS)63-	3	rigorously followed by some transition alone
$Mn(CN)_6^{3-}$	4	16 Representation of the second of the secon
$Fe(C_2O_4)_3^{3-}$	so in Sum mer seemedin	Parish pointed out that transition-metri con
Fe(H <sub>2</sub> O) <sub>6</sub> <sup>2+</sup>	ith weak ligand 6 lds.	
Co(H <sub>2</sub> O) <sub>6</sub> <sup>2+</sup>	lectron configur 7:ons c	from rule plays no part in determining the e
$Ni(en)_3^{2+}$	amplexes with 108 5 vs	counds. Thus, in the case of octahed 02 co
$Cu(NH_3)_6^{2+}$	9	21
$Zn(en)_3^{2+}$	10	22

Table 16.2 Complexes with high  $\Delta$  values but with no see some and additional strong back bonding<sup>†</sup>

No. of <i>d</i> electrons provided by metal ion	Total no. of valence electrons on metal atom	Fe: (
0	12	
0	14	
0	16	
1	13	
joined by an Mn &-	Mn(CO), group21are	CO)10, two
1	17	
2 ville and it electro	ns) 18 as a complex	
14 five a electrons)	16	
5 mM	17	)
6	18	
8	16 O)—al	
	provided by metal ion  0 0 0 1 3 aM as ye bankel	provided by metal ion walence electrons on metal atom  0 12 0 14 0 16 1 13 3 14 15 10 19 (OD) 10 4 16 17 2 18 4 16 5 17 6 18

<sup>†</sup> P. R. Mitchell and R. V. Parish, J. Chem. Educ., 46, 811 (1969).

density contributed to the metal atom by  $\sigma$  bonding. Thus one finds complexes such as Fe(CO)<sub>5</sub>, Fe(CNR)<sub>5</sub>, and Pt(SnCl<sub>3</sub>)<sub>5</sub><sup>-3</sup>. The 16-electron complexes are found with ligands which do not back-bond as strongly and cannot remove much electron density from the metal atom. Examples are AuCl<sub>4</sub><sup>-</sup>, PdCl<sub>4</sub><sup>2-</sup>, and Ni(C<sub>4</sub>H<sub>7</sub>N<sub>2</sub>O<sub>2</sub>)<sub>2</sub> [bis(dimethylglyoximato)nickel(II)]. The cyanide complexes of nickel(II) are a borderline case; both Ni(CN)<sub>4</sub><sup>2-</sup> and Ni(CN)<sub>5</sub><sup>3-</sup> are known.

The 18-electron rule is so valuable that a detailed discussion of its application is warranted. In the following paragraphs we shall show how one can rationalize the structure and bonding of a series of compounds of various degrees of complexity. First let us consider a simple example, Cr(CO)<sub>6</sub>. The chromium atom

Table 16.3 Complexes with back bonding which conform to the 18-electron rule

Complex	No. of <i>d</i> electrons provided by metal ion or atom	Total no. of valence electrons on metal atom
V(CO) <sub>6</sub>	ad as a complex of M	merider the cor 810 mi
$Mo(CO)_3(PF_3)_3$	6	18
HMn(CO) <sub>5</sub>	7	18
Ni(CN) <sub>5</sub> 3-	8	18
Fe(CO) <sub>5</sub>	8	18
CH <sub>3</sub> Co(CO) <sub>4</sub>	9	18
Co(CO) <sub>4</sub> -	10 - 10 - 10 - 10 - 10 - 10	18
Ni(CNR) <sub>4</sub>	10	18

furnishes 6 valence electrons, and the six carbon monoxide ligands furnish 12 electrons.

In Mn<sub>2</sub>(CO)<sub>10</sub>, two Mn(CO)<sub>5</sub> groups are joined by an Mn—Mn bond. The formation of this bond effectively adds one valence electron to each manganese atom:

The Mn—Mn bond of  $Mn_2(CO)_{10}$  can be easily cleaved by treatment with an alkali metal in an ether to give the  $Mn(CO)_5$ —ion. We may look upon this as a reduction of the Mn(0) to Mn(-1).


The Mn(CO)<sub>5</sub><sup>-</sup> ion reacts with alkyl halides to give organic derivatives such as CH<sub>3</sub>Mn(CO)<sub>5</sub>. The CH<sub>3</sub> group may be considered as a one-electron donor.

Alternatively, we may consider the compound as a complex of Mn(I) and a CH<sub>3</sub> ion:


Mn <sup>+</sup> :	
5 CO:	10
CH <sub>3</sub> -:	112
	18

100mM/6


In Fe<sub>2</sub>(CO)<sub>9</sub>, we have bridging carbon monoxide ligands (which in effect contribute one electron to each metal atom) and an Fe—Fe single bond.



Ferrocene, Fe( $C_5H_5$ )<sub>2</sub>, may be looked upon as a complex of Fe(II) with two  $C_5H_5^-$  ions (each with six  $\pi$  electrons) or as a complex of Fe(0) with two  $C_5H_5$  radicals (each with five  $\pi$  electrons).




It is convenient to consider bis(benzene)chromium as a complex of Cr(0) and benzene ligands:




The reaction of Mo(CO)<sub>6</sub> with cycloheptatriene yields the complex

(η<sup>6</sup>-C<sub>7</sub>H<sub>8</sub>)Mo(CO)<sub>3</sub>, in which three essentially localized double bonds are coordinated to the molybdenum atom. The formula lateral does of nonlocal and additional actions are coordinated to the molybdenum atom.



When this compound is treated with the triphenylcarbonium ion,  $C(C_6H_5)_3^+$ , a hydride ion is abstracted, yielding a cationic complex,  $(\eta^7-C_7H_7)Mo(CO)_3^+$ , containing the planar, aromatic  $C_7H_7^+$  ring:



Mo:	6
$C_7H_7^+$ :	6
3 CO:	6
3 CO.	18

Consider the Re<sub>3</sub>Cl<sub>12</sub><sup>3-</sup> ion, illustrated in Fig. 16.1. A molecular orbital treatment of the bonding<sup>2</sup> shows that the Re—Re bonds are double bonds. Indeed, such double bonding must also be assumed in order to obtain agreement with the 18-electron rule.

Re <sup>3+</sup> :	4
5 Cl-:	10
2 Re=Re bonds:	4
Z Re Re doing.	18

Figure 16.2 shows a skeletal representation of a molybdenum complex containing the cycloheptatrienyl group,  $C_7H_7$ , and the 3,5-dimethylpyrazolylborato anion,  $H_2B(C_5H_7N_2)_2^-$ . To rationalize this structure in terms of the 18-electron rule, it is necessary to assume that the  $C_7H_7$  ring is bound in *trihapto* fashion

F. A. Cotton and G. Wilkinson, "Advanced Inorganic Chemistry," 4th ed., pp. 1097-1098, Interscience, New York, 1980.




Figure 16.1 Structure of the Re<sub>3</sub>Cl<sub>12</sub><sup>3-</sup> ion. [Reproduced with permission from J. A. Bertrand, F. A. Cotton, and W. A. Dollase, J. Am. Chem. Soc., 85, 1349 (1963). Copyright 1963 American Chemical Society.]

and that the H atom near the molybdenum atom is engaged in a three-center B—H—Mo bond.

Mo+:	5
2 N donor atoms:	4
В—Н—Мо:	2
2 CO: 900 000 000 000	4
trihapto C <sub>7</sub> H <sub>7</sub> :	3
es the soldition of 1000	18

Exceptions to the 18-electron rule are known, even for compounds with strongly back-bonding ligands. However, most of the exceptional compounds are readily converted to compounds which follow the rule, and, in a sense, this reactivity can be looked upon as conformity to the rule. For example, both V(CO)<sub>6</sub> and Fe(C<sub>5</sub>H<sub>5</sub>)<sub>2</sub>+ have 17 valence electrons and are easily reduced to V(CO)<sub>6</sub><sup>-</sup> and Fe(C<sub>5</sub>H<sub>5</sub>)<sub>2</sub>, respectively. The tetrakis(phosphine)platinum(0) complexes, Pt(PR<sub>3</sub>)<sub>4</sub>, have a tendency to lose PR<sub>3</sub>, giving the 16- and 14-electron species, Pt(PR<sub>3</sub>)<sub>3</sub> and Pt(PR<sub>3</sub>)<sub>2</sub>. This dissociation is most extensive when R is a




Figure 16.2 Skeletal representation of [H<sub>2</sub>B(3,5-dimethylpyrazolyl)<sub>2</sub>]-Mo(CO)2C7H7. [Reproduced with permission from F. A. Cotton et al., J. Chem. Soc. Chem. Commun., 777. (1972).]

very bulky group. Thus when R = tert-butyl or cyclohexyl, the  $Pt(PR_3)_2$  species can actually be isolated.<sup>3</sup>

#### POLYHEDRAL METAL CLUSTER COMPOUNDS

Compounds containing metal-metal bonds are called metal cluster compounds. We have already considered three such complexes  $[Mn_2(CO)_{10}, Fe_2(CO)_9]$ , and  $Re_3Cl_{12}^{3-}$  and have shown that they conform to the 18-electron rule. Clusters of more than three metal atoms generally consist of polyhedral arrangements of the metal atoms and thus are part of the fascinating and rapidly growing branch of chemistry which we can call "polyhedral cluster chemistry." In Chap. 10 we discussed the bonding in molecules containing polyhedral clusters of non-transition-metal atoms (e.g., boranes, carboranes, and species such as  $Ge_9^{2-}$ ) and molecules containing clusters of both transition-metal and nonmetal atoms (e.g., metallocarboranes). All such compounds, as well as those containing clusters of only transition-metal atoms, can be treated as one large family of compounds.

When applying the 18-electron rule to polyhedral clusters containing transition-metal atoms, it is usually convenient to treat the entire cluster as a unit. Of course, we assume that each transition-metal atom conforms to the 18-electron

rule, and therefore we write, for a given metal atom,

$$18 = v + l + (6 - c) \tag{16.1}$$

Here v is the number of valence electrons of the free metal atom, l is the number of electrons donated by the ligands attached to the metal atom, and c is the net number of electrons contributed by the metal atom to the cluster bonds. It is assumed that three of the metal orbitals are engaged in bonding to other cluster atoms; hence six electrons are involved in bonding a given transition-metal atom to the other cluster atoms. Of these six electrons, c are contributed by the metal atom and c0 are contributed by the other cluster atoms. Thus we obtain the c1 cerm in Eq. 16.1. By rearrangement of Eq. 16.1 we obtain

$$c = v + l - 12$$

The total number of electrons involved in cluster bonding is the sum of the values of c for the transition-metal atoms and the number of electrons contributed by any non-transition-element atoms in the cluster. The number of cluster electrons, C, is given by the expression

$$C = V + L + m - 12t - q \tag{16.2}$$

where V is the total number of valence electrons of the transition elements in the cluster

L is the total number of ligand electrons donated to the transition-element atoms

m is the total number of electrons contributed to the cluster by non-transition-element cluster atoms

<sup>&</sup>lt;sup>3</sup> T. Yoshida and S. Otsuka, *Inorg. Syn.*, 19, 101 (1979).

t is the number of transition-element atoms in the cluster q is the charge on the entire cluster molecule

Calculation of the number of cluster electrons using Eq. 16.2 has the advantage that it is unnecessary to assign ligands to particular metal atoms. Thus the calculation is straightforward even when there are ligands that bridge two or three metal atoms.

The 2n + 2 rule, introduced in Chap. 10, has been applied with a fair record of success to all kinds of polyhedral cluster compounds. Let us review the rule. If the number of cluster electrons equals 2n + 2, where n is the number of cluster atoms, the cluster is expected to have the closo geometry of the corresponding *n*-vertexed regular polyhedron.<sup>4</sup> If C = 2n + 4, the cluster is expected to have a nido geometry, corresponding to an (n + 1)-vertexed regular polyhedron lacking one vertex. If C = 2n + 6 or C = 2n + 8, the cluster is expected to have an arachno or hypho geometry, corresponding to a regular polyhedron lacking two or three vertices, respectively. If C < 2n + 2, the cluster is expected to be a capped regular polyhedron. C = 2n corresponds to monocapping, C = 2n - 2corresponds to bicapping, etc. It should be noted that, according to the rules, the capping of a closo cluster compound and the removal of cluster atoms (and their associated ligands) from a closo compound to form nido, arachno, or hypho compounds are processes which involve no change in the number of cluster electrons. Hence each step in these conversions involves the addition or removal of a cluster atom which has three empty orbitals.

For simplicity, we shall refer to the various rules which correlate the number of cluster electrons with cluster geometry as the "2n + 2 rule," even though 2n + 2 cluster electron systems strictly correspond to closo structures only. Now let us consider the application of the rule to various cluster compounds.

The trigonal bipyramidal complex Os<sub>5</sub>(CO)<sub>16</sub>, with 12 cluster electrons, is a closo cluster.<sup>5</sup>

$$V = 5 \times 8 = 40$$

$$L = 16 \times 2 = 32$$

$$-12t = -12 \times 5 = -60$$

$$C = 12 = 2n + 2$$

Formal removal of two Os(CO)<sub>2</sub> groups from this complex gives the triangular arachno complex Os<sub>3</sub>(CO)<sub>12</sub>.

$$V = 3 \times 8 = 24$$

$$L = 12 \times 2 = 24$$

$$-12t = -12 \times 3 = -36$$

$$C = 12 = 2n + 6$$

<sup>&</sup>lt;sup>4</sup> The "regular," or closo, polyhedra include, but do not appear to be restricted to, triangulated polyhedra such as the trigonal bipyramid, octahedron, pentagonal bipyramid, dodecahedron, tricapped trigonal prism, bicapped square antiprism, and icosahedron.

<sup>&</sup>lt;sup>5</sup> C. R. Eady, B. F. G. Johnson, J. Lewis, B. E. Reichert, and G. M. Sheldrick, J. Chem. Soc. Chem. Commun., 271 (1976).

Formal addition of an Os(CO), group to Os<sub>5</sub>(CO)<sub>16</sub> gives Os<sub>6</sub>(CO)<sub>18</sub>, in which the six osmium atoms do not have an octahedral configuration (as one might offhand predict), but rather the configuration of a capped trigonal bipyramid, as shown in Fig. 16.3.6

$$V=6\times 8=\begin{array}{c} 48 \text{ we brown our give a parallelse}\\ L=18\times 2=\begin{array}{c} 36 \\ 84 \end{array}$$

The tetrahedral complex ( $\eta^5$ -C<sub>5</sub>H<sub>5</sub>)RhFe<sub>3</sub>(CO)<sub>11</sub>, with 12 cluster electrons, should be looked upon as a nido derivative of a trigonal bipyramidal cluster.

$$V = 3 \times 8 + 9 = 33$$

$$L = 11 \times 2 + 5 = 27$$

$$-12t = -12 \times 4 = -48$$

$$C = 12 = 2n + 4$$

The complex Re<sub>4</sub>(CO)<sub>16</sub><sup>2-</sup> has an open "butterfly" configuration, as shown in Fig. 16.4.8 It can be looked upon as an arachno derivative of an octahedral structure, in accord with its 14 cluster electrons.

$$V = 4 \times 7 = 28$$

$$L = 16 \times 2 = 32$$

$$-q = 2$$

$$62$$

$$-12t = -12 \times 4 = -48$$

$$C = 14 = 2n + 6$$

$$C = 12 \times 4 = 2n + 6$$

$$C = 14 = 2n + 6$$

<sup>6</sup> R. Mason, K. M. Thomas, and D. M. P. Mingos, J. Am. Chem. Soc., 95, 3802 (1973).

<sup>7</sup> M. R. Churchill and M. V. Veidis, J. Chem. Soc. Chem. Commun., 1470 (1970). <sup>8</sup> M. R. Churchill and R. Bau, *Inorg. Chem.*, 7, 2606 (1968).





Figure 16.3 Structure of Os<sub>6</sub>(CO)<sub>18</sub>, showing the monocapped trigonal bipyramidal geometry of the Os6 cluster.



The complex Ru<sub>6</sub>(CO)<sub>17</sub>C has a carbon atom situated in the center of an octahedral cage of metal atoms. By assuming that the central carbon atom contributes all its valence electrons to the cluster bonding, we calculate that there are 14 cluster electrons, in accord with the octahedral structure.

The complex Fe<sub>5</sub>(CO)<sub>15</sub>C has a square pyramidal arrangement of metal atoms, with a carbon atom situated slightly below the center of the square base. <sup>10</sup> The structure appears to be a nido derivative of the iron analog of the Ru<sub>6</sub>(CO)<sub>17</sub>C complex. Indeed, the number of cluster electrons conforms to this interpretation

$$V = 5 \times 8 = 40$$

$$L = 15 \times 2 = 30$$

$$m = \frac{4}{74}$$

$$-12t = -12 \times 5 = \frac{-60}{14} = 2n + 4$$

<sup>&</sup>lt;sup>9</sup> A. Sirigu, M. Bianchi, and E. Benedetti, J. Chem. Soc. Chem. Commun., 546 (1969).

<sup>&</sup>lt;sup>10</sup> E. H. Braye, L. F. Dahl, W. Hubel, and D. L. Wampler, J. Am. Chem. Soc., 84, 4633 (1962).




Figure 16.5 Proposed structure of C<sub>2</sub>B<sub>3</sub>H<sub>5</sub>Fe(CO)<sub>3</sub>. (From R. N. Grimes, Ann. N.Y. Acad. Sci., Symposium on New Horizons in Organometallic Chemistry, August 1973.)

It has been proposed that  $C_2B_3H_5Fe(CO)_3$  has the octahedral structure shown in Fig. 16.5.<sup>11</sup> Clearly this is a closo structure, with 14 cluster electrons.

$$V = 8$$

$$L = 3 \times 2 = 6$$

$$m \begin{cases} C: 2 \times 3 = 6 \\ B: 3 \times 2 = \frac{6}{26} \end{cases}$$

$$-12t = -12$$

$$C = 14 = 2n + 2$$

$$D = 3 \times 2 = 6$$

$$26 \times 26 \times 26 \times 26$$

$$-12t = -12 \times 26 \times 26 \times 26 \times 26$$

The bis(acetylene) complex  $(C_2Ph_2)_2Fe_3(CO)_8$ , whose structure is shown in Fig. 16.6, is an example of a compound containing a pentagonal bipyramidal cluster.<sup>12</sup> In agreement with the rule, the cluster contains 16 electrons:

$$V = 3 \times 8 = 24$$

$$L = 8 \times 2 = 16$$

$$m = 4 \times 3 = 12$$

$$-12t = -12 \times 3 = -36$$

$$C = 16 = 2n + 2$$

The complex Fe<sub>2</sub>(CO)<sub>6</sub>(HOCC(CH<sub>3</sub>)C(CH<sub>3</sub>)COH) has a nido structure based on a pentagonal bipyramid, <sup>13</sup> as shown in Fig. 16.7, and accordingly has 16 cluster electrons.

$$V = 2 \times 8 = 16 
L = 6 \times 2 = 12 
m = 4 \times 3 = 12 
-12t = -12 \times 2 = -24 
C = 16 = 2n + 4$$

<sup>&</sup>lt;sup>11</sup> R. N. Grimes, Ann. N.Y. Acad. Sci., from Symposium on New Horizons in Organometallic Chemistry, August 1973.

<sup>&</sup>lt;sup>12</sup> R. P. Dodge and V. Schomaker, J. Organomet. Chem., 3, 274 (1965).

<sup>&</sup>lt;sup>13</sup> A. A. Hock and O. S. Mills, Acta Crystallogr., 14, 139 (1961).

Figure 16.6 Structure of (C2Ph2)2Fe3(CO)8.

The anion Co<sub>8</sub>(CO)<sub>18</sub>C<sup>2-</sup> contains a carbon atom at the center of a square antiprismatic cluster of cobalt atoms.14 The closo geometry is consistent with the 18 cluster electrons of the complex. The metallocarborane [(CH<sub>3</sub>)<sub>3</sub>P]<sub>2</sub>-Pt(CMe)<sub>2</sub>(BH)<sub>6</sub> contains a trigonal prismatic cluster of six boron atoms, with the rectangular faces capped with two carbon atoms and a platinum atom.15 This closo geometry is consistent with the 20 cluster electrons. Twelve of the rhodium atoms in the anion Rh<sub>13</sub>(CO)<sub>24</sub>H<sub>3</sub><sup>2-</sup> are situated at the corners of a truncated hexagonal bipyramid, with the thirteenth rhodium atom in the center, as shown in Fig. 16.8.16 Thus the atoms have a hexagonally close-packed arrangement. If we assume that the central rhodium atom contributes its 9 valence electrons to the cluster bonding, we calculate that there are 26 cluster electrons, consistent with the closo geometry.

#### Some Difficult Cases

Ingenuity is needed to demonstrate that certain cluster compounds follow the 2n + 2 rule. For example, the complex  $Ru_4Cl(CO)_{13}$  has a folded butterfly arrangement of four Ru atoms, with a dihedral angle of 91° between the two Ru<sub>3</sub>

<sup>15</sup> A. J. Welch, J. Chem. Soc. Dalton Trans., 225 (1976).

<sup>16</sup> P. Chini, G. Longoni, and V. G. Albano, Adv. Organomet. Chem., 14, 285 (1976).




Figure 16.7 Structure of Fe<sub>2</sub>(CO)<sub>6</sub>[C<sub>6</sub>H<sub>6</sub>(OH)<sub>2</sub>].

<sup>14</sup> V. G. Albano, P. Chini, G. Ciani, M. Sansoni, D. Strumolo, B. T. Heaton, and S. Martinengo, J. Am. Chem. Soc., 98, 5027 (1976).





Figure 16.8 Structure of the Rh<sub>13</sub>(CO)<sub>24</sub>H<sub>3</sub><sup>2-</sup> ion. Notice that the metal atoms are part of an hep lattice. [Reproduced with permission from P. Chini, G. Longoni, and V. G. Albano, Adv. Organomet. Chem., 14, 285 (1976).]

planes and a chlorine atom bridging the terminal Ru atoms:17



Assuming that the chlorine atom is a cluster atom and that it contributes 5 electrons to the cluster, we calculate a total of 16 cluster electrons. This result pentagonal bipyramidal cluster. (The chlorine atom and the two "hinge" Ru atoms occupy equatorial sites.) Alternatively, if we look upon the chlorine atom as electrons. This result may be rationalized by looking upon the chlorine atom as electrons. This result may be rationalized by looking upon the complex as an complex differs from that of Fe<sub>4</sub>N(CO)<sub>12</sub>, which has a similar geometry (a obviously contains a closo trigonal bipyramidal cluster, with the nitrogen atom occupying an equatorial site.

G. R. Steinmetz, A. D. Harley, and G. L. Geoffroy, *Inorg. Chem.*, 19, 2985 (1980).
 M. Tachikawa et al., *J. Am. Chem. Soc.*, 102, 6648 (1980).

The complex HOs<sub>4</sub>(CO)<sub>13</sub><sup>-</sup> has a tetrahedral arrangement of metal atoms and 12 cluster electrons, corresponding to a nido cluster based on a trigonal bipyramid.<sup>19</sup> On the other hand, the corresponding iron complex, HFe<sub>4</sub>(CO)<sub>13</sub><sup>-</sup>, has a butterfly structure with one of the CO groups bridging the terminal iron atoms of the butterfly.<sup>20</sup>

The bridging CO group is attached to one iron atom by the carbon atom and to the other iron atom by both the carbon and oxygen atoms. Presumably this CO group acts as a 4-electron donor; thus the complex has 14 cluster electrons and should be considered an arachno derivative of an octahedral cluster.

Numerous other examples of unsymmetric bridging CO groups (or "semi-bridging" CO groups) are known. A remarkable example is found in the cluster  $(\eta^5-C_5H_5)_3Nb_3(CO)_7$ , in which one of the seven CO groups acts as an  $\eta^2-(\mu_3-C, \mu_2-O)$  bridge facing a nearly equilateral Nb<sub>3</sub> triangle:<sup>21</sup>

Presumably this unusual CO group acts as a 6-electron donor ligand, giving an electron pair to each of the niobium atoms. The number of cluster electrons is thus 12, corresponding to an arachno derivative of a trigonal bipyramidal cluster.

The complex Ni<sub>5</sub>(CO)<sub>12</sub><sup>2-</sup> has a trigonal bipyramidal structure with 16 cluster electrons.<sup>22</sup> Perhaps one should look upon this as having an arachno cluster derived from a pentagonal bipyramidal geometry (two of the equatorial vertices corresponding to axial sites of the pentagonal bipyramid).

The complex Rh<sub>6</sub>(CO)<sub>15</sub>C<sup>2-</sup> contains a trigonal prismatic cluster of metal atoms with a central carbon atom.<sup>23</sup> The number of cluster electrons, 18, suggests that the cluster is an arachno derivative of an eight-vertex regular polyhedral cluster. This interpretation is reasonable if we recognize that a trigonal prism is essentially a square antiprism with two vertices missing.

<sup>&</sup>lt;sup>19</sup> P. A. Dawson, B. F. G. Johnson, J. Lewis, D. A. Kaner, and P. R. Raithby, J. Chem. Soc. Chem. Commun., 961 (1980).

<sup>&</sup>lt;sup>20</sup> M. Manassero, M. Sansoni, and G. Longoni, *J. Chem. Soc. Chem. Commun.*, 919 (1976).

<sup>&</sup>lt;sup>21</sup> W. A. Herrmann et al., J. Am. Chem. Soc., 103, 1692 (1981).

<sup>&</sup>lt;sup>22</sup> G. Longoni, P. Chini, L. D. Lower, and L. F. Dahl, J. Am. Chem. Soc., 97, 5034 (1975).

<sup>&</sup>lt;sup>23</sup> V. G. Albano, M. Sansoni, P. Chini, and S. Martinengo, *J. Chem. Soc. Dalton Trans.*, 651 (1973).




Figure 16.9 Structure of  $(\eta^5-C_5H_5)$ CoFe(CMe)<sub>4</sub>(BH)<sub>8</sub>. [Reproduced with permission from R. B. King, E. K. Nishimura, and K. S. RaghuVeer, Inorg. Chem., 19, 2478 (1980). Copyright 1980 American Chemical Society.]

The nature of the bonding in  $\eta^5$ -C<sub>5</sub>H<sub>5</sub>CoFe(CMe)<sub>4</sub>(BH)<sub>8</sub>, pictured in Fig. 16.9, has been the subject of considerable discussion.<sup>24</sup> The feature causing caps two pentagonal bipyramidal clusters. The situation is quite rational, howwhich it indeed is rather closely attached. The iron atom achieves 18 valence clusters. Since the iron atom uses three orbitals in its bonding to each cluster, it each cluster has 16 cluster electrons, conforming to the closo pentagonal bipyramidal structures.

Equation 16.2 can be used to calculate the number of cluster electrons in a compound containing transition-metal atoms which are expected to conform to the 18-electron rule. Thus it is applicable to transition-metal clusters with

<sup>&</sup>lt;sup>24</sup> W. M. Maxwell, E. Sinn, and R. N. Grimes, J. Am. Chem. Soc., 98, 3490 (1976); R. B. King, E. K. Nishimura, and K. S. RaghuVeer, Inorg. Chem., 19, 2478 (1980).

 $\pi$ -acceptor ligands such as carbonyl groups, olefins, and cyclopentadienyl groups. However, cluster complexes such as Mo<sub>6</sub>Cl<sub>8</sub><sup>4+</sup> and Nb<sub>6</sub>Cl<sub>12</sub><sup>2+</sup>, in which the metal atoms are not required to have 18 valence electrons, are best treated on an individual basis by simple MO theory<sup>25</sup> or ligand-field theory. The bonding in such complexes, involving metal atoms with oxidation states of +2 or higher, can be analyzed almost entirely in terms of the metal valence d orbitals.

The complex Mo<sub>6</sub>Cl<sub>8</sub><sup>4+</sup>, pictured in Fig. 16.10, consists of an octahedron of molybdenum atoms with a chlorine atom over each face. Let us assume that each Mo  $d_{z^2}$  orbital is oriented along the fourfold symmetry axis and that the lobes of the  $d_{xy}$  orbital are directed toward the four chlorine atoms which are essentially coplanar with the Mo atom. It is then reasonable to assign the  $d_{z^2}$ ,  $d_{xz}$ , and  $d_{yz}$ orbitals to cluster bonding and to assume that the  $d_{xy}$  orbital is strongly antibonding because of repulsions by the four chlorine atoms. The  $d_{x^2-y^2}$  orbitals of the six Mo atoms will then overlap in the regions over the Mo-Mo edges of the octahedral cluster. One combination of these six  $d_{x^2-y^2}$  orbitals, pictured in Fig. 16.11, is strongly antibonding. The other five combinations are bonding, or at least nonbonding, and would be expected to hold 10 valence electrons. These 10 electrons, plus the 14 inner cluster electrons corresponding to the 2n + 2 rule, make a total of 24 cluster electrons expected. In fact, if we strip the chloride ions from Mo<sub>6</sub>Cl<sub>8</sub><sup>4+</sup>, we are left with Mo<sub>6</sub><sup>12+</sup>, which does contain 24 valence electrons.

25 F. A. Cotton and T. E. Haas, Inorg. Chem., 3, 10 (1964).




Figure 16.10 Structure of the Mo<sub>6</sub>Cl<sub>8</sub><sup>4+</sup> complex.




Figure 16.11 The  $a_{2x}$  combination of the  $d_{x^2-y^2}$  orbitals of Mo<sub>6</sub>Cl<sub>8</sub><sup>4+</sup>, corresponding to a strongly antibonding MO.




Figure 16.12 Structure of the Nb<sub>6</sub>Cl<sub>12</sub><sup>2+</sup> complex.

The complex  $\mathrm{Nb_6Cl_{12}^{2+}}$ , pictured in Fig. 16.12, consists of an octahedron of niobium atoms with a chlorine atom over each edge. Let us assume that each  $d_{z^2}$  orbital is aligned along the fourfold symmetry axis and that the lobes of the  $d_{x^2-y^2}$  orbital are directed toward the four neighboring chlorine atoms. The  $d_{z^2}$ ,  $d_{xz}$ , and  $d_{yz}$  orbitals are assigned to cluster bonding, and the  $d_{x^2-y^2}$  orbital is strongly antibonding. The  $d_{xy}$  orbitals of the six Nb atoms then engage in rather poor three-center overlap in the regions over the triangular faces of the octahedral cluster. Five combinations of these six orbitals are probably antibonding and would not be expected to hold valence electrons. However, one combination, pictured in Fig. 16.13, is weakly bonding and might be expected to hold a pair of valence electrons. This pair of electrons, plus the 14 inner cluster electrons, make a total of 16 cluster electrons expected. In fact the  $\mathrm{Nb_6}^{14+}$  cluster does have 16 the complex:<sup>26</sup>

$$Nb_6Cl_{12}^{2+} \xrightarrow{-e^-} Nb_6Cl_{12}^{3+} \xrightarrow{-e^-} Nb_6Cl_{12}^{4+}$$

#### **Applications**

The relations between cluster geometry and the number of cluster electrons have permitted the systematization and prediction of the structures of many unusual compounds. But perhaps even more important, these concepts have been successfully used to design syntheses of new types of compounds. Thus, recognition of analogies, such as that between  $(\pi - C_5 H_5)$ Co and BH (each contributes two electrons and three orbitals to polyhedral bonding) and that between  $(\pi - C_5 H_5)$ Ni and CH (each contributes three electrons and three orbitals) and recognition of the structural effects of oxidation and reduction reactions have led to the preparation of many novel metallocarboranes.

<sup>&</sup>lt;sup>26</sup> F. W. Koknat and R. E. McCarley, *Inorg. Chem.*, 13, 295 (1974).

<sup>&</sup>lt;sup>27</sup> K. Wade, Inorg. Nucl. Chem. Lett., 8, 559, 563 (1972); J. Chem. Soc. Chem. Commun., 792, (1971).

<sup>28</sup> R. N. Grimes, Acc. Chem. Res., 11, 421 (1978).




Figure 16.13 The  $a_{2\mu}$  combination of the  $d_{x\nu}$  orbitals of Nb<sub>6</sub>Cl<sub>12</sub><sup>2+</sup>, corresponding to a weakly bonding MO.

#### Exceptions

Many of the higher polyhedral cluster compounds do not follow the 2n + 2 rule. For example, most (if not all) eight-vertex clusters have closo structures (either square antiprismatic or dodecahedral) even when they do not have the prescribed 18 cluster electrons. Examples of exceptions to the 2n + 2 rule are (η<sup>5</sup>-C<sub>5</sub>H<sub>5</sub>Co)<sub>4</sub>B<sub>4</sub>H<sub>4</sub>, with 16 cluster electrons, and (η<sup>5</sup>-C<sub>5</sub>H<sub>5</sub>Ni)<sub>4</sub>B<sub>4</sub>H<sub>4</sub>, with 20 cluster electrons.<sup>29</sup> Although both of these clusters have dodecahedral geometries, they have significant structural differences which are probably related to the electron deficiency of the cobalt compound and the electron surplus of the nickel compound. In the cobalt compound, the metal atoms occupy the high-coordinate dodecahedral sites (the B vertices of Fig. 14.3), whereas, in the nickel compound, the metal atoms occupy the low-coordinate sites (the A vertices of Fig. 14.3). In the nickel compound, the nickel atoms are essentially paired, with very short Ni-Ni distances. It seems likely that localized metal-metal bonding is involved in this electron-rich compound.

A 12-vertex cluster with 28 cluster electrons is predicted to have a nido structure, corresponding to a 13-vertex closo polyhedron with a missing vertex. The structure of the 28-electron metallocarborane (η<sup>5</sup>-C<sub>5</sub>H<sub>5</sub>Co)<sub>2</sub>C<sub>4</sub>B<sub>6</sub>H<sub>10</sub>, shown in Fig. 16.14a, essentially fits this description. However, the structure of the 28-electron compound (n<sup>5</sup>-C<sub>5</sub>H<sub>5</sub>Co)(CCH<sub>3</sub>)<sub>4</sub>B<sub>7</sub>H<sub>6</sub>OC<sub>2</sub>H<sub>5</sub>, shown in Fig. 16.14b, is completely different.30 The molecule resembles a severely distorted icosahedron whose two halves have been partially separated, forming a large opening on one side. Although the 2n + 2 rule is successful in this case to the limited extent of predicting a noncloso structure, no completely satisfactory explanation of this unusual structure has been found.

Examples of rhodium and nickel complexes that do not follow the 2n + 2rule are listed in Table 16.4, and some of these complexes are pictured in Figs. 16.15 and 16.16. It is probably significant that five of the examples have 24 cluster electrons, even though the corresponding structures have little in com-

<sup>30</sup> J. R. Pipal and R. N. Grimes, J. Am. Chem. Soc., 100, 3083 (1978).

<sup>&</sup>lt;sup>29</sup> J. R. Bowser, A. Bonny, J. R. Pipal, and R. N. Grimes, J. Am. Chem. Soc., 101, 6229 (1979).




Figure 16.14 Structures of two 12-vertex complexes with 28 cluster electrons. (a)  $(\eta^5 - C_5 H_5)_2 \text{Co}_2 C_4 B_6 H_{10}$ ; (b)  $(\eta^5 - C_5 H_5) \text{Co}(\text{CMe})_4 B_7 H_6 \text{OEt}$ . [Reproduced with permission from J. R. Society.]




Figure 16.15 Skeletal structures of Rh<sub>22</sub>(CO)<sub>33</sub><sup>4-</sup> (a) and Rh<sub>22</sub>(CO)<sub>35</sub>H<sub>x</sub><sup>5-</sup> (b). [Reproduced with permission from S. Martinengo, G. Ciani, and A. Sironi, J. Am. Chem. Soc., 102, 7564 (1980), and J. L. Vidal, R. C. Schoening, and J. M. Troup, Inorg. Chem., 20, 227 (1981). Copyright 1980 and 1981 American Chemical Society.]

Table 16.4 Geometries and numbers of cluster electrons for high-nuclearity clusters that do not conform to the 2n + 2 rule

Complex Comple	Cluster geometry	Vertices of polyhedron, n	Cluster electrons, C
Rh <sub>12</sub> (CO) <sub>25</sub> C <sub>2</sub>	Two carbon atoms bonded together (1.47 Å) inside a complicated cluster resembling Rh <sub>13</sub> (CO) <sub>24</sub> H <sub>3</sub> <sup>2-</sup> but with two atoms missing from the Rh <sub>6</sub> plane and an extra Rh in	s are most <sup>2</sup> les s on unsymm	calculation calculation difficult.
Rh <sub>15</sub> (CO) <sub>28</sub> (C) <sub>2</sub>	one of the Rh <sub>3</sub> planes <sup>a</sup> Two carbon atoms and a metal atom inside a pentagonal prism capped on the bases and two sides <sup>a</sup>	usly the 2n ± 2 present treather mists made of t	20 noit
Rh <sub>14</sub> (CO) <sub>25</sub> 4-	Cube of metal atoms with five faces capped,	13	24
Rh <sub>14</sub> H(CO) <sub>25</sub> <sup>3-</sup> Rh <sub>14</sub> (CO) <sub>26</sub> <sup>2-</sup>	and a central metal atom <sup>b</sup> Resembles Rh <sub>13</sub> (CO) <sub>24</sub> H <sub>3</sub> <sup>2-</sup> , with one square face capped <sup>c</sup>	13	24
Rh <sub>15</sub> (CO) <sub>27</sub> 3-	Resembles Rh <sub>13</sub> (CO) <sub>24</sub> H <sub>3</sub> <sup>2-</sup> , with two square faces capped <sup>b</sup>	14 ATZ-MOI	24 anxo
Rh <sub>22</sub> (CO) <sub>37</sub> <sup>4-</sup>	Close-packed cluster with four layers, $6/7/6/3$ , in the sequence ABAC, as in Fig. $16.15a^d$	d dat arrungemen	24 Rhyeonii/i-
Rh <sub>22</sub> (CO) <sub>35</sub> H <sub>x</sub> <sup>5-</sup>	Both bcc and ccp Rh packing, as in Fig. 16.15be	e company gai	21101 en 1
Ni <sub>8</sub> (PPh) <sub>6</sub> (CO) <sub>8</sub>	Cube of nickel atoms capped with six PPh groups	14	24
Rh <sub>17</sub> (S) <sub>2</sub> (CO) <sub>32</sub> <sup>3-</sup>	16-Atom cluster of Rh atoms with four staggered layers, 4/4/4/4, with an Rh atom and two S atoms inside, as in Fig. 16.16g	16	40

<sup>a</sup> P. Chini, G. Longoni, and V. G. Albano, Adv. Organomet. Chem., 14, 285 (1976).

<sup>b</sup> S. Martinengo, G. Ciani, A. Sironi, and P. Chini, J. Am. Chem. Soc., 100, 7096 (1978).

S. Martinengo, G. Ciani, and A. Sironi, J. Chem. Soc. Chem. Commun., 1140 (1980).

d See Fig. 16.15a; S. Martinengo, G. Ciani, and A. Sironi, J. Am. Chem. Soc., 102, 7564 (1980). See Fig. 16.15b; J. L. Vidal, R. C. Schoening, and J. M. Troup, Inorg. Chem., 20, 227 (1981).

L. D. Lower and L. F. Dahl, J. Am. Chem. Soc., 98, 5046 (1976).

<sup>8</sup> J. L. Vidal, R. A. Fiato, L. A. Cosby, and R. L. Pruett, *Inorg. Chem.*, 17, 2574 (1978).

tronic with O. However, these assumptions are somewhat arbitrary. For




Figure 16.16 Skeletal structure of Rh<sub>17</sub>(S)<sub>2</sub>(CO)<sub>32</sub><sup>3-</sup>. [Reproduced with permission from J. L. Vidal, R. A. Fiato, L. A. Cosby, and R. L. Pruett, Inorg. Chem., 17, 2574 (1978). Copyright 1978 American Chemical Society.]

mon. Perhaps high-nuclearity clusters tend to have certain "magic" numbers of cluster electrons, with little relationship between structure and the number of cluster electrons. The extended Hückel method has been applied to some simple transition-metal clusters containing up to 15 metal atoms,<sup>31</sup> but no general pattern, extendable to higher clusters, is apparent in the results. Of course, MO calculations are most readily carried out on species of high symmetry, and calculations on unsymmetric complexes such as Rh<sub>12</sub>(CO)<sub>25</sub>C<sub>2</sub> will be quite difficult.

Obviously the 2n + 2 rule for polyhedral clusters must be used with discretion. Our present treatment of the bonding in these systems is much like the use which chemists made of rudimentary periodic tables in the nineteenth century. We can hope that soon our understanding of these systems will improve and that the empirical rules will be refined or replaced with more reliable rules.

#### OXIDATION-STATE AMBIGUITY

#### **Nitrosyls**

The following reactions illustrate four methods for the preparation of transitionmetal nitrosyls (i.e., complexes containing the NO group as a ligand).

$$Fe_{2}(CO)_{9} + 4NO \rightarrow 2Fe(NO)_{2}(CO)_{2} + 5CO$$

$$Ir(PPh_{3})_{2}(CO)Cl + NO^{+} \rightarrow [Ir(PPh_{3})_{2}(CO)(NO)Cl]^{+}$$

$$CoI_{2} + Co + 4NO \rightarrow [Co(NO)_{2}I]_{2}$$

$$Ni(CN)_{4}^{2-} + NO^{-} \rightarrow Ni(CN)_{3}NO^{2-} + CN^{-}$$

In many nitrosyl complexes, the metal—N—O bond angle is very close to  $180^{\circ}$ , and it is convenient to assume that the ligand is the :N = O:+ ion, which is isoelectronic with CO. In other complexes, the metal—N—O bond angle is around  $130^{\circ}$ , and it is reasonable to assume that the ligand is :N = O:-, isoelectronic with  $O_2$ . However, these assumptions are somewhat arbitrary. For example, one may look upon *trans*-Co(diars)<sub>2</sub>(NCS)NO+ as a complex of Co(III) and NO-,

$$L_5\overset{2+}{\text{Co}} + \overset{\cdot}{\text{N}} = 0$$
  $\longrightarrow$   $L_5\overset{+}{\text{Co}} - N$ 

or as a complex of Co(I) and NO+,

$$L_5Co:+:N\equiv O:^+ \longrightarrow L_5Co-N$$

<sup>&</sup>lt;sup>31</sup> J. W. Lauher, J. Am. Chem. Soc., **100**, 5305 (1978); see also D. M. P. Mingos and A. J. Welch, J. Chem. Soc. Dalton Trans., 1674 (1980).

In the former case, NO<sup>+</sup> acts as a  $\sigma$  donor; in the latter case, NO<sup>+</sup> acts as a  $\sigma$ acceptor. In either case, it is easy to predict the bent configuration for the Co—NO linkage: a linear configuration would force an extra pair of electrons onto the cobalt atom, in violation of the 18-electron rule. The closely related complex, Co(diars)<sub>2</sub>NO<sup>2+</sup>, may be looked upon as a complex of Co(I) and NO<sup>+</sup>,

$$L_4\ddot{C}o^+ + :N \equiv O:+ \rightarrow L_4\ddot{C}o - \stackrel{+}{N} \equiv O:+$$

or as a complex of Co(III) and NO-,

$$L_4\text{Co}^{3+} + -\dot{N} = \dot{O} \rightarrow L_4\ddot{\text{Co}} - \dot{N} \equiv O:+$$

The linear geometry is readily predicted if one assumes that the cobalt atom must have 18 valence electrons. A bent configuration would remove a pair of electrons from the valence shell of the cobalt atom, leaving only 16 electrons. Of course, considerable back bonding occurs,

$$L_4\ddot{C}o - \overset{\dagger}{N} \equiv O:^+ \leftrightarrow L_4\dot{C}o = \overset{\dagger}{N} = O:^+$$

but this interaction does not remove electrons from the formal valence shell of the cobalt atom.

The Co(diars)<sub>2</sub>NO<sup>2+</sup> ion has a trigonal bipyramidal arrangement of donor atoms<sup>32</sup> (shown in Fig. 16.17), with the linear nitrosyl group occupying an equatorial position. The fact that the nitrosyl group occupies an equatorial position, rather than an axial position, can be explained on the basis that  $d\pi$  back bonding is favored at an equatorial position relative to an axial position.<sup>33</sup> It is reasonable to assume that a linear nitrosyl group, which, in the absence of back bonding, has two atoms with +1 formal charges, would engage in stronger back bonding than an organoarsine ligand. Therefore one predicts that the stable structure would be that with an equatorial nitrosyl group.

When Co(diars), NO2+ is treated with thiocyanate ion, trans-Co(diars),-(NCS)NO+ is formed. The addition of the electron pair of the NCS- ion to the cobalt atom would cause the 18-electron rule to be violated if no electronic rearrangement took place. Actually, the addition causes an electron pair to

The reason for this preference is discussed in Chap. 18, pp. 439-440.




Figure 16.17 Structure of the Co(diars)2NO2+ ion. The C and H. atoms have been omitted for clarity.

<sup>&</sup>lt;sup>32</sup> J. H. Enemark and R. D. Feltham, Proc. Natl. Acad. Sci. USA, 69, 3534 (1972).

transfer from the cobalt to a nonbonding orbital of the nitrogen atom, thus enforcing the bent nitrosyl configuration:

$$SCN^{-} + [L_4Co = N = O]^{2+} \longrightarrow \left[ (SCN)L_4Co - N \right]^{+}$$

Enemark and Feltham<sup>34</sup> have called this a "stereochemical control of valence."

The 5-coordinate compound IrCl<sub>2</sub>(NO)(PPh<sub>3</sub>)<sub>2</sub>, pictured in Fig. 16.18, is interesting because, although it is isoelectronic with Co(diars)<sub>2</sub>NO<sup>2+</sup>, it has an entirely different structure.<sup>35</sup> We have already pointed out that the Co(diars)<sub>2</sub>-NO<sup>2+</sup> structure corresponds to a d<sup>8</sup> complex of Co<sup>+</sup> and NO<sup>+</sup>, with 18 valence electrons. Although most d<sup>8</sup> complexes have only 16 valence electrons, 18 valence electrons are allowed in this case because the ligands engage in strong back bonding. The analogous structure for IrCl<sub>2</sub>(NO)(PPh<sub>3</sub>)<sub>2</sub> is unstable because most of the ligands do not engage in strong back bonding. To compensate for the buildup of negative charge on the iridium atom, a pair of electrons is transferred to the NO<sup>+</sup> ion, converting it into an NO<sup>-</sup> ion with a bent coordination. The compound may be looked upon as a d<sup>6</sup> complex of iridium(III).

The strength of the N—O bond and the charge on the nitrogen atom in a metal nitrosyl complex would be expected to depend on whether the NO coordination is bent or linear, and, in the case of linear coordination, on the degree of  $d\pi \to \pi^*$  back bonding. On the basis of valence bond structures for linear co-

ordination 
$$(M-N) = O: + \longleftrightarrow M = N = O$$
 and bent coordination  $(M-N) = O$ 

one would expect the N—O bond to be weaker in the bent complexes and in those complexes with strong back bonding. Strong back bonding should be favored in complexes of metal atoms with relatively high electron density. The nitrogen atom charge would be expected to be lower (more negative) in the bent complexes. The N—O bond strength can be measured by the N—O stretching frequency and the N—O bond distance, and the nitrogen atom charge can be measured by the nitrogen 1s electron binding energy. In Table 16.5 these

<sup>35</sup> D. M. P. Mingos and J. A. Ibers, Inorg. Chem., 10, 1035 (1971).




Figure 16.18 Structure of IrCl<sub>2</sub>(NO)(PPh<sub>3</sub>)<sub>2</sub>. The C and H atoms have been omitted for clarity.

<sup>34</sup> Enemark and Feltham, op. cit.

Table 16.5 Properties of some transition-metal nitrosyl complexes

Complexes with linearly coordinated NO groups	Oxidatio metal, as NO <sup>+</sup>	n state of suming	NO stretching frequency, cm <sup>-1</sup>	$N$ 1s $E_B$ , eV	r <sub>N-O</sub> , Å
Na <sub>2</sub> [Fe(NO)(CN) <sub>5</sub> ]	Fe(II)	70.2	1939	403.3	1.13
trans-[FeCl(NO)(diars) <sub>2</sub> ](ClO <sub>4</sub> ) <sub>2</sub>	Fe(II)		1865	402.9	
[Ir(NO)2(PPh3)2]PF6	Ir(-I)		1740	400.2	1.21
$K_3[Mn(NO)(CN)_5]$	Mn(I)		1725	399.7	1.21
Rh(NO)(PPh <sub>3</sub> ) <sub>3</sub>	Rh(-I)		1650	400.8	
$K_3[Cr(NO)(CN)_5]$	Cr(I)		1645	400.7	1.21
Complexes with bent NO groups	Oxidation state of metal, assuming NO-		NO stretching frequency, cm <sup>-1</sup>	$N$ 1s $E_B$ , eV	$r_{N=0}$ ,
[Co(NO)(NH <sub>3</sub> ) <sub>5</sub> ]Cl <sub>2</sub>	Co(III)		1620	400.7	1.15
RhI <sub>2</sub> (NO)(PPh <sub>2</sub> CH <sub>3</sub> ) <sub>2</sub>	Rh(III)		1628	400.3	~ 1.23
trans-[CoCl(NO)(diars) <sub>2</sub> ]Cl	Co(III)		1550	400.5	

quantities are tabulated for various transition-metal nitrosyl complexes.<sup>36</sup> As expected, the low stretching frequencies (corresponding to weak bonds) are found for the bent nitrosyls and for the linear nitrosyls of metals in very low oxidation states. The tabulated stretching frequencies, which range from 1550 to 1939 cm<sup>-1</sup>, may be compared with the frequencies for free NO+ (2200 cm<sup>-1</sup>), free NO (1840 cm<sup>-1</sup>), and organic nitroso compounds, RNO (~1550 cm<sup>-1</sup>). The low nitrogen 1s binding energies (corresponding to relatively negative nitrogen atom charges) are found for the bent nitrosyls (as expected) and for the linear nitrosyls of metals in very low oxidation states. The correlation with oxidation state is reasonable inasmuch as one would expect the charge on the nitrogen atom to be affected by the charge on the adjacent metal atom. The N-O bond-distance data for the bent nitrosyls are inconclusive, but the data for the linear nitrosyls are consistent with weaker bonds for the nitrosyls of metals in low oxidation states.

#### Bipyridyl Complexes37

Bipyridyl (bipy) acts as a bidentate ligand toward many metal atoms.

The free molecule reacts in either solutions with alkali metals to form the anionic species bipy- (paramagnetic) and bipy- (diamagnetic), in which the extra electrons presumably occupy the  $\pi^*$  orbitals of the molecule. Transition-metal

<sup>&</sup>lt;sup>36</sup> P. Finn and W. L. Jolly, *Inorg. Chem.*, 11, 893 (1972).

<sup>&</sup>lt;sup>37</sup> W. R. McWhinnie and J. D. Miller, Adv. Inorg. Chem. Radiochem., 12, 135 (1969).

Table 16.6 Magnetic moments of chromium bipyridyl complexes†

Compound		$\mu_{ ext{eff}}$
Cr(bipy) <sub>3</sub> I <sub>2</sub>	at Production	2.9
Cr(bipy) <sub>3</sub> I		2.07
Cr(bipy) <sub>3</sub>	1865	0.0
Li[Cr(bipy) <sub>3</sub> ] · 4THF		1.83
Na <sub>2</sub> [Cr(bipy) <sub>3</sub> ] · 7THF		~ 2.85
Na <sub>3</sub> [Cr(bipy) <sub>3</sub> ] · 7THF		~ 3.85
Ca <sub>3</sub> [Cr(bipy) <sub>3</sub> ] · 7NH <sub>3</sub>		~ 2.46

† W. R. McWhinnie and J. D. Miller, Adv. Inorg. Chem. Radiochem., 12, 135 (1969).

complexes of bipyridyl can similarly be reduced. For example,  $Cr(bipy)_3^{2+}$  can be reduced to  $Cr(bipy)_3^+$ ,  $Cr(bipy)_3$ ,  $Cr(bipy)_3^-$ ,  $Cr(bipy)_3^{2-}$ ,  $Cr(bipy)_3^{3-}$ , and even  $Cr(bipy)_3^{6-}$ , as indicated by the formulas in Table 16.6. In all these species, there is ambiguity as to the oxidation state of the chromium. Thus  $Cr(bipy)_3$  could be formulated as a Cr(III) complex of three bipy-anions, as a Cr(0) complex of three bipy ligands, or as several other possible combinations. The magnetic data of Table 16.6 help to rule out some of the possibilities. Inasmuch as  $Cr(bipy)_3$  is diamagnetic, it is reasonable to describe it as a  $d^6$  chromium(0) complex in which much of the electron density of the metal has been delocalized onto the ligands by  $d\pi \to \pi^*$  back bonding. In the anionic complexes, the unpaired electron density is probably principally in the  $\pi^*$  orbitals of the bipyridyl groups.

#### Metal Dithienes<sup>38</sup>

The reaction of metallic nickel with sulfur and diphenylacetylene yields the planar 4-coordinate complex indicated in the following reaction:

"W. R. McWhiante and J. D. Miller, Adv. Thory, Chem. Radiochem

This complex can be reduced to a monoanion,  $Ni(S_2C_2Ph_2)_2^-$ , and a dianion,  $Ni(S_2C_2Ph_2)_2^{2-}$ , which have essentially the same structure. There is ambiguity in the assignment of oxidation states to the nickel atoms in these complexes. For example, the neutral complex can be formulated (1) as a nickel (0) complex of two

dithioketone ligands.

(2) as a nickel(II) complex of a dithioketone and a dithiolate anion,

or (3) as a nickel(IV) complex of two dithiolate anions,

As a kind of noncommital compromise, these compounds have been labeled "dithiene" complexes.

Some experimental evidence favors considering all three species as Ni(II) species, on which basis the reduction is formulated as follows:

On successive reduction of the neutral complex, the stretching frequency of the C=C bond increases and that of the C=S bond decreases. The infrared and visible absorption spectra of the -2 complex are similar to those of organosubstituted ethylenedithiolates. The nickel  $2p_{3/2}$  binding energies for all three species are practically the same (852.9, 852.5, and 852.8 eV, respectively), corresponding to similar charges on the nickel atom in all three species.39


<sup>&</sup>lt;sup>39</sup> S. O. Grim, L. J. Matienzo, and W. E. Swartz, J. Am. Chem. Soc., 94, 5116 (1972).

#### **PROBLEMS**

- **16.1** Propose a formula and structure for an iron carbonyl complex of cyclobutadiene. Show that the 18-electron rule and the polyhedral cluster rules are obeyed.
- 16.2 Propose a structure for the acetylene complex  $(C_6H_5)_2C_2Fe_3(CO)_9$  which satisfies the 18-electron and polyhedral cluster rules.
- 16.3 Rationalize the bonding in the molecule H<sub>6</sub>Cu<sub>6</sub>(PPh<sub>3</sub>)<sub>6</sub>, which contains an octahedral Cu<sub>6</sub> cluster.
- 16.4 Suggest a synthetic method to cap the rings of ferrocene to produce two pentagonal bipyramidal clusters joined by a common iron atom. Show that the 18-electron and polyhedral cluster rules would be satisfied in the product.
- **16.5** Which of the following complexes are likely to be unstable:  $ZrCl_4$ , diamagnetic  $NiCl_4^{2-}$ ,  $Ti(CO)_4^{4+}$ ,  $Cd(CO)_3$ ,  $Fe_3(CO)_{12}$ ,  $AuF_4^{2-}$ ? Why?
- 16.6 Rationalize the relative magnitudes of the following reduction potentials.


$$e^{-} + \text{Fe}(\text{CN})_{6}^{3-} = \text{Fe}(\text{CN})_{6}^{4-}$$
  $E^{\circ} = 0.36 \text{ V}$   
 $e^{-} + \text{Fe}(\text{H}_{2}\text{O})_{6}^{3+} = \text{Fe}(\text{H}_{2}\text{O})_{6}^{2+}$   $E^{\circ} = 0.77 \text{ V}$   
 $e^{-} + \text{Fe}(\text{phen})_{3}^{3+} = \text{Fe}(\text{phen})_{2}^{2+}$   $E^{\circ} = 1.14 \text{ V}$ 

- 16.7 Predict the structures of Fe(CO)<sub>4</sub>CN-, Mn(CO)<sub>4</sub>NO, Co(NO)<sub>3</sub>, and [Fe(NO)<sub>2</sub>Br]<sub>2</sub>.
- 16.8 For the "brown ring" species, Fe(H<sub>2</sub>O)<sub>5</sub>NO<sup>2+</sup>, the N—O stretching frequency is 1745 cm<sup>-1</sup> and  $\mu_{\text{eff}} = 3.9$ . Describe the bonding in this complex.
  - 16.9 Show how oxidation-state ambiguities could arise in complexes of the following dianion:



- 16.10 Nickelocene, Ni( $C_5H_5$ )<sub>2</sub>, has a structure analogous to that of ferrocene, but the Ni—C distance is about 0.16 Å longer than the Fe—C distance. Can you rationalize the bonding in nickelocene with the 18-electron rule?
- 16.11 How many carbonyl ligands would you expect to find in the following complexes?
  - (a) H<sub>2</sub>Ru<sub>4</sub>(CO)<sub>x</sub>, with a tetrahedral cluster
- (b)  $H_3Os_4(CO)_xI$ , with a folded butterfly arrangement of Os atoms, and an I atom bridging the terminal Os atoms
- (c) HFe<sub>5</sub>N(CO)<sub>x</sub>, with a square pyramidal arrangement of Fe atoms, and an N atom in the middle of the basal plane
- 16.12 What net charges, if any, would you expect on the following complexes?
  - (a) RhFe<sub>4</sub>C(CO)<sub>14</sub>x± (square pyramidal cluster with a C atom in the basal plane)
  - (b) Rh<sub>10</sub>As(CO)<sub>22</sub>x± (bicapped square antiprism with a central As atom)
  - (c) (η<sup>5</sup>-C<sub>5</sub>H<sub>5</sub>)<sub>4</sub>Ni<sub>4</sub>B<sub>5</sub>H<sub>5</sub><sup>x±</sup> (square antiprism with one square face capped)
- 16.13 What kinds of cluster structures would you expect in the following complexes? (a)  $Rh_7(CO)_{16}^{3-}$ ; (b)  $Fe_3S_2(CO)_9$ ; (c)  $Fe_4(CH)(CO)_{12}H$ ; (d)  $Ru_4(CO)_{12}(MeC = CMe)$
- 16.14 Both Ru<sub>4</sub>(CO)<sub>12</sub>H<sub>4</sub> (12 cluster electrons) and Re<sub>4</sub>(CO)<sub>12</sub>H<sub>4</sub> (8 cluster electrons) have tetrahedral structures. However, the hydrogen atoms of the ruthenium complex occupy  $\mu_2$  edge-bridging sites, and those of the rhenium complex occupy  $\mu_3$  face-bridging sites. Explain the difference in the structures.
- 16.15 A compound of empirical formula FeBC<sub>7</sub>O<sub>3</sub>H<sub>5</sub> (formula determined by high-resolution mass spectroscopy) was obtained by irradiation at 360 nm of a solution of  $C_4H_4$ Fe(CO)<sub>3</sub> and  $B_5H_9$  in ether. Suggest a structure and indicate how the 2n + 2 cluster electron rule is satisfied.

16.16 Rationalize the change in structure of the  $M_3C_3$  framework on going from  $Fe_3(CO)_9(PhCCPh)$  (framework A) to  $Os_3(CO)_{10}(PhCCPh)$  (framework B).



16.17 Rationalize the cluster structure of Fe<sub>2</sub>Ni(CO)<sub>6</sub>(C<sub>2</sub>Ph<sub>2</sub>)( $\eta^5$ -C<sub>5</sub>H<sub>5</sub>)<sup>-</sup>, shown in Fig. 16.19, in terms of the 2n + 2 rule.




Figure 16.19 Structure of Fe<sub>2</sub>Ni(CO)<sub>6</sub>- $(C_2Ph_2)(\eta^5-C_5H_5)^-$ . (See Prob. 16.17.) It is significant that the two Fe—C(1) distances are quite different. The phenyl groups are omitted for clarity. [Reproduced with permission from M. I. Bruce, J. R. Rodgers, M. R. Snow, and F. S. Wong, J. Chem. Soc. Chem. Commun., 1285 (1980).]

16.18 Some cluster compounds are best described as condensed polyhedra in which two polyhedra are joined through a common vertex, edge, or face. Mingos<sup>40</sup> has noted that in such cases the calculated number of cluster electrons is equal to the sum of the characteristic number of cluster electrons for the parent polyhedra minus the number of "cluster" electrons characteristic of the atom, pair of atoms, or face of atoms common to both polyhedra (6, 10, and 12 electrons, respectively). Show that this generalization aids rationalization of the structures of Os<sub>7</sub>(CO)<sub>21</sub> (capped octahedron), Ru<sub>10</sub>C<sub>2</sub>(CO)<sub>24</sub><sup>2-</sup> (two octahedra sharing an edge), and Os<sub>8</sub>(CO)<sub>22</sub>H<sup>-</sup> (a capped trigonal bipyramid and a tetrahedron sharing an edge).

# ELECTRONIC SPECTRA OF COORDINATION COMPOUNDS

Probably the most clear-cut evidence for the electronic energy levels of transition-metal compounds is provided by the electronic spectra of these compounds. Most of this chapter will be concerned with so-called ligand-field spectra, which can be rationalized using simple electrostatic ligand-field splitting diagrams. However, we will also discuss charge-transfer spectra and photoelectron spectra, which require energy level diagrams derivable from molecular orbital (MO) theory for their rationalization.

#### LIGAND-FIELD SPECTRA1-4

First we shall discuss electronic transitions between d orbitals for octahedral and tetrahedral complexes. These transitions are often referred to as d-d or ligand-field transitions. When such transitions occur in complexes with centers of symmetry, such as regular octahedral complexes, the intensities of the absorption bands are low. However, relatively strong absorption bands are obtained for d-d transitions in complexes which lack centers of symmetry, such as cis complexes of the type  $MA_4B_2$  and tetrahedral complexes. The change in intensity of d-d-d

<sup>2</sup> B. N. Figgis, "Introduction to Ligand Fields," Interscience, New York, 1966.

<sup>4</sup> R. S. Drago, "Physical Methods in Chemistry," pp. 359-410, Saunders, Philadelphia, 1977.

C. J. Ballhausen, "Introduction to Ligand Field Theory," McGraw-Hill, New York, 1962.

<sup>&</sup>lt;sup>3</sup> C. K. Jørgensen, "Modern Aspects of Ligand Field Theory," pp. 343-353, American Elsevier, New York, 1971.

transitions on going from octahedral to tetrahedral complexes can be demonstrated by adding excess concentrated hydrochloric acid to an aqueous solution of a Co(II) salt. The color changes from the pale red of Co(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> to the intense blue of CoCl<sub>4</sub><sup>2-</sup>.

Consider a  $d^1$  octahedral complex, for which one observes a single absorption band corresponding to the process  $t_{2g}{}^{1}e_{g}{}^{*0} \rightarrow t_{2g}{}^{0}e_{g}{}^{*1}$ . This transition is represented in spectroscopic notation by the symbols  ${}^{2}T_{2g} \rightarrow {}^{2}E_{g}$ , where the left superscripts indicate the spin multiplicities of the states. (The spin multiplicity is 2S + 1, where S is the total spin of the state.) In the case of a  $d^1$  tetrahedral complex, which has an energy level diagram that is essentially the inverse of that for a  $d^1$  octahedral complex, the notation for the transition is  ${}^2E \rightarrow {}^2T_2$ . The ligand-field transition of a do complex may be treated in essentially the same way as that of a  $d^1$  complex if one recognizes that a  $d^9$  configuration corresponds to a positive hole in a filled  $d^{10}$  configuration. The electrostatic behavior of a hole is the opposite of that of an electron, and so for a  $d^9$  octahedral complex one simply inverts the d1 octahedral energy level diagram. The electronic transition is  ${}^{2}E_{g} \rightarrow {}^{2}T_{2g}$  (the same as that for a  $d^{l}$  tetrahedral complex, except for the g subscripts). For a  $d^9$  tetrahedral complex, the transition is  ${}^2T_2 \rightarrow {}^2E$ . In general, a  $d^n$  octahedral complex has electronic states analogous to those of a  $d^{10-n}$ tetrahedral complex, and vice versa.

If a d5 metal ion is subjected to an octahedral or tetrahedral field which is weak enough not to cause electron pairing, so that each d orbital has one electron, the metal ion will be essentially spherically symmetric, like a  $d^0$  or  $d^{10}$  ion. Removal of a d electron from such a complex, to form a weak-field  $d^4$  complex, is analogous to removal of an electron from a  $d^{10}$  complex, and addition of a delectron, to form a weak-field d6 complex, is analogous to addition of an electron to a  $d^0$  complex. Thus a  $d^6$  weak-field octahedral complex undergoes a  ${}^5T_{2g} \rightarrow {}^5E_g$  transition analogous to the  ${}^2T_{2g} \rightarrow {}^2E_g$  transition of a  $d^1$  octahedral complex. In general, weak-field  $d^{n+5}$  complexes have transitions analogous to

those of the corresponding  $d^n$  complexes.

Thus far, we have discussed one-electron and pseudo-one-electron systems. In such cases there is only one conceivable ligand-field transition, and only one ligand-field band is observed. The situation is much more complicated when more than one electron must be considered. That is, the energy level diagrams shown in Figs. 15.2, 15.4, and 15.10 are oversimplified. In general, there are several possible electronic states corresponding to a particular distribution of two or more electrons in d-orbital levels. These states arise because of the interaction of the electrons with one another. The states have different energies, causing relatively complicated spectra in some cases. If the ligand field of the complex were so strong as to make interelectronic interactions negligible by comparison, than only one d-d transition would be observed for a complex, for example,  $t_{2g}^2 e_g^{*0} \rightarrow t_{2g}^1 e_g^{*1}$ . Actually, of course, the electrons interact appreciably, and the energy level for each MO configuration is split into various terms. If we were able to decrease gradually the ligand-field strength to zero, we would observe that each term would gradually approach an energy corresponding to one of the states of the




Figure 17.1 Correlation diagram for an octahedral  $d^2$  complex.

free ion. Thus the states of the complex can be correlated with those of the free metal ion. In Fig. 17.1 the correlation diagram for a  $d^2$  octahedral complex is shown. Notice that, no matter how strong or weak the field, the ground state is always  ${}^3T_{1g}$ . Now, one of the rules of spectroscopy is that a transition involving a change in multiplicity is forbidden. Therefore, inasmuch as the ground state of the complex is a triplet state, the only allowed transitions are those to other triplet states. Notice that in Fig. 17.1 only the energy levels for triplet states are drawn with solid lines. The allowed transitions, marked with vertical arrows, are  ${}^3T_{1g}(F) \rightarrow {}^3T_{2g}$ ,  ${}^3T_{1g}(F) \rightarrow {}^3A_{2g}$ , and  ${}^3T_{1g}(F) \rightarrow {}^3T_{1g}(P)$ . The two different  ${}^3T_{1g}$  levels are distinguished by indicating, in parentheses, the free-ion states from which they are derived. Inasmuch as the  ${}^3A_{2g}$  level crosses the  ${}^3T_{1g}(P)$  level, the highest-energy transition of a  $d^2$  octahedral complex can be either  ${}^3T_{1g}(F) \rightarrow {}^3T_{1g}(P)$  or  ${}^3T_{1g}(F) \rightarrow {}^3A_{2g}$ , depending on the magnitude of  $\Delta_o$ .

Although the detailed methods of construction of the correlation diagram in Fig. 17.1 are beyond the scope of this book, it is important to have an understanding of the physical basis of the various splittings shown in the diagram. Let us consider the triplet states, which are those of main concern in the spectra of octahedral  $d^2$  complexes. The ground state, based on the  $t_{2g}^2$  configuration, is threefold degenerate (actually a  ${}^3T_{1g}$  state) because there are three ways of placing

See F. A. Cotton, "Chemical Applications of Group Theory," 2d ed., pp. 254–260, Wiley-Interscience, New York, 1971.

 $<sup>^{6}</sup>$  A and B states are nondegenerate, E states are twofold degenerate, and T states are threefold degenerate.

the electrons in the  $t_{2g}$  orbitals (with the restriction that the spins be parallel):

$$(d_{xy})^{1}(d_{xz})^{1}$$
  
 $(d_{xy})^{1}(d_{yz})^{1}$   
 $(d_{xz})^{1}(d_{yz})^{1}$ 

There are two triplet states based on the  $t_{2g}^{\ \ j}e_g^{*1}$  configuration. The one of lower energy (the triply degenerate  ${}^3T_{2g}$  state) has the electrons in orbitals which are as far apart as possible:

$$(d_{xy})^{1}(d_{z^{2}})^{1}$$
  
 $(d_{yz})^{1}(d_{y^{2}})^{1}$   
 $(d_{yz})^{1}(d_{x^{2}})^{1}$ 

The state of higher energy (the triply degenerate  ${}^3T_{1g}$  state) has the electrons in orbitals which are relatively close together:

$$(d_{xy})^{1}(d_{x^{2}-y^{2}})^{1}$$

$$(d_{xz})^{1}(d_{z^{2}-x^{2}})^{1}$$

$$(d_{yz})^{1}(d_{y^{2}-z^{2}})^{1}$$


The reader will remember from Chap. 1 that the choice of five linear combinations of d functions, corresponding to the five d orbitals, is completely arbitrary. Here we have chosen to use unconventional orbitals such as  $d_{y^2}$  and  $d_{z^2-x^2}$  when convenient. There is only one triplet state derived from the  $e_g^{*2}$  configuration (the nondegenerate  ${}^{3}A_{2g}$  state), corresponding to the following orbital occupancy:

$$(d_{x^2-v^2})^1(d_{z^2})^1$$

By similar procedures it is possible to deduce the number, the degeneracies, and the relative energies of the states derived from other electron configurations:  $d^3$ ,  $d^4$ , etc.

A correlation diagram of the type shown in Fig. 17.1 can be drawn for each electron configuration in the series  $d^1$  to  $d^9$  for both octahedral and tetrahedral ions. However, when only qualitative information regarding the allowed spectral transitions of high-spin complexes is desired, the Orgel diagrams<sup>7</sup> shown in Figs. 17.2 and 17.3 can be consulted. These diagrams were constructed by taking advantage of the hole formalism, the spherical symmetry of d5 ions in weak fields, and the fact that the splitting of a given free-ion state is inverted on going from an octahedral to a tetrahedral field. The diagrams give the term symbols of the ground state and all higher states having the same multiplicity. States having the same term symbol are distinguished by parenthetical indication of their free-ion states. The diagrams give the energies of states derived from free-ion ground

L. E. Orgel, J. Chem. Phys., 23, 1004 (1955).



**Figure 17.2** Qualitative Orgel diagram for high-spin octahedral and tetrahedral complexes with 1,4,6, or 9 d electrons.

states, in units of  $\Delta$  relative to the energies of the free-ion ground states. [These energies are very approximate for  $T_1(F)$  states, especially at  $\Delta \geq 5000$  cm<sup>-1</sup>, because these states have their energies depressed by "mixing" with the higherlying  $T_1(P)$  states.] To use the Orgel diagrams, it is only necessary to know that the complex is high-spin (weak-field) and to know the number of d electrons and whether the complex is octahedral ( $O_h$  symmetry) or tetrahedral ( $T_d$  symmetry). The term symbols with the subscripts g (for "gerade") correspond to octahedral complexes, which have centers of symmetry; the symbols without the g subscripts correspond to tetrahedral complexes, which lack centers of symmetry. The multiplicities of the states should be indicated by left superscripts. As a simple example of the use of the Orgel diagrams, let us determine the spectroscopic notation for the lowest-energy ligand-field transition of the octahedral Ni( $H_2O_b^{2^+}$  ion. Because the complex is a  $d^8$  system, we obtain the ground-state and first excited-state terms from the left-hand side of Fig. 17.3. The complex has two




Figure 17.3 Qualitative Orgel diagram for high-spin octahedral and tetrahedral complexes with 2, 3, 7, or 8 d electrons.

unpaired electrons, corresponding to a multiplicity of 3, and so the transition is  ${}^{3}A_{2g} \rightarrow {}^{3}T_{2g}$ . From the diagram, we see that the ground state lies  $\frac{4}{3}\Delta$  below the free-ion energy and that the first excited state lies  $\frac{4}{3}\Delta$  below the free-ion energy. Hence the transition energy is the difference  $\Delta$ .

## The Ligand-Field Splitting, $\Delta$ , and the Interelectronic Repulsion Parameter, B

Before we consider electronic transition energies quantitatively, it is important to have some understanding of the factors which determine the magnitudes of the ligand-field splitting,  $\Delta$ , and the so-called Racah parameter, B. The following generalizations regarding  $\Delta_o$  and  $\Delta_t$  have been drawn from a large body of spectroscopic data.

- 1. For complexes of the first transition series,  $\Delta_o$  ranges from 7500 to 12,500 cm<sup>-1</sup> for + 2 ions and from 14,000 to 25,000 cm<sup>-1</sup> for + 3 ions.
- 2. For metal ions of the same group and with the same charge,  $\Delta_o$  increases by 30 to 50 percent from the first transition series to the second, and from the second to the third.
- 3. We have already pointed out that, other things being equal,  $\Delta_t \approx \frac{4}{9}\Delta_o$ .
- 4. Ligands may be arranged in a series in the order of their abilities to split d-orbital levels, i.e., in the order of the Δ values for the complexes of a given metal ion. This series is called the "spectrochemical series." For some common ligands, it is I<sup>-</sup> < Br<sup>-</sup> < Cl<sup>-</sup> < F<sup>-</sup> < OH<sup>-</sup> < C<sub>2</sub>O<sub>4</sub><sup>2-</sup> ~ H<sub>2</sub>O < NCS<sup>-</sup> < pyridine ~ NH<sub>3</sub> < en < bipyridyl < o-phenanthroline < NO<sub>2</sub><sup>-</sup> < CN<sup>-</sup>. Slightly different orders are found for different metal ions, and this series should be used with caution.

The spectrochemical series constitutes experimental evidence for the superiority of the MO treatment of bonding in complexes over the electrostatic ligand-field treatment. Although the order of the halide ions,  $I^- < Br^- < CI^- < F^-$ , is quite logical, the electrostatic theory alone cannot explain why  $F^-$  does not give the strongest field of all ligands, as would be expected because of its small size. Undoubtedly  $p\pi$ - $d\pi$  repulsions are responsible for the relatively low  $\Delta$  values of halide complexes. Ammonia and the amines have no  $p\pi$  lone-pair orbitals and therefore give relatively high  $\Delta$  values. The water molecule has only one  $p\pi$  lone-pair orbital in contrast to two for the OH<sup>-</sup> ion; consequently water gives greater  $\Delta$  values than OH<sup>-</sup>. The very high  $\Delta$  values of CN<sup>-</sup> and NO<sub>2</sub><sup>-</sup> complexes are due, of course, to  $d\pi \to p\pi^*$  back bonding. The valence bond representations of the bonding of these ligands to metal ions containing d electrons are resonance hybrids of the following type:

hybrids of the following type:

$$M^{-}-C \equiv N \iff M \equiv C \equiv N^{-}$$

$$M^{-}-M \iff M \equiv N$$

$$M^{-}-N \iff M \equiv N$$

$$0^{-1} \iff M \equiv N$$

Table 17.1 Values of f and g for estimating  $\Delta_o$  and of h and k for estimating  $\beta \uparrow$ 

Ligand	$f_{color}$	h	Metal ion	$g \times 10^{-3}$ , cm <sup>-1</sup>	k
Br-	0.72	2.3	Mn <sup>2+</sup>	the transit 0.8 cm	0.07
-SCN-	0.75		Ni <sup>2+</sup>	8.7	0.12
Cl-	0.78	2.0	Co <sup>2+</sup>	in 29 de la laboreni	0.09
OPCl <sub>3</sub>	0.82		V2+	12.0	0.08
N <sub>3</sub> -	0.83		Fe <sup>3+</sup>	14.0	0.24
Et mariognisal t	0.9	0.8	Cu <sup>3+</sup>	15.7	
OSMe <sub>2</sub>	0.91		Cr <sup>3+</sup>	17.4	0.21
OCMe <sub>2</sub>	0.92	1.2	Co3+	18.2	0.35
EtOH	0.97		Ru <sup>2+</sup>	A 20 CHARLES DISH	
Me <sub>2</sub> NCHO	0.98		Ag3+	20.4	
$C_2O_4^{2-}$	0.99	1.5	Ni <sup>4+</sup>	22 Alsh Singsa	
H <sub>2</sub> O	1.00	1.0	Mn <sup>4+</sup>	24	0.5
SC(NH <sub>2</sub> ) <sub>2</sub>	1.01		Mo <sup>3+</sup>	24.6	0.15
-NCS-	1.02		Rh3+	27	0.30
-NCSe-	1.03		Pd <sup>4+</sup>	29	
-NH <sub>2</sub> CH <sub>2</sub> CO <sub>2</sub> -	1.18		Tc4+	31	
CH <sub>3</sub> CN	1.22		Ir <sup>3+</sup>	32	0.3
C <sub>5</sub> H <sub>5</sub> N	1.23		Pt <sup>4+</sup>	36	0.5
NH <sub>3</sub>	1.25	1.4	inted out that, other	have already not	
en is of summing	1.28	1.5	sanged in a series		
-SO <sub>3</sub> <sup>2-</sup>	1.2				
diars	1.33		HE STATE OF THE STATE OF		
dipy	1.33		PHE PARIED, SE, ENG.		
-NO <sub>2</sub> -	1.4		178 2 L 21-yi		
CN- allements	1.7	2.0	PA PARA		

<sup>†</sup> C. K. Jørgensen, "Modern Aspects of Ligand Field Theory," pp. 347-348, American Elsevier, New York, 1971; C. K. Jørgensen, "Absorption Spectra and Chemical Bonding in Complexes," p. 113, Pergamon, Oxford, 1962.

Jørgensen has shown that  $\Delta_o$  can be roughly estimated from the empirical relation  $\Delta_o = fg$ , where f is a parameter characteristic of the ligand and g is a parameter characteristic of the metal.<sup>8</sup> The relation can sometimes be helpful when experimental spectral data are not available. Some f and g values are given in Table 17.1.

The energy separation between states having the maximum possible multiplicity (e.g., between the  ${}^{3}F$  and  ${}^{3}P$  states of a  $d^{2}$  ion) is proportional to a theoretical parameter, B, called the Racah parameter:

$$E(^{3}P) - E(^{3}F) = 15B$$

Values of B for some common ions in the free state are given in Table 17.2. The value of B for a complex is always less than that for the free ion. This reduction of B upon complexation corresponds to a reduction of interelectronic repulsion, due to delocalization of the metal electrons onto the ligands, and is known as the "nephelauxetic" (cloud-expanding) effect. The factor,  $\beta$ , by which B is reduced

<sup>8</sup> Jørgensen, op. cit.

from the free-ion value has been shown to be related to empirical parameters h for the ligand and k for the metal by the equation

$$\beta = \frac{B_{\text{complex}}}{B_{\text{free ion}}} = 1 - hk$$

Some h and k values are given in Table 17.1.

Moderate success has been attained in calculation of the energies of the electronic states of octahedral transition-metal complexes using semiempirical methods. The results of Tanabe and Sugano are presented in the form of graphs in Fig. 17.4. Instead of using absolute units for the electronic energies and  $\Delta_a$ , which would restrict each diagram to just the one case in which the separations of the free-ion terms matched those in the diagram, the state energies and  $\Delta_o$  are expressed in units of the Racah parameter, B. The diagrams are drawn so that the ground state has zero energy for all values of  $\Delta_a/B$ . Thus sharp changes in the slopes of the lines occur where the ground state changes. Of course, these sharp changes are merely artifacts of the method of plotting.

### Spectral Calculations9

Figure 17.5 shows the absorption spectra of the Ni(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> and Ni(en)<sub>3</sub><sup>2+</sup> complex ions. The spectrum of Ni(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> has two main bands in the visible region, with a "window" in the green region (~ 5500 Å); hence this complex is green. The spectrum of Ni(en)<sub>3</sub><sup>2+</sup> has one band in the visible region, with windows in the blue and red regions; hence this complex is purple. Each spectrum has three bands, as expected for d8 octahedral complexes. The Ni(en)32+ bands are at higher frequencies than the corresponding Ni(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> bands, in accord with the spectrochemical series. On the basis of the Orgel and Tanabe-Sugano diagrams, one would assign the lowest-frequency band in each spectrum to a  ${}^3A_{2g} \rightarrow {}^3T_{2g}$  transition, the intermediate-frequency band to a  ${}^3A_{2g} \rightarrow {}^3T_{1g}(F)$  transition, and the highest-frequency band to a  ${}^3A_{2g} \rightarrow {}^3T_{1g}(P)$  transition. The plausibility of these assignments

Table 17.2 Free-ion values of B for transition-metal ions (in cm-1)

Metal	M <sup>2+</sup>	M <sup>3+</sup>
Ti	695	
V Cr	755	861
Cr	810	918
Mn	860	965
Fe	917	1015
Co	971	1065
Ni nipola mana		1115

<sup>&</sup>lt;sup>9</sup> For more detail, see R. S. Drago, "Physical Methods in Chemistry," pp. 359-410, Saunders, Philadelphia, 1977.






Figure 17.4 Tanabe-Sugano energy level diagrams for octahedral complexes with  $d^2$ - $d^8$  electron configurations. [After Y. Tanabe and S. Sugano, J. Phys. Soc. Japan, 9, 753, 766 (1954), reproduced with permission from B. N. Figgis, "Introduction to Ligand Fields," Interscience, New York, 1966.]





and 15,000 cm<sup>-1</sup>. We shall assign these transmions by contracting observed




Figure 17.5 Absorption spectra of  $Ni(H_2O)_6^{2+}$  (solid line) and  $Ni(en)_3^{2+}$  (dashed line). The colors of the visible region of the spectrum are indicated above. [Reproduced with permission from F. A. Cotton, J. Chem. Educ., 41, 466 (1964).]

can be verified by using the  $d^8$  Tanabe-Sugano diagram. Consider, for example, Ni(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, which has transitions at 9000, 14,000, and 25,000 cm<sup>-1</sup>. Clearly the lowest transition energy, 9000 cm<sup>-1</sup>, corresponds to  $\Delta_o$ . (This value is in fair agreement with the value estimated from f and g parameters, 8700 cm<sup>-1</sup>.) From the appropriate data in Tables 17.1 and 17.2, one calculates  $\beta = 0.88$  and  $\Delta/B = 9000/906 = 9.9$  on the abscissa of the  $d^8$  Tanabe-Sugano diagram, one finds E/B values of 16.5 and 29, or transition energies of 15,000 and 26,000 cm<sup>-1</sup>, respectively, for the  ${}^3A_{2g} \rightarrow {}^3T_{1g}(F)$  and  ${}^3A_{2g} \rightarrow {}^3T_{1g}(P)$  transitions. The agreement with the experimental values is quite good.

The  $Co(H_2O)_6^{2+}$  ion has absorption bands at 8350 and 19,000 cm<sup>-1</sup> which have been assigned to the transitions  ${}^4T_{1g}(F) \to {}^4T_{2g}$  and  ${}^4T_{1g}(F) \to {}^4T_{1g}(P)$ , 884 cm<sup>-1</sup> and  $\Delta_o = 9000$  cm<sup>-1</sup> for  $Co(H_2O)_6^{2+}$ . Using these values and the  $d^7$  ranabe-Sugano diagram, we obtain 8600 and 20,000 cm<sup>-1</sup> for the  ${}^4T_{1g}(F) \to {}^4T_{1g}(F) \to {}^4T_{1g}(F)$  transitions, respectively, in fair agreement with the observed bands. The  ${}^4T_{1g}(F) \to {}^4A_{2g}$  band is estimated to be at 16,000 cm<sup>-1</sup>. The two-electron excitation  $t_{2g}{}^5e^{*2} \to t_{2g}{}^3e^{*4}$ ) and is probably obscured by the relatively strong  ${}^4T_{1g}(F) \to {}^4T_{1g}(P)$  band.

Let us now consider the tetrahedral complex, CoCl<sub>4</sub><sup>2-</sup>. Although from the Orgel diagram we predict three transitions, only two have been observed, <sup>10</sup> at 6300 and 15,000 cm<sup>-1</sup>. We shall assign these transitions by comparing the observed

<sup>10</sup> Ballhausen, op. cit.

frequencies with those estimated for the three allowed transitions. We have already estimated  $\Delta_a = 9000 \text{ cm}^{-1}$  for  $\text{Co}(\text{H}_2\text{O})_6^{2+}$ . Because chloride gives about 0.78 as strong a ligand field as water (see Table 17.1) and because  $\Delta_i \approx \frac{4}{3}\Delta_{ab}$ , we predict  $\Delta$ , for  $CoCl_4^{2-}$  to be  $0.78(\frac{4}{0})$  9000 = 3100 cm<sup>-1</sup>. From Fig. 17.3, we see that the energy of the  ${}^4A_2 \rightarrow {}^4T_2$  transition is  $\Delta$ , and that the energy of the  ${}^4A_2 \rightarrow {}^4T_1(F)$  transition should be about  ${}^2\Delta_r$ . From Fig. 17.3 we also see that the energy of the  ${}^4A_2 \rightarrow {}^4T_1(P)$  transition should be  ${}^6\Delta_1$  plus the energy of the  ${}^4T_1(P)$ state. Now a P state is not split by a tetrahedral field, and as a rough approximation we may assume that the  ${}^4T_1(P)$  energy is the same as that of the  ${}^4P$  state of the free Co<sup>2+</sup> ion, or 15B = 14,600 cm<sup>-1</sup>. Thus the energy of the  ${}^4A_2 \rightarrow {}^4T_1(P)$ transition should be approximately  $\frac{6}{5}\Delta$ , + 14,600. Using our estimated value of  $\Delta_t$ , we calculate 3100, 5600, and 18,000 cm<sup>-1</sup> for the transitions  ${}^4A_2 \rightarrow {}^4T_2$ ,  ${}^4A_2 \rightarrow {}^4T_1(F)$ , and  ${}^4A_2 \rightarrow {}^4T_1(P)$ , respectively. It seems reasonable to assign the observed bands to the latter two transitions and to assume that the band predicted to be at 3100 cm<sup>-1</sup> (in the infrared region) has not been observed because of the inconvenient spectral region.

Almost all cobalt(III) complexes of the type  $CoL_6$  are strong-field (low-spin) complexes, corresponding to the right-hand side of the  $d^6$  Tanabe-Sugano diagram. The  ${}^1A_{1g}$  ground state, based on the  $t_{2g}$  configuration, is represented by the electron configuration

$$(d_{xy})^2(d_{xz})^2(d_{yz})^2$$

There are two singlet states based on the  $t_{2g}^{5}e_{g}^{*1}$  configuration. The  ${}^{1}T_{1g}$  state corresponds to the orbital occupancies

$$(d_{xy})^{1}(d_{xz})^{2}(d_{yz})^{2}(d_{x^{2}-y^{2}})^{1}$$

$$(d_{xy})^{2}(d_{xz})^{1}(d_{yz})^{2}(d_{z^{2}-x^{2}})^{1}$$

$$(d_{xy})^{2}(d_{xz})^{2}(d_{yz})^{1}(d_{y^{2}-z^{2}})^{1}$$

and the  ${}^{1}T_{2g}$  state corresponds to the orbital occupancies

$$(d_{xy})^{1}(d_{xz})^{2}(d_{yz})^{2}(d_{z^{2}})^{1} (d_{xy})^{2}(d_{xz})^{1}(d_{yz})^{2}(d_{y^{2}})^{1} (d_{xy})^{2}(d_{xz})^{2}(d_{yz})^{1}(d_{x^{2}})^{2}$$

The  ${}^{1}T_{1g}$  state is of lower energy because in that state the  $t_{2g}$  hole is as close as possible to the  $e_{g}^{*}$  electron. Two transitions, from the  ${}^{1}A_{1g}$  ground state to the  ${}^{1}T_{1g}$  and  ${}^{1}T_{2g}$  states, are generally observed for cobalt(III) complexes. Transitions to higher singlet states, based on the  $t_{2g}{}^{4}e_{g}^{*}$  and  $t_{2g}{}^{3}e_{g}^{*}$  configurations, are of extremely high energy and are usually not observed.


In a cobalt(III) complex of type  $CoL_4X_2$ , the symmetry is lowered and the  ${}^1T_{1g}$  and  ${}^1T_{2g}$  levels are split. The splitting of the  ${}^1T_{2g}$  level is smaller than the width of the  ${}^1A_{1g} \longrightarrow {}^1T_{2g}$  absorption band, and therefore there is no significant change in

Table 17.3 Predicted energy shifts of the components of the  ${}^{1}T_{1g}$  state on going from  $CoL_{6}$  to  $CoL_{4}X_{2}$ 

Electron configuration	$trans-CoL_4X_2$ (X at +z, -z)	cis-CoL <sub>4</sub> X <sub>2</sub> (X at +x, +y)
$(d_{xy})^1(d_{xz})^2(d_{yz})^2(d_{x^2-y^2})^1$	0 <sup>1</sup> A <sub>2g</sub>	2δ ¹B <sub>1</sub>
$(d_{xy})^2(d_{xz})^1(d_{yz})^2(d_{z^2-x^2})^1$ $(d_{xy})^2(d_{xz})^2(d_{yz})^1(d_{y^2-z^2})^1$	$\begin{vmatrix} 2\delta \\ 2\delta \end{vmatrix} {}^{1}E_{g}$	$\left.\begin{array}{c}\delta\\\delta\end{array}\right ^{1}A_{2},^{1}B_{2}$

that absorption band. However, the splitting of the  ${}^{1}T_{1g}$  level is relatively large and causes the first absorption band to split into two components. We shall discuss the relative magnitudes of this splitting of the first absorption band in trans- and cis-CoL<sub>4</sub>X<sub>2</sub>. Let us suppose that the change in energy of the  $d_{x^2-y^2}$ orbital when an L ligand is replaced by an X ligand is zero when X is on the z axis, and  $\delta$  when X is on the x or y axis. Let us also suppose that the  $t_{2g}$  orbitals are unaffected by the ligands (i.e., that  $\pi$  interactions are unimportant). Then the energy levels of the components of the  ${}^{1}T_{1g}$  state will be changed on going from CoL<sub>6</sub> to trans-CoL<sub>4</sub>X<sub>2</sub> and cis-CoL<sub>4</sub>X<sub>2</sub>, as shown in Table 17.3.11 It can be seen that the splitting of the trans complex is twice as great as that of the cis complex and that one component of the trans complex has the same energy as that of the original  ${}^{1}T_{1g}$  state. These results are in agreement with the experimental spectra. The splitting of the first band of a trans complex is about twice that of a cis complex, and a subband unshifted from the first band of the CoL6 complex is found only for the trans isomer of CoL<sub>4</sub>X<sub>2</sub>. Because a cis complex lacks a center of symmetry, its bands are more intense than those of the corresponding trans complex. The spectra of cis- and trans-Co(en)<sub>2</sub>F<sub>2</sub>+, shown in Fig. 17.6, illustrate these effects. 12

<sup>&</sup>lt;sup>12</sup> F. Basolo, C. J. Ballhausen, and J. Bjerrum, Acta Chem. Scand., 9, 810 (1955).



ris- and trans-Co(en)<sub>2</sub>F<sub>2</sub>+. The splitting of the <sup>1</sup>A<sub>1g</sub> — <sup>1</sup>T<sub>1g</sub> band is very apparent in the spectrum of the trans complex and is evidenced only by a band asymmetry in the spectrum of the cis complex. The dashed curve shows the probable shape of the high-frequency component of the split band for the cis isomer. [Reproduced with permission from F. Basolo et al., Acta Chem. Scand., 9, 810 (1955).]

<sup>11</sup> H. Yamatera, Bull. Chem. Soc. Jpn., 31, 95 (1958).

### CHARGE-TRANSFER SPECTRA


### Ligand-to-Metal Charge Transfer

An electronic transition between orbitals that are centered on different atoms is called a charge-transfer transition, and the absorption band is usually very strong. Such bands are often prominent in the spectra of complexes in which there are electrons in  $\pi$  orbitals of the ligands. An energy level diagram for a complex of this type is shown in Fig. 15.11. The spectra of RuCl<sub>6</sub><sup>2</sup>- and IrBr<sub>6</sub><sup>2</sup>- $(d^4)$  and  $d^5$  complexes, respectively) show two sets of bands that have been assigned to transitions from the weakly bonding  $\pi$  orbitals on the ligands to the antibonding  $t_{2g}^*$  and  $e_g^*$  orbitals of the metal atom. In IrBr<sub>6</sub><sup>3</sup> (a  $d^6$  complex), the  $t_{2g}^*$ orbitals are filled, and only the transitions to the  $e_g^*$  orbitals can be observed.

In the halogenopentaammine complexes of the type Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup>, strong charge-transfer bands are observed in the ultraviolet region, as shown in Fig. 17.7. These bands appear at progressively lower frequencies on going from the chloro to the bromo to the iodo complex, as one might expect from the trend in reduction potentials for these halogens. Indeed, in Co(NH<sub>3</sub>)<sub>5</sub>I<sup>2+</sup>, the chargetransfer bands largely obscure the weaker d-d transitions.

### Metal-to-Ligand Charge Transfer

The visible absorption spectra of iron(II) complexes with ligands containing the α-diimine unit






Figure 17.7 The spectra of the Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup> ions. where X is a halogen. (Reproduced with permission from W. L. Jolly, "The Synthesis and Characterization of Inorganic Compounds," Prentice-Hall, Englewood Cliffs, N.J., 1970.)

# Table 17.4 Charge-transfer band maxima of Fe(II)-TIM complexes†

Complex	Band maximum, cm <sup>-1</sup>
Fe(TIM)CH <sub>3</sub> CN(CO) <sup>2+</sup>	23,200
Fe(TIM)(P(OEt) <sub>3</sub> ) <sub>2</sub> <sup>2+</sup>	19,500
Fe(TIM)(CH <sub>3</sub> CN) <sub>2</sub> <sup>2+</sup>	18,200
Fe(TIM)(imidazole) <sub>2</sub> <sup>2+</sup>	15,200
Fe(TIM)(NH <sub>3</sub> ) <sub>2</sub> <sup>2+</sup>	14,300

† M. J. Incorvia and J. I. Zink, *Inorg. Chem.*, **16**, 3161 (1977).

have intense charge-transfer bands associated with the transfer of charge from metal  $t_{2g}$  orbitals to the antibonding orbitals of the  $\alpha$ -diimine group. In the case of the 1,10-phenanthroline complex Fe(phen)<sub>3</sub><sup>2+</sup>, the transition occurs at 19,600 cm<sup>-1</sup>. A series of 6-coordinate iron(II) complexes containing the tetraimine macrocyclic ligand (TIM) shown below, have been prepared with various monodendentate ligands occupying the two axial sites. If The band maxima of these complexes, corresponding to metal-to-TIM charge transfer, are listed in Table 17.4. It can be seen that the transition energy is a function of the  $\pi$ -acceptor ability of the axial ligands. As the  $\pi$ -acceptor ability increases, the energy of the  $d_{xz}$  and  $d_{yz}$  orbitals decreases relative to that of the  $\pi^*$ (TIM) orbital, causing the  $t_{2g} \rightarrow \pi^*$ (TIM) charge-transfer band to move to higher energies.

$$H_3C$$
 $CH_3$ 
 $H_2C$ 
 $N$ 
 $N$ 
 $CH_2$ 
 $CH_2$ 
 $CH_2$ 
 $CH_3$ 
 $CH_2$ 
 $CH_3$ 
 $CH_3$ 
 $CH_4$ 
 $CH_5$ 
 $CH_5$ 
 $CH_5$ 
 $CH_5$ 

### SPECTRA OF COMPOUNDS WITH METAL-METAL BONDS<sup>15</sup>

TIM

Compounds which contain metal-metal bonds are intensely colored. For example,  $Mn_2(CO)_{10}$  is bright yellow,  $Re_2Cl_8^{2-}$  is deep blue,  $Co_2(CO)_8$  is purple-black,

<sup>&</sup>lt;sup>13</sup> E. Konig, Coord. Chem. Rev., 3, 471 (1969); P. Krumholz, Struct. Bonding (Berlin), 9, 139 (1971).

<sup>14</sup> M. J. Incorvia and J. I. Zink, Inorg. Chem., 16, 3161 (1977).

<sup>&</sup>lt;sup>15</sup> W. C. Trogler and H. B. Gray, Acc. Chem. Res., 11, 232 (1978); W. C. Trogler, J. Chem. Educ., 57, 424 (1980).

Mo<sub>2</sub>Cl<sub>8</sub><sup>4</sup> is cherry red, and Fe<sub>2</sub>(CO)<sub>9</sub> is gold. The MO energy level diagrams shown in Fig. 15.13 are appropriate for these compounds; the observed transitions are of the types  $\sigma \to \sigma^*$ ,  $\pi \to \pi^*$ , and  $\delta \to \delta^*$  and are fully allowed. In the case of  $Mn_2(CO)_{10}$ , the  $\sigma \to \sigma^*$  band peaks at 29,400 cm<sup>-1</sup>. One expects that this excitation should be accompanied by weakening or dissociation of the Mn—Mn bond. Indeed, ultraviolet irradiation of Mn<sub>2</sub>(CO)<sub>10</sub> in carbon tetrachloride solution leads to the intermediate formation of Mn(CO), radicals, which abstract chlorine atoms from the solvent to form the chlorine-substituted mononuclear complex: And to the complex of the c

$$Mn_2(CO)_{10} \xrightarrow{hv} 2Mn(CO)_5CI$$

Photochemical cleavage of metal-metal bonds is fairly common in metal cluster compounds. However, it appears that excitation to the relatively weakly antibonding  $\pi^*$  and  $\delta^*$  states is ineffective for such cleavage.

#### PHOTOELECTRON SPECTRA

The various electronic energy levels of a complex can be directly identified by photoelectron spectroscopy. Figure 17.8 shows the ultraviolet photoelectron spectra of crystalline MnF<sub>2</sub> and FeF<sub>2</sub>, which have the rutile structure (octahedral




Figure 17.8 Ultraviolet photoelectron spectra of MnF<sub>2</sub> and FeF<sub>2</sub>. [Adapted from R. T. Poole, J. D. Riley, J. G. Jenkin, J. Liesegang, and R. C. G. Leckey, Phys. Rev. B, 13, 2620 (1976).]

coordination of the metal ions and trigonal coordination of the fluoride ions).16 The MnF<sub>2</sub> spectrum has two main bands. The band at lower energy corresponds to photoionization from the half-filled 3d shell. The asymmetry of this band is probably due to the splitting of the d shell by the octahedral field into the  $t_{2g}^{3}$  and  $e_g^{*2}$  subshells; the low-energy shoulder can reasonably be assigned to the antibonding  $e_g^{*2}$  electrons. The intense band at higher energy is due to the fluoride 2p electrons. The asymmetry of this band is probably due to spin-orbit splitting into  $2p_{3/2}$  and  $2p_{1/2}$  components. chloring stores from the solvent to form the

The spectrum of FeF2 is very similar to that of MnF2, except for an extra small band at the low-energy end of the spectrum. This new feature is part of a final-state multiplet. Photoemission from  $Mn^{2+}$  (3d<sup>5</sup>), with a half-filled d shell, can only lead to quintet final states. In Fe<sup>2+</sup> ( $3d^6$ ), the extra d electron is antiparallel to the other five d electrons, and photoemission can give both quartet and sextet final states. The small band is due to the <sup>6</sup>A<sub>1g</sub> final state; the larger band

is due to quartet states.

### PROBLEMS

- 17.1 The Mn(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> ion has an extremely pale pink color, attributable to transitions which are formally forbidden. Explain why there are no completely allowed d-d transitions.
- 17.2 Two d-d bands can be seen, at 17,000 and 26,000 cm<sup>-1</sup>, in the absorption spectrum of V(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>. Assign the bands.
- 17.3 Predict the colors of the following complexes, which have absorption bands at the indicated frequencies:  $CrF_6^{3-}$  (14,900, 22,700 cm<sup>-1</sup>),  $Cu(NH_3)_4^{2+}$  (14,000 cm<sup>-1</sup>),  $FeO_4^{2-}$  (12,700, 19,600 cm<sup>-1</sup>), Co(en)<sub>3</sub><sup>2+</sup> (21,400, 29,600 cm<sup>-1</sup>).
- 17.4 Predict the d-d absorption spectra (frequencies and spectroscopic assignments for all bands) of CoF<sub>6</sub><sup>3-</sup> (high-spin), NiCl<sub>4</sub><sup>2-</sup>, and Fe(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> (high-spin). Estimate parameters when necessary.
- 17.5 Without referring to any data, indicate how many spin-allowed ligand-field electron transitions you would expect to observe for the following complexes: VCl<sub>4</sub>, CrO<sub>4</sub><sup>2-</sup>, FeO<sub>4</sub><sup>2-</sup>, Fe(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>,  $Cr(H_2O)_6^{3+}$ ,  $Ni(NH_3)_6^{2+}$ ,  $Fe(CN)_6^{4-}$ ,  $Co(H_2O)_6^{2+}$ ,  $Mn(H_2O)_6^{2+}$ ,  $MnO_4^{2-}$ ,  $Zn(OH)_4^{2-}$ .
- 17.6 The  $CrO_4^{2-}$  ion is a  $d^0$  complex and yet is colored. (a) Explain. (b) Would you expect the energy of the transition to be higher or lower than that for MnO<sub>4</sub>-? (Hint: Consider the appropriate
- 17.7 Deduce the number, degeneracies, and relative energies of the quartet states for an octahedral  $d^3$
- 16 R. T. Poole, J. D. Riley, J. G. Jenkin, J. Liesegang, and R. C. G. Leckey, Phys. Rev. B, 13, 2620 (1976).

### OTHER PROPERTIES OF COORDINATION COMPOUNDS

We continue our study of the properties of simple transition-metal compounds. In this chapter we cover static properties that are affected by the metal valence d electrons: magnetic properties, structural effects of the Jahn-Teller theorem, and both structural and thermodynamic consequences of ligand-field stabilization energy and metal-ligand  $\pi$  bonding. Reactions of transition-metal compounds will be covered in later chapters.

### PARAMAGNETISM

### **Magnetic Moment**

When a substance is subjected to a magnetic field, H, a magnetization, I, is induced. The ratio I/H is called the "volume susceptibility,"  $\kappa$ , and can be measured by a variety of techniques, including the Gouy balance method, the Faraday method, and an nmr method.¹ The volume susceptibility is simply related to the "gram susceptibility,"  $\chi_M$ , and the "molar susceptibility,"  $\chi_M$ ,

$$\chi = \frac{\kappa}{d} \qquad \chi_{M} = \frac{\kappa M}{d}$$

where d and M are the density and molecular weight of the substance, respectively. For most substances,  $\kappa$ ,  $\chi$ , and  $\chi_M$  have negative values; such substances

<sup>&</sup>lt;sup>1</sup> W. L. Jolly, "The Synthesis and Characterization of Inorganic Compounds," pp. 369-384, Prentice-Hall, Englewood Cliffs, N.J., 1970.

Table 18.1 Some representative molar magnetic susceptibilities†

Compound	State	$\chi_M \times 10^6$	Compound	State	$\chi_M \times 10^6$
H <sub>2</sub> He N <sub>2</sub> NO O <sub>2</sub> H <sub>2</sub> O	g g g g g g g g g g g g g g g l	-4.0 -1.9 -12.0 1,472 (292 K) 2,324 (147 K) 3,450 -13.1 (373 K) -12.97	CCl <sub>4</sub> CBr <sub>4</sub> C <sub>6</sub> H <sub>6</sub> C <sub>6</sub> H <sub>12</sub> [Cr(H <sub>2</sub> O) <sub>6</sub> ]Cl <sub>3</sub> MnCl <sub>2</sub> · 4H <sub>2</sub> O FeCl <sub>3</sub> · 6H <sub>2</sub> O	1 1 1 1 s s s	-66.8 -93.7 -54.8 -66.1 5,950 14,600 15,250
(CI	1 s s soln	-12.93 (273 K) -12.65 (273 K) -39.0	K <sub>3</sub> Fe(CN) <sub>6</sub> FeCl <sub>2</sub> · 4H <sub>2</sub> O K <sub>4</sub> Fe(CN) <sub>6</sub> CuSO <sub>4</sub> · 5H <sub>2</sub> O	S S S	2,290 12,900 -130 1,460
EBr II Ig a	s s s l	-39.4 -49.1 -63.8 -33.4 +16.1	ZnSO <sub>4</sub> · 7H <sub>2</sub> O Ce(NO <sub>3</sub> ) <sub>3</sub> · 5H <sub>2</sub> O Ce(SO <sub>4</sub> ) <sub>2</sub> · 4H <sub>2</sub> O Gd(C <sub>2</sub> H <sub>3</sub> SO <sub>4</sub> ) <sub>3</sub> · 9H <sub>2</sub> O U(C <sub>2</sub> O <sub>4</sub> ) <sub>2</sub> · 5H <sub>2</sub> O	S S S	-143 2,310 -97 24,100 3,760

<sup>†</sup> Values are for 290 to 295 K unless otherwise indicated. They are taken from G. Foëx, Tables of Constants and Numerical Data (U.I.C.P.A.), No. 7, "Constantes Sélectionnées Diamagnétisme et Paramagnétisme," Masson, Paris, 1957. They are in units of 10<sup>-6</sup> cm<sup>3</sup> mol<sup>-1</sup>.

are weakly repelled by a magnetic field and are called "diamagnetic." substances having unpaired electrons that do not strongly interact with one another,  $\kappa$ ,  $\chi$ , and  $\chi_M$  have relatively large positive values; these substances are attracted into a magnetic field and are called "paramagnetic." A list of miscellaneous substances and their molar susceptibilities is given in Table 18.1.

When a paramagnetic substance is placed in a magnetic field, the moments of the paramagnetic molecules or ions tend to align with the field; however, thermal agitation tends to randomize the orientations of the individual moments. Theoretical analysis of the situation leads to the relation

$$\chi_M^{\rm corr} = \frac{N\mu^2}{3kT}$$

 $\chi_M^{\rm corr} = \frac{N\mu^2}{3kT}$ where  $\chi_{M}^{corr}$  is the molar susceptibility which has been corrected both for the diamagnetic contribution to the susceptibility (due to the nonparamagnetic atoms in the sample) and for any small temperature-independent paramagnetism arising from paramagnetic excited states of the system, N is Avogadro's number, k is the Boltzmann constant,  $\mu$  is the "magnetic moment" of the molecule, and T

<sup>&</sup>lt;sup>2</sup> If the uncorrected value of  $\chi$  is used, the corresponding value of  $\mu$  is usually called the "effective" magnetic moment,  $\mu_{\text{eff}}$ . For a discussion of diamagnetic contributions and temperature-independent paramagnetism, see F. A. Cotton and G. Wilkinson, "Advanced Inorganic Chemistry," 4th ed., pp. 1359-1365, Wiley-Interscience, New York, 1980, and Landolt-Börnstein, "Magnetic Properties of Coordination and Organometallic Transition Metal Compounds," E. König, vol. II/2, 1966; E. König and G. König, vol. II/8, 1976, Springer-Verlag, New York.

is the absolute temperature. By substituting numerical values for N and k, we obtain

$$\chi_M^{\text{corr}} = \frac{0.125\mu^2}{T} \quad \text{or} \quad \mu = 2.83\sqrt{\chi_M^{\text{corr}}T}$$
(18.1)

The importance of the magnetic moment,  $\mu$ , in transition-metal chemistry lies in the fact that, for most compounds, it is both experimentally measurable and theoretically calculable. Often the magnitude of the calculated moment is markedly changed by a change in the assumed structure or a change in the assumed type of bonding. In such cases comparison of experimental  $\mu$  values with calculated  $\mu$  values can be of considerable value in characterization of the compounds.

The magnetic moment of a transition-metal complex is a combination of spin and orbital moments. In many complexes, the ligand field almost completely quenches the orbital contribution, and the magnetic moment can be calculated by the following "spin-only" formula,

$$\mu = 2\sqrt{S(S+1)}$$

where S is the total spin of the complex. Because in the ground state S is one-half the number of unpaired electrons, n, we may write

$$\mu = \sqrt{n(n+2)}$$


In Table 18.2, the experimental  $\mu$  values for various octahedral complexes of the first transition series are listed with the  $\mu$  values calculated by the spin-only

Table 18.2 Experimental and calculated values of the magnetic moment†

No. of unpaired electrons,	Compound	Ground state	Experimental $\mu$	$[n(n+2)]^{1/2}$
spin states arel because of the grahedral com-	CsTi(SO <sub>4</sub> ) <sub>2</sub> · 12H <sub>2</sub> O K <sub>4</sub> Mn(CN) <sub>6</sub> · 3H <sub>2</sub> O‡ K <sub>2</sub> PbCo(NO <sub>2</sub> ) <sub>6</sub> ‡ (NH <sub>4</sub> ) <sub>2</sub> Cu(SO <sub>4</sub> ) <sub>2</sub> · 6H <sub>2</sub> O	${}^{2}T_{2g}$ ${}^{2}T_{2g}$ ${}^{2}E_{g}$ ${}^{2}E_{g}$	1.8 2.2 1.8 1.9	1.73 1.73 1.73 1.73
2	(NH <sub>4</sub> )V(SO <sub>4</sub> ) <sub>2</sub> · 12H <sub>2</sub> O Cr(dipy) <sub>3</sub> Br <sub>2</sub> · 4H <sub>2</sub> O‡ (NH <sub>4</sub> ) <sub>2</sub> Ni(SO <sub>4</sub> ) <sub>2</sub> · 6H <sub>2</sub> O	${}^{3}T_{1g}$ ${}^{3}T_{1g}$ ${}^{3}A_{2g}$	2.7 3.3 3.2	2.83 2.83 2.83
a high spin of	KCr(SO <sub>4</sub> ) <sub>2</sub> · 12H <sub>2</sub> O (NH <sub>4</sub> ) <sub>2</sub> Co(SO <sub>4</sub> ) <sub>2</sub> · 6H <sub>2</sub> O	<sup>4</sup> A <sub>2g</sub> <sup>4</sup> T <sub>1g</sub>	3.8 5.1	3.87 3.87
And Joseph States of the	$CrSO_4 \cdot 6H_2O$ $(NH_4)_2Fe(SO_4)_2 \cdot 6H_2O$	$^5E_g$ $^5T_{2g}$	4.8 5.5	4.90 4.90
of a Rolling	$K_2Mn(SO_4)_2 \cdot 6H_2O$	$^6A_{1g}$	5.9	5.92

<sup>&</sup>lt;sup>†</sup> W. L. Jolly, "The Synthesis and Characterization of Inorganic Compounds," pp. 369-384, Prentice-Hall, Englewood Cliffs, N.J., 1970.

<sup>‡</sup> Strong-field (low-spin) complexes.





rigure 10.1 Energy level diagrams to and strongly tetragonally distorted octahedral ds The strongs temperature  $d_{yz}$ ,  $d_{yz}$ ,  $d_{xz}$  complexes, showing the electron occupancies. quenches the orisital contribution; and the magnetic moment can be calculated by


formula. The data permit us to distinguish readily between strong- and weakfield complexes. For example, [Cr(H<sub>2</sub>O)<sub>6</sub>]SO<sub>4</sub> is a weak-field d<sup>4</sup> complex with  $\mu = 4.8$ , whereas [Cr(dipy)<sub>3</sub>]Br<sub>2</sub> · 4H<sub>2</sub>O is a strong-field  $d^4$  complex with  $\mu = 3.3$ . Similar pairs of weak- and strong-field complexes, respectively, are the d5 complexes  $K_2[Mn(H_2O)_6](SO_4)_2$  ( $\mu = 5.9$ ) and  $K_4[Mn(CN)_6] \cdot 3H_2O$  ( $\mu = 2.2$ ) and the  $d^7$  complexes  $(NH_4)_2[Co(H_2O)_6](SO_4)_2$  ( $\mu = 5.1$ ) and  $K_2Pb[Co(NO_2)_6]$  ( $\mu = 1.8$ ). The  $d^6$  weak-field complex  $(NH_4)_2[Fe(H_2O)_6](SO_4)_2$  ( $\mu = 5.5$ ) may be compared with the strong-field K<sub>4</sub>[Fe(CN)<sub>6</sub>], which is not listed in the table because it is diamagnetic.

Consider the effect on a  $d^8$  octahedral complex of a tetragonal elongation. Two possible electron configurations are shown in Fig. 18.1. In the case of a regular octahedral complex, there are two unpaired electrons. However, in the case of strong distortion or a square planar complex, a zero-spin state results. Indeed, all square planar d8 complexes are diamagnetic unless the ligands have unpaired electrons. In tetrahedral complexes, high-spin and low-spin states are, in principle, possible for the configurations  $d^3$ ,  $d^4$ ,  $d^5$ , and  $d^6$ , but because of the relatively small magnitude of  $\Delta_i$ , there are no known low-spin tetrahedral com-

### High-Spin-Low-Spin Crossover

Octahedral complexes with 4, 5, 6, or 7 d electrons can be either high-spin or low-spin, depending on the magnitude of the ligand-field splitting,  $\Delta_o$ . When the ligand-field splitting has an intermediate value such that the two states of the complex have similar energies, the two states can coexist in measurable amounts at equilibrium. Many "crossover" systems of this type have been studied.3 In

R. L. Martin and A. H. White, Transition Met. Chem., 4, 113 (1968); H. A. Goodwin, Coord-Chem. Rev., 18, 293 (1976).



solutions, these systems are fairly straightforward; the change in magnetic susceptibility with temperature can be interpreted in terms of the heat of conversion of one isomer to another. For example, susceptibility-versus-temperature data for CH<sub>2</sub>Cl<sub>2</sub> solutions of the iron(II) d<sup>6</sup> complex Fe[(pz)<sub>3</sub>BH]<sub>2</sub> [where the (pz)<sub>3</sub>BH ligand has the structure shown below] are shown in Fig. 18.2.4 Clearly the data do not conform to Eq. 18.1. However, treatment of the system as an equilibrium between two spins yields  $\Delta H = 3.85$  kcal mol<sup>-1</sup> and  $\Delta S = 11.4$  eu for the highspin - low-spin conversion. On the other hand, spin crossover in solids is a complex phenomenon because of cooperative structural changes and changes in the energy separation of the high-spin and low-spin states with temperature.5 Thus the magnetism of Fe(phen), (NCS), changes sharply at 174 K, as shown in of the electron mais be able to encurite at Fig. 18.3.6

### Orbital Angular Momentum<sup>7</sup>

About half of the experimental  $\mu$  values listed in Table 18.2 are close to the theoretical  $\mu$  values calculated from the spin-only formula. However, the re-

<sup>&</sup>lt;sup>4</sup> J. P. Jesson, S. Trofimenko, and D. R. Eaton, J. Am. Chem. Soc., 89, 3158 (1967).

E. König and S. Kremer, Theoret. Chim. Acta. 20, 143 (1971).

<sup>&</sup>lt;sup>6</sup> E. König and K. Madeja, *Inorg. Chem.*, **6**, 48 (1967). For similar systems, see M. G. Burnett, V. McKee, and S. M. Nelson, J. Chem. Soc. Dalton Trans., 1492 (1981).

B. N. Figgis and J. Lewis, Prog. Inorg. Chem. 6, 37 (1964).




Figure 18.3 The magnetic moment of Fe(phen)<sub>2</sub>(NCS)<sub>2</sub> as a function of temperature. [Adapted from E. König and K. Madeja, Inorg. Chem., 6, 48 (1967). Copyright 1967 American Chemical Society.]

maining experimental  $\mu$  values differ significantly from the simple theoretical values. The deviations are generally due to incomplete quenching of the orbital magnetic moment by the ligand field.

An electron must be able to circulate about an axis if it is to have orbital angular momentum. Therefore an orbital must be available, in addition to the orbital containing the electron, which has the following properties. It must have the same shape and energy as the orbital containing the electron. It must be superimposable on the orbital containing the electron by rotation about an axis. And, finally, it cannot contain an electron having the same spin as the first electron. These conditions are fulfilled in the case of d electrons in an octahedral or tetrahedral field whenever any two  $t_2$  or  $t_{2g}$  orbitals  $(d_{xy}, d_{xz}, d_{yz})$  contain one or three electrons. Thus unquenched orbital angular momentum will remain for a metal complex with 1, 2, 4, or 5 electrons in the  $t_2$  or  $t_{2g}$  orbitals, corresponding to  $T_1$ ,  $T_2$ ,  $T_{1g}$ , or  $T_{2g}$  ground states. In Table 18.2 practically all the complexes for which  $\mu$  deviates markedly from the spin-only  $\mu$  value have T ground states.

For the purpose of estimating  $\mu$  values for complexes with unquenched orbital angular momentum, the values in Table 18.3 can be used. These are theoretical values, a calculated from free-ion parameters, and one should not expect agreement with experimental values for complexes to better than  $\pm 0.2$ .

<sup>8</sup> B. N. Figgis, "Introduction to Ligand Fields," Interscience, New York, 1966.

Table 18.3 Calculated values of  $\mu$  at 300 K for octahedral and tetrahedral stereochemistries, assuming free-ion values of spin-orbit coupling†

${}^{2}T_{2(g)}$ state	es	$^3T_{1(g)}$ state	es	$0014T_{1(g)}$ state	es	5T2(g) state	es
Ti <sup>3+</sup>	0.1.90 1	00 V3+ 11/0	2.7	Cr3+	3.4	Cr2+	4.7
Mo <sup>5+</sup>	1.0	Cr <sup>2+</sup>	3.5	Co <sup>2+</sup>	5.1	Mn <sup>3+</sup>	4.5
Mn <sup>2+</sup>	2.55	Mo <sup>4+</sup>	1.9			Fe <sup>2+</sup>	5.65
Fe <sup>3+</sup>	2.45	W <sup>4+</sup>	1.5	/ ALVE TILE	THE PARTY OF THE P	Co3+	5.75
Ru <sup>3+</sup>	2.1	Mn³+	3.65				
Os <sup>3+</sup>	1.85	Re3+	2.4			nement with	
Ir4+	1.8	Fe <sup>4+</sup>	3.55				
Cu <sup>2+</sup>	2.2	Ru <sup>4+</sup>	3.2				
		Os <sup>4+</sup>	1.9				
		Ni <sup>2+</sup>	4.0				

<sup>†</sup> B. N. Figgis, "Introduction to Ligand Fields," Interscience, New York, 1966.

Smaller but significant discrepancies between experimental moments and calculated spin-only moments are found for complexes with  $A_2$ ,  $A_{2g}$ , E, and  $E_g$ ground states. These discrepancies are caused by angular momentum introduced to the ground state by a mixing in of higher T states. Theory shows that the magnetic moment of such a complex can be calculated from the relation

The smooth region is 
$$\mu = \left(1 - \frac{\lambda'}{\Delta}\right) [n(n+2)]^{1/2}$$
 (18.2)

Assume that the first parameter  $\lambda'$  for metal ions in

Appropriate values of the spin-orbit coupling parameter,  $\lambda'$ , for metal ions in octahedral and tetrahedral environments are given in Table 18.4.

Magnetic data may be used to determine the type of bonding in cobalt(II) complexes. Tetrahedral Co(II) complexes have room-temperature magnetic moments that range from 4.40 to 4.88. For example,  $\mu = 4.59$  for  $CoCl_4^{2-}$ . We a this ignification of your of y wesus ten

Table 18.4 Values of λ' for several metal ions†

Metal ion	Symmetry	Ground state	λ', cm <sup>-1</sup>	
V4+	T TE MON	<sup>2</sup> E	500	
V2+	$T_d$	4A <sub>2g</sub>	228	
Cr3+	O <sub>h</sub>		368	
Cr2+	O <sub>h</sub>	<sup>4</sup> A <sub>2g</sub>	116	
Mn <sup>4+</sup>	O <sub>h</sub>	5E <sub>g</sub>	552	
Mn³+	O <sub>h</sub>	<sup>4</sup> A <sub>2g</sub>	178	
-e2+	$O_h$	$^{5}E_{g}$	-200	
CO <sup>2+</sup>	$T_d T_d$	5E	-688	
Co <sup>2+</sup>		<sup>4</sup> A <sub>2</sub>	-1030	
Vi <sup>2+</sup>	$O_h$	$^{2}E_{g}$	-1260	mee sneghas
Cu <sup>2+</sup>	$O_h$	$^3A_{2g}$	-1660	
_u	$O_h$	$^{2}E_{g}$	-1000	

<sup>†</sup> B. N. Figgis, "Introduction to Ligand Fields," Interscience, New York, 1966.

can show that this is a reasonable value by use of Eq. 18.2:

$$\mu = \left(1 + \frac{688}{3100}\right)(3.87) = 4.73$$

Octahedral weak-field Co(II) complexes such as  $(NH_4)_2[Co(H_2O)_6](SO_4)_2$  have room-temperature moments of 5.0 to 5.1, in remarkably close agreement with the value of 5.1 from Table 18.3. Octahedral strong-field Co(II) complexes appear to be very rare. However,  $K_2Pb[Co(NO_2)_6]$  has been reported to have  $\mu=1.8$ , in fair agreement with the value estimated by using Eq. 18.2:

$$\mu = \left(1 + \frac{1030}{12,600}\right)(1.73) = 1.87$$

# FERROMAGNETISM, FERRIMAGNETISM, AND

If there is coupling between the individual magnetic moments of a paramagnetic sample, spontaneous ordering of the moments will occur below a critical temperature. If this ordering involves alignment of all the moments in the same direction to produce a permanent magnetic moment, the substance is said to be "ferromagnetic" and the critical temperature is called the "Curie temperature." If some of the moments are systematically aligned opposed to the others, but the relative numbers or magnitudes of the moments are such as to give a finite resultant magnetic moment, the substance is said to be "ferrimagnetic." The phenomenological properties of ferrimagnetism are essentially the same as those of ferromagnetism. If half the moments are aligned opposed to the other half, giving zero net moment, the substance is said to be "antiferromagnetic" and the critical temperature is called the Néel temperature. Schematic representations of the various types of magnetism are shown in Fig. 18.4, and rough plots of  $\chi$  versus temperature for a paramagnet, a ferromagnet (or ferrimagnet), and an antiferromagnet are shown in Fig. 18.5.

We have already discussed ferromagnetic metals in Chap. 12. However,




Figure 18.4 A schematic representation of the various type of magnetism.




Figure 18.5 Schematic plots of magnetic susceptibility versus temperature for the various types of magnetism.  $T_c$  = Curie temperature;  $T_N$  = Néel temperature.

many compounds also exhibit ferromagnetism. For example CrO2, which is used in recording tapes, is ferromagnetic, with a room-temperature magnetization of 515 gauss and a Curie temperature of 386 K. A familiar example of a ferrimagnetic material is magnetite, Fe<sub>3</sub>O<sub>4</sub>. Here the Fe(II) moments are aligned parallel, but the Fe(III) moments are antiparallel, and the observed net moment arises only from the Fe(II) moments. The classic example of antiferromagnetism is MnO, which has the NaCl structure and a Néel temperature of 116 K. The three-dimensional distribution of spins in the antiferromagnetic form of this compound has been elucidated by neutron diffraction,9 which can distinguish between sets of atoms having opposed moments. The neutron diffraction patterns at 80 and 293 K are shown in Fig. 18.6. The 80-K pattern shows extra reflections not present in the 293-K pattern. The reflections at 80 K correspond to a unit cell of lattice constant 8.85 Å; those at 293 K correspond to a cell of lattice constant 4.43 Å. However, the lattice constant determined by x-ray diffraction (which cannot distinguish spins) is 4.43 Å at both temperatures. These results are most plausibly interpreted in terms of the low-temperature arrangement of Mn<sup>2+</sup> spins shown in Fig. 18.7.<sup>10</sup> It can be seen that the repeat distance for spins aligned in the same direction is twice as great as that for manganese atoms.

The coupling between the individual moments of most ferromagnetic, ferrimagnetic, and antiferromagnetic substances is stronger than can be accounted for by simple dipole-dipole interactions. It is believed that the dipoles are coupled through the electrons of intervening nonmetal atoms, by a process called "superexchange." 11 For example, in MnO, one superexchange mechanism is believed

<sup>&</sup>lt;sup>9</sup> C. G. Shull, W. A. Strauser, and E. O. Wollan, *Phys. Rev.*, 83, 333 (1951).

<sup>10</sup> Y. Y. Li, Phys. Rev., 100, 627 (1955).

J. B. Goodenough, "Magnetism and the Chemical Bond," Interscience, New York, 1963.




Figure 18.6 Neutron diffraction patterns for MnO below and above the Néel temperature of 116 K. [Reproduced with permission from C. G. Shull, W. A. Strauser, and E. O. Wollan, Phys. Rev., 83, 333 (1951).]





Figure 18.7 Arrangement of Mn<sup>2+</sup> spins in the antiferromagnetic form of MnO. Above 116 K the Mn<sup>2+</sup> ions are still magnetic, but they are no longer ordered. Note that the oxygen atoms are not shown.

to involve  $\sigma$  interactions between the half-filled  $e_g$  orbitals of Mn<sup>2+</sup> ions and the filled  $p\sigma$  orbitals of oxide ions, as follows.



At any instant, the oxide electron which interacts with Mn<sub>1</sub> must have its spin opposed to that of the Mn<sub>1</sub> electron, leaving an electron of opposite spin to interact with Mn2. Thus the manganese electrons are antiferromagnetically coupled.

### JAHN-TELLER DISTORTIONS

A regular octahedral environment is the most stable one for a spherically symmetric metal ion surrounded by six ligand atoms. For metal ions with certain d electron configurations which are not spherically symmetric, the regular octahedral configuration is not the most stable. The situation can be expressed in a general and rigorous way by the Jahn-Teller theorem:12 Any nonlinear molecule in a degenerate electronic state will undergo distortion to remove the degeneracy and to lower the energy. For example, consider a high-spin  $d^4$  complex. In a regular octahedral environment the  $e_g^*$  electron is doubly degenerate; it can occupy either the  $d_z^2$  or the  $d_{x^2-y^2}$  orbital. However, if the complex undergoes a tetragonal distortion, the  $e_g^*$  levels are split and the electron can then occupy the lower of the two orbitals (the  $d_{z^2}$  orbital in the case of tetragonal elongation; the  $d_{x^2-y^2}$  orbital in the case of tetragonal contraction). The same sort of distortion is expected in the case of  $d^9$  and low-spin  $d^7$  complexes. Examples of Jahn-Teller distortions of octahedral coordination are found in CrF2 and MnF3 (d4 configurations), in NaNiO<sub>2</sub> (low-spin d<sup>7</sup> configuration), and in many copper(II) compounds, such as CuCl<sub>2</sub> and CuF<sub>2</sub> (d<sup>9</sup> configurations). In each of these cases the metal ion is surrounded by six anions at the vertices of an elongated octahedron. Complexes with  $d^8$  configurations are a special case. In general, the complexes are either regular octahedral (with two unpaired electrons) or square planar and diamagnetic. The reason for the lack of  $d^8$  octahedral complexes with small or intermediate tetragonal elongation can be seen by reference to Fig. 18.8. The energy of the singlet state either will never be below that of the undistorted triplet state (as in Fig. 18.8a) or will become lower than that of the undistorted triplet state in a highly distorted complex (as in Fig. 18.8b). In either case, the triplet state is much more stable than the singlet state in the undistorted octahedral complex. In Fig. 18.8a no degree of distortion will make the complex

<sup>&</sup>lt;sup>12</sup> H. A. Jahn and E. Teller, *Proc. R. Soc. London Ser. A*, **161**, 220 (1937).




Figure 18.8 Potential energy curves illustrating stability of the high-spin regular octahedral design octahedr complex (a) and stability of the highly distorted (essentially square planar) low-spin d8 complex (b). (Adapted with permission from L. E. Orgel, "An Introduction to Transition-Metal Chemistry. Ligand Field Theory," 2d ed., Chapman and Hall, London, 1966.)

more stable than the undistorted triplet-state complex. In Fig. 18.8b, a large tetragonal distortion is required to stabilize the singlet state relative to the undistorted triplet state.

Degeneracies arising from partially filled  $t_{2g}$  levels should also produce Jahn-Teller distortions, but the effects are relatively small because the  $t_{2g}$  orbitals are relatively unaffected by the ligands. Evidence for Jahn-Teller distortions and the consequent splitting of energy levels is found in the spectra of many complexes. For example, consider the absorption spectrum of Ti(H2O)63+, shown in Fig. 18.9. This band is obviously not a simple symmetric band such as one might expect for a  ${}^2T_{2g} \rightarrow {}^2E_g$  transition. The breadth and asymmetry of the band are evidence of transitions to two excited states caused by distortion of the complex.

Relatively weak distortions are expected for tetrahedral complexes with  $d^3$ ,  $d^4$ ,  $d^8$ , and  $d^9$  configurations.<sup>13</sup> In the  $d^3$  and  $d^8$  complexes, one of the  $l_2$  orbitals

13 L. E. Orgel, "An Introduction to Transition-Metal Chemistry. Ligand Field Theory," 2d ed. Chapman and Hall, London, 1966. dons), in NaNiO, (low-spin all donne





Figure 18.9 The visible absorption spectrum of Ti(H2O)63+. duced with permission from F. A. Cotton, J. Chem. Educ., 41, 466 (1964).1






Figure 18.10 Distortions of tetrahedral coordination. (a) Elongation caused by t21 and t24 configurations; (b) flattening caused by 122 and t25 configurations. (Adapted with permission from L. E. Orgel, "An Introduction to Transition-Metal Chemistry. Ligand Field Theory," 2d ed., Chapman and Hall, London, 1966.)

has one more electron than the other two. This situation should cause an elongation of the tetrahedron, as shown in Fig. 18.10a. In the  $d^4$  and  $d^9$ complexes, one of the  $t_2$  orbitals has one fewer electron than the other two (i.e., an electron hole). This situation should cause a flattening of the tetrahedron, as shown in Fig. 18.10b. In agreement with these predictions, it has been found that the CuCl<sub>4</sub><sup>2-</sup> complex has a flattened tetrahedral configuration and that the oxide environment around the Ni<sup>2+</sup> in NiCr<sub>2</sub>O<sub>4</sub> is that of an elongated tetrahedron.

There are apparent exceptions to the Jahn-Teller theorem, in which certain physical properties correspond to symmetric structures when distorted structures are expected. All such apparent exceptions to the theorem are probably examples of the so-called dynamic Jahn-Teller effect, in which the direction of distortion of a complex (say an elongation of one axis of an octahedron) randomly moves among the available symmetry axes of the complex more rapidly than the physical measurement can "follow." The physical measurement thus "sees" an average structure, with no apparent distortion. For example, the room-temperature epr spectrum of a dilute solution of Cu(H2O)62+ in a host crystal of [Zn(H2O)6]SiF6 shows only one transition, corresponding to a regular octahedral geometry for the Cu(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> ions. <sup>14</sup> However, it is believed that, in the crystal, each cation is tetragonally distorted along one of three mutually perpendicular axes. At room temperature only one transition is observed because, on the epr time scale, each cation appears to be symmetric. However, when the crystal is cooled to 20 K, the interchange of distortion axes slows down, and the spectrum becomes that expected for three magnetic sites. metals are plotted as a function of atomic purple

### LIGAND-FIELD STABILIZATION ENERGY tained for the lattice energies of o

When a transition-metal ion is placed in an octahedral field, three of the d orbitals are stabilized by  $\frac{2}{3}\Delta_o$  and two of the d orbitals are destabilized by  $\frac{2}{3}\Delta_o$ . In the case of an octahedral complex with the configuration  $t_{2g}^{p}e_{g}^{*q}$ , the net stabilization energy is  $(\frac{2}{5}p - \frac{3}{5}q)\Delta_o$ . For example, a  $d^3$  complex such as  $Cr(H_2O)_6^{3+}$  is stabilized by  $\frac{6}{3}\Delta_o$ , that is (using  $\Delta_o = 17,400 \text{ cm}^{-1}$ ), by 20,900 cm<sup>-1</sup> or 59.7 kcal mol<sup>-1</sup>, relative to a hypothetical  $\text{Cr}(\text{H}_2\text{O})_6^{3+}$  ion in which the three d electrons have a

<sup>14</sup> B. Bleaney and D. J. E. Ingram, Proc. Phys. Soc. London Sect. A, 63, 408 (1950); A. Abragam and M. H. L. Pryce, Proc. R. Soc. London Ser. A. 206, 164 (1951).




Figure 18.11 Hydration energies of the +2 ions of the first transition series plotted versus atomic number. Solid circles are experimental points; open circles correspond to values from which spectrally evaluated ligand-field stabilization energies have been subtracted. [Reproduced with permission from F. A. Cotton, J. Chem. Educ., 41, 466 (1964).]

spherically symmetric disposition. Obviously these stabilization energies are of great importance in determining the relative thermodynamic properties of transition-metal complexes.

Consider the hydration energies of the +2 ions of the first transition series:

$$M^{2+}(g) \rightarrow M^{2+}(aq) \qquad \Delta H^{\circ} = -\Delta H_{hyd}$$

These energies, obtained from thermochemical data, are plotted as a function of atomic number in Fig. 18.11. If one draws a smooth curve through the three points corresponding to the spherically symmetric metal ions ( $Ca^{2+}$ ,  $Mn^{2+}$ , and  $Zn^{2+}$ ), for which one would expect no net ligand-field stabilization, it is obvious that all the other points lie above the curve. It is reasonable to assume that the deviations from the curve are due to the extra ligand-field stabilization energies of the  $M(H_2O)_6^{2+}$  ions. If we subtract the appropriate values of  $(\frac{2}{3}p-\frac{3}{3}q)\Delta_o$  (calculated from spectral  $\Delta_o$  data) from the hydration energies, we obtain the points indicated by open circles, which fall on the smooth curve. This result gives strong support to the concept of the splitting of d orbitals in octahedral fields.

In Fig. 18.12 the lattice energies of the dichlorides of the first-transition-series metals are plotted as a function of atomic number. The plot shows that the lattice energies of the salts other than CaCl<sub>2</sub>, MnCl<sub>2</sub>, and ZnCl<sub>2</sub> are exceptionally large, undoubtedly because of ligand-field stabilization energy. Similar plots are obtained for the lattice energies of other MX<sub>2</sub> salts and for MX<sub>3</sub> salts.

In the absence of ligand-field stabilization effects the ionic radii of the transition-metal ions would be expected to decrease steadily with increasing atomic number. However, from the festoons which appear in the plot of the radii of the +2 ions versus atomic number, shown in Fig. 18.13, it is clear that the stabilization energies correlate with the distances between atoms in ionic solids. The greater the ligand-field stabilization energy, the smaller the ionic radius, relative to the hypothetical spherically symmetric ion. Octahedral ions with high ligand-field stabilization energies have their d electrons mainly or entirely in the




Figure 18.12 Lattice energies of the dichlorides of the metals of the first transition series.

 $t_{2g}$  orbitals, directed between the ligands. Thus ligands can approach the ions closely, with minimal repulsion by the d electrons. On the other hand, if the d electrons are uniformly distributed among the  $t_{2g}$  and antibonding  $e_g$  orbitals, there is no ligand-field stabilization energy. Ligands are repelled by the  $e_g$  electrons, and therefore the effective ionic radius is greater.

In the case of an ion which can exist in either a low-spin or high-spin form, there are two corresponding ionic radii. The low-spin ion, which has fewer




Figure 18.13 Ionic radii of the +2 ions of the first transition series, as in high-spin compounds.

antibonding  $e_g$  electrons, has the smaller ionic radius. Various examples of low-spin and high-spin ionic radii can be found in Appendix F.

A ligand-field stabilization energy can be calculated for an ion of any geometry. The relative energies, in units of  $\Delta_a$ , for the various d orbitals in several coordination geometries are given in Table 18.5. From these data one can readily calculate that a 4-coordinate d<sup>8</sup> complex has a ligand-field stabilization energy of  $2.456\Delta_o$  in a square planar geometry, and  $0.356\Delta_o$  in a tetrahedral geometry. On this basis, one would expect all 4-coordinate complexes of a d8 ion such as Ni2+ to be square planar. Indeed, most 4-coordinate Ni(II) complexes are square planar, but a few are tetrahedral. The tetrahedral complexes are mainly of the following types: NiX<sub>4</sub><sup>2-</sup>, NiX<sub>3</sub>L<sup>-</sup>, NiX<sub>2</sub>L<sub>2</sub>, and Ni(AA)<sub>2</sub>, where X is a halogen or SPh, and L and AA are bulky monodentate and bidendate ligands, respectively. Obviously steric repulsions between ligands favor tetrahedral structures over square planar structures. Thus we can readily rationalize the formation of tetrahedral complexes with bulky ligands. In the case of halide ligands, the ligand-field strengths are so low that ligand-field stabilization energies are less important than steric repulsion energies. It is significant that Pd(II) and Pt(II) complexes, which have relatively large ligand-field splittings (and therefore relatively large ligand-field stabilization energies), are always square planar.

Ligand-field stabilization effects are clearly seen in the structures of various spinels. The spinel structure, named after the mineral  $MgAl_2O_4$ , is adopted by a large number of compounds of the type  $M^{II}M^{II}_2O_4$ . The structure consists of a close-packed lattice of oxide ions with one-third of the metal ions in tetrahedral holes and two-thirds of the metal ions in octahedral holes. In a "normal" spinel, the M(II) ions occupy tetrahedral holes and the M(III) ions occupy octahedral holes: thus  $[M^{II}]_{tet}[M^{III}_2]_{oct}O_4$ . In an "inverse" spinel, half of the M(III) ions exchange positions with the M(II) ions, thus:  $[M^{III}]_{tet}[M^{II}M^{III}]_{oct}O_4$ . The oxides

Table 18.5 The energy levels of d orbitals in various coordination geometries (in units of  $\Delta_o$ )

no.	Structure	$d_{z^2}$	$d_{x^2-y^2}$	$d_{xy}$	$d_{xz}$	$d_y$
	Linear†	1.028	0.620	NO.	-	0.1
	Trigonal‡		-0.628	-0.628	0.114	
	Tetrahedral	-0.321	0.546	0.546	-0.386	-0.3
		-0.267	-0.267	0.178	0.178	0.1
	Square planar‡	-0.428	1.228	0.228	-0.514	-0.5
	Trigonal bipyramid§	0.707	-0.082	-0.082	-0.272	-0.2
	Square pyramid§	0.086	0.914		-0.457	-0.4
	Octahedron	0.600		-0.086		-0.4
	Trigonal prism		0.600	-0.400	-0.400	700
	Pentagonal bipyramid	0.096	-0.584	-0.584	0.536	0.3
	i cittagonai bipyramid	0.493	0.282	0.282	-0.528	-0.5

<sup>†</sup> Ligands lie on z axis.

Ligands lie in xy plane.

<sup>§</sup> Pyramid base in xy plane.

Mn<sub>3</sub>O<sub>4</sub> and Co<sub>3</sub>O<sub>4</sub> are normal spinels, and Fe<sub>3</sub>O<sub>4</sub> and NiAl<sub>2</sub>O<sub>4</sub> are inverse spinels. These differences can be explained in terms of ligand-field stabilization energies. 15 Because  $\Delta_a > \Delta_t$ , octahedral site stabilization energies are usually much greater than tetrahedral site stabilization energies. In Mn<sub>3</sub>O<sub>4</sub>, the Mn<sup>3+</sup> ions, but not the Mn2+ ions, are ligand-field-stabilized, and therefore the Mn3+ ions occupy the sites which provide the maximum stabilization. In Co<sub>3</sub>O<sub>4</sub>, the Co<sup>3+</sup> ions occupy octahedral sites as low-spin d6 ions; if the structure were to invert, half of the Co3+ ions would be transferred to tetrahedral sites where they would probably become high-spin and lose a tremendous amount of ligand-field stabilization energy. In Fe<sub>3</sub>O<sub>4</sub>, the Fe<sup>2+</sup> ions, but not the Fe<sup>3+</sup> ions, are ligand-field-stabilized; hence the Fe2+ ions occupy octahedral sites. Similarly, in NiAl2O4, only the Ni2+ ions are ligand-field-stabilized, and therefore they occupy octahedral sites.

Spinels containing ions with magnetic moments have interesting magnetic properties. In the spinel structure, these ions are close enough to interact with one another, and one often observes ferromagnetism and antiferromagnetism. For example, in the black mineral magnetite, Fe<sub>3</sub>O<sub>4</sub>, all the ions in the octahedral holes have their magnetic spins aligned, and the Fe3+ ions in the tetrahedral holes have their spins aligned in the opposite direction, thus:

Hence the Fe3+ ions are antiferromagnetically coupled; their mutual interaction yields no magnetic moment. The net ferrimagnetism of the compound is entirely attributable to the Fe2+ ions. If the Fe2+ are replaced with diamagnetic ions, as in ZnFe<sub>2</sub>O<sub>4</sub>, the resulting spinel is normal and completely antiferromagnetic, with no net magnetic moment.

### STRUCTURAL EFFECTS OF LIGAND-METAL PI BONDING

### **π-Donor Bonding**

Most of the transition-metal dioxo complexes of the type MO<sub>2</sub>X<sub>4</sub> have d<sup>0</sup> or d<sup>2</sup> electron configurations. All the  $d^0$  complexes have the cis structure, and the  $d^2$ complexes have the trans structure. 16 These structures are logical consequences of the maximization of  $p\pi \to d\pi$  bonding between the strongly  $\pi$ -donating oxygen atoms and the metal atoms. In the  $d^0$  cases, the cis configuration is clearly preferred. If we assume the oxygen atoms are on the x and y axes, then they have exclusive use of one  $d\pi$  orbital each  $(d_{xz} \text{ for } O_x; d_{yz} \text{ for } O_y)$  and share a third  $(d_{xy})$ . In the trans form (oxygen atoms on the +x and -x axes) the oxygen atoms would have to share two  $d\pi$  orbitals  $(d_{xy}$  and  $d_{xz})$  and leave one unused  $(d_{yz})$ . This latter

<sup>15</sup> For a different explanation, see J. K. Burdett, G. D. Price, and S. L. Price, J. Am. Chem. Soc., 104, 92 (1982). <sup>16</sup> W. P. Griffith and T. D. Wickins, *J. Chem. Soc.* (A), 400 (1968).

orbital accommodates the electron pair in the  $d^2$  trans complexes. Examples of  $d^0$  cis complexes are  $MoO_2Cl_4{}^{2-}$  and  $VO_2F_4{}^{3-}$ . Examples of  $d^2$  trans complexes are  $OsO_2(CN)_4{}^{2-}$  and  $ReO_2py_4{}^+$ .

### π-Acceptor Bonding

After the discovery in 1890 that nickel carbonyl can be prepared by the reaction of nickel metal with carbon monoxide, <sup>17</sup> it was suspected that the Ni(CO)<sub>4</sub> molecule consists of a nickel atom tetrahedrally bonded to four carbon monoxide molecules, essentially as indicated in the following valence bond structure.

This structure seemed plausible because, in it, the nickel atom achieves the stable electron configuration of the rare gas krypton. Of course incidentally the nickel atom has acquired an extremely negative formal charge, a situation which we now recognize as electronically unstable. When, in 1935, Brockway and Cross 18 determined the structure by electron diffraction, they verified the tetrahesmall, only  $1.82 \pm 0.03$  Å. This is about 0.34 Å less than the sum of the Cross proposed that the Ni—C bonds have multiple-bond character, corresponding to significant contributions from resonance structures such as the following.

Thus they rationalized the short Ni—C bond and eliminated the extremely negative formal charge associated with the first structure. This proposal constituted the first clear-cut application of the concept of "back bonding," so called because it involves the shift of electron density from otherwise nonbonding  $\pi$  orbitals on the metal atom back to antibonding  $\pi^*$  orbitals on the ligands.

L. Mond, C. Langer, and F. Quincke, J. Chem. Soc., 57, 749 (1890).
 L. O. Brockway and P. C. Cross, J. Chem. Phys., 3, 828 (1935).

Back bonding is favored by an increase in electron density on the metal atom and therefore is most prominent in low-oxidation-state metal complexes. The tendency for a transition metal to back-bond also increases as one descends a periodic-table family, i.e., on going from the first row to the second row, and then to the third row. For example, although Fe<sup>2+</sup> and Ru<sup>3+</sup> show relatively weak back bonding, Ru<sup>2+</sup> is a strong back-bonder. Striking evidence for the strong back-bonding ability of Ru<sup>2+</sup> can be seen in the structural data for the *cis*-tetraam-minebis(isonicotinamide)ruthenium(II) and -(III) ions, <sup>19</sup>

$$\begin{array}{c}
O \\
N \\
- Ru(NH_3)_4^{2+,3+}
\end{array}$$

In the Ru(III) complex, the Ru—N(isn) bond distances (2.099 Å average) are only slightly less than the Ru—NH<sub>3</sub> bond distances (2.125 Å average). Presumably both the isonicotinamide and ammonia molecules are principally  $\sigma$  donors in this complex where back bonding is unimportant. On the other hand, in the Ru(II) complex, the Ru—N(isn) bond distances (2.060 Å average) are significantly shorter than the Ru—NH<sub>3</sub> bond distances (2.143 Å average). The difference is explained by assuming  $d\pi \to \pi^*$  interactions in the Ru<sup>II</sup>—N(isn) bonds. Isonicotinamide, like many other aromatic molecules, has empty  $\pi^*$  MOs which can accept metal  $d\pi$  electron density. The fact that the Ru<sup>II</sup>—N(isn) bond is shorter than the Ru<sup>III</sup>—N(isn) bond is particularly striking; ordinarily, when  $\pi$  bonding is not involved, metal-ligand distances decrease with increasing oxidation state, as in the case of the Ru—NH<sub>3</sub> bonds.

It has been noted that, in  $d^8$  trigonal bipyramidal complexes with ligands of different  $\pi$ -acceptor strength, the stronger  $\pi$  acceptors have a distinct preference for the equatorial sites, at least in the case of ligands with cylindrically symmetric acceptor orbitals, such as CO, CN-, and PR<sub>3</sub>. Thus in Mn(CO)<sub>4</sub>NO and Co(PPh<sub>2</sub>Me)<sub>2</sub>Cl<sub>2</sub>NO, the strongly  $\pi$ -accepting nitrosyl groups occupy equatorial positions, and in Fe(CO)<sub>4</sub>CN- and Fe(CO)<sub>4</sub>py, the relatively weakly  $\pi$ -accepting cyanide and pyridine ligands occupy axial positions.<sup>20</sup> This structural preference can be rationalized in terms of the relative number of  $d\pi$  orbitals available to ligands at the axial and equatorial sites.<sup>21</sup> The  $d_{x^2-y^2}$  and  $d_{xy}$  orbitals are available only to the three equatorial ligands, corresponding to  $\frac{2}{3}$  orbital per equatorial ligand. The  $d_{xz}$  and  $d_{yz}$  orbitals are available to all five ligands. If we apportion

<sup>&</sup>lt;sup>19</sup> D. E. Richardson, D. D. Walker, J. E. Sutton, K. O. Hodgson, and H. Taube, *Inorg. Chem.*, 18, 2216 (1979).

<sup>&</sup>lt;sup>20</sup> We assign relative  $\pi$ -acceptor abilities to ligands as consistently as possible with both theoretical expectations and experimental data. The structural data cited for trigonal bipyramidal complexes are merely a small part of a large body of data which are consistent with NO<sup>+</sup> being a better  $\pi$  acceptor than CN<sup>-</sup>. This result is of course expected. Differences in the properties of these isoelectronic species can be logically ascribed to the difference in their net charge. Because of the positive charge of NO<sup>+</sup>, one expects it to be a better  $\pi$  acceptor than CN<sup>-</sup>.

For a general MO study of the favored sites for  $\pi$  acceptors in  $d^0$ - $d^{10}$  trigonal bipyramidal complexes, see A. R. Rossi and R. Hoffmann, *Inorg. Chem.*, 14, 365 (1975).




Figure 18.14 Configuration of the anion of Zeise's salt.  $K[PtCl_3(C_2H_4)] \cdot H_2O$ .

these orbitals to the axial and equatorial ligands in proportion to the number of symmetry-allowed  $\pi$  bonds that can be formed, each axial ligand gets only  $\frac{4}{7}$  orbital whereas each equatorial ligand gets a total of  $(\frac{2}{3} + \frac{2}{7})$  or  $\frac{20}{21}$  orbital.

It is interesting to consider the configurations of metal-olefin complexes. The structure of the anion of Zeise's salt, K[PtCl<sub>3</sub>(C<sub>2</sub>H<sub>4</sub>)] · H<sub>2</sub>O, the first metalolefin complex prepared, is shown in Fig. 18.14.22 Several features of the structure are worthy of comment. (1) The C-C bond length, 1.375 Å, is significantly greater than that of free ethylene, 1.337 Å. This bond lengthening reflects the shift of electron density into the antibonding  $\pi^*$  orbital of the coordinated ethylene molecule. (2) The hydrogen atoms are bent back from the metal atom, as expected for an approach to sp<sup>3</sup> hybridization of the carbon atoms. (3) The trans chlorine atom is slightly farther from the metal atom than the cis chlorine atoms. This slight weakening of the trans Pt—Cl bond is probably a consequence of the relatively strong Pt $-C_2H_4\sigma$  bond. (The synergism of the  $d\pi \to \pi^*$  back bonding and the  $C_2H_4 \to Pt \sigma$  bond makes the latter bond much stronger than it would be otherwise.) The d,s,p hybridization of the metal orbital involved in  $\sigma$  bonding to the ethylene is such as to give good overlap with the  $\pi$  orbital of  $C_2H_4$ ; consequently the hybridization of the orbital involved in  $\sigma$  bonding to the trans chlorine is such as to give relatively poor overlap. (4) The C—C bond is perpendicular to the plane of the complex. This configuration is not easily rationalized in terms of ease of back bonding; it appears that back bonding from the  $d_{xy}$  orbital would be just as effective as back bonding from the  $d_{xz}$  orbital. Indeed, solution nmr studies indicate that the coordinated ethylene molecule undergoes rotation about the platinum-olefin axis, thus indicating that the configuration in which the olefin lies in the plane of the PtCl<sub>3</sub> group has a stability comparable to that in which the olefin is perpendicular to the plane,23 The structure observed for the salt is probably a consequence of the minimization of steric repulsions between the ethylene ligand and the cis chlorine atoms combined with subtle crystal packing forces.

We generally find stronger evidence for back bonding when the metal atom has a low oxidation state. Consider, the example, tris(ethylene)nickel(0), which is

<sup>&</sup>lt;sup>22</sup> R. A. Love, T. F. Koetzle, G. J. B. Williams, L. C. Andrews, and R. Bau, *Inorg. Chem.*, 14, 2653 (1975).

<sup>&</sup>lt;sup>23</sup> S. Maricic, C. R. Redpatch, and J. A. S. Smith, *J. Chem. Soc.*, 4905 (1963).




Figure 18.15 Two conceivable geometries for  $Ni(C_2H_4)_3$ . (a) The "planar" geometry; (b) the "upright" geometry.

believed to have the structure shown in Fig. 18.15a, in which the six carbon atoms and the nickel atom are coplanar. It is instructive to consider the reasons for the stability of this geometry as opposed to the "upright" structure of Fig. 18.15b, in which the C—C bonds are perpendicular to the coordination plane. Presumably the  $\sigma$  bonding is equally strong in each case, and therefore the difference in stability must be due to differences in the  $d\pi \to \pi^*$  back bonding. Let us first consider the effects of hypothetical  $\sigma$  interactions in the absence of  $\pi$  interactions. In both structures,  $\sigma$  interaction of the metal d orbitals with the bonding  $\pi$  orbitals of the C<sub>2</sub>H<sub>4</sub> molecules yields three sets of MOs:<sup>25</sup> an antibonding e' set consisting essentially of the destabilized  $d_{xy}$  and  $d_{x^2-y^2}$  orbitals, a nonbonding e' set consisting of the  $d_{xz}$  and  $d_{yz}$  orbitals, and a bonding e' set consisting essentially of stabilized  $\pi$  orbitals of the C<sub>2</sub>H<sub>4</sub> ligands. This set of MOs is shown for both structures in Fig. 18.16. If now we allow interactions with the empty  $\pi^*$  orbitals of the C<sub>2</sub>H<sub>4</sub>

<sup>24</sup> N. Rösch and R. Hoffman, *Inorg. Chem.*, 13, 2656 (1974); R. M. Pitzer and H. F. Schaefer, J. Am. Chem. Soc., 101, 7176 (1979).

The z axis is perpendicular to the coordination plane. We shall ignore the  $d_{z^2}$  orbital.




Figure 18.16 Schematic MO energy level diagrams of  $\pi$  bonding in Ni(C<sub>2</sub>H<sub>4</sub>)<sub>3</sub>. The left-hand diagram is for the planar structure; the right-hand diagram for the upright structure. The orbital interactions are introduced stepwise. First, interaction with the C<sub>2</sub>H<sub>4</sub>  $\pi$  levels is shown in the columns marked  $\sigma$ . Second, the effects of the C<sub>2</sub>H<sub>4</sub>  $\pi$ \* levels are shown, in the columns marked  $\sigma + \pi$ . [Reproduced with permission from N. Rösch and R. Hoffmann, Inorg. Chem., 13, 2656 (1974). Copyright 1974 American Chemical Society.]

Table 18.6 Comparison of ethylene and tetracyanoethylene complexes†

Compound	$r_{\rm C-C}$ (complex) $-r_{\rm C-C}$ (free olefin), Å
$Rh(C_2H_4)(C_2F_4)(C_5H_5)$	0.021
$K[PtCl_3(C_2H_4)] \cdot H_2O$	0.038
$Nb(C_2H_4)(C_2H_5)(C_5H_5)_2$	0.069
Ni(t-BuNC) <sub>2</sub> C <sub>2</sub> (CN) <sub>4</sub>	0.132
$Ir(CO)(Br)(PPh_3)_2C_2(CN)_4$	0.162
$Ir(CO)(C_6N_4H)(PPh_3)_2C_2(CN)_4$	0.182

<sup>†</sup> Data from R. A. Love, T. F. Koetzle, G. J. B. Williams, L. C. Andrews, and R. Bau, Inorg. Chem., 14, 2653 (1975).

molecules, we find that the two structures give different results. In the planar structure, the upper e' MO engages in back bonding and is strongly stabilized, and the e" MO, which has no interaction partner, stays at the same energy. In the upright structure, the otherwise nonbonding e" MO engages in weak back bonding and is slightly stabilized, and the upper e' MO stays at the same energy. The stabilization of the e'' MO in the upright structure is relatively slight because the e''MO is farther away in energy from the C<sub>2</sub>H<sub>4</sub> π\* than the e' MO which is destabilized by the  $\sigma$  interaction. In the complex, the MOs of Fig. 18.15 are occupied by 12 electrons (8 from the nickel atom and 4 from the ethylene ligands); consequently the energy of the planar structure should be less than that of the upright structure.

Olefins with electronegative or  $\pi$ -accepting substituents, such as tetracyanoethylene, function as much better  $\pi$  acceptors than ethylene. Table 18.6 gives the lengthening of the olefin C-C bond on going from the free olefin to the coordinated olefin for several complexes of ethylene and tetracyanoethylene. The lengthening is much greater for tetracyanoethylene, consistent with stronger back bonding in the tetracyanoethylene complexes.

## OTHER EFFECTS OF BACK BONDING

There is controversy regarding the question as to whether the trifluoromethyl group,  $CF_3$ , can act as a  $\pi$ -acceptor ligand when bonded to a transition metal. Vibrational frequencies for CF<sub>3</sub>I and CF<sub>3</sub>Mn(CO)<sub>5</sub> have yielded the C-F stretching force constants 5.9 and 4.6 mdyn/Å, respectively.26 The marked weakening of the C-F bond in CF<sub>3</sub>Mn(CO)<sub>5</sub> has been attributed to overlap of filled metal  $d\pi$  orbitals with C-F  $\sigma^*$  antibonding orbitals. A similar rationale has been used to explain the fact that the Fe—C distance in (CHF<sub>2</sub>CF<sub>2</sub>)<sub>2</sub>Fe(CO)<sub>4</sub>is about 0.05 Å shorter than in analogous unfluorinated compounds.<sup>27</sup> However,

<sup>27</sup> M. R. Churchill, *Inorg. Chem.*, 6, 185 (1967).

<sup>&</sup>lt;sup>26</sup> F. A. Cotton and R. M. Wing, J. Organomet. Chem., 9, 511 (1967).

theoretical calculations have failed to show any good evidence for such  $d\pi \to \sigma^*$ back bonding.<sup>28</sup> Perhaps the strengthening of the metal-carbon bond and weakening of the C-F bond on going from a metal alkyl to a metal fluoroalkyl is merely a consequence of rehybridization of the carbon orbitals. Because of the high electronegativity of fluorine, the carbon orbitals involved in C-F bonds should have more p character than those involved in C—H bonds. Hence the carbon orbital involved in the metal-CF3 bond should have more s character than that involved in the metal-CH3 bond. Because of the generally observed increase in bond strength with increase in orbital s character, 29 the changes that occur on going from a metal alkyl to a metal fluoroalkyl are thus rationalized.

Back bonding from a transition metal to a carbon monoxide ligand involves a shift of electron density from the metal atom to the antibonding  $\pi^*$  orbital of the CO. Thus one expects increased back bonding to be accompanied by decreased C-O bond strength and increased negative charge on the carbon and oxygen atoms. We can follow changes in C—O bond strength with the C—O stretching force constant, calculated from vibrational spectroscopic data. We can follow changes in the carbon and oxygen atomic charges with the corresponding coreelectron binding energies, obtained from x-ray photoelectron spectroscopy. Figure 18.17 shows a plot of carbon 1s binding energy versus C—O force constant for carbonyl compounds, covering a wide variety of transition metals and other ligands.30 An increase in force constant corresponds to an increase in bond strength, and an increase in core binding energy corresponds to a decrease in negative charge. The observed linear correlation between these physical quantities is strong support for the idea that these quantities are good measures of back bonding. Of the compounds represented in Fig. 18.17, the one with the lowest C-O force constant is  $\eta^7$ -C<sub>7</sub>H<sub>7</sub>V(CO)<sub>3</sub>. Vanadium is on the left side of the transition series, with a relatively low nuclear charge, and therefore does not hold its valence electrons as tightly as metals to its right in the periodic table. This fact, coupled with the facts that the  $C_7H_7$  group is not a strong  $\pi$  acceptor and that only three carbonyl groups are competing for  $d\pi$  electron density, rationalizes the strong metal-CO back bonding in this molecule. The compound with the highest C—O force constant is Mn(NO)<sub>3</sub>CO. The relatively weak metal-CO back bonding in this molecule is undoubtedly due to strong electron withdrawal by the three NO groups, which are exceedingly strong  $\pi$  acceptors.

Chemical reactivity can be affected by back bonding.<sup>31</sup> The pyrazinium ion,

, has a pK of 0.6. When the free nitrogen atom of this ion

<sup>&</sup>lt;sup>28</sup> M. B. Hall and R. F. Fenske, *Inorg. Chem.*, 11, 768 (1972).

<sup>&</sup>lt;sup>29</sup> See pp. 121-124. 30 S. C. Avanzino, A. A. Bakke, H.-W. Chen, C. J. Donahue, W. L. Jolly, T. H. Lee, and A. J. Ricco,

Inorg. Chem., 19, 1931 (1980). <sup>31</sup> P. Ford, D. F. P. Rudd, R. Gaunder, and H. Taube, J. Am. Chem. Soc., 90, 1197 (1968); H. Taube, Surv. Prog. Chem., 6, 1 (1973).




Figure 18.17 Plot of carbon 1s binding energy for gas-phase metal carbonyl compounds versus C-0 stretching force constant. [Reproduced with permission from S. C. Avanzino, A. A. Bakke, H.-W. Chen. C. J. Donahue, W. L. Jolly, T. H. Lee, and A. J. Ricco. Inorg. Chem., 19, 1931 (1980). Copyright 1980 American Chemical Society.]

is coordinated to the cationic species Ru(NH<sub>3</sub>)<sub>5</sub><sup>3+</sup>, the acidity of the coordinated pyrazinium ion increases, presumably because of the inductive effect of the metal cation.

$$\left[ (NH_3)_5 Ru - N \right]^{4+} pK \approx -0.8$$

For the same reason one might expect  $Ru(NH_3)_5^{2+}$  to increase the acidity of the pyrazinium ion, only not as much as  $Ru(NH_3)_5^{3+}$ . However, the acidity is actually decreased.

$$\left[ (NH_3)_5 Ru - N \right]^{3+} \qquad pK = 2.5$$

From this we conclude that back bonding from the Ru(II) to the pyrazine ring more than compensates for the inductive effect.

#### PROBLEMS

- \*18.1 The following compounds have effective magnetic moments of 5.85 to 5.95; Fe(NO<sub>3</sub>)<sub>3</sub> · 9H<sub>2</sub>O, FeCl<sub>3</sub> · 6H<sub>2</sub>O, K<sub>3</sub>Fe(C<sub>2</sub>O<sub>4</sub>)<sub>3</sub> · 3H<sub>2</sub>O, Fe(urea)<sub>6</sub>Cl<sub>3</sub> · 6H<sub>2</sub>O, Na<sub>3</sub>FeF<sub>6</sub>, [Fe(dipy)<sub>2</sub>Cl<sub>2</sub>][FeCl<sub>4</sub>], [Fe(phen)<sub>2</sub>Cl<sub>2</sub>][FeCl<sub>4</sub>], Fe(acac)<sub>3</sub>. The following have  $\mu_{\text{eff}}$  values of 2.3 to 2.4; [Fe(phen)<sub>2</sub>(CN)<sub>2</sub>]NO<sub>3</sub> · 4H<sub>2</sub>O, [Fe(dipy)<sub>2</sub>(CN)<sub>2</sub>]NO<sub>3</sub>, H<sub>3</sub>O[Fe(phen)(CN)<sub>4</sub>] · H<sub>2</sub>O, K<sub>3</sub>Fe(CN)<sub>6</sub>, Fe(dipy)<sub>3</sub>(ClO<sub>4</sub>)<sub>3</sub> · 3H<sub>2</sub>O, Fe(phen)<sub>3</sub>(ClO<sub>4</sub>)<sub>3</sub> · 3H<sub>2</sub>O. Using this and other information, estimate the ligand-field strength corresponding to crossover in Fe<sup>3+</sup> O<sub>6</sub> complexes.
- \*18.2 Which would you expect to have the greater magnetic moment, CoCl<sub>4</sub><sup>2-</sup> or CoI<sub>4</sub><sup>2-</sup>? Why?

  18.3 The complex Cr<sub>2</sub>(OAc)<sub>4</sub> · 2H<sub>2</sub>O (see structure, page 347) is diamagnetic. What can you say regarding the nature of the bonding in this compound?
- \*18.4 The following compounds have the indicated effective magnetic moments. Describe the structure and bonding of these compounds on the basis of the  $\mu_{\text{eff}}$  values.  $K_2 \text{NiF}_6$ , 0.0;  $\text{Ni}(\text{NH}_3)_2 \text{Cl}_2$ , 3.3;  $\text{Ni}(\text{PEt}_3)_2 \text{Cl}_2$ , 0.0;  $\text{Ni}(\text{Ph}_4 \text{AsO})_2 \text{Cl}_2$ , 3.95.
- 18.5 Ni( $C_5H_5$ )<sub>2</sub> has the same type of structure as that of ferrocene. Would you expect Ni( $C_5H_5$ )<sub>2</sub> to be paramagnetic or diamagnetic? Why?
- 18.6 Although a  $d^8$  tetrahedral complex is somewhat stabilized by flattening of the tetrahedron (show this by consideration of the energy level diagram), more stabilization is obtained by elongation of the tetrahedron. Similar, but opposite, statements apply to  $d^9$  complexes. Explain.
- \*18.7 Equilibrium constants for the stepwise formation of mono-, bis-, and tris(ethylenediamine) complexes of Co<sup>2+</sup>, Ni<sup>2+</sup>, and Cu<sup>2+</sup> in aqueous solution are as follows:

Ion	$\log K_1$	$\log K_2$	$\log K_3$
Co <sup>2+</sup>	5.89	4.83	3.10
Ni <sup>2+</sup>	7.52	6.28	4.26
Cu2+	10.55	9.05	-1.0

$$M(H_2O)_6^{2+} + en \implies M(H_2O)_4(en)^{2+} + 2H_2O \qquad K_1$$
  
 $M(H_2O)_4(en)^{2+} + en \implies M(H_2O)_2(en)_2^{2+} + 2H_2O \qquad K_2$   
 $M(H_2O)_2(en)_2^{2+} + en \implies M(en)_3^{2+} + 2H_2O \qquad K_3$ 

Explain the anomalously low value of  $K_3$  for  $Cu^{2+}$ .

- 18.8 Prepare a table in which you indicate, for each of the following complexes, the number of unpaired electrons, the estimated magnetic moment, whether or not one would expect an appreciable Jahn-Teller distortion, the number of d-d transitions, and whether or not one would expect ligand-field stabilization:  $Co(CO)_4^-$ ,  $Cr(CN)_6^{4-}$ ,  $Fe(H_2O)_6^{3+}$ ,  $VCI_4$ ,  $Co(NO_2)_6^{4-}$ ,  $Co(NH_3)_6^{3+}$ ,  $Ir(CO)Cl(PPh_3)_2$ ,  $CuCl_2^-$ ,  $MnO_4^{2-}$ ,  $Cu(H_2O)_6^{2+}$ .
- \*18.9 Suggest a reason for the fact that a number of tetrahedral Co(II) complexes are stable, whereas the corresponding Ni(II) complexes are not.
- 18.10 Using ligand-field stabilization energy as the criterion, indicate whether you would expect the following spinels to be normal or inverse: CuFe<sub>2</sub>O<sub>4</sub>, CuCr<sub>2</sub>O<sub>4</sub>, NiFe<sub>2</sub>O<sub>4</sub>, MnCr<sub>2</sub>O<sub>4</sub>.
- 18.11 Calculate the difference in ligand-field stabilization energy (in units of  $\Delta_o$ ) between octahedral and tetrahedral coordination for high-spin configurations from  $d^1$  to  $d^{10}$ . Assume that  $\Delta_t = \frac{4}{7}\Delta_o$ .
- \*18.12 Can you explain why it might be possible to observe the effects of Jahn-Teller distortion in the electronic spectrum of a crystal even though x-ray diffraction data conform to a symmetric structure?

  18.13 Explain the fact that the high-spin d<sup>6</sup> complex CoF<sub>6</sub><sup>3-</sup> shows two absorption bands in the visible spectral region

- 18.14 List three different experimental methods which could be used for measuring back bonding in a transition-metal carbonyl.
- 18.15 Without referring to any data, describe the structures of the following complexes:  $Fe(CO)_2(NO)_2$ ,  $Fe(CO)_4H_2$ ,  $Mn(CO)_4NO$ ,  $Fe(CO)_4CN^-$ ,  $Fe(CO)_4C_2H_4$ . For the latter complex, indicate precisely the orientation of the  $C_2H_4$  group.
- 18.16 Can you explain why the Néel temperature of MnS is higher than that of MnO? (Consider the factors influencing superexchange.) Similarly, can you explain the following trend in Néel temperature? MnO, 116 K; FeO, 198 K; CoO, 291 K; NiO, 525 K.
- \*18.17 Why would you not expect TiO or VO to be antiferromagnetic?
- 18.18 Using data from Tables 18.3 and 18.4 (and estimated  $\Delta$  values when necessary), calculate values of  $\mu$  for the first 11 compounds of Table 18.2. Show that the average deviation from the experimental values is much less than in the case of the  $[n(n+2)]^{1/2}$  values.

# KINETICS AND MECHANISMS OF REACTIONS OF TRANSITION-METAL COMPLEXES

In the remaining chapters of this book we will be concerned with the reactions of transition-metal compounds. In this chapter we discuss the kinetics and mechanisms of ligand substitution and redox reactions for Werner-type complexes (i.e., complexes like the classical octahedral and square planar complexes studied in the early part of this century by Werner). Reactions of organometallic and bioinorganic systems will be covered in the following chapters.

# SUBSTITUTION REACTIONS OF OCTAHEDRAL COMPLEXES<sup>1</sup>

## Lability

The rates of replacement of the ligands of hexacoordinate complexes by other ligands vary over an extremely wide range — from very high rates ( $k \approx 10^9 \, M^{-1} \, \text{s}^{-1}$  at room temperature) to very low rates ( $k \approx 10^{-9} \, M^{-1} \, \text{s}^{-1}$  at room temperature).<sup>2</sup> . The complex  $\text{Co(NH}_3)_6^{3+}$  is an example of a relatively inert, or slow-reacting, complex. Although the thermodynamic driving force of the following reaction is

A rate constant of  $10^9 M^{-1} \text{ s}^{-1}$  corresponds to a half-life of  $10^{-9}$  s with 1 M reagents, and  $k = 10^{-9}$ 

M<sup>-1</sup> s<sup>-1</sup> corresponds to a half-life of about 30 years under the same conditions.

<sup>&</sup>lt;sup>1</sup> F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., Wiley, New York, 1967; R. G. Wilkins, "The Study of Kinetics and Mechanism of Reactions of Transition Metal Complexes," Allyn and Bacon, Boston, 1974.

enormous,

$$Co(NH_3)_6^{3+} + H^+ + Cl^- \rightarrow Co(NH_3)_5Cl^{2+} + NH_4^+$$

the complex must be heated in 6 M hydrochloric acid for many hours to obtain any perceptible amount of the chloro complex. On the other hand,  $Cu(NH_3)_4(H_2O)_2^{2+}$  is a labile, or fast-reacting, complex. When a solution containing this blue species is added to concentrated hydrochloric acid, the solution turns green essentially as rapidly as the solutions are mixed.

$$Cu(NH_3)_4(H_2O)_2^{2+} + 4H^+ + 4Cl^- \rightarrow CuCl_4^{2-} + 4NH_4^+ + 2H_2O$$

A chemist who wishes to synthesize an octahedral complex must have some idea of the lability of the complex in order to choose appropriate experimental conditions for the synthesis. When a particular geometric or optical isomer is to be prepared, it is necessary that the rate of isomerization or racemization be slow enough to permit the isolation of a pure isomer. Obviously any generalizations or rules that can be used to predict the relative reactivities of complexes are important.

The size of the central atom affects the ease with which ligands can be replaced. The smaller the central atom (other factors being equal), the more tightly the ligands are held and the more inert the complex is. Thus, the rate constants for the exchange of solvent and coordinated water molecules in the aqueous ions  $Mg(H_2O)_6^{2+}$ ,  $Ca(H_2O)_6^{2+}$ , and  $Sr(H_2O)_6^{2+}$  are  $\sim 10^5$ ,  $\sim 2 \times 10^8$ , and  $\sim 4 \times 10^8$  s<sup>-1</sup>, respectively, at 25°C. The charge of the central atom is also important; the higher the charge, the more inert the complex. This effect can be seen in the water exchange rate constants for the following aqueous ions:

$$\begin{cases} \text{Na(H}_2\text{O})_6^+ \ (k \approx 8 \times 10^9 \text{ s}^{-1}; \ r_{\text{Na}^+} = 0.95 \text{ Å}) \\ \text{Ca(H}_2\text{O})_6^{2+} \ (k \approx 2 \times 10^8 \text{ s}^{-1}; \ r_{\text{Ca}^{2+}} = 0.99 \text{ Å}) \end{cases}$$

and

$$\begin{cases} Mg(H_2O)_6^{2+} (k \approx 10^5 \text{ s}^{-1}; r_{Mg^{2+}} = 0.65 \text{ Å}) \\ Ga(H_2O)_6^{3+} (k \approx 10^3 \text{ s}^{-1}; r_{Ga^{3+}} = 0.62 \text{ Å}) \end{cases}$$

The net effect of changes in both charge and size can be seen in the marked decrease in reactivity in the series of complexes AlF<sub>6</sub><sup>3-</sup>, SiF<sub>6</sub><sup>2-</sup>, PF<sub>6</sub><sup>-</sup>, and SF<sub>6</sub>. The addition of base to a solution of AlF<sub>6</sub><sup>3-</sup> causes the instant precipitation of Al(OH)<sub>3</sub>, whereas SF<sub>6</sub> undergoes no detectable reaction with hot concentrated base solutions over long periods of time.

The degree of lability or inertness of a transition-metal complex can be correlated with the d electron configuration of the metal ion. Let us consider a simple qualitative approach first used by Taube.<sup>3</sup> If a complex contains electrons in the antibonding  $e_g^*$  orbitals, the ligands are expected to be relatively weakly bound and to be easily displaced. If a complex contains an empty  $t_{2g}$  orbital, the four lobes of that orbital correspond to directions from which an incoming ligand

<sup>&</sup>lt;sup>3</sup> H. Taube, Chem. Rev., 50, 69 (1952). Land a sear Of audia le 310-lind a or abnogazano

Table 19.1 Kinetic classification of octahedral complexes

Electron	Faming Skouter
configuration	Complex
	Labile
dl	CaEDTA <sup>2-</sup> , Sc(H <sub>2</sub> O) <sub>5</sub> OH <sup>2+</sup> , TiCl <sub>6</sub> <sup>2-</sup> Ti(H <sub>2</sub> O) <sub>6</sub> <sup>3+</sup> , VO(H <sub>2</sub> O) <sub>5</sub> <sup>2+</sup> , MoCl <sub>5</sub> <sup>2-</sup>
d4 (high-spin)	V(phen) <sub>3</sub> <sup>3+</sup> , ReOCl <sub>5</sub> <sup>2-</sup> Cr(H <sub>2</sub> O) <sub>6</sub> <sup>2+</sup> Mn(H <sub>2</sub> O) <sub>6</sub> <sup>2+</sup> , Fe(H <sub>2</sub> O) <sub>4</sub> Cl <sub>2</sub> <sup>+</sup>
d <sup>6</sup> (high-spin)	Fe(H <sub>2</sub> O) <sub>6</sub> <sup>2+</sup> , Fe(H <sub>2</sub> O) <sub>4</sub> Cl <sub>2</sub> <sup>3</sup> Fo(NH <sub>3</sub> ) <sub>6</sub> <sup>2+</sup>
d8 d9	Ni(en) <sub>3</sub> <sup>2+</sup> Cu(NH <sub>3</sub> ) <sub>4</sub> (H <sub>2</sub> O) <sub>2</sub> <sup>2+</sup>
1	Ga(C <sub>2</sub> O <sub>4</sub> ) <sub>3</sub> <sup>3</sup> - Inert
d <sup>3</sup>	V(H <sub>2</sub> O) <sub>6</sub> <sup>2+</sup> , Cr(en) <sub>2</sub> Cl <sub>2</sub> <sup>+</sup>
d <sup>4</sup> (low-spin) d <sup>5</sup> (low-spin)	Cr(CN) <sub>6</sub> <sup>4-</sup> , Mn(CN) <sub>6</sub> <sup>3-</sup> Mn(CN) <sub>6</sub> <sup>4-</sup> , Fe(CN) <sub>6</sub> <sup>3-</sup>
d <sup>6</sup> (low-spin)	$Fe(CN)_6^{4-}$ , $Fe(CN)_6^{6-}$

(which is to displace one of the bound ligands) can approach the complex with relatively little electrostatic repulsion. Therefore one concludes that a complex with one or more  $e_g^*$  electrons or with fewer than three d electrons should be relatively labile, and that a complex with any other electron configuration should be relatively inert. In Table 19.1, examples of octahedral complexes with all possible electron configurations are listed and categorized as labile or inert, depending on whether ligand substitution takes place in less than or more than 1 min at room temperature with 0.1 M reactants. All the data are consistent with Taube's simple rule.

Electrostatic ligand-field theory can be used to predict the relative labilities of octahedral transition-metal complexes if the geometric configurations of the activated complexes of the substitution reactions are known or assumed. The change in ligand-field stabilization energy on going from the reactant complex to the activated complex corresponds to the ligand-field contribution to the activation energy of the reaction. If the reaction is assumed to proceed by a mechanism in which the rate-determining step involves considerable dissociation of the original complex, a 5-coordinate square pyramid activated complex is a reasonable assumption. The ligand-field contributions to the activation energy, based on that assumption, are given in Table 19.2 for complexes with various electron configurations. If the reaction is assumed to proceed by a mechanism in which the rate-determining step involves association of the incoming ligand with the original complex, a 7-coordinate pentagonal bipyramid activated complex is a

Table 19.2 Ligand-field stabilization energies and contributions to activation energies (in units of  $\Delta_o$ ) for dissociative mechanisms (octahedron  $\rightarrow$  square pyramid)†

Electron configuration	Octahedron	Square pyramid	Contribution to $E_a$
d <sup>0</sup> d <sup>1</sup> d <sup>2</sup> d <sup>3</sup> d <sup>4</sup> (high-spin) d <sup>4</sup> (low-spin) d <sup>5</sup> (high-spin) d <sup>6</sup> (low-spin) d <sup>6</sup> (low-spin) d <sup>6</sup> (low-spin) d <sup>7</sup> (low-spin)	0 0.400 0.800 1.200 0.600 1.600 0 2.000 0.400 2.400 0.800	0 0.457 0.914 1.000 0.914 1.457 0 1.914 0.457 2.000 0.914	0 -0.057 -0.114 0.200 -0.314 0.143 0 0.086 -0.057 0.400 -0.114
d' (low-spin) d <sup>8</sup> d <sup>9</sup>	1.800 1.200 0.600	1.914 1.000 0.914 0	-0.114

<sup>†</sup> F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., Wiley, New York, 1967.

Table 19.3 Ligand-field stabilization energies and contributions to activation energies (in units of  $\Delta_o$ ) for associative mechanisms (octahedron  $\rightarrow$  pentagonal bipyramid)†

Electron configuration	Octahedron	Pentagonal bipyramid	Contribution to $E_a$
d <sup>0</sup> d <sup>1</sup> d <sup>2</sup> d <sup>3</sup> d <sup>4</sup> (high-spin) d <sup>5</sup> (high-spin) d <sup>5</sup> (low-spin) d <sup>6</sup> (high-spin) d <sup>6</sup> (low-spin) d <sup>7</sup> (high-spin) d <sup>7</sup> (high-spin) d <sup>7</sup> (low-spin) d <sup>8</sup> d <sup>9</sup> d <sup>10</sup>	0 0.400 0.800 1.200 0.600 1.600 0 2.000 0.400 2.400 0.800 1.800 1.200 0.600 0	0 0.528 1.056 0.774 0.493 1.302 0 1.830 0.528 1.548 1.056 1.266 0.774 0.493	0 -0.128 -0.256 0.426 0.107 0.298 0 0.170 -0.128 0.852 -0.256 0.534 0.426 0.107

<sup>†</sup> F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., Wiley, New York, 1967.

Table 19.4 Log k for substitution reactions of aqueous +2 ions at  $25^{\circ}$ C†

(4,01)	**J-	Entering ligand			
Metal ion	H <sub>2</sub> O‡	NH <sub>3</sub> §	HF§	phen§	
V2+	2.0	CHIM	cakti (Sil	0.5	
Cr2+	8.5	obivitation (ali	e constants (K	~ 8.0	
Mn <sup>2+</sup>	7.5		6.3	~5.4	
Fe <sup>2+</sup>	6.5		6.0	5.9	
Co <sup>2+</sup>	6.0	5.1	5.7	5.3	
Ni <sup>2+</sup>	4.3	3.7	3.5	3.4	
Cu <sup>2+</sup>	8.5	out tell this b	7.5	7.9	
Zn <sup>2+</sup>	7.5 norm	onumer of activ	ranvawet	6.8	

† R. G. Wilkins, Acc. Chem. Res., 3, 408 (1970).

‡ Bulk water-coordinated water exchange rate constants (s-1).

§ Second-order rate constants  $(M^{-1} \text{ s}^{-1})$ .

reasonable assumption. The corresponding ligand-field contributions to the

activation energy are given in Table 19.3.

It is remarkable that, in spite of the different assumptions involved, the data in Tables 19.1 to 19.3 are to a large extent in qualitative agreement. Both sets of ligand-field data indicate that complexes with  $d^3$ ,  $d^8$ , and low-spin  $d^6$  configurations should be inert. The main disagreement between the ligand-field results and the qualitative predictions of Taube is in the case of  $d^8$  complexes, which are predicted to be labile by the Taube rule. However, examination of quantitative rate data shows that, in a sense, both predictions are correct. Consider the rate constant data<sup>4</sup> for +2 ions given in Table 19.4. Although the rate constants for Ni(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> are not as low as the corresponding constants for the  $d^3$  V(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> ion, they are definitely lower than those for all the other +2 ions listed.

#### Mechanisms

The data in Table 19.4 and a large number of similar kinetic data have the following general features:

1. For a given aqueous ion, the rate of replacement of a coordinated water molecule is not strongly affected by the nature of the entering ligand.

2. The water exchange reaction is always faster than substitution reactions involving other ligands.

These results suggest that the reactions proceed in two steps, the first of which is the formation of an aquo ion-ligand "outer-sphere" complex, and the second

<sup>&</sup>lt;sup>4</sup> R. G. Wilkins, Acc. Chem. Res., 3, 408 (1970).

of which is the exchange of an "inner-sphere" coordinated water molecule with the outer-sphere coordinated ligand.

$$M(H_2O)_6^{n+} + L \stackrel{K_1}{\rightleftharpoons} M(H_2O)_6 \cdot L^{n+}$$
 (19.1)

$$M(H_2O)_6 \cdot L^{n+} \xrightarrow{k_2} M(H_2O)_5 L^{n+} + H_2O$$
 (19.2)

When the overall rate constants  $(K_1k_2)$  are divided by estimated outer-sphere complex formation constants  $(K_1)$ , the resulting values of  $k_2$  are very close to the corresponding water exchange rate constants. This result shows that the formation of the activated complex in the second, rate-determining step consists mainly of the breaking of the  $M-OH_2$  bond and that the entering ligand influences  $k_2$ only very slightly. However, the volumes of activation,  $\Delta V_a$ , for solvent exchange reactions in methanol<sup>5</sup> have the following values in cubic centimeters per mole: -5.0 for Mn<sup>2+</sup>, +0.4 for Fe<sup>2+</sup>, +8.9 for Co<sup>2+</sup>, and +11.4 for Ni<sup>2+</sup>. Presumably a similar trend would be found in water. Because a negative volume of activation corresponds to an associative-type process (in which the rate is affected by the entering ligand) and a positive volume of activation corresponds to a dissociative-type process (in which the rate is unaffected by the entering ligand),6 the data suggest that reaction step 19.2 undergoes a changeover from associative to dissociative on going from left to right in the transition series. Further work is needed to clarify the mechanisms of these substitution reactions.

In some substitution reactions, the entering ligand is not at all involved in the dissociation step, and a 5-coordinate intermediate is formed. The reactions of the Co(CN)<sub>5</sub>H<sub>2</sub>O<sup>2-</sup> ion with various ligands are examples of such reactions:<sup>7</sup>

$$Co(CN)_5H_2O^{2-} \xrightarrow{k_1} Co(CN)_5^{2-} + H_2O$$

$$Co(CN)_5^{2-} + X^{-} \xrightarrow{k_3} Co(CN)_5X^{3-}$$
Kinetic data for  $X^- = Rr^-$  In SCN

Kinetic data for  $X^- = Br^-$ ,  $I^-$ , SCN<sup>-</sup>, and  $N_3^-$  give the same value,  $1.6 \times 10^{-3} s^{-1}$ . for  $k_1$ . In fact, essentially the same value has been obtained for the rate constant of the water exchange reaction.

The base hydrolyses of pentaamminecobalt(III) complexes have been extensively studied.

$$Co(NH_3)_5X^{2+} + OH^- \rightarrow Co(NH_3)_5OH^{2+} + X^-$$

The reactions are first order in the complex and first order in hydroxide ion, and one might reasonably suspect a mechanism involving an ion pair, analogous to reactions 19.1 and 19.2, or a simple bimolecular displacement in which the hydroxide ion enters the coordination sphere as the X-ion leaves. However, an extensive set of experimental data indicates that these base hydrolyses proceed by

F. K. Meyer, K. E. Newman, and A. E. Merbach, J. Am. Chem. Soc., 101, 5588 (1979). <sup>6</sup> G. A. Lawrance and D. R. Stranks, Acc. Chem. Res., 12, 403 (1979).

A. Haim and W. K. Wilmarth, *Inorg. Chem.*, 1, 573 (1962); A. Haim, R. J. Grassie, and W. K. Wilmarth, Adv. Chem. Ser., 49, 31 (1965).

the following mechanism:8,9

$$\begin{array}{cccc} \text{Co(NH}_3)_5 X^{2+} + \text{OH}^- & \stackrel{\text{fast}}{\Longleftrightarrow} & \text{Co(NH}_3)_4 (\text{NH}_2) X^+ + \text{H}_2 \text{O} \\ \\ \text{Co(NH}_3)_4 (\text{NH}_2) X^+ & \stackrel{\text{slow}}{\Longrightarrow} & \text{Co(NH}_3)_4 (\text{NH}_2)^{2+} + X^- \\ \\ \text{Co(NH}_3)_4 (\text{NH}_2)^{2+} + \text{H}_2 \text{O} & \stackrel{\text{fast}}{\Longrightarrow} & \text{Co(NH}_3)_5 \text{OH}^{2+} \end{array}$$

In this mechanism the rate-determining and dissociative step takes place after the removal of a proton from one of the coordinated ammonia molecules. A deprotonation of this type is not unreasonable in view of the finite acidities of metal ammine complexes.<sup>10</sup> [For example, pK = 8.4 for Pt(NH<sub>3</sub>)<sub>5</sub>Cl<sup>3+</sup>, and  $pK \approx 6.5$  for Au(en)<sub>2</sub><sup>3+</sup>.] Strong evidence for the mechanism is obtained from studies11 of the hydrolysis in the presence of various anions (Y-). These studies show that Co(NH<sub>3</sub>)<sub>5</sub>Y<sup>2+</sup> ions are formed in addition to Co(NH<sub>3</sub>)<sub>5</sub>OH<sup>2+</sup> ions. The product ratio Co(NH<sub>3</sub>)<sub>5</sub>Y<sup>2+</sup>/Co(NH<sub>3</sub>)<sub>5</sub>OH<sup>2+</sup>, shows little dependence on the leaving group X-, is independent of the OH- concentration, but depends on the Yconcentration and varies from one Y- to another. The results clearly indicate a common reactive intermediate in all the reactions.

The following arguments have been offered to rationalize the mechanism. The X<sup>-</sup> ion can dissociate from the deprotonated complex more easily than from the original complex because of the lower positive charge of the deprotonated complex. Loss of X- is probably somewhat aided by the deprotonation because the NH<sub>2</sub>- ligand can donate some of its π lone-pair electron density to the electron-deficient cobalt atom of the 5-coordinate intermediate.

## SUBSTITUTION REACTIONS OF SQUARE PLANAR COMPLEXES<sup>12</sup>

It is believed that substitution reactions of square planar complexes almost always proceed by an associative mechanism involving an intermediate which contains both the leaving ligand and the entering ligand. It is assumed that the entering ligand approaches the complex from one side of the plane, over the ligand to be displaced. The leaving ligand presumably moves down as the entering ligand approaches, so that the intermediate has a trigonal bipyramidal configuration.

<sup>8</sup> Basolo and Pearson, op. cit.; Wilkins, op. cit. 9 M. L. Tobe, Acc. Chem. Res., 3, 377 (1970).

<sup>10</sup> Basolo and Pearson, op. cit., p. 33. D. A. Buckingham, I. I. Olsen, and A. M. Sargeson, J. Am. Chem. Soc., 88, 5443 (1966).

<sup>12</sup> Basolo and Pearson, op. cit.; Wilkins, op. cit.

A 5-coordinate intermediate, or at least a 5-coordinate activated complex, is quite reasonable in view of the fact that there are many stable 5-coordinate  $d^8$  complexes.

For reactions of Pt(II) complexes in aqueous solution, the rate law often has

the form

$$Rate = k_1[complex] + k_2[complex][Y^-]$$
 (19.3)

where Y<sup>-</sup> is the entering ligand. The second term corresponds to the bimolecular displacement of the leaving ligand by the entering Y<sup>-</sup> ligand, and the first term corresponds to a two-step path in which first the leaving ligand is displaced by a water molecule in a rate-determining step and then the coordinated water molecule is relatively rapidly displaced by Y<sup>-</sup>. Kinetic data on a wide variety of Pt(II) complexes show that the rate of a ligand substitution reaction depends on the natures of the entering ligand, the leaving ligand, and the ligand trans to the leaving ligand. The relation between the reaction rate and the ligand trans to the leaving ligand is called the "trans effect," and we shall discuss this effect before considering the effects of the entering and leaving ligands.

#### The Kinetic Trans Effect

Ligands can be put in order according to their abilities to labilize (make susceptible to substitution) trans leaving groups. In the following list, the ligands are given in the order of increasing trans effect (i.e., increasing trans labilizing ability):  $H_2O < OH^- < F^- \approx RNH_2 \approx py \approx NH_3 < Cl^- < Br^- < SCN^- \approx I^- \approx NO_2^- \approx C_6H_5^- < SC(NH_2)_2 \approx CH_3^- < NO \approx H^- \approx PR_3 < C_2H_4 \approx CN^- \approx CO.$ 

The effect is illustrated by the reaction of the PtCl<sub>4</sub><sup>2-</sup> ion with two molecules of ammonia. After one chloride ion has been displaced, there are two kinds of chloride ions remaining in the complex: the chloride ion which is trans to an ammonia molecule and the chloride ions which are trans to each other. Because chloride is more trans-directing than ammonia, the chloride ions which are trans to each other are more labile than the chloride ion trans to the ammonia molecule. Hence the second molecule of ammonia displaces one of the more labile chloride ions and yields *cis*-Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub>.

Trans-Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub> can be prepared by the reaction of the Pt(NH<sub>3</sub>)<sub>4</sub><sup>2+</sup> ion with two chloride ions. The first step yields Pt(NH<sub>3</sub>)<sub>3</sub>Cl<sup>+</sup>, which contains two ammonia molecules trans to each other and an ammonia molecule trans to the chloride ion. The latter ammonia molecule is labilized by the chloride ion and is displaced next:

The trans effect can be used as the basis for the synthesis of many other isomeric Pt(II) complexes. For example, *cis*- and *trans*-PtNH<sub>3</sub>NO<sub>2</sub>Cl<sub>2</sub><sup>-</sup> are prepared from PtCl<sub>4</sub><sup>2-</sup> by the following routes.

Notice that a different isomer is obtained by simply reversing the order of

introduction of the groups.

We shall now show that it is possible to rationalize the trans effect on the basis of a trigonal bipyramidal intermediate. In this intermediate, the leaving ligand, the entering ligand, and the trans ligand occupy the three equatorial positions of the trigonal bipyramid. We have already pointed out in Chap. 18 that, in a trigonal bipyramidal  $d^8$  complex, there is a greater interaction of the filled  $d\pi$  orbitals with the equatorial ligands than with the axial ligands. Therefore  $d\pi \rightarrow \pi^*$  back bonding and  $d\pi$ - $p\pi$  nonbonding repulsions affect the bonding of the equatorial ligands more than that of the axial ligands. It also appears that the equatorial  $\sigma$  atomic orbitals of the metal are somewhat more electronegative than the axial  $\sigma$  atomic orbitals, perhaps because of greater s character in the equatorial orbitals. Consequently strongly basic ligands with relatively electropositive donor atoms tend to favor the equatorial sites over the axial sites (other factors being equal).

In the following reactions,

the geometry of the principal product is determined by the relative trans-directing abilities of A and B. The faster reaction corresponds to the more stable trigonal bipyramidal intermediate. Obviously the more strongly trans-directing

ligand is the one which gives the more stable intermediate when it is in an equatorial, rather than an axial, position. Hence strong trans-directing ligands are those which engage in strong back bonding (CN<sup>-</sup>, CO, olefins, etc.) or are very strong  $\sigma$  donors (CH<sub>3</sub><sup>-</sup>, H<sup>-</sup>, PR<sub>3</sub>, etc.). Ligands which are strong  $\pi$  donors (H<sub>2</sub>O, OH<sup>-</sup>, NH<sub>2</sub><sup>-</sup>, etc.) are weakly trans-directing.

# Effect of Entering and Leaving Ligands13

One of the fascinating problems associated with nucleophilic displacement reactions is that of predicting reactivity in terms of the properties of the entering and leaving ligands. Consider a series of reactions of the type

$$trans$$
-PtL<sub>2</sub>Cl<sub>2</sub> + Y<sup>-</sup>  $\rightarrow trans$ -PtL<sub>2</sub>ClY + Cl<sup>-</sup>

in which the ligand L is kept constant but the ligand Y is varied. On the basis of the general rate law for Pt(II) substitution reactions (Eq. 19.3), we may take the bimolecular rate constant  $k_2$  as a measure of the nucleophilicity of the entering ligand Y. It has been found that the nucleophilicity order of the Y ligands is remarkably constant on going from one Pt(II) complex to another, i.e., on changing L. In most cases, the reaction rate increases in the following order of entering ligands: ROH < OR $^-$  < Cl $^ \approx$  py  $\approx$  NO $_2^-$  < N $_3^-$  < Br $^-$  < I $^-$  < SCN $^-$  < SO $_3^{2-}$  < CN $^-$  < C $_6^{4}$ +S $^-$  < PR $_3$ . In fact the  $k_2$  values of a wide variety of Pt(II) substitution reactions may be correlated using the following linear free-energy relation.

$$\log k_2 = s\eta_{\rm Pt}^{\circ} + {\rm constant}$$

The parameter s depends on the complex and is called the "nucleophilic discrimination factor"; the parameter  $\eta_{\text{Pt}}^{\circ}$  depends on the entering ligand and is called the "nucleophilic reactivity constant." A large value of s means that  $\log k_2$  is very sensitive to changes in the nucleophilic character of Y, and a small value of s means that  $\log k_2$  is relatively insensitive to changes in Y. The effects of changes in Y on the activation energy of the reaction can be understood by reference to Fig. 19.1. If the entering ligand forms a stronger bond to the platinum atom than the leaving ligand (as shown in Fig. 19.1a), then changes in the entering ligand cause relatively small changes in activation energy (i.e., s is small). On the other hand, if the entering ligand forms a weaker bond to the platinum atom than the leaving atom (as shown in Fig. 19.1b), then changes in the entering ligand cause relatively large changes in activation energy (i.e., s is large). Incidentally, the fact that the reaction of Fig. 19.1b is endothermic (uphill energetically) should be  $n^0$ cause for alarm. Reactions for which  $\Delta H^{\circ} > 0$  and  $\Delta G^{\circ} > 0$  can proceed spontaneously if the reaction quotient (the product of the concentrations of the product species divided by the product of the concentrations of the reactant species, each concentration being raised to a power equal to the coefficient of that

<sup>&</sup>lt;sup>13</sup> F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., Wiley, New York, 1967.




Figure 19.1 Plots of energy versus reaction coordinate for displacement reactions of Pt(II) complexes, showing the effect on the activation energy of changing the bonding energy of the entering ligand, Y. In example (a), the entering ligand is more strongly bound than the leaving ligand and the energy of the activated complex is only slightly affected by the nature of Y. In example (b), the leaving ligand is more strongly bound than the entering ligand and the energy of the activated complex is strongly affected by the nature of Y.

species in the net reaction) is small enough to make  $\Delta G$  less than zero. In other words, mass action can overcome an unfavorable equilibrium constant.

The effect of the leaving ligand on the rate of a displacement from Pt(II) can be seen by reference to Fig. 19.2. If the entering ligand forms a stronger bond than the leaving ligand (as shown in Fig. 19.2a), changes in the leaving ligand




Figure 19.2 Plots of energy versus reaction coordinate for displacement reactions of Pt(II) complexes, showing the effect on the activation energy of changing the bonding energy of the leaving ligand, X. showing the entering ligand is more strongly bound than the leaving ligand and the energy of In example (a), the entering ligand is more strongly bound than the leaving ligand are activated complex is strongly affected by the nature of X. In example (b), the leaving ligand is more strongly bound than the entering ligand and the energy of the activated complex is only slightly affected by the nature of X.

cause relatively small changes in activation energy; the rate is essentially independent of the nature of the leaving ligand. On the other hand, if the leaving ligand forms a stronger bond than the entering ligand (as shown in Fig. 19.2b), changes in the leaving ligand cause relatively large changes in activation energy; the rate is a sensitive function of the nature of the leaving ligand. Both situations are found in reactions of thiourea with complexes of the type Pt(dien)X+:

$$Pt(dien)X^+ + tu \rightarrow Pt(dien)tu^{2+} + X^-$$

The rate is essentially the same for the relatively weakly bound leaving ligands Cl-, Br, and I but shows a definite trend with the more strongly bound leaving ligands:Cl<sup>-</sup>  $\approx$  Br<sup>-</sup>  $\approx$  I<sup>-</sup>  $\gg$  N<sub>3</sub><sup>-</sup>  $\approx$  NO<sub>2</sub><sup>-</sup> > SCN<sup>-</sup> > CN<sup>-</sup>.

Pyridine is a relatively weakly bound ligand, and in reactions of the type

$$Pt(dien)X^+ + py \rightarrow Pt(dien)py^{2+} + X^-$$

the reaction rate shows a marked trend even among weakly bound leaving groups:

 $NO_3^- > H_2O > Cl^- > Br^- > I^- > N_3^- > SCN^- > NO_2^- > CN^-$ .

The entering- and leaving-ligand series have a close similarity to the trans-effect series, but distinct differences can be seen. Some of these differences are probably due to the fact that the entering- and leaving-group series are affected by differences in the solvation of ligands, whereas the trans-effect series is independent of such solvation effects.

# OXIDATION-REDUCTION REACTIONS14-16 | brazil galvas) and mail

## Outer-Sphere Electron Transfer<sup>17</sup>

Many complexes undergo oxidation-reduction reactions more rapidly than they undergo substitution reactions. When two such complexes engage in a redox reaction, it is clear that electron transfer must occur through the intact coordination shells of the metal ions. These reactions are called "outer-sphere" electrontransfer reactions. The following is an example of such a reaction.

$$\operatorname{Fe}(\operatorname{CN})_{6}^{4-} + \operatorname{IrCl}_{6}^{2-} \rightarrow \operatorname{Fe}(\operatorname{CN})_{6}^{3-} + \operatorname{IrCl}_{6}^{3-}$$

Even when one of the complexes is labile, the reaction will generally proceed by an outer-sphere mechanism if the inert complex does not possess a donor atom which can be used to form a bridge to the labile complex. For example, this is the situation in the reduction of Co(NH<sub>3</sub>)<sub>6</sub><sup>3+</sup> by Cr(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>.

<sup>15</sup> H. Taube, "Electron Transfer Reactions of Complex Ions in Solution," Academic, New York,

<sup>16</sup> A. G. Sykes, "Kinetics of Inorganic Reactions," Pergamon, Oxford, 1966.

<sup>&</sup>lt;sup>17</sup> See T. J. Meyer, Acc. Chem. Res., 11, 94 (1978).

The simplest type of outer-sphere redox reactions are those in which no net reaction occurs, i.e., electron-exchange reactions such as the following.

$$Fe(H_2O)_6^{2+} + Fe(H_2O)_6^{3+} \rightarrow Fe(H_2O)_6^{3+} + Fe(H_2O)_6^{2+}$$

The rates of such reactions can be followed by the use of isotopic tracers. An energy-versus-reaction coordinate diagram for symmetric outer-sphere electron exchange is shown in Fig. 19.3. The curve represents the energy of the system along a particular configurational coordinate. In this case the coordinate could well be, for example, the average metal-ligand distance for the complex on the right minus the average metal-ligand distance for the complex on the left, while maintaining a constant metal-metal distance. There are two possible ground states for the system, in either of which the reduced complex has a greater metal-ligand distance than the oxidized complex. That is, the electron in question can be on the left complex (corresponding to the left minimum in the diagram) or on the right complex (corresponding to the right minimum). Orbital overlap between the two sites leads to the level splitting at the midpoint of the diagram, where the two complexes have the same size. In principle, electron transfer from left to right could suddenly occur by absorption of a photon with the energy indicated by  $E_1$  in Fig. 19.3. The immediately formed product species would be highly excited, inasmuch as the oxidized species would have a large metal-ligand distance and the reduced species would have a small metal-ligand distance. As we shall soon see, optical transitions of this type have been observed in mixed-valence systems, in which the two metal atoms are permanently linked together by a bridging ligand. In ion-pair systems such as we are now discussing, electron exchange proceeds by thermal activation. By absorption of a relatively small amount of thermal energy, the system can be brought to the midpoint of the diagram. This involves shortening the metal-ligand distance of the larger complex and lengthening the metal-ligand distance of the smaller complex to make the system structurally symmetric. At this point, the electron is delocalized, and transfer can occur in either direction.

The barrier height, indicated by  $E_2$  in the figure, corresponds to the structural reorganizational contribution to the activation energy of the electron exchange. Thus the more the two complexes differ initially in size, the higher will be the




Figure 19.3 Potential energy of a symmetric electron-exchange system along a particular configurational coordinate of the entire sys-

Table 19.5 Rate constants of electron-exchange reactions†

Reaction Reaction	$k \text{ at } 25^{\circ}\text{C}, M^{-1}\text{s}^{-1}$
$Cr(H_2O)_6^{2+} + Cr(H_2O)_6^{3+}$	down ≥2 × 10 <sup>-5</sup> > modes on density either of
$Co(NH_3)_6^{2+} + Co(NH_3)_6^{3+}$	2 cm <10 <sup>-9</sup> cm brood motoga-currov-yers
$Co(en)_3^{2+} + Co(en)_3^{3+}$	1.4 × 10 <sup>-4</sup> up and ni mwana si agamba
CoEDTA <sup>2-</sup> + CoEDTA <sup>-</sup>	1.4 × 10 <sup>-4</sup>
$Co(H_2O)_6^{2+} + Co(H_2O)_6^{3+}$	$\sim$ )
$Co(o\text{-phen})_3^{2+} + Co(o\text{-phen})_3^{3+}$	usud-igipin campanada, eleganos relacibilita
$V(H_2O)_6^{2+} + V(H_2O)_6^{3+}$	$1.0  imes 10^{-2}$
$Fe(H_2O)_6^{2+} + Fe(H_2O)_6^{3+}$	sintaining a constant metal-metal pratect
$Fe(CN)_6^{4-} + Fe(CN)_6^{3-}$	it don'740 to reduct of courses will not sell
$Fe(o-phen)_3^{2+} + Fe(o-phen)_3^{3+}$	etal-ligand distance than the ext 201<1 com
$Ru(NH_3)_6^{2+} + Ru(NH_3)_6^{3+}$	$8 imes 10^2$ , and $90^\circ$ mass $10^\circ$ mass $10^\circ$
$Os(bipy)_3^{2+} + Os(bipy)_3^{3+}$	E V 104
$IrCl_6^{3-} + IrCl_6^{2-}$	etap between the two stress to see the less than the less to the less than the less th

† F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., Wiley, New York, 1967; R. G. Wilkins, "The Study of Kinetics and Mechanism of Reactions of Transition Metal Complexes," Allyn and Bacon, Boston, 1974; H. Taube, "Electron Transfer Reactions of Complex Ions in Solution," Academic. New York, 1970; J. Halpern, *Quart. Rev.*, **15**, 207 (1961).

activation energy and the slower will be the electron exchange. Relatively large changes in size can accompany the removal or addition of an  $e_g^*$  electron, and electron exchange reactions which involve changes in the number of  $e_g^*$  electrons are generally slower than those involving only changes in the number of  $t_{2g}$  electrons. This electronic effect can be seen in the rate-constant data of Table 19.5. The  $Cr(H_2O)_6^{2+}-Cr(H_2O)_6^{3+}$  exchange and several of the Co(II)-Co(III) exchange reactions are very slow, whereas all the other exchange reactions are relatively fast. However, the Co(II)-Co(III) exchange reactions require special comment.

The simple transfer of one electron from Co(II) to Co(III) leads to an excited state of each product ion and involves an asymmetric activated complex:

$$Co^{II}(t_{2g}{}^{5}e_{g}{}^{*2}) + Co^{III}(t_{2g}{}^{6}) \rightarrow Co^{III}(t_{2g}{}^{5}e_{g}{}^{*1}) + Co^{II}(t_{2g}{}^{6}e_{g}{}^{*1})$$

Inasmuch as the symmetry of the reaction requires the steps leading to and from the activated complex to be symmetric, this process is unacceptable. It is believed that the reaction actually involves an excited state of one reactant. If the Co(III) is excited to the  $t_{2g}^4 e_g^{*2}$  configuration, the following symmetric reaction can occur.

$$Co^{II}(t_{2g}{}^{5}e_{g}{}^{*2}) + Co^{III}(t_{2g}{}^{4}e_{g}{}^{*2}) \rightarrow Co^{III}(t_{2g}{}^{4}e_{g}{}^{*2}) + Co^{II}(t_{2g}{}^{5}e_{g}{}^{*2})$$

If the Co(II) is excited to the  $t_{2g}^{6}e_{g}^{*1}$  configuration, the exchange is also symmetric.

$$Co^{II}(t_{2g}^{6}e_{g}^{*1}) + Co^{III}(t_{2g}^{6}) \rightarrow Co^{III}(t_{2g}^{6}) + Co^{II}(t_{2g}^{6}e_{g}^{*1})$$

In either case, the excitation energy contributes to the activation energy, and therefore most Co(II)-Co(III) exchange reactions are slow. However, in the case of Co(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, the ligand-field strength is low and excitation to the high-spin state is fairly easy. Hence the  $Co(H_2O)_6^{2+}$  -  $Co(H_2O)_6^{3+}$  exchange is rapid. In the case of Co(o-phen)<sub>3</sub><sup>2+</sup>, the ligand-field strength is very high and excitation to the low-spin state is easy. Hence the Co(o-phen)<sub>3</sub><sup>2+</sup>-Co(o-phen)<sub>3</sub><sup>3+</sup> exchange is also

Part of the enhanced rate of the Co(o-phen)<sub>3</sub><sup>2+</sup>-Co(o-phen)<sub>3</sub><sup>3+</sup> exchange may be due to another effect, which also causes the Fe(o-phen)<sub>3</sub><sup>2+</sup>-Fe(o-phen)<sub>3</sub><sup>3+</sup> exchange to be faster than other Fe(II)-Fe(III) exchanges. The latter enhancement is probably due to the facts that (1) o-phenanthroline is an aromatic system which can be reduced relatively easily to a radical anion and (2) electron delocalization in the o-phen complexes allows the transferring electron to penetrate the coordination shells easily.

Spontaneous outer-sphere redox reactions in which there is a net chemical change are usually faster than the corresponding electron-exchange reactions. Some data are given in Table 19.6. Usually the greater the thermodynamic driving force for a redox reaction, the greater the rate. A rough estimate of the rate constant  $k_{12}$  can be obtained from the following relation, <sup>18</sup>

$$k_{12} \approx (k_{11}k_{22}K_{12})^{1/2}$$

Table 19.6 A comparison of redox and electronexchange rate constants at 25°C†

Reaction	$k, M^{-1}s^{-1}$
Fe(CN) <sub>6</sub> <sup>4-</sup> + IrCl <sub>6</sub> <sup>2-</sup> Fe(CN) <sub>6</sub> <sup>4-</sup> + Fe(CN) <sub>6</sub> <sup>3-</sup> IrCl <sub>6</sub> <sup>3-</sup> + IrCl <sub>6</sub> <sup>2-</sup>	$ 3.8 \times 10^{5} \\ 7.4 \times 10^{2} \\ 10^{3} $
$Cr(H_2O)_6^{2+} + Fe(H_2O)_6^{3+}$ $Cr(H_2O)_6^{2+} + Cr(H_2O)_6^{3+}$ $Fe(H_2O)_6^{2+} + Fe(H_2O)_6^{3+}$	$\begin{array}{c} \sim 2 \times 10^3 \\ \approx 2 \times 10^{-3} \\ 4 \end{array}$
$\begin{aligned} &\text{Fe}(o\text{-phen})_3^{2+} + \text{Co}(\text{H}_2\text{O})_6^{3+} \\ &\text{Fe}(o\text{-phen})_3^{2+} + \text{Fe}(o\text{-phen})_3^{3+} \\ &\text{Co}(\text{H}_2\text{O})_6^{2+} + \text{Co}(\text{H}_2\text{O})_6^{3+} \end{aligned}$	$1.4 \times 10^4$ $10^5$ $\sim 5$
$Fe(H_2O)_6^{2+} + Co(H_2O)_6^{3+}$ $Fe(H_2O)_6^{2+} + Fe(H_2O)_6^{3+}$ $Co(H_2O)_6^{2+} + Co(H_2O)_6^{3+}$	10‡ 0.9‡ ~ 1‡

<sup>†</sup> F. Basolo and R. G. Pearson, "Mechanisms of Inorganic Reactions," 2d ed., Wiley, New York, 1967; R. G. Wilkins, "The Study of Kings." Kinetics and Mechanism of Reactions of Transition Metal Complexes," Allyn and Bacon, Boston, 1974; A. G. Sykes, "Kinetics of Inorganic Reactions," Pergamon, New York, 1966.

‡ At 0°C.

<sup>18</sup> R. A. Marcus, Ann. Rev. Phys. Chem., 15, 155 (1964). "H. Tunks, H. Stierts, and R. L. Rich, J. Pro. Conv. Sinc. 75, 4118 (1983); 14, Louise and H.

where  $k_{11}$  and  $k_{22}$  are the rate constants of the electron-exchange reactions and  $K_{12}$  is the equilibrium constant.

## Inner-Sphere Redox Reactions19

In an "inner-sphere" redox reaction, the two metal ions are connected in the activated complex through a bridging ligand common to both coordination shells. The first definitive proof of such a mechanism was obtained by Taube and his coworkers, 20 who showed that aqueous chromium(II) is oxidized by a pentaamminecobalt(III) complex, Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup>, to give the species Cr(H<sub>2</sub>O)<sub>5</sub>X<sup>2+</sup>. The result proves that, in the redox reaction, the X<sup>-</sup> ion is transferred directly from Co(III) to Cr(II) and that in the activated complex the two metal atoms are bridged by the X<sup>-</sup> ion, as shown in the following structure:

## (NH<sub>3</sub>)<sub>5</sub>CoXCr(H<sub>2</sub>O)<sub>5</sub><sup>4+</sup>

This particular reaction system was chosen because the Co(III) complex retains its integrity in solution for long periods of time, both Cr(II) and Co(II) complexes are labile, and Cr(III) complexes are inert. Each of these chemical characteristics was essential to the success of the experiment.

It can be shown that the transfer of X- from Co(III) to Cr(II) favors the

<sup>19</sup> H. Taube, "Electron Transfer Reactions of Complex Ions in Solution," Academic, New York, 1970.

<sup>20</sup> H. Taube, H. Myers, and R. L. Rich, *J. Am. Chem. Soc.*, **75**, 4118 (1953); H. Taube and H. Myers, *J. Am. Chem. Soc.*, **76**, 2103 (1954).




Figure 19.4 Changes in the d orbitals of Co and Cr as X- moves from Co to Cr. Electron transfer occurs at stage B.

transfer of the electron from Cr(II) to Co(III). The d electron structures of the two metals are shown in Fig. 19.4, stage A before electron transfer, stage B in the activated complex, and stage C immediately after electron transfer. In stage A, before X<sup>-</sup> has shifted toward the chromium atom, the electron in the  $d\sigma$  orbital has an energy below that of the  $d\sigma$  orbitals of the cobalt atom. When X<sup>-</sup> moves toward the chromium atom, the cobalt  $d\sigma$ -orbital energy levels split as their center of gravity is lowered and the chromium  $d\sigma$ -orbital energy levels move together as their center of gravity is raised. Electron transfer occurs when the energy of the lower cobalt  $d\sigma$  orbital is approximately the same as that of the lower chromium  $d\sigma$  orbital. Further shift of X- traps the electron on the cobalt atom and completes the transfer of X<sup>-</sup> to the chromium atom.

## Electron Transfer Through Extended Bridges

The reduction of  $Co(NH_3)_5 py^{3+}$  by  $Cr(H_2O)_6^{2+}$   $(k = 4.0 \times 10^{-3} M^{-1} s^{-1})$  yields Cr(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup> as the only Cr-containing product. The reaction undoubtedly proceeds by an outer-sphere mechanism. On the other hand, the complex

$$\left[ (NH_3)_5 Co - N - CONH_2 \right]^{3+}$$

reacts with  $Cr(H_2O)_6^{2+}$  much more rapidly  $(k = 17.4 M^{-1} s^{-1})$  to give the following Cr(III) complex.

$$\begin{bmatrix} HN \\ \\ NH_2 \end{bmatrix}^{4+}$$

Separate experiments have verified that the latter species is the immediate, primary product; hence it is certain that the Cr(II) attacks the original complex at the remote keto group and that the electron is transferred to the Co(III) through the conjugated bonds of the isonicotinamide.21

Isied and Taube<sup>22</sup> prepared the complex

$$\left[ (NH_3)_5 CoO_2 C - \left( N - Ru(NH_3)_4 SO_4 \right]^{2+} \right]$$

in the Co(III)—L—Ru(II) from and, by spectrophotometric measurements, determined the rate  $(k \sim 1 \times 10^2 \text{ s}^{-1})$  of the *intra*molecular electron-transfer reaction:

$$Co(III)$$
— $L$ — $Ru(II)$   $\rightarrow$   $Co(II)$ — $L$ — $Ru(III)$ 

<sup>&</sup>lt;sup>21</sup> H. Taube and E. S. Gould, Acc. Chem. Res., 2, 321 (1969).

<sup>&</sup>lt;sup>12</sup> S. S. Isied and H. Taube, J. Am. Chem. Soc., 95, 8198 (1973).

They found that the following complex, with a CH<sub>2</sub> group between the carboxylate group and the aromatic ring, underwent the analogous electron transfer much more slowly ( $k \sim 2 \times 10^{-2} \, \mathrm{s}^{-1}$ ).

$$\left[ (NH_3)_5CoO_2CCH_2 - \left( N-Ru(NH_3)_4H_2O \right)^{4+} \right]$$

The difference is undoubtedly mainly due to blockage of the  $\pi$  bonding between the metal atoms. In fact, electron transfer in the latter complex may proceed by a different sort of route. Molecular models of the complex show that the carbonyl group is close to the  $\pi$  cloud of the ring, and thus the CH<sub>2</sub> linkage may be completely bypassed in the electron transfer.

The reactions of aqueous chromium(II) with the complexes (I, II, and III) shown here illustrate outer- and inner-sphere redox processes and give information regarding the ability of the terephthalic acid ring to function as a bridge for

electron transfer.<sup>23</sup> In all three reactions, the Co(III) atoms are reduced stepwise. In the reactions of complexes I and III, reduction of the first Co(III) is relatively slow and rate-determining. These processes are believed to be outer-sphere processes, and their slowness is attributable to the fact that the numbers of  $e_s^*$  electrons on both the chromium and cobalt atoms change in the reaction. In the

<sup>&</sup>lt;sup>23</sup> M. Hery and K. Wieghardt, *Inorg. Chem.*, 15, 2315 (1976).

reaction of complex II, the first Co(III) is reduced rapidly, and the remaining Co(III) atoms are reduced slowly. It should be noted that complex II has one uncomplexed carboxylic oxygen atom adjacent to a Co(NH<sub>3</sub>)<sub>5</sub> moiety. The first step of the reaction presumably involves the rapid inner-sphere reduction of this Co(III) center, with attack of the Cr<sup>2+</sup> at the uncomplexed carbonyl oxygen; a mixed [Co(III)]<sub>2</sub>-Cr(III) complex is formed which then is further reduced relatively slowly by outer-sphere processes. Although complex III has an uncomplexed carboxylic oxygen atom, its reduction proceeds by a slow outer-sphere mechanism because the carboxylate group is not directly attached to a Co(III) atom. It is clear that terephthalic does not significantly facilitate the transfer of electrons from one carboxylate group to the other in such reactions.

#### Mixed-Valence Compounds<sup>24-26</sup>

Symmetric mixed-valence complexes are of considerable theoretical interest because of their close relation to electron-transport phenomena. Some of these are valence-localized species, in which two metal ions of different oxidation state are trapped at specific sites having different dimensions. Such systems can be represented by an energy-versus-configuration diagram such as Fig. 19.3. Others are valence-delocalized species, in which the two metal ions have the same, average oxidation state and the system is structurally symmetric. Such systems are represented by the energy-versus-configuration diagram of Fig. 19.5. We shall first describe a valence-localized complex, shown below.<sup>27</sup>

$$\left[ Cl(bipy)_2Ru - N - Ru(bipy)_2Cl \right]^{3+}$$

Each ruthenium atom of this mixed-valence complex is coordinated to two bipyridine ligands, a chloride ion, and a bridging pyrazine (pyz) ligand. The complex has a weak absorption band in the near infrared (1300 nm), whereas the

<sup>&</sup>lt;sup>26</sup> T. J. Meyer, Acc. Chem. Res., 11, 94 (1978). <sup>27</sup> R. W. Callahan, F. R. Keene, T. J. Meyer, and D. J. Salmon, J. Am. Chem. Soc., **99**, 1064 (1977).




Figure 19.5 Energy-versus-configuration diagram for a mixed-valence complex with complete delocalization. The energy levels correspond to the bonding and antibonding combinations of the metal orbitals which hold the electron.

<sup>&</sup>lt;sup>24</sup> H. Taube, Ann. N.Y. Acad. Sci., 313, 481 (1978).

<sup>&</sup>lt;sup>25</sup> T. J. Meyer, Ann. N.Y. Acad. Sci., **313**, 496 (1978).

corresponding +2 and +4 complexes show no absorption in this region. The band has been interpreted as an "intervalence transition" corresponding to  $E_1$  in Fig. 19.3. As expected from Franck-Condon considerations, the absorption band is broad. This interpretation of the spectrum implies that the oxidation states of the metal atoms are +2 and +3, rather than +2.5 and +2.5. Confirmation is provided by the appearance of a symmetric pyrazine stretch band in the infrared. The latter band does not appear in the infrared spectra of the +2 and +4 complexes, nor in that of free pyrazine, but it does appear in the spectrum of the monomeric complex (bipy)<sub>2</sub>Ru(pyz)Cl<sup>+</sup>. The band is forbidden in a symmetric bridging pyrazine and in the free ligand but is allowed when the twofold symmetry of the ligand is broken by asymmetric complexation.

The following cyanogen complex is a well-characterized example of a valence-delocalized complex.<sup>28</sup>

$$(NH_3)_5Ru-N\equiv C-C\equiv N-Ru(NH_3)_5^{5+}$$

In the +6 complex, the C-N stretching frequency is 2330 cm<sup>-1</sup>. In the +4 complex, this frequency is reduced (by  $d\pi \to \pi^*$  delocalization) to 1960 cm<sup>-1</sup>. It is significant that in the +5 (mixed-valence) complex, a single C-N stretching frequency is observed at 2210 cm<sup>-1</sup>, intermediate between those of the +4 and +6 complexes. Thus one can say that the lifetime of any state of the complex in which one ruthenium is +2 and the other +3 must be less than the period of a molecular vibration,  $\sim 10^{-13}$  s. Further evidence for delocalization is found in the observation of a narrow band in the infrared corresponding to the electron transition indicated in Fig. 19.5. The fact that the band is narrow indicates that it cannot correspond to an intervalence transition such as that indicated in Fig. 19.3.

Another example of a valence-delocalized complex is the following osmium complex:28

$$(NH_3)_5O_5-N \equiv N-O_5(NH_3)_5^{5+}$$

Because of the symmetry of the complex, the N-N stretch is inactive in the infrared. It has been determined that the equilibrium constant for the reaction of the +4 complex with the +6 complex.

$$[2,2]^{4+} + [3,3]^{6+} \implies 2[2.5,2.5]^{5+}$$

is greater than 10<sup>20</sup>, corresponding to a free-energy change of more than 27 kcal mol<sup>-1</sup>. Clearly there is a marked stabilization of the mixed-valence complex by electron delocalization. The related complex,

$$Cl(NH_3)_4Os-N \equiv N-Os(NH_3)_4Cl^{3+}$$

has a pK of 12, but when oxidized to the  $[3,3]^{4+}$  state, the pK drops to 6.6. These data prove that the mixed-valence complex is delocalized, because if it were

<sup>28</sup> H. Taube, op. cit.

valence-trapped [Os(II) on one side and Os(III) on the other], the pK would be near 6.6, as in the case of the [3,3]<sup>4+</sup> complex.<sup>29</sup>


The complex

$$\left[ (NH_3)_5 Ru - N - Ru(NH_3)_5 \right]^{5+}$$

appears to be delocalized according to some criteria, but localized according to others. Probably it represents an example of intermediate coupling between the metal atoms. The x-ray photoelectron spectrum of the complex shows two ruthenium core level peaks with binding energies close to those observed for the [2,2]4+ and [3,3]6+ complexes and with relative intensities of 1:1. This result is obviously consistent with a valence-trapped complex.30 However, Hush has pointed out that, even in cases where the ground state is delocalized, it is possible to have two core-ionized states, leading to two photopeaks.31 Thus the x-ray photoelectron spectrum cannot be interpreted unambiguously. It is significant that this complex at least shows intermediate coupling between the metal centers, whereas the analogous complex, in which the five ammonias on each ruthenium are replaced by two bipyridines and a chloride ion, is definitely valence-trapped. It is not clear whether the valence trapping is a consequence of four  $\pi$ -acceptor atoms on Ru(II) competing with the bridging ligand for  $d\pi$  electron density (this would diminish coupling between the centers) or whether it is a result of having a chloride ion in the coordination sphere. The Ru(II)-Cl<sup>-</sup> distance is expected to be much larger than the Ru(III)-Cl- distance, and this difference may affect valence trapping.

Various physical methods have shown that the iron atoms in the following mixed-valence biferrocenylene complex are equivalent, and a [2.5, 2.5]+ descrip-

tion seems appropriate.32



It is not known whether or not the <sup>29</sup> H. Taube, private communication. <sup>30</sup> P. H. Citrin, J. Am. Chem. Soc., 95, 6472 (1973); P. H. Citrin and A. P. Ginsberg, J. Am. Chem. Soc., 103, 3673 (1981).

<sup>&</sup>lt;sup>31</sup> N. S. Hush, Chem. Phys., 10, 361 (1975). <sup>32</sup> D. O. Cowan, D. LeVanda, J. Park, and F. Kaufman, Acc. Chem. Res., 6, 1 (1973).

However, high-quality calculations for this system predict valence trapping.<sup>33</sup> Clearly this system deserves further theoretical study.

#### Unstable Intermediate Oxidation States<sup>34</sup>

Redox reactions involving changes in oxidation state of more than one unit often involve intermediates in unusual oxidation states. For example, the reaction of Tl<sup>3+</sup> with Fe<sup>2+</sup>

$$2Fe^{2+} + Tl^{3+} \rightarrow 2Fe^{3+} + Tl^{+}$$

is first order in each of the reactants during the first part of the reaction, suggesting the formation of either Tl(II) or Fe(IV) as an intermediate:

$$Fe^{2+} + Tl^{3+} \rightarrow Fe^{3+} + Tl(II)$$

or

$$Fe^{2+} + Tl^{3+} \rightarrow Fe(IV) + Tl^{+}$$

When the products Fe<sup>3+</sup> and Tl<sup>+</sup> are added to the reaction mixture, Fe<sup>3+</sup>, but not Tl<sup>+</sup>, decreases the reaction rate. This result is in accord with the following mechanism:

$$Fe^{2+} + Tl^{3+} \implies Fe^{3+} + Tl(II)$$

$$Tl(II) + Fe^{2+} \longrightarrow Tl^{+} + Fe^{3+}$$

The reaction of chromium(VI) with iodide and iron(II) in dilute acid solution has some remarkable features. The oxidation of iodide by chromium(VI) is normally slow, but in the presence of iron(II), which is rapidly oxidized by chromium(VI), iodine is rapidly formed. Iron(III) does not oxidize iodide rapidly in dilute acid; therefore one concludes that a reactive intermediate, presumably an intermediate oxidation state of chromium, is responsible for the oxidation of the iodide. When a large excess of iodide is present, two equivalents of iodide are oxidized per mole of Fe<sup>2+</sup>:

$$Fe^{2+} + 2I^{-} + Cr(VI) \rightarrow Fe^{3+} + I_2 + Cr(III)$$

This result suggests that the first reactive intermediate formed is chromium(V),

$$Fe^{2+} + Cr(VI) \rightarrow Cr(V) + Fe^{3+}$$

and that the iodide reduces the Cr(V) to Cr(III):

$$Cr(V) + 2I^- \rightarrow Cr(III) + I_2$$

It is not known whether or not the latter reaction involves the intermediate formation of Cr(IV). This oxidation of iodide in the presence of iron(II) is an example of an *induced* reaction.

M. C. Böhm, R. Gleiter, F. Delgado-Pena, and D. O. Cowan, *Inorg. Chem.*, 19, 1081 (1980).
 Sykes, op. cit.

#### **PROBLEMS**

19.1 Arrange the following complexes in order of increasing lability. Fe(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, Cr(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, Y(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, Al(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, Sr(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, K(H<sub>2</sub>O)<sub>6</sub><sup>4</sup>.

\*19.2 Explain why the following reaction is catalyzed by Co2+:

$$Co(NH_3)_6^{3+} + 6CN^- \rightarrow Co(CN)_6^{3-} + 6NH_3$$

19.3 There are two isomers of Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub>, A and B. When A is treated with thiourea (tu), Pt(tu)<sub>4</sub><sup>2+</sup> is formed. When B is treated with thiourea, Pt(NH<sub>3</sub>)<sub>2</sub>(tu)<sub>2</sub><sup>2+</sup> is formed. Identify the isomers and explain the data.

19.4 Using the trans effect, predict the product of the reaction of 2 mol of ethylenediamine with 1 mol of PtCl<sub>6</sub><sup>2-</sup>.

\*19.5 The reaction of CrCl<sub>3</sub> with liquid ammonia ordinarily gives principally [Cr(NH<sub>3</sub>)<sub>5</sub>Cl]Cl<sub>2</sub>, but when a trace of KNH<sub>2</sub> is present, the main product is [Cr(NH<sub>3</sub>)<sub>6</sub>]Cl<sub>3</sub>. Explain.

\*19.6 Suggest a method for preparing the complex (NC)<sub>5</sub>Fe—CN—Co(CN)<sub>5</sub>6-.

\*19.7 The oxidation of Sn(II) by Fe<sup>3+</sup> is first order in each reagent. How would you try to determine whether Sn(III) is involved in the mechanism?

19.8 Suggest methods for the preparation of the three isomers of PtNH<sub>3</sub>py(NO<sub>2</sub>)Br.

19.9 The rate of the aqueous vanadium(II) – vanadium(III) electron-exchange reaction may be expressed Rate =  $k[V^{II}][V^{III}]$ , where k shows the following dependence on hydrogen-ion concentration:

$$k = a + \frac{b}{[H^+]}$$

Explain this result in terms of two parallel reaction paths. (Hint: The so-called hydrolysis of an aquo metal ion is really the ionization of a Brönsted acid.)

19.10 Slow substitution reactions are found for octahedral complexes with what electron configura-

\*19.11 The reaction Ni(CO)<sub>4</sub> + L  $\rightarrow$  Ni(CO)<sub>3</sub>L + CO is first order in Ni(CO)<sub>4</sub> and zero order in L, whereas the reaction Co(CO)<sub>3</sub>NO + L  $\rightarrow$  Co(CO)<sub>2</sub>(NO)L + CO is second order (first order in the complex and in L). Explain the difference.

19.12 It has been observed that two of the water molecules in the aqueous Cu(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> ion undergo exchange with the bulk solvent molecules much more rapidly than the other four. Explain.

## HOMOGENEOUS CATALYSIS

A reaction is said to be catalyzed when its rate is increased by the presence of a substance (the catalyst) which does not appear in the equation for the net, overall reaction. In homogeneous catalysis the catalyst and the reactants are molecularly dispersed in the same phase, either liquid or gaseous. In heterogeneous catalysis the catalyst and reactants are in different phases; usually heterogeneous catalysts are solids, and the reactants are liquids or gases. In this chapter we shall discuss various examples of homogeneous catalysis by transition-metal compounds. Heterogeneous catalysis will be covered in Chap. 21.

A transition-metal catalyst provides a site where the rate-determining step of a reaction can take place more easily than it can in the absence of the catalyst. The activation energy of the catalyzed reaction is less than that of the uncatalyzed reaction, and therefore the catalyzed reaction is more rapid than the uncatalyzed reaction. Generally a catalyzed reaction is the sum of a sequence of reaction steps, only one of which is rate-determining. In the case of reactions catalyzed by transition-metal complexes, the various reaction steps can usually be categorized into three broad types. We shall discuss these three types of reaction before describing the detailed mechanisms of particular catalyzed reactions.

1. Dissociation and addition. We have seen that there are many transition-metal complexes with only 16, or even 14, electrons in the valence shell of the metal atom. Sixteen-electron complexes are often found with d<sup>8</sup> metal ions, such as Co(I), Rh(I), Ni(II), and Pd(II). Such complexes are said to be coordinatively unsaturated; they can add ligands to form coordinatively saturated 18-electron compounds, and conversely the latter can undergo dissociation to form coordinatively unsaturated compounds. Compounds of both kinds are commonly

involved in catalytic processes. Typically, a  $d^8$  metal complex, by gain or loss of ligands, reversibly converts between 4-coordination and 5-coordination, as follows:

Distribution 
$$L_4M + :X \rightleftharpoons L_4MX$$

$$\frac{d^8}{d^8}$$

Here X is a species such as CO, an olefin, or a halide ion, which can donate an electron pair to the metal atom.

2. Oxidative addition and reductive elimination. If, in the addition of a species to a complex, the metal atom formally provides part or all of the electrons used in bonding the metal atom to the added species, the process is called "oxidative addition," and the reverse process is called "reductive elimination." The simplest example of oxidative addition is the addition of a proton to a metal complex. For example,

$$\begin{array}{c|c}
C \\
C \\
C \\
C \\
C
\end{array}$$

$$\begin{array}{c|c}
C \\
\hline
C \\
\hline
C \\
\hline
C \\
C
\end{array}$$

$$\begin{array}{c|c}
C \\
\hline
C \\
\hline
C \\
C
\end{array}$$

$$\begin{array}{c|c}
C \\
\hline
C \\
C
\end{array}$$

$$\begin{array}{c|c}
C \\
\hline
C \\
C
\end{array}$$

$$\begin{array}{c|c}
C \\
C \\
C
\end{array}$$

According to the usual methods of calculating oxidation state, the hydrogen of the adduct exists as a coordinated hydride ion and the iron is in the +2 oxidation state.

More commonly, oxidative addition involves the addition of a molecule which cleaves into two fragments that bond separately to the metal atom. The oxidation state of the metal effectively increases by two units, and, unless the metal atom loses a ligand in the process, the coordination number also increases by two units.

$$L_4M + Y : Z \implies L_4M$$
Z

Note that the metal atom formally must provide two of the four electrons used to bond groups Y and Z. Typically, the added molecule is a small molecule such as  $H_2$ , RX, HX,  $X_2$ , etc., and the oxidative addition converts a coordinatively unsaturated  $d^8$  complex to a coordinatively saturated  $d^6$  complex. For example,

J. P. Collman and L. S. Hegedus, "Principles and Applications of Organotransition Metal Chemistry," pp. 176-258, University Science Books, Mill Valley, Calif., 1980.

However, relatively large molecules can also add oxidatively,

And there are some examples of oxidative addition to coordinatively saturated complexes, with the loss of a neutral ligand such as CO,  $PR_3$ , or  $N_2$ :

$$Os(CO)_5 \xrightarrow{H_2} H_2Os(CO)_4 + CO$$

Many intramolecular oxidative additions are known. For example, oxidative addition of an ortho C—H bond of one of the phenyl groups in Ir(PPh<sub>3</sub>)<sub>3</sub>Cl yields a four-membered metallacycle:<sup>2</sup>

Transition-metal complexes which easily undergo one-electron oxidations (such as complexes of Co<sup>2+</sup> and Cr<sup>2+</sup>) can undergo oxidative addition with an overall one-electron change. The net reaction is of the form

$$2L_nM + Y - Z \longrightarrow L_nM - Y + L_nM - Z$$

However, such reactions usually occur in two steps, the first being rate-determining. For example, alkyl halides react with  $Co(CN)_5^{3-}$  as follows:

$$Co^{II}(CN)_5^{3-} + RX \xrightarrow{slow} X - Co^{III}(CN)_5^{3-} + R$$

$$Co^{II}(CN)_5^{3-} + R \xrightarrow{fast} R - Co^{III}(CN)_5^{3-}$$

3. Insertion reactions. A third important type of reaction involved in catalysis amounts to the insertion of a group between the metal atom and a ligand. Two examples of migratory insertions (i.e., intramolecular insertions) follow:

$${}^{O}C$$
 $M$ 
 $R$ 
 $M$ 
 $M$ 
 $M$ 
 $M$ 
 $M$ 
 $M$ 

<sup>&</sup>lt;sup>2</sup> The prefix "metalla" indicates that one of the carbon atoms in the ring has been replaced by <sup>a</sup> metal atom.

In each of these examples, the coordination number of the metal atom decreases by one.

Intermolecular insertion reactions involve the direct attack of nucleophilic reagents on unsaturated ligands without prior coordination of the nucleophile to the metal. For example, alkyl- and aryllithium reagents react directly with iron pentacarbonyl to form anionic acyl derivatives.

$$RLi + Fe(CO)_{5} \longrightarrow Li^{+} \begin{bmatrix} R & O \\ C & C \\ OC - Fe \\ C & C \end{bmatrix}$$

Nucleophilic attack at a terminal carbon atom of an  $\eta^3$ -allyl group leads to the corresponding olefin complex and a formal two-electron reduction of the metal: metal:

$$\begin{array}{c|c}
OC & \downarrow & NO \\
\hline
MO & \downarrow & CH - CH_2OMe \\
\hline
MO & \downarrow & CH_2 \\
\hline
OC & N \\
O & O
\end{array}$$

It is significant that, in the above example, the  $\eta^3$ -allyl group is attacked preferentially over three other unsaturated ligands in the complex.

# OLEFIN HYDROGENATION

Most catalytic processes for the hydrogenation of double bonds require the use of high temperatures and high hydrogen pressures. The first practical system for the homogeneous reduction of olefins and other unsaturated molecules at 25°C and atm pressure involved the complex RhCl(PPh<sub>3</sub>)<sub>3</sub>, often known as Wilkinson's catalyst.3 In solution this complex dissociates to a small extent at 25°C:

$$RhCl(PPh_3)_3 \implies RhCl(PPh_3)_2 + PPh_3 \qquad K = 1.4 \times 10^{-4}$$

A simplified mechanism for the catalytic hydrogenation of olefins or acetylenes, involving species derived from Wilkinson's catalyst, is shown by the following cyclic scheme:

The 14-electron species RhCl(PPh<sub>3</sub>)<sub>2</sub> adds a molecule of hydrogen oxidatively to form the 5-coordinate, 16-electron dihydro complex. This in turn adds a molecule of olefin to form a 6-coordinate, 18-electron complex. Transfer of a hydrogen atom to the  $\beta$ -carbon atom yields a 5-coordinate alkyl intermediate which then undergoes another rearrangement to give the hydrogenated product and to reform the RhCl(PPh<sub>3</sub>)<sub>2</sub> species. All of the three broad types of reaction steps (addition, oxidative addition, and insertion) are represented in this mechanism.

## **OLEFIN DIMERIZATION AND METATHESIS**

It has been shown that metallacyclic intermediates participate in homogeneous catalytic reactions such as olefin dimerization and olefin metathesis (disproportionation).<sup>4</sup> An example is the nickel-catalyzed cyclodimerization of ethylene to give cyclobutane, <sup>5</sup> a compound that is otherwise difficult to obtain:

$$2C_2H_4 \longrightarrow \begin{array}{c} H_2C-CH_2 \\ | \\ | \\ H_2C-CH_2 \end{array}$$

<sup>&</sup>lt;sup>3</sup> F. A. Cotton and G. Wilkinson, "Advanced Inorganic Chemistry," 4th ed., pp. 1266–1271, Wiley-Interscience, New York, 1980.

<sup>&</sup>lt;sup>4</sup> G. Wilke, Pure Appl. Chem., 50, 677 (1978).

<sup>&</sup>lt;sup>5</sup> R. H. Grubbs and A. Miyashita, J. Am. Chem. Soc., 100, 7416 (1978).

It is believed that an important step in the process is the conversion of a bis(ethylene)nickel(0) complex to a nickelacyclopentane:

Phosphine-promoted reductive elimination of the two Ni—C bonds forms cyclobutane and Ni(PPh3)3, which can react with more ethylene to regenerate the bis(ethylene) complex.

The olefin metathesis (or disproportionation) reaction may be represented by

The reaction is catalyzed by a wide variety of catalysts, generally prepared by the reaction of halides of molybdenum, tungsten, or rhenium with alkylating agents such as EtAlCl<sub>2</sub>, AlR<sub>3</sub>, and ZnR<sub>2</sub>. It was once believed that olefin metatheses proceed by a concerted process involving a cyclobutane-like intermediate:

$$\|\cdots M\cdots\| \longrightarrow \boxed{M} \longrightarrow \stackrel{\square}{\stackrel{M}{\stackrel{M}{\stackrel{}}{\stackrel{}}}}$$
 (20.1)

Although such a mechanism might be thought to be symmetry-forbidden according to the symmetry forbidden according to the symmetry for symmetry fo ing to the orbital symmetry considerations discussed in Chap. 5, it has been shown that, because of the overlap of the metal d orbitals with the olefin MOs, the process is symmetry-allowed. Nevertheless, it is now believed that olefin metatheses are chain reactions involving transition-metal carbenes ( $L_nM = CR_2$ ) and metallacyclobutane intermediates. The chain-propagating steps are believed to be of the

<sup>&</sup>lt;sup>6</sup> F. D. Mango and J. H. Schachtschneider, J. Am. Chem. Soc., 93, 1123 (1971). <sup>7</sup> T. J. Katz and J. H. Schachtschneider, J. Am. Chem. Soc., 93, 1150 (1975); M. T. Mocella, M. A. Busch, F. J. Katz and J. McGinnis, J. Am. Chem. Soc., 97, 1592 (1975); M. T. Mocella, M. A. Busch, F. J. Marchen, Soc., 97, 1592 (1975); M. T. Mocella, M. A. Busch, Prog. Linero, Chem. 24, 1 and E. L. Muetterties, J. Am. Chem. Soc., 98, 1283 (1976); R. H. Grubbs, Prog. Inorg. Chem., 24, 1 (1978) (1978).

following type:

$$L_{n}M=C \xrightarrow{a} + \xrightarrow{e} \xrightarrow{b} \xrightarrow{h} \xrightarrow{a} \xrightarrow{h} \xrightarrow{h} \xrightarrow{h} \xrightarrow{a} \xrightarrow{e} + L_{n}M=C \xrightarrow{g} \xrightarrow{h} (20.2)$$

There are a variety of kinetic data that tend to support such a mechanism and to rule out mechanism 20.1.8 Consider, for example, an experiment in which cyclooctene, 2-butene, and 4-octene are allowed to react simultaneously and the relative amounts of the hydrocarbons formed are determined by analysis near the very beginning of the reaction:

It is obvious that, whatever the reaction mechanism, the concentration of  $C_6$  is much less than that of  $C_4$  or  $C_8$  early in the reaction. Therefore if the reaction proceeded according to mechanism 20.1, at first the ratios  $C_{14}/C_{12}$  and  $C_{14}/C_{16}$  would be near zero, because  $C_{14}$  would not form from  $C_6$  as quickly as  $C_{12}$  and  $C_{16}$  form from  $C_4$  and  $C_8$ . On the other hand, if the reaction proceeded according to mechanism 20.2,  $C_{14}$  would initially predominate over  $C_{12}$  and  $C_{16}$ . (From purely statistical considerations, the initial rate of formation of  $C_{14}$  should be twice that of  $C_{12}$  or  $C_{16}$ .) The experimental data show that at the start of the reaction  $C_{14}$  is formed in a greater amount than either  $C_{12}$  or  $C_{16}$ .

Further support for mechanism 20.2 is found in the actual isolation of catalytically active carbene complexes, such as (CO)<sub>5</sub>WCR<sub>2</sub> and Cl<sub>2</sub>(PEt<sub>3</sub>)<sup>2</sup>

W(0)CHCMe<sub>3</sub>, and metallacyclobutanes such as 
$$(\eta^5 - C_5H_5)_2\text{Ti}$$
  $\stackrel{R}{\searrow}_{R}$ 

Both (CO)<sub>5</sub>WCR<sub>2</sub> and Cl<sub>2</sub>(PEt<sub>3</sub>)<sub>2</sub>W(O)CHCMe<sub>3</sub> have been shown to react with olefins, as in general reaction 20.2, and to catalyze the metathesis of olefins.

Stable platinacyclobutanes have been formed by the oxidative addition of cyclopropanes to Pt(II) complexes,10

$$\frac{1}{2}\begin{bmatrix} CH_2 & Cl & Cl \\ CH_2 & Pt & Pt & CH_2 \end{bmatrix} + \begin{bmatrix} R & py & Cl - Pt - Cl \\ Cl & CH_2 & py \end{bmatrix}$$

and by the cyclometallation of bis(neopentyl)platinum complexes,11

$$\begin{array}{c} L \\ \text{CH}_2\text{C}(\text{CH}_3)_3 \\ \text{CH}_2\text{C}(\text{CH}_3)_3 \end{array} \xrightarrow{-L} L - \text{Pt} \\ \begin{array}{c} -L \\ \text{CH}_2 \\ \text{C}(\text{CH}_3)_2 \end{array}$$

These platinacyclobutanes apparently are too stable to engage in olefin metathesis reactions. At high temperatures, however, they decompose to form cyclopropane and propylene (or their substituted derivatives) by competitive reductive elimination and  $\beta$ -hydride elimination.

# **OLEFIN ISOMERIZATION**

Many transition-metal compounds catalyze the migration of double bonds in alkenes. The mechanism involves the reversible transfer of a hydrogen atom from the from the transition metal to the coordinated olefin to give a  $\sigma$ -bonded alkyl

<sup>&</sup>lt;sup>9</sup> Collman and Hegedus, op. cit.; R. H. Grubbs et al., J. Am. Chem. Soc., **102**, 6876 (1980); **103**, 8 (1981) 7358 (1981). <sup>10</sup> J. Rajaram and J. A. Ibers, *J. Am. Chem. Soc.*, **100**, 829 (1978).

P. Foley and G. M. Whitesides, J. Am. Chem. Soc., 100, 829 (1978).

group. For example, the HCo(CO)<sub>4</sub>-catalyzed isomerization of allyl alcohol to propionaldehyde is believed to proceed by the following mechanism:

$$HCo(CO)_4$$
 $+CO$ 
 $CH_2$ = $CHCH_2OH$ 
 $CH_2$ = $CHCH_2OH$ 
 $HCo(CO)_3$ 
 $HCo(CO)_3$ 
 $CH_3CH$ = $CHOH$ 
 $CH_3CH$ = $CHOH$ 

#### **HYDROFORMYLATION**

The hydroformylation reaction is the addition of H<sub>2</sub> and CO to an olefin to form an aldehyde:

$$RCH = CH_2 + H_2 + CO \longrightarrow RCH_2CH_2CHO$$

The classical hydroformylation process involves the use of  $Co_2(CO)_8$  as a catalyst, temperatures in the range 150 to 180°C, and pressures of 200 to 400 atm. Under these reaction conditions, the  $Co_2(CO)_8$  is converted to  $HCo(CO)_4$ ,

$$H_2 + Co_2(CO)_8 \longrightarrow 2HCo(CO)_4$$

and the mechanism is as follows:

Disadvantages of this process are that some 15 percent of the olefin is hydrogenated to the saturated hydrocarbon, that ketones are formed as by-products, and that some of the aldehyde is reduced to the alcohol. A more effective process,

which is carried out industrially at 100°C and a few atmospheres pressure. involves rhodium triphenylphosphine complexes.<sup>12</sup> The mechanism is essentially the same as that of the cobalt-catalyzed process, except that the (Ph<sub>3</sub>P)<sub>2</sub>RhCO group replaces the Co(CO)<sub>3</sub> group.

#### WATER GAS SHIFT REACTION

The water gas shift reaction,

$$H_2O + CO \implies CO_2 + H_2$$

has received renewed attention because of the need to produce hydrogen from nonpetroleum sources (e.g., coal). Commercially, the reaction is best carried out over solid metal oxide catalysts at elevated temperatures. However, the reaction can proceed homogeneously using alkaline solutions of various metal carbonyls.13 A postulated general cycle for such homogeneous catalysis is the following:

In this mechanism, ML, might represent, for example, the Fe(CO)<sub>4</sub> group. The attack of hydroxide on  $L_nMCO$  presumably forms an anionic carboxylic acid intermediate which in turn abstracts a proton from the solvent to form L<sub>n</sub>MH(COOH). This species undergoes decarboxylation to form the dihydride, which reductively eliminates H<sub>2</sub> and adds CO to re-form L<sub>n</sub>MCO, thus completing the cycle. Atmosph the density of this step are not known, it is believed that both Co(II) and

#### ACETIC ACID FROM ETHYLENE<sup>14</sup>

The first step of the overall oxidation of ethylene to acetic acid is the oxidation of ethylene to acetaldehyde, a reaction which is carried out industrially by the

<sup>14</sup> G. W. Parshall, Science, 208, 1221 (1980).

<sup>&</sup>lt;sup>12</sup> Cotton and Wilkinson, op. cit., pp. 1292-1294. <sup>13</sup> P. C. Ford, *Acc. Chem. Res.*, 14, 31 (1981). Also see D. J. Darensbourg, A. Rokicki, and M. Y. arensbourg, *X* 

Darensbourg, J. Am. Chem. Soc., 103, 3223 (1981).

Wacker process. It has been known since 1894 that ethylene is readily oxidized by aqueous PdCl<sub>2</sub> solutions to acetaldehyde. Chemists at Wacker-Chemie combined this reaction with a copper-catalyzed reoxidation of palladium by air to achieve the catalytic air oxidation of ethylene:

$$C_2H_4 + \frac{1}{2}O_2 \longrightarrow CH_3CHO$$

The major mechanistic features of the process are shown in the following schematic catalytic cycle:15

$$Pd^{2+} \xrightarrow{C_{2}H_{4}} Pd^{2+} \xrightarrow{CH_{2}} Pd^{2+} \xrightarrow{H_{2}O} H^{+} OH$$

$$CH_{2} CH_{2}$$

$$CCH_{2} - Pd^{+}$$

$$2Cu^{+}$$

$$2Cu^{2+} O_{2}$$

$$2Cu^{2+} OH OH$$

$$HC-Pd^{+} CH_{3} CH_{2} H$$

The second step in the production of acetic acid from ethylene is the oxidation of acetaldehyde. The process involves heating acetaldehyde with air at 65°C in the presence of a Co<sup>2+</sup> catalyst. Acetaldehyde is initially oxidized by a noncatalytic free-radical process to give peracetic acid:

$$\begin{array}{ccc}
O & O & O \\
\parallel & \parallel & \parallel \\
CH_3CH + O_2 & \longrightarrow CH_3COOH
\end{array}$$

The Co<sup>2+</sup> catalyzes the reaction between peracetic acid and acetaldehyde to form two molecules of acetic acid:

CH<sub>3</sub>COOH + CH<sub>3</sub>CHO 
$$\xrightarrow{C_0^{2+}}$$
 2CH<sub>3</sub>COOH

Although the details of this step are not known, it is believed that both Co(II) and

Co(III) are involved, and that the acetoxy radical, CH<sub>3</sub>CO·, is an intermediate. Another way of making acetic acid, methanol carbonylation, appears to be very promising for future technology. The process consists of three parts:

J. E. Bäckvall, B. Akermark, and S. O. Ljunggren, J. Am. Chem. Soc., 101, 2411 (1979).
 G. C. Allen and A. Aguilo, Adv. Chem. Ser., 76, 363 (1968).

$$\begin{array}{ccc} \text{CH}_3\text{OH} + \text{HI} & \longrightarrow & \text{CH}_3\text{I} + \text{H}_2\text{O} \\ \text{CH}_3\text{I} + \text{CO} & \longrightarrow & \text{CH}_3\text{COI} \\ \underline{\text{CH}_3\text{COI} + \text{H}_2\text{O}} & \longrightarrow & \text{CH}_3\text{COOH} + \text{HI} \\ \hline \text{CH}_3\text{OH} + \text{CO} & \longrightarrow & \text{CH}_3\text{COOH} \\ \end{array}$$

The second part, the carbonylation of methyl iodide, is catalyzed by rhodium carbonyl iodide complexes, as shown by the following scheme:17

Oxidative addition of methyl iodide to Rh(CO)<sub>2</sub>I<sub>2</sub><sup>-</sup> forms a 6-coordinate Rh(III) complex which undergoes rearrangement to give a 5-coordinate acetyl complex. After the addition of CO, reductive elimination of the product, CH<sub>3</sub>COI, regenerates the Rh(CO)<sub>2</sub>I<sub>2</sub>-.

## TEMPLATE SYNTHESES<sup>18</sup>

The term "template synthesis" has been suggested for reactions in which a central metal ion serves as a "template" on which to coordinate ligands which then react to form chelate rings. In some cases this process can surround the metal ion with a fused cyclic ring system, i.e., a "macrocyclic" ligand. A common procedure involves the cyclic condensation of an  $\alpha$ -diketone with a 1,2- or 1,3-diamine. Thus the following planar nickel complex has been prepared by treating 2 mol of 1,3-diaminopropane monohydrochloride with 2 mol of biacetyl, followed by 1 mol of nickel acetate.

D. Forster, Adv. Organomet. Chem., 17, 255 (1979).

L. F. Lindoy and D. H. Busch, Prep. Inorg. React., 6, 1 (1971).

Mercaptoethylamine reacts with biacetyl in the presence of nickel ion to form a Schiff-base complex which in turn can be condensed with  $\alpha, \alpha'$ -dibromo-o-xylene to form a macrocyclic ligand:

#### **PROBLEMS**

20.1 Treatment of Cr(CO)<sub>6</sub> with LiCH<sub>3</sub>, followed by [(CH<sub>3</sub>)<sub>3</sub>O]BF<sub>4</sub>, yields the carbene complex CH<sub>3</sub>

(CO)<sub>5</sub>CrC . Propose a mechanism for this synthesis. OCH<sub>3</sub>

**20.2** When  $[(C_6H_5O)_3P]_4RhH$  is heated with a large excess of  $D_2$  at  $100^{\circ}C$ , the orthohydrogen atoms undergo exchange to form  $[(C_6H_3D_2O)_3P]_4RdD$ . Explain.

20.3 The hydrosilylation reaction is

$$RCH = CH_2 + HSiR_3 \rightarrow RCH_2CH_2SiR_3$$

The reaction is catalyzed by Pd(PPh<sub>3</sub>)<sub>4</sub>. Suggest a mechanism.

**20.4** Although H<sub>2</sub> has a high dissociation energy, it readily adds oxidatively to many transition-metal complexes. Explain.

20.5 Give a plausible mechanism for the hydroformylation reaction using  $RhH(CO)(PPh_3)_2$  as the catalyst.

20.6 Ni[P(OEt)<sub>3</sub>]<sub>4</sub> catalyzes the dimerization of ethylene in acid solution to give 1-butene. Propose separate mechanisms for this reaction which (a) involve insertion of alkenes into Ni—C bonds, coupled with  $\beta$  elimination, and (b) involve carbene intermediates.

20.7 Many low-oxidation-state transition-metal complexes form adducts with Lewis acids such as BF<sub>3</sub>:

Do you think that such reactions should be classed as oxidative additions?

- \*20.8 Predict the product of the reaction of
  - (a) (n5-C5H5)Fe(CO)2- with CH3COCI
- (b) Ir(PPh<sub>3</sub>)<sub>2</sub>(CO)Cl with CH<sub>2</sub>N<sub>2</sub> (CH<sub>2</sub>N<sub>2</sub> readily yields the methylene group and molecular nitrogen)
  - (c) Co<sub>2</sub>(CO)<sub>8</sub> with RC≡CR
- 20.9 Formate ion is suspected as a by-product in the metal-carbonyl-catalyzed water gas shift reaction. Explain how it might form.
- 20.10 Assuming that the Wacker process proceeds by the mechanism described in this chapter, do you expect that some of the hydrogen of the acetaldehyde originates in the solvent? How would you ascertain this experimentally?
- \*20.11 Suppose that cyclooctene and 2-hexene were allowed to react in the presence of an olefin metathesis catalyst. What would you expect for the relative yields of  $C_{12}$ ,  $C_{14}$ , and  $C_{16}$  hydrocarbons near the beginning of the reaction (a) if mechanism 20.1 were followed and (b) if mechanism 20.2 were followed?

## TWENTY-ONE

## HETEROGENEOUS CATALYSIS

In this chapter we restrict the scope of heterogeneous catalysis to systems with solid catalysts and liquid or gaseous reactants. The catalyst provides a surface where effective interaction of adsorbed reactant molecules can take place. Hence the most effective catalysts are usually those with high surface areas per unit volume, e.g., powders or porous solids. For many years research and development in the field of heterogeneous catalysis was mainly empirical, because there were few physicochemical tools available for the characterization of surfaces and adsorbed species. Now, however, there are at least a dozen techniques for studying surfaces, some of which are listed and briefly described in Table 21.1. Unfortunately, none of these techniques gives as much chemical information as can be obtained from the nmr spectrum of a coordination compound in solution or from an x-ray diffraction study of a crystalline coordination compound. Generally several of the techniques in Table 21.1 must be applied to a given surface problem in order to characterize the system even approximately.

## EFFECTS OF SURFACE SITE ON ADSORPTION

The faces of a crystal and the internal layers of atoms are identified by a set of three numbers known as the "Miller indices." These are the smallest integers which are proportional to the reciprocals of the intercepts of the plane on the a, b, and c

E. L. Muetterties, Angew. Chem. Int. Ed., 17, 545 (1978); G. A. Somorjai, Acc. Chem. Res., 9, 248 (1976); G. A. Somorjai, "Chemistry in Two Dimensions: Surfaces," Cornell University Press, Ithaca, N.Y., 1981.

axes of the crystal. Several examples of crystal planes in cubic crystals are illustrated in Fig. 21.1. In Fig. 21.1a, one of the set of parallel planes intercepts the a axis at 2 unit cell lengths and is parallel to the b and c axes (i.e., it intercepts the b and c axes at  $\infty$ ). Thus the Miller indices for these planes are the smallest set of integers proportional to  $(\frac{1}{2}, \frac{1}{\infty}, \frac{1}{\infty})$ , or (100). In Fig. 21.1d, one of the set of planes intercepts the axes at 1, 1, and  $\frac{1}{2}$  unit cell lengths; hence these planes are designated the (112) planes.




Figure 21.1 Examples of crystal planes. Unit cell spacings and Miller indices are indicated.

Table 21.1 Physical methods for studying surfaces†

Technique	Principle	Application	Sensitivity (monolayer)	Penetration depth
Auger electron spectros- copy (AES)			10-2-10-3	1-7 layers
Ion scattering spectros- copy (ISS)	Energy loss for rare-gas ion scattering from a surface reveals the mass of the surface atom involved in the scattering process	Analysis of surface composition	~ 10 <sup>-3</sup> -10 <sup>-4</sup>	l layer
Secondary ion mass spec- troscopy (SIMS)	Ion (typically rare-gas ion)-stimulated sec- ondary ion emission	Analysis of surface composition	~ 10 <sup>-6</sup>	1 layer
Ion neutralization spec- troscopy (INS)	Incident low-energy ions are neutralized by electron transfer from surface atoms which then stimulate an Auger electron emission	Analysis of surface composition and valence band structure	10-2	1 or > 1 layer
X-ray photoelectron spectroscopy (XPS)	X-ray stimulated electron emission from valence and inner shells of surface atoms	Analysis of surface composition and of surface atom oxidation states	$\sim 10^{-1} - 10^{-2}$	1 – 7 layers
Ultraviolet photoelectron spectroscopy (UPS)	Ultraviolet radiation-stimulated electron emission from valence shell of surface atoms	Electronic structure and orientation of chemisorbed molecules	10-1-10-2	1-3 layers; ~ 1 layer in synchroton radiation mode

1-7 layers	1-7 layers	1-7 layers	1 layer		
$\sim 10^{-1} - 10^{-2}$ 1-7 layers	10-2	10-2-10-3	~ 10-2	~ 10-3	<b>6</b> 03
Symmetry features of surface atom environments, unit cell dimensions, and structural features of the surface	Analysis of vibrational states	Analysis of surface composition and electronic features	Analysis of vibrational states	Characterization of chemisorbed species	Determination of residence times on surface and activation energies of adsorption and reaction
Elastic scattering of low-energy electrons from the surface and the near-surface atoms	High-resolution analysis of energy loss in inelastically scattered electrons from a surface	Programmed escalation of incident electron energy with scanning of the resultant x-rays from the surface	Spectral analysis of infrared radiation re- flected from a surface	Mass-spectral detection of desorbed species during programmed surface warm-	Measurement of angular distribution of scattered beam
Low-energy electron dif- fraction (LEED)	High-resolution electron loss spectroscopy (HRELS)	Appearance potential spectroscopy (APS)	Infrared reflection- absorption	Thermal desorption spectroscopy	Molecular beam surface scattering

† Partly from Muetterties, Angew. Chem. Int. Ed., 17, 545 (1978).




Figure 21.2 A representation of a stepped surface of a bcc metal on which there are (111) terraces (unshaded circles), steps (light shaded circles), and kinks (dark shaded circles). (*Drawing courtesy of C. E. Smith and G. A. Somorjai.*)

Even a highly polished single-crystal surface is usually quite rough on a microscopic or atomic level. For example, consider the surface of a hexagonal close-packed metal. If viewed microscopically, the crystal would show scratches and defects. On the atomic level, "steps" and "kinks", illustrated in Fig. 21.2, are generally present.<sup>2</sup> Thus the structural environment of a surface atom is not only determined by the particular crystal plane involved but also by whether the atom occupies a terrace, step, or kink site. On the terrace or flat section of a (111) face of a cubic close-packed metal, the coordination number is 9. At a step between the step is so irregular as to have a kink, the kink atom has a coordination number of 6. The (110) face of a cubic close-packed metal (Fig. 21.3) is a continuously stepped surface, like corduroy fabric, and the protruding atoms have a coordination number of only 7.

One might expect the reactivity between adsorbed molecules and surface metal atoms to increase with a decrease in metal-metal coordination number. Indeed, data on the reactivity of molecules with various metal faces agree with this

<sup>2</sup> E. L. Muetterties, Angew. Chem. Int. Ed., 17, 545 (1978).




Figure 21.3 A perspective view of the (110) face of a bcc metal. The coordination numbers of the exposed atoms and those in the troughs are 7 and 11, respectively.

Figure 21.4 Possible bonding configurations for acetonitrile at a terrace site, a step site, and immediately below a step site. Reasonable distortion of the molecule can bring the hydrogen atoms in contact with the surface in the case of molecules at a step or immediately below a step. [Reproduced with permission from C. M. Friend, J. Stein, and E. L. Muetterties, J. Am. Chem. Soc., 103, 767 (1981). Copyright 1981 American Chemical Society.]

prediction. For example, the (110) surface of platinum reversibly chemisorbs cyanogen (C<sub>2</sub>N<sub>2</sub>) relatively strongly, whereas the (111) surface of platinum interacts with cyanogen only slightly.3 Similar results are found in the adsorption of acetonitrile (CH<sub>3</sub>CN) on nickel metal. Acetonitrile is weakly and reversibly bound by nickel (111) surfaces; 1 or 2 percent irreversible decomposition, probably due to a few step or kink sites, is observed when the acetonitrile is desorbed from these surfaces by heating in high vacuum to approximately 90°C.4 The decomposition is characterized by the evolution of gaseous hydrogen and the retention of carbon and nitrogen on the remaining surface. On the other hand, thermal desorption of acetonitrile from the highly stepped nickel (110) surface requires a slightly higher temperature (about 110°C), and about 90 percent decomposition occurs. Figure 21.4 shows the bonding configurations for acetonitrile (at a terrace site, at a step site, and immediately below a step site) which have been proposed to explain these results. At a terrace site, the C-N bond is believed to be perpendicular to the surface, and the hydrogen atoms do not get close enough to the surface to permit C-N bond cleavage. However, the hydrogen atoms of molecules at or near step sites can interact with the surface and thus lead to irreversible decomposition.

It is interesting, with respect to the study of acetonitrile on nickel surfaces, that methyl isocyanide (CH3NC) is strongly and irreversibly bound to all clean nickel surfaces. It cannot be thermally desorbed except with decomposition and evolution of N2 and H2 gas. This result is perhaps not surprising from studies of molecular complexes. Acetonitrile is known to be a fairly weak  $\sigma$  donor and a weak  $\pi$  acceptor, whereas methyl isocyanide is a strong  $\sigma$  donor and a strong  $\pi$  acceptor. An interesting, but unexplained, fact is that methyl isocyanide chemisorbed on carbon-containing nickel (111) surfaces rearranges on heating and can be thermally desorbed in the form of acetonitrile. Indeed, ordinary Raney nickel Figure 21.5. Infrared absorption band in the C . O streets resign for CO on a Politicity surface at 300

k as a function of increasing coverage. The produced with permission turn 4. (I brindends bidl & M <sup>4</sup> C. M. Friend, J. Stein, and E. L. Muetterties, J. Am. Chem. Soc., 103, 767 (1981).

(prepared by dissolving the aluminum out of an Al-Ni alloy with aqueous alkali) is an effective catalyst for the CH<sub>3</sub>NC → CH<sub>3</sub>CN isomerization.<sup>5</sup>

# EFFECTS OF SURFACE COVERAGE ON ADSORPTION OF CARBON MONOXIDE

The concentration of a species adsorbed in a single layer on a surface is generally expressed in terms of the fractional coverage,  $\theta$ . In principle, the coverage can range from zero (no adsorbed species) to one, corresponding to one adsorbed species per surface atom. Figure 21.5 shows the change in the infrared adsorption

5 Ibid.





Figure 21.5 Infrared absorption band in the C—O stretch region for CO on a Pd(111) surface at 300 K as a function of increasing coverage. [Reproduced with permission from A. M. Bradshaw and F. M. Hoffmann. Surf. Sci., 72, 513 (1978).]



(c)

Figure 21.6 Structural models, based on LEED studies, of CO adsorbed on a Pd(111) surface. (a)  $\theta = 0.33$ ; (b)  $\theta = 0.5$ ; (c)  $\theta =$ 0.63; (d)  $\theta = 0.66$ . Although the spacing and pattern of the CO molecules were determined by LEED, the CO positions relative to the metal atoms were not determined. [Reproduced with permission from T. Engel and G. Ertl, Adv. Catal., 28, 1 (1979).]

band for the C—O stretch as a function of increasing coverage of carbon monoxide on a palladium (111) surface at 300 K.6 At low coverage, the C-O stretch frequency is 1823 cm<sup>-1</sup> and remains constant until about  $\theta = 0.18$ . On further increase in coverage, a very broad band forms whose maximum shifts to higher frequencies. This shift is particularly rapid at  $0.3 < \theta < 0.4$ . Beyond  $\theta =$ 0.41, a relatively narrow band emerges around 1920 cm<sup>-1</sup> and continues to shift to a higher frequency. The 1823 cm<sup>-1</sup> stretch frequency observed at low coverage is believed to correspond to coordination of the CO molecules at threefold coordination sites. This type of coordination is consistent with the results of low-energy electron diffraction (LEED) studies, which show that, at  $\theta = \frac{1}{2}$ , the CO groups are distributed on the surface in a hexagonal pattern, as shown in Fig. 21.6a. An increase in coverage beyond  $\theta = \frac{1}{3}$  causes compression of the unit cell of the adsorbed CO molecules until, at  $\theta = 0.5$ , a more compact pattern of CO molecules is obtained. This compression is connected with an enormous shift in the infrared band, corresponding to the shift of the CO molecules to twofold coordination sites, as shown in Fig. 21.6b. Further increase in coverage is believed to lead to the structure of Fig. 21.6c at  $\theta = 0.63$  and to that of Fig. 21.6d at  $\theta = 0.66$ .

(d)

Different results have been obtained in a study of the adsorption of CO on a rhodium (111) surface.7 The vibrational spectrum of CO as a function of coverage at 300 K is shown in the electron energy loss spectrum of Fig. 21.7. At very low exposures only one C—O stretching peak is observed, at 1990 cm<sup>-1</sup>. This peak is believed to be due to CO groups attached to single metal atoms. The slight gradual shift of this peak to higher frequencies with increasing coverage may be due to a decrease in  $d\pi \to \pi^*$  back bonding because of the increased competi-

<sup>6</sup> A. M. Bradshaw and F. M. Hoffmann, Surf. Sci., 72, 513 (1978).

<sup>&</sup>lt;sup>7</sup> L. H. Dubois and G. A. Somorjai, Surf. Sci., 91, 514 (1980).




Figure 21.7 Energy loss spectrum showing vibrational bands of CO adsorbed on an Rh(111) surface at 300 K as a function of exposure. Note that a Langmuir (L) corresponds to an exposure of the surface to 10-6 torr for a period of 1 s. [Reproduced with permission from L. H. Dubois and G. A. Somorjai, Surf. Sci., 91, 514 (1980).]

tion for electron density among the CO groups. The effect is consistent with the slight shift of the metal-carbon frequency at 480 cm<sup>-1</sup> to lower frequencies with increasing coverage. Such competitive effects have been seen in molecular carbonyl complexes. At higher coverage, a shoulder near 1870 cm<sup>-1</sup> appears. This peak presumably corresponds to bridging CO groups. The vibration spectral data are consistent with LEED studies of the system, which show that, at  $\theta \approx \frac{1}{3}$ , the CO molecules are situated on top of the metal atoms in the hexagonal pattern shown in Fig. 21.8a. The more compact structure seen at  $\theta \approx 0.75$ , in which the CO molecules are in both bridging and nonbridging sites (Fig. 21.8b), is consistent with the vibrational spectra obtained at higher coverages. Note that in




Figure 21.8 Structural representations of CO adsorbed on an Rh(111) surface. (a)  $\theta = 0.33$ ; (b)  $\theta = 0.75$ . [Reproduced with permission from L. H. Dubois and G. A. Somorjai, Surf. Sci., 91, 514 (1980).]

this compact structure the ratio of nonbridging to bridging CO groups is 2:1, in reasonable agreement with the intensity ratio in the high-coverage vibrational spectra.

#### THE FISCHER-TROPSCH PROCESS<sup>8</sup>

In this process, hydrocarbons are synthesized by passing a mixture of hydrogen and carbon monoxide over certain transition-metal surfaces.

$$nCO + (2n + 1)H_2 \rightarrow C_nH_{2n+2} + nH_2O$$

A previously widely accepted mechanism for this reaction involves the generation of a methyl group on the surface, followed by a series of steps in which, in effect, methylene groups are successively inserted between the metal and the alkyl group, thus building up a linear alkyl group. The alkyl group is severed from the metal in a hydrogenation step, thus releasing a product hydrocarbon molecule. The methyl group is presumably formed by the reaction of adsorbed hydrogen atoms (formed by the surface dissociation of  $H_2$ ) with adsorbed CO in a sequence such as the following:

The alkyl-chain growth steps in this mechanism are of the following type,

<sup>&</sup>lt;sup>8</sup> For a general discussion of the mechanistic features, see E. L. Muetterties and J. Stein, *Chem. Rev.*, **79**, 479 (1979), and W. A. Herrmann, *Angew. Chem. Int. Ed.*, **21**, 117 (1982).

and the hydrocarbon production step is presumably as follows:

$$\begin{array}{ccc} R & \xrightarrow{H_2} & H + RH \\ & & & & \end{array}$$

This mechanism derived some credibility from the fact that the various proposed steps have known analogs in homogeneous organometallic reactions.

However, both x-ray and ultraviolet photoelectron spectroscopy have shown that carbon monoxide is dissociated to surface carbide and oxide atoms on some metal surfaces. For example, consider the oxygen 1s spectra of CO on tungsten shown in Fig. 21.9.9 The data indicate that CO is adsorbed molecularly at 100 K,

<sup>9</sup> J. T. Yates, Jr., T. E. Madey, and N. E. Erickson, Surf. Sci., 43, 257 (1974).




Figure 21.9 X-ray photoelectron spectrum of CO on tungsten, showing oxygen 1s photolines. Binding energy increases from right to left; lower binding energies correspond to a more negative charge. (a) Clean tungsten; (b) CO adsorbed at 100 K; (c) same as (b) after warming to 320 K for 30 s; (d) CO adsorbed at 300 K. Peaks  $\alpha_1$  and  $\alpha_2$  correspond to nonbridging CO molecules, V to bridging CO molecules and  $\beta$  to oxide ions on the surface (i.e., dissociated CO). A peak with the same binding energy as  $\beta$ -CO is obtained for oxygen adsorbed on W. [Reproduced with permission from J. T. Yates, Jr., T. E. Madey, and N. E. Erickson, Surf. Sci., 43, 257 (1974).]

but that, on warming, the oxygen atoms become directly bonded to the metal surface and acquire a more negative charge than they have in the undissociated CO groups. The relative ease with which various metal surfaces break the C-O bond of carbon monoxide can be related to the stability of the corresponding metal carbides. Thus tungsten and molybdenum dissociate CO below 170 K, whereas metals with thermally unstable carbides, such as iron and nickel, dissociate CO between 300 and 420 K, and adsorption on the platinum metals (most of which do not form carbides) is mainly nondissociative. On this basis it has been proposed that CO dissociation is involved in Fischer-Tropsch synthesis.10 It is proposed that adsorbed hydrogen atoms convert the oxygen atoms to water, which is desorbed, and convert the carbon atoms to CH or CH, groups, which undergo polymerization, perhaps as follows.11

This mechanism provides an explanation of the relative activities of metals in Fischer-Tropsch synthesis. On iron, the CO is expected to be completely dissociated at synthesis temperature. The concentration of CH<sub>2</sub> groups is therefore high and, in agreement with observations, formation of higher hydrocarbons is facilitated. On nickel, CO dissociation is more difficult. Thus the concentration of CH<sub>2</sub> is expected to be lower, and in agreement with observation, hydrogenation, with formation of methane, predominates. On tungsten and molybdenum, which are poor Fischer-Tropsch catalysts, the carbide species are probably too stable to be easily hydrogenated.

It has been observed that diazomethane, CH<sub>2</sub>N<sub>2</sub>, reacts on metal surfaces to give mainly ethylene, together with nitrogen. Presumably the ethylene forms by the simple dimerization of CH2 groups:

However, when a mixture of hydrogen and diazomethane is passed over Co, Fe, and Ru, a linear hydrocarbon mixture, similar to that produced in the Fischer-Tropsch synthesis, is obtained. These data give strong support to a mechanism involving the dissociation of CO and the formation of adsorbed CH2 groups. It is interesting that this mechanism is essentially the same as that proposed by Fischer and Tropsch in 1926.12

The oil crisis of the 1970s has caused chemists to seek chemical raw materials from sources other than petroleum. The Fischer-Tropsch process could compete with petroleum if (1) the process selectivity were improved (i.e., if high relative yields of particular hydrocarbons, rather than a broad spectrum of hydrocarbons, could be obtained), (2) crude oil were to become even scarcer, and (3) coal were to

<sup>10</sup> R. W. Joyner, J. Catal., 50, 176 (1977).

R. C. Brady and R. Pettit, J. Am. Chem. Soc., 102, 6181 (1980).

<sup>12</sup> F. Fischer and H. Tropsch, Brennst.-Chem., 7, 97 (1926).

become relatively inexpensive.<sup>13</sup> Considerable effort is being expended to improve the efficiency and selectivity of the process.

## ZIEGLER-NATTA OLEFIN POLYMERIZATION<sup>14</sup>

The Ziegler-Natta process for the polymerization of olefins uses a catalyst formed from TiCl<sub>4</sub> and AlEt<sub>3</sub>. The AlEt<sub>3</sub> reduces the TiCl<sub>4</sub> to a fibrous form of TiCl<sub>3</sub> and replaces some of the surface chlorine atoms with ethyl groups. The rate of polymerization is proportional to the total amount of TiCl<sub>3</sub> and the pressure of the olefin and is independent of the AlEt<sub>3</sub> concentration. A critical step in the process is believed to be the interposition of an olefin molecule between the titanium atom and an alkyl group. This step requires a titanium-alkyl bond and the possibility of coordinating the olefin. The simplest configuration meeting these requirements is an essentially octahedrally coordinated titanium atom at a surface step site, coordinated to only four chlorine atoms. A fifth octahedral site is occupied by an alkyl group, and the sixth site is available for the olefin. The olefin forms a  $\sigma$  bond to the metal using its filled  $\pi$  orbital. In a concerted step, the alkyl group breaks its bond to the metal and forms a bond to one of the olefin carbon atoms, as the other olefin carbon atom becomes attached to the metal. The process is shown in the following scheme:

When propylene undergoes Ziegler-Natta polymerization, dense, highly stereoregular polymers are obtained, in contrast to the low-density, branched polymers obtained by free-radical processes. It is assumed that, because of the nonequivalence of the coordination sites of olefin and alkyl group at the active titanium

<sup>&</sup>lt;sup>13</sup> The latter two conditions were met in Germany during World War II and are currently met in South Africa and Australia.

<sup>14</sup> P. Cossee, J. Catal., 3, 80 (1964); E. J. Arlman and P. Cossee, J. Catal., 3, 99 (1964).

center, the growing alkyl group moves back to its original position after each insertion of a new monomer. Thus the polymerization consists of a sequence of sterically identical steps which lead to stereoregularity in the product.

### AMMONIA SYNTHESIS<sup>15</sup>

The synthesis of ammonia from nitrogen and hydrogen is one of the most important processes of chemical industry; tens of millions of tons of ammonia are produced annually throughout the world. Practically all ammonia is made by the Haber process, in which the synthesis is carried out on "promoted" iron catalysts (i.e., iron containing a few percent of oxides such as Al<sub>2</sub>O<sub>3</sub>, K<sub>2</sub>O, and CaO) at pressures around 300 atm and temperatures near 500°C.

In addition to surface reaction steps in which N—H bonds are formed, the following surface reaction steps must be considered in the Haber process<sup>15</sup>:

$$H_2 \iff 2H_{(ad)}$$
 $N_2 \iff N_{2(ad)}$ 
 $N_2 \iff 2N_{(ad)}$ 
 $NH_{3(ad)} \iff NH_3$ 

The (ad) subscripts refer to metal-adsorbed species. There has been considerable controversy as to whether the initial N—H bond formation involves the reaction of molecular nitrogen or the reaction of atomic nitrogen. If  $N_{2(ad)}$  were the reacting species, then the surface would become essentially saturated with  $N_{(ad)}$  under steady-state reaction conditions (at least under conditions far from  $2NH_3 \rightleftharpoons N_2 + 3H_2$  equilibrium, at low ammonia pressures). Photoelectron spectroscopic studies of the catalyst surface under such conditions show that the  $N_{(ad)}$  concentration is far below the saturation value. Hence it is believed that  $NH_3$  is formed on the surface by a sequence starting with nitrogen atoms:

$$N_{(ad)} \xrightarrow{H_{(ad)}} NH_{(ad)} \xrightarrow{H_{(ad)}} NH_{2(ad)} \xrightarrow{H_{(ad)}} NH_{3(ad)}$$

When the hydrogen pressure is not high, the reaction rate is independent of the hydrogen pressure and is first order in nitrogen. That is, the dissociative adsorption of nitrogen is the rate-determining step. At higher hydrogen pressures, the reaction rate is of a fractional order in hydrogen, corresponding to a partial shifting of the rate-determining step to the  $N_{(ad)} + H_{(ad)} \rightarrow NH_{(ad)}$  step. Hence the critical steps of the reaction mechanism are

$$N_2 \implies N_{2(ad)} \implies 2N_{(ad)}$$

and

$$N_{(ad)} + H_{(ad)} \iff NH_{(ad)}$$

<sup>15</sup> G. Ertl, Catal. Rev., 21, 201 (1980).




Figure 21.10 Potential energy diagram for ammonia synthesis on an iron surface (lower curve) and via gas-phase radicals (upper dashed lines). Energy values in kilocalories per mole. [Adapted from G. Ertl, Catal. Rev., 21, 201 ((1980).]

The overall potential energy diagram for the reaction on an iron surface is schematically shown in Fig. 21.10. Obviously if the reaction proceeded through gas-phase species such as N and H, the activation energy for the reaction would be enormous. The catalyst provides a surface which greatly stabilizes the atomic and radical species and allows the reaction to proceed with no large energy barrier.

### ELECTRODE SURFACE MODIFICATION

The kinetic properties of electrodes are directly related to the chemical and structural features of their surfaces. Thus electrode properties can be controlled by suitable chemical modification of their surfaces.

In Chap. 13 we discussed how light can be used to drive redox reactions at the junction between a semiconductor and a solution. However, semiconducting photoanode materials are susceptible to oxidative decomposition when photogenerated holes rise to the top of the valence band. That is, the semiconductor

itself may be oxidized. Thus ordinary n-type silicon photoanodes develop an insulating coat of oxide on their surface when exposed to light and are useless for any practical photooxidation. However, it has been found that the silicon surface can be stabilized by covering the surface with ferrocene groups.16 This is accomplished by the reaction of a compound such as trichlorosilylferrocene with the surface hydroxyl groups that are present on the normal air-oxidized surface of silicon:

This ferrocene derivatization causes a dramatic improvement in the photoanode durability. The derivatized silicon can photooxidize anything oxidizable by the ferricenium ion. For example, the photooxidation of ferrocyanide can proceed continuously by the following cycle:

It is hoped that further study of derivatized photoelectrodes may lead to an improved photoelectrolytic system for deriving energy from sunlight.

The development of an electrode at which the reduction of molecular oxygen to water proceeds at the reversible potential (1.23 V versus the standard hydrogen electrode) would constitute a major advance in fuel cell technology. Present acid electrolyte oxygen cathodes made of platinum are expensive and produce useful current densities only at overpotentials of several hundred millivolts. Some encouraging results toward the development of an efficient oxygen cathode have been obtained by adsorbing on a graphite surface dimeric cobalt porphyrin molecules in which the two porphyrin rings are constrained to lie parallel to one another.<sup>17</sup> The complex shown in Fig. 21.11 has been found to catalyze the reduction of oxygen to water very effectively. There is little doubt that this complex functions by binding the O2 molecule jointly to the two cobalt atoms during the four-electron reduction process. A plausible mechanism is shown in Fig. 21.12.

<sup>17</sup> J. P. Collman, P. Denisevich, Y. Konai, M. Marrocco, C. Koval, and F. C. Anson, J. Am. Chem. Soc., 102, 6027 (1980).

<sup>&</sup>lt;sup>16</sup> A. B. Bocarsly, E. G. Walton, and M. S. Wrighton, J. Am. Chem. Soc., 102, 3390 (1980); M. S. Wrighton, Chem. Eng. News, 29-47 (Sept. 3, 1979).




Figure 21.11 Structure of the dimeric cobalt-porphyrin complex which, when adsorbed on graphite, acts as an effective catalyst for the reduction of O<sub>2</sub> to H<sub>2</sub>O. [Adapted from J. P. Collman, P. Denisevich, Y. Konai, M. Marrocco, C. Koval, and F. C. Anson, J. Am. Chem. Soc., 102, 6027 (1980).]




Figure 21.12 Proposed mechanism of the electrode surface-catalyzed reduction of O<sub>2</sub> to H<sub>2</sub>O. [Reproduced with permission from J. P. Collman et al., J. Am. Chem. Soc., 102, 6027 (1980). Copyright 1980 American Chemical Society.]

## CATALYSIS BY METAL CLUSTERS

Metal cluster compounds are obviously intermediate in character between mononuclear molecular complexes and metals. A question of considerable interest is: Can cluster compounds be used as valid models of metal surfaces with chemisorbed ligands?18 It has been shown that some ligands can interact with clusters in ways that are unknown with monomeric complexes. For example, acetonitrile reacts with either Fe<sub>2</sub>(CO)<sub>8</sub><sup>2-</sup> or HFe<sub>3</sub>(CO)<sub>11</sub><sup>-</sup> to form a mixture of Fe<sub>3</sub>(CH<sub>3</sub>C=NH)(CO)<sub>9</sub> and Fe<sub>3</sub>(N=CHCH<sub>3</sub>)(CO)<sub>9</sub>, which undergo the interconversion reactions shown in the following scheme:19


<sup>&</sup>lt;sup>18</sup> E. L. Muetterties, T. N. Rhodin, E. Band, C. F. Brucker, and W. R. Pretzer, Chem. Rev., 79, 91 (1979); J. F. Hamilton and R. C. Baetzold, Science, 205, 1213 (1979). <sup>19</sup> M. A. Andrews and H. D. Kaesz, *J. Am. Chem. Soc.*, **101**, 7238 (1979).

Of particular interest is the fact that  $HFe_3(CO)_9N$ = $CHCH_3$  readily reacts with either  $H_2$  or CO at room temperature to form complexes containing the ethylimido group,  $CH_3CH_2N$ . Unfortunately attempts to displace ethylamine from these complexes leads to decomposition of the cluster to iron metal. However, the reactions do show that several metal atoms acting in concert can lead to the reduction of nitriles. Thus the system probably serves as a rough model for what happens at the surface of the iron catalysts that actually catalyze the hydrogenation of nitriles.

Treatment of the square pyramidal complex  $Fe_5C(CO)_{14}^{2-}$  with hydrogen chloride leads to the formation of  $HFe_4(CH)(CO)_{12}$ , a butterfly  $Fe_4$  cluster with an  $\eta^2$ -CH group spanning the terminal Fe atoms.<sup>20</sup>

$$Fe_5C(CO)_{14}^{2-} + 4HCl \rightarrow HFe_4(CH)(CO)_{12} + 2CO + FeCl_2 + 2Cl^- + H_2$$

The latter complex can be reversibly deprotonated to give  $Fe_4C(CO)_{12}^{2-}$ . Oxidation of  $Fe_4C(CO)_{12}^{2-}$  with  $AgBF_4$  in the presence of  $H_2$  re-forms  $HFe_4(CH)(CO)_{12}$  by a process that may involve oxidative addition of hydrogen to an  $Fe_4C(CO)_{12}$  intermediate. This conversion of a carbide atom in a metal cluster to a CH group is a formal analog of a proposed step in Fischer-Tropsch reactions. The reactions are summarized in the following scheme.




In another study of the Fe<sub>n</sub>C cluster system,<sup>21</sup> it has been shown that the octahedral complex Fe<sub>6</sub>C(CO)<sub>16</sub><sup>2-</sup> is oxidized by tropylium bromide in methanol

to give the complex  $Fe_4(CO)_{12}CCO_2CH_3$ , in which the  $C-C-OCH_3$  group bridges the terminal iron atoms of an  $Fe_4$  butterfly cluster. This complex, in turn, original  $Fe_6C(CO)_{16}^{2-}$  complex. A proposed mechanism for the processes is shown in the following scheme.

<sup>&</sup>lt;sup>20</sup> M. Tachikawa and E. L. Muetterties, *J. Am. Chem. Soc.*, **102**, 4541 (1980); M. A. Beno, J. M. Williams, M. Tachikawa, and E. L. Muetterties, *J. Am. Chem. Soc.*, **102**, 4542 (1980).

<sup>&</sup>lt;sup>21</sup> J. S. Bradley, G. B. Ansell, and E. W. Hill, *J. Am. Chem. Soc.*, **102**, 4342 (1960). Eng. News, 27 (April 28, 1980); J. S. Bradley, G. B. Ansell, M. E. Leonowicz, and E. W. Hill, *J. Am. Chem. Soc.*, **103**, 4968 (1981).



Oxidation of the octahedral cluster removes two adjacent iron atoms from the cluster, exposing the central carbon atom. Carbon monoxide, formed in the oxidation reaction, presumably reacts with the exposed carbon atom, and then reaction with the methanol solvent gives the methyl ester fragment. Regenerating the cluster in its active form requires addition of an oxidizing agent, so the cycle cannot be considered catalytic. However, the process essentially involves the synthesis of an organic molecule from CO and  $H_2$  and thus is analogous to the Fischer-Tropsch process.

We have already pointed out that the steps

$$CH_3 \Longrightarrow H CH_2 \Longrightarrow H H C$$

are probably important in metal-catalyzed processes such as the Fischer-Tropsch synthesis. Steps of this type have actually been observed<sup>22</sup> in a reversible equilibrium between  $Os_3(\mu-H)(\mu-CH_3)(CO)_{10}$  and  $Os_3(\mu-H)_2(\mu-CH_2)(CO)_{10}$  and the conversion of these compounds to  $Os_3(\mu-H)_3(\mu_3-CH)(CO)_9$ :

$$(CO)_{4}$$

$$Os$$

$$Os$$

$$H_{3}$$

$$CO)_{3}Os$$

$$H_{4}$$

$$H_{2}$$

$$CO)_{3}Os$$

$$H_{2}$$

$$H_{2}$$

$$H_{2}$$

$$H_{2}$$

$$COs(CO)_{3}$$

$$H_{3}$$

$$COs(CO)_{3}$$

$$H_{4}$$

$$COs(CO)_{3}$$

$$H_{5}$$

$$COs(CO)_{3}$$

$$H_{7}$$

$$COs(CO)_{3}$$

$$H_{7}$$

$$COs(CO)_{3}$$

Thus we have a model of the process by which C—H bonds break at metal surfaces.

The study of cluster compounds suggests that the main advantage of clusters as catalysts will be their ability to provide novel molecular transformations because of the unique coordination environments provided by the metal atoms. In any case, it is clear that clusters do provide analogs for structures and processes that have been postulated in surface catalysis.

## Oxidation of the octahedral chater removes two adjunent from SMSHBORN

- 21.1 Carbon dioxide adsorbed on an Rh (111) surface gives essentially the same electron energy loss spectrum as carbon monoxide adsorbed on the same surface. Both systems show absorption in the C—O stretching region. What can you say with respect to the nature of the adsorption of CO<sub>2</sub>?
- \*21.2 Copper metal has an interatomic distance of 2.55 Å. Calculate the surface concentration of atoms (in atoms per square centimeter) on the (111), (100), and (110) crystal faces.
- 21.3 List several reasons why discrete metal cluster complexes are (a) good analogs of catalytic metal surfaces and (b) poor analogs of such surfaces.
- 21.4 Why would you expect platinum to be a poor catalyst for the Haber process?

# TWENTY-TWO

## SOME BIOLOGICAL SYSTEMS

Metallobiomolecules are natural products which contain one or more metallic elements. A classification scheme for some of the more extensively studied metallobiomolecules is given in Fig. 22.1.<sup>1</sup> These molecules are complex coordination compounds whose metal-containing sites (the "active sites") are usually involved in electron transfer, the binding of exogenous molecules, and catalysis. The comparative study of these sites and analogously structured synthetic coordination compounds is the main part of the interdisciplinary field of bioinorganic chemistry. In this chapter we shall describe just a few of the many bioinorganic systems that have been studied in recent years.

### METALLOPORPHYRINS AND RELATED SYSTEMS

The porphyrin ligands have the general structure shown in Fig. 22.2; they are derivatives of porphine (the compound in which all the R groups are hydrogen atoms). The most commonly used synthetic porphyrins are octaethylporphyrin ( $R_p = C_2H_5$ ,  $R_m = H$ ) and tetraphenylporphyrin ( $R_m = C_6H_5$ ,  $R_p = H$ ). Many metalloporphyrins are known, in which the two protons bonded to the pyrrole nitrogen atoms have been removed and in which a metal ion is coordinated to the four nitrogen atoms. These compounds are important because many natural

J. A. Ibers and R. H. Holm, Science, 209, 223 (1980).




Figure 22.1 Partial classification of metallobiomolecules in terms of biological function. Only a few examples of each class are given. [Reproduced with permission from J. A. Ibers and R. H. Holm, Science, 209, 223 (1980).]

Figure 22.2 The porphyrin skeleton. Note that there are two main types of substituents—those on the pyrrole rings  $(R_p)$  and those in the intermediate, meso, positions  $(R_m)$ . The parent nucleus, porphyrin, corresponds to  $R_p = R_m = H$ .

products (e.g., chlorophylls, hemes, cytochromes, and vitamin B<sub>12</sub>) contain similar groups.

### Hemoglobin and Myoglobin<sup>2</sup>

The proteins hemoglobin and myoglobin serve to transport and to store oxygen, respectively. These are life functions essential to all vertebrates. The active site in both proteins is the planar heme group (Fig. 22.3) embedded in a convoluted protein chain (globin), with a coordinate bond between the iron atom and the nitrogen atom of the imidazole side chain of a histidine residue (the "proximal" histidine). Myoglobin, shown in Fig. 22.4, consists of one globin and one heme group. Hemoglobin consists of four myoglobinlike subunits, with two of the globins somewhat different from the other two. In each subunit, an oxygen molecule can bond to the iron atom on the side of the porphyrin opposite the proximal histidine, thus forming a hexacoordinate iron complex.

Hemoglobin carries oxygen via the circulatory system from the lungs to tissues. There the oxygen can be transferred to myoglobin, where it is stored until

<sup>2</sup> M. F. Perutz, Sci. Am., 239, 92 (December 1978); N. M. Senozan and R. L. Hunt, J. Chem. Educ., 59, 173 (1982).

$$H_3C$$
 $H_2C$ 
 $CO_2^ CO_2^ CH_2$ 
 $CH_2$ 
 $CH_3$ 
 $CH_3$ 
 $CH_3$ 
 $CH_3$ 

Figure 22.3 The heme group.




Figure 22.4 A schematic representation of the myoglobin molecule. Note the heme unit attached to the chain near residue 40.




Figure 22.5 The oxygen-binding curves for myoglobin (Mb) and hemoglobin (Hb), showing the pH dependence for the latter. (Reproduced with permission from F. A. Cotton and G. Wilkinson, "Advanced Inorganic Chemistry," 4th ed., Wiley-Interscience, New York, 1980.)

hemoglobin is the cooperative (or "autocatalytic") nature of its O<sub>2</sub> binding. The effect of this cooperativity can be seen in the oxygen-binding curves of Fig. 22.5. At high oxygen concentrations, hemoglobin and myoglobin bind O<sub>2</sub> approximately equally strongly. However, at low oxygen concentrations, such as in muscle tissue during or immediately after muscular activity, hemoglobin is a poorer oxygen binder and therefore can pass its oxygen on to myoglobin. The difference in O<sub>2</sub>-binding ability between myoglobin and hemoglobin is accentuated at low pH values; hence the transfer from hemoglobin to myoglobin has a greater driving force where it is most needed, viz., in tissues where oxygen has been converted to CO<sub>2</sub>.

The oxygen-binding curve of hemoglobin indicates that the four subunits of hemoglobin do not act independently: they somehow communicate with each other. When one heme group reacts with an  $O_2$  molecule, the other three show an increased ability to react with  $O_2$  molecules. Thus hemoglobin behaves somewhat as if it could combine either with four oxygen molecules or none at all:

$$Hb + 4O_2 \implies Hb(O_2)_4$$

It is generally believed that coordination of an oxygen molecule to the 5-coordinate iron(II) in a deoxy heme causes conformational changes within the protein which affect the ability of the other heme groups to combine with oxygen. This is the basis of the "allosteric" theory, which explains heme-heme interaction without postulating any direct communication between the heme groups. The hemoglobin molecule is believed to have two alternative structures, designated T for "tense" and R for "relaxed," which favor the deoxygenated and oxygenated states, respectively. These structures are very similar but differ significantly in the bonding both between subunits and within subunits. These structural changes are closely integrated and occur in a concerted action.

In both structures, the four subunits are held together in essentially a tetrahedral arrangement by hydrogen bonds and "salt bridges." (A salt bridge is an electrostatic bond between a quaternary nitrogen atom, with a positive formal charge, and an oxygen atom with a negative formal charge.) In the transition from the T structure to the R structure, one pair of subunits rotates by 15° relative to the other pair of subunits, and various groups within each subunit shift position so as to favor the coordination of molecular oxygen. The rearrangement of the subunits involves changes in hydrogen bonding and salt bridging. There are more salt bridges in the T structure than in the R structure. Thus the salt bridges explain the influence of protons (and  $CO_2$ ) on the oxygen-binding curve. The addition of protons favors the formation of the T state and lowers the oxygen affinity of hemoglobin by increasing the number of quaternary, positively charged, nitrogen atoms which can form salt bridges. Conversely, the transition from the R structure to the T structure brings negatively charged oxygen atoms

<sup>&</sup>lt;sup>3</sup> M. F. Perutz, op. cit.; D. K. White, J. B. Cannon, and T. G. Traylor, *J. Am. Chem. Soc.*, **101**, 2443 (1979); F. Basolo, B. M. Hoffman, and J. A. Ibers, *Acc. Chem. Res.*, **8**, 384 (1975).




Figure 22.6 A schematic representation of the equilibrium between the T and R structures of hemoglobin. The straight lines joining subunits represent salt bridges; the wavy lines represent weakened salt bridges. [Adapted from M. F. Perutz, Sci. Am., 239, 92 (December 1978).]

into proximity with nitrogen atoms and thus favors the protonation of these nitrogen atoms. A schematic representation of the transition from the T structure to the R structure is shown in Fig. 22.6. The salt bridges linking the subunits in the T structure break progressively as oxygen is coordinated, and even salt bridges that have not yet broken are weakened, a situation represented in Fig. 22.6 by wavy lines. The  $T \longrightarrow R$  transition does not take place after a fixed number of oxygen molecules have been bound, but it becomes more probable with each additional oxygen molecule bound.

Perutz has postulated that a change in configuration of the heme group upon coordination of an oxygen molecule triggers interconversion of the T and R structures. In the deoxy form, the high-spin iron(II) atom is 5-coordinate and is situated between the plane of the porphyrin and the coordinated nitrogen atom. Upon oxygenation the iron atom, which is variously thought to be Fe(II) or Fe(III), becomes low-spin (and of smaller size), and it is believed to move into the plane of the porphyrin. This stereochemical change is illustrated in Fig. 22.7. Perutz proposes that the iron atom is held in a tense 5-coordinate state by the




Figure 22.7 Illustration of the movement of the proximal histamine upon coordination of oxygen to the iron atom of the heme group in hemoglobin.

protein and that this tension is released upon oxygenation. The change in coordination triggers relaxation throughout the subunit, and the movement is transmitted to salt bridges. Recent studies indicate that it may be more appropriate to look upon the tension of the T state as a set of small strains in many bonds. Indeed, other workers propose that the T structure should be characterized by restraint rather than tension. The restraint may consist of steric repulsion which prevents the proximal histidine from approaching the iron atom with an orientation favorable for bonding. Transition to the R structure presumably involves rearrangements which allow the iron atom to move toward the porphyrin and to bind oxygen. Nevertheless, in spite of uncertainties about the mechanism, it is certain that the change in coordination geometry at the iron atom plays an important part in the cooperativity phenomenon of hemoglobin.

It is interesting to note that the reactions of hemoglobin with protons when it liberates oxygen explain how hemoglobin aids the transport of CO<sub>2</sub> to the lungs. About two protons are taken up for every four molecules of oxygen released, and two protons are released again when four molecules of oxygen are absorbed. The CO<sub>2</sub> released in tissues is too insoluble to be transported entirely as such, but it can be solubilized by conversion to bicarbonate. Thus the reaction occurring during the release of oxygen by hemoglobin can be roughly represented as follows.

$$Hb(O_2)_4 + 2CO_2 + 2H_2O \implies H_2Hb^{2+} + 2HCO_3^- + 4O_2$$

Considerable effort has been expended in attempts to synthesize model compounds which mimic the oxygen-carrying properties of the heme group in natural proteins. The main problem in such work has been the fact that oxygen reacts irreversibly with simple iron-porphyrin systems to form binuclear iron(III) oxides of the following type.

One strategy has been to inhibit this irreversible oxidation by preparing porphyrins which have a protective enclosure for binding oxygen on one side of the porphyrin ring, with the other side protected by a bulky axially coordinated nitrogen base. Two examples of this type which have been intensively studied are the "picket-fence" and "capped" porphyrins, shown in Figs. 22.8 and 22.9, respectively. Another example, the "doubly bridged" porphyrin, is shown in

<sup>&</sup>lt;sup>4</sup> J. M. Hopfield, J. Mol. Biol., 77, 207 (1973).

<sup>&</sup>lt;sup>5</sup> J. P. Collman, Acc. Chem. Res., 10, 265 (1977); M. F. Perutz, op. cit.

<sup>&</sup>lt;sup>6</sup> J. P. Collman, Acc. Chem. Res., 10, 265 (1977); J. P. Collman et al., J. Am. Chem. Soc., 102, 4182 (1980).

<sup>&</sup>lt;sup>7</sup> J. R. Budge, P. E. Ellis, R. D. Jones, J. E. Linard, F. Basolo, J. E. Baldwin, and R. L. Dyer, *J. Am. Chem. Soc.*, **101**, 4760 (1979); R. D. Jones, D. A. Summerville, and F. Basolo, *Chem. Rev.*, **79**, 139 (1979).

<sup>&</sup>lt;sup>8</sup> A. R. Battersby and A. D. Hamilton, J. Chem. Soc. Chem. Commun., 117 (1980).

Figure 22.8 A picket-fence porphyrin with an appended imidazole base. [Reproduced with permission from J. P. Collman, Acc. Chem. Res., 10, 265 (1977). Copyright 1977 American Chemical Society.]




Figure 22.9 Schematic representation of the capped porphyrin (x = 2 or 3). [Reproduced with permission from Budge et al., J. Am. Chem. Soc. 101, 4762 (1979). Copyright 1979 American Chemical Society.]





Figure 22.10 A porphyrin with an anthracene bridge across one face and a pyridine bridge across the other. The corresponding Fe(II) metalloporphyrin has the hemoglobinlike properties described in the text. [Reproduced with permission from A. R. Battersby and A. D. Hamilton, J. Chem. Soc. Chem. Commun., 117 (1980).]

Fig. 22.10. The latter compound has not received the attention it probably deserves. It is a fairly good analog of a natural heme group because it possesses the following features: (1) a hydrophobic pocket for the O<sub>2</sub> molecule, (2) no substituents at the four meso positions of the porphyrin, (3) a basic fifth ligand covalently bound to the porphyrin, (4) the ability to bind oxygen readily and reversibly, and (5) the ability to bind carbon monoxide reversibly. Incidentally, the poisonous character of carbon monoxide is due to its ability to displace oxygen from its site in the heme group. In the blood of heavy smokers, as much as 20 percent of the oxygen sites can be blocked by carbon monoxide.

The irreversible oxidation of simple iron porphyrin systems, although fast, is slower than the oxygenation step. Thus a second strategy for the study of model heme compounds is the use of fast reaction and fast spectroscopy methods. In a typical flash photolysis study, a mixture of  $O_2$  and  $O_3$  is equilibrated with a solution of a heme model compound. Under these conditions, the compound is almost entirely in the form of the heme  $O_3$  complex. A short laser pulse causes complete dissociation of this complex, and the deoxy heme then reacts with  $O_3$  at a high, but measurable, rate. Subsequently, the heme  $O_3$  complex dissociates and is reconverted to the heme  $O_3$  complex. These reactions can be followed by fast ultraviolet-visible spectroscopy.

#### Vitamin B<sub>12</sub>10

This compound and its derivatives are cobalt complexes with the general structure shown in Fig. 22.11. In the isolated vitamin, R is a cyanide ion. However, in vivo, the cyanide ion is not present, and X is probably a loosely bound water molecule. In both the cyano and aquo forms of the vitamin, the cobalt is present in the +3 oxidation state. The cobalt(III) can be reduced to cobalt(II) (vitamin  $B_{12r}$ ) by catalytic hydrogenation, by treatment with chromium(II) acetate at pH 5, or by controlled potential electrolysis. Further reduction to cobalt(I) (vitamin  $B_{12s}$ ) is effected by treatment with chromium(II) acetate at pH 9.5, with zinc dust in aqueous ammonium chloride, or with sodium borohydride. In vitamin  $B_{12s}$ , the R site is vacant, and the 5-coordinate cobalt(I) atom is extremely reactive. Some of the reactions of vitamin  $B_{12s}$  are summarized in the following scheme:



Vitamin  $B_{12s}$  may be intimately involved in biological functions, where it can act as a methyl-transfer agent (e.g., in the biosynthesis of methionine) or as a reducing agent (e.g., in the reduction of ribose).

The reaction of adenosine triphosphate with vitamin  $B_{12s}$  forms a cobalt-carbon bond, as shown in Fig. 22.12. The resulting molecule is known as vitamin  $B_{12}$  coenzyme and was the first organometallic compound discovered in living systems. This coenzyme is required in various biological processes, but the detailed mechanisms of these processes are unknown. Many of these processes are 1,2 rearrangements in which a group X and an H atom exchange positions:

<sup>&</sup>lt;sup>10</sup> B. M. Babior, Acc. Chem. Res., **8**, 376 (1975); R. H. Abeles and D. Dolphin, Acc. Chem. Res., **9**, 114 (1976).

$$\begin{array}{ccc}
 & H & H \\
 & C - C & \Longrightarrow & C - C \\
 & X & X & X
\end{array}$$

The nature of the group X is highly variable; it may be a complex alkyl [e.g., CH(NH<sub>2</sub>)COOH] or acyl (COR) group, or a relatively simple nucleophilic group (e.g., OH or NH<sub>2</sub>). For example, in conjunction with glutamate mutase, the

Figure 22.11 General structure of vitamin B<sub>12</sub> and its derivatives.

Figure 22.12 Schematic structure of vitamin B<sub>12</sub> coenzyme, showing the group coordinated at the R site.

following reaction is catalyzed:

One possible mechanism of the hydrogen transfer in such reactions is shown in the following scheme.<sup>11</sup>

$$\begin{array}{c}
R \\
CH_2 \\
CO^{II}
\end{array}
\longrightarrow
\begin{array}{c}
RCH_2 \cdot \\
\cdot CO^{II}
\end{array}
\longrightarrow
\begin{array}{c}
Substrate-H \\
\cdot CO^{II}
\end{array}
\longrightarrow
\begin{array}{c}
RCH_3 \\
+ substrate \cdot \\
\cdot CO^{II}
\end{array}$$

Here RCH<sub>2</sub> represents the adenosyl group of the coenzyme. An enzyme-catalyzed cleavage of the carbon-cobalt bond gives cobalt(II) and the adenosyl radical. The radical then abstracts the hydrogen atom from the enzyme-bound substrate molecule to form adenosine and the substrate radical. After migration of the group X on the substrate radical, the rearranged radical retrieves a hydrogen atom from the adenosine to give the product molecule and thus completes the catalytic cycle. Little is known about the mechanism of the migration of group X; current research focuses on elucidating this step.

Certain relatively simple cobalt complexes, such as bis(dimethylglyoximato)-cobalt complexes,

Babior, op. cit; for another mechanism, see R. Hamilton, T. R. B. Mitchell, E. A. McIlgorm, J. J. Rooney, and M. A. McKervey, J. Chem. Soc. Chem. Commun., 686 (1981).

mimic many of the reactions of vitamin B<sub>12</sub>. 12 The cobalt atom exhibits four oxidation states, Co(I), Co(II), Co(III), and Co(IV). The monovalent species, in analogy to vitamin B<sub>12s</sub>, is a strong nucleophile that undergoes Michael additions and nucleophilic displacements to give complexes with alkyl groups directly bonded to cobalt(III). It is hoped that the study of such model complexes will, by the use of analogy, clarify the reactions of vitamin B<sub>12</sub>.

#### IRON-SULFUR PROTEINS AND NITROGEN FIXATION<sup>13</sup>

The iron-sulfur proteins have relatively low molecular weights and contain iron atoms tetrahedrally coordinated to sulfur atoms. Representative structures of the iron-sulfur centers in these proteins are pictured in Fig. 22.13. The proteins containing single iron atoms coordinated tetrahedrally by four mercapto sulfur atoms are called "rubredoxins." The proteins containing two-iron and four-iron clusters are called "ferredoxins." Both rubredoxins and ferredoxins can be oxidized and reduced; they function as electron carriers in a wide variety of biological systems. The ferredoxin from Micrococcus aerogenes contains two cubic Fe<sub>4</sub>S<sub>4</sub> groups connected to a protein chain with a very complicated conformation, 14 as shown in Fig. 22.14. The four tetrahedrally arranged iron atoms in each Fe<sub>4</sub>S<sub>4</sub> cluster are connected to the protein by four more sulfur atoms which are in cysteine groups.15

The complex Fe<sub>4</sub>S<sub>4</sub>(SCH<sub>2</sub>Ph)<sub>4</sub><sup>2-</sup>, which has the structure shown in Fig. 22.15, is a synthetic ferredoxin analog.16 This complex is synthesized by the reaction of

<sup>12</sup> G. N. Schrauzer, Angew. Chem. Int. Ed., 15, 417 (1976); 16, 223 (1977); R. M. Magnuson, J. Halpern, I. Y. Levitin, and M. G. Vol'pin, Chem. Commun., 44 (1978); J. Topich and J. Halpern, Inorg. Chem., 18, 1339 (1979).

<sup>13</sup> W. Lovenberg, ed., "Iron-Sulfur Proteins," vols. 1-3, Academic, New York, 1973, 1977.

14 K. T. Yasunobu and M. Tanaka, in "Iron-Sulfur Proteins," W. Lovenberg, ed., vol. 2, chap. 2, Academic, New York, 1973.

<sup>15</sup> L. C. Sieker, E. Adman, and L. H. Jensen, *Nature*, 235, 40 (1972).

<sup>16</sup> T. Herskovitz, B. A. Averill, R. H. Holm, J. A. Ibers, W. D. Phillips, and J. F. Weiher, *Proc. Natl.* Acad. Sci. USA, 69, 2437 (1972). Also see R. H. Holm, Acc. Chem. Res., 10, 427 (1977).

Figure 22.13 The mononuclear unit (a) found in rubredoxin, and the binuclear complex (b) and tetranuclear cluster (c) of ferredoxins. The S-Cys groups are cysteine amino acid residues of the same bacterium has a molecular weight of approximately 230,000 ...niaprories





Figure 22.14 The skeleton of M. aerogenes ferredoxin. (Reproduced with permission from K. T. Yasunobu and M. Tanaka, in W. Lovenberg, ed., "Iron-Sulfur Proteins," vol. 2, chap. 2, Academic, New York, 1973.)

iron(III) chloride, sodium methoxide, sodium hydrosulfide, and benzyl mercaptan in methanol solution. Many of the properties of the complex (magnetic susceptibility,  $^{57}$ Fe Mössbauer spectrum, electronic spectrum, and redox properties) are analogous to those of ferredoxins which contain Fe<sub>4</sub>S<sub>4</sub> clusters. Although the compound might be formulated as a complex of two Fe(II) atoms and two Fe(III) atoms, all the physical methods, including x-ray photoelectron spectroscopy, indicate that the iron atoms are equivalent. Hence a delocalized electronic description, in terms of identical iron atoms in the "+2.5" oxidation state, is probably appropriate.

The enzyme "nitrogenase," present in various bacteria, catalyzes the reduction of molecular nitrogen to ammonia. Nitrogenase is composed of two proteins: an iron protein and a molybdenum-iron protein. The Fe protein obtained from the bacterium *Clostridium pasteurianum* is a dimer of a subunit which has an approximate molecular weight of 28,000, two iron atoms, two acid-labile sulfide groups, and six "free" cysteine residues. The Mo-Fe protein from the same bacterium has a molecular weight of approximately 230,000 and contains



two molybdenum atoms and approximately 30 atoms each of iron and acid-labile sulfide groups. About half the iron content of the Mo-Fe protein is in Fe<sub>4</sub>S<sub>4</sub> centers which probably serve as intramolecular electron-transfer sites. Most of the remaining iron is associated with molybdenum in the "Mo-Fe cofactor," which presumably is the catalytic site of the enzyme. In the cofactor, the Fe/Mo ratio is  $7 \pm 1$ .

The Mo-Fe protein has been studied by x-ray absorption spectroscopy. 17 In the region of the molybdenum and iron K absorption edges, one observes a series of peaks (due to transitions of the 1s electron to unoccupied molecular orbitals having mainly transition-metal character) superimposed on a steeply rising absorption due to transitions of the 1s electron into continuum levels. The spectrum at the molybdenum absorption edge is shown in Fig. 22.16. Extended absorption fine structure of this type is generally referred to as EXAFS. The shape of the edge and the positions of the edge features give information about the complex in the vicinity of the metal atom. By Fourier transform analysis and curve fitting of the molybdenum and iron EXAFS spectra, the information summarized in Table 22.1 has been obtained. This information includes the

<sup>17</sup> S. P. Cramer, K. O. Hodgson, W. O. Gillum, and L. E. Mortenson, J. Am. Chem. Soc., 100, 3398 (1978); M. R. Antonio, B.-K. Teo, W. H. Orme-Johnson, M. J. Nelson, S. E. Groh, P. A. Lindahl, S. M. Kauzlarich, and B. A. Averill, J. Am. Chem. Soc., 104, 4703 (1982). For a discussion of the application of the EXAFS method to molybdenum complexes, see S. P. Cramer et al., J. Am. Chem. Soc., 100, 2748 (1978).




Figure 22.16 The x-ray absorption spectrum of lyophilized, semireduced C. pasteurianum Mo-Fe protein, showing the EXAFS region associated with the molybdenum K absorption edge. [Adapted with permission from Cramer et al., J. Am. Chem. Soc., 100, 3814 (1978). Copyright 1978 American Chemical Society.]

approximate atomic weight (and hence the identity) of the atoms which are neighbors of the molybdenum and iron atoms, the approximate number of these neighbor atoms, and their approximate distances from the molybdenum or iron atom. The uncertainties in the structural data are so great that we have only a rough idea of the nature of the Mo-Fe site of nitrogenase, but they do serve as the basis for reasonable conjecture. Thus, it has been proposed 18 that the molybdenum site has a structure like that shown in Fig. 22.17, in which the molybdenum atom is linked to two Fe<sub>4</sub>S<sub>4</sub> cubes by sulfide groups and Mo—Fe bonds. In this proposed structure, the iron atoms are of two structural types (two Fe<sup>A</sup> and six Fe<sup>B</sup>). Antiferromagnetic coupling of the six Fe<sup>B</sup> atoms via a diamagnetic

18 B.-K. Teo and B. A. Averill, Abstracts of the 178th National A. C. S. Meeting, September 1979, For Movie posters has been studied by sorgy shapiplion space

Table 22.1 Structural features of the Mo-Fe cofactor of nitrogenase obtained from molybdenum and iron is and proposed to the proposed **EXAFS** spectra

	Neighboring atoms	No. of neighboring atoms	Distance to neighboring atoms, Å
Мо	Fe	2-3	227 200 low cada Ho saurit w
Mo	NEWS HORIZAMON	3-4 beaude	O William Committee Commit
Mo	S	1-2	
e	Fe on make	$2.3 \pm 0.9$	~2.5
e	Mo	$0.4 \pm 0.1$	$2.66 \pm .03$
e	SUL TO LEGIS		2.76 ± .03
	0	$3.4 \pm 1.6$	2.25 ± .02
e	O or N	$1.2 \pm 1.0$	1.81 ± .07




Figure 22.17 A proposed model for the molybdenum site of the Mo-Fe protein of nitrogenase. [From B.-K. Teo and B. A. Averill, Abstracts of the 178th National A. C. S. Meeting, September 1979, INOR 238.]]

Fe<sup>A</sup>S<sub>2</sub>MoS<sub>2</sub>Fe<sup>A</sup> unit could conceivably result in a net spin of ½ for the entire site, and would be consistent with the experimental epr spectrum, which indicates that the protein is a spin ½ system. <sup>19</sup> Molybdenum-iron complexes having some of the structural features of nitrogenase have been synthesized. <sup>20–23</sup> The structures of some of these complexes are shown in Fig. 22.18. The molybdenum EXAFS spectrum of the complex Mo<sub>2</sub>Fe<sub>6</sub>S<sub>9</sub>(SEt)<sub>8</sub><sup>3–</sup> (Fig. 22.18a) is sufficiently similar to that of *C. pasteurianum* nitrogenase to indicate that the complex is a fair approximation to the molybdenum site of nitrogenase. Thus the cubane-like MoFe<sub>3</sub>S<sub>4</sub> cluster of this species is looked upon as a preliminary model of the coordination unit of molybdenum in the enzyme. <sup>24</sup> However, much more synthetic effort will be required in order to obtain model systems in which the metal composition approaches that of the Mo–Fe cofactor of the enzyme (6 to 8 Fe/Mo).

It is traditionally believed that the reduction of molecular nitrogen occurs at the molybdenum site of the enzyme. The evidence is all circumstantial, and it is not even known whether the initial coordination of nitrogen occurs at an iron atom or a molybdenum atom, although most opinions favor the molybdenum atom. The overall mechanism of the reduction process is schematically represented by the diagram in Fig. 22.19. The electrons required in the reduction are transferred to nitrogenase by the reduced forms of ferredoxins or flavodoxins. The source of these electrons is the oxidation of pyruvate. The electrons are first transferred to the smaller protein (Fe protein). The reduced Fe protein forms a complex with the Mo-Fe protein and the monomagnesium salt of ATP and then transfers its reducing electron to the Mo-Fe protein and thus to the dinitrogen bound at the active site. A series of such electron-transfer steps, with concomi-

<sup>&</sup>lt;sup>19</sup> G. Palmer et al., Arch. Biochem. Biophys., 153, 325 (1972).

<sup>&</sup>lt;sup>20</sup> T. E. Wolff, J. M. Berg, K. O. Hodgson, R. B. Frankel, and R. H. Holm, *J. Am. Chem. Soc.*, **101**, 4140 (1979).

<sup>&</sup>lt;sup>21</sup> T. E. Wolff, J. M. Berg, P. P. Power, K. O. Hodgson, and R. H. Holm, *Inorg. Chem.*, **19**, 430 (1980).

<sup>&</sup>lt;sup>22</sup> D. Coucouvanis et al., J. Am. Chem. Soc., **102**, 1732 (1980); D. Coucouvanis, Acc. Chem. Res., **14**, 201 (1981).

<sup>&</sup>lt;sup>23</sup> G. Christou and C. D. Garner, *J. Chem. Soc. Dalton Trans.*, 2354 (1980). <sup>24</sup> R. H. Holm, *Chem. Soc. Rev.*, **10**, 455 (1981).




Figure 22.18 Synthetic complexes having some of the structural features of nitrogenase. (a) Mo<sub>2</sub>Fe<sub>6</sub>S<sub>9</sub>(SEt)<sub>8</sub><sup>3-</sup>; the two ethyl groups of the bridge and the six ethyl groups of the terminal thiolate ligands are omitted. [Reproduced with permission from Wolff et al., J. Am. Chem. Soc., 101, 4140 (1979).] (b) Mo<sub>2</sub>Fe<sub>7</sub>S<sub>8</sub>(SEt)<sub>12</sub><sup>3-</sup>; the ethyl groups of the bridging and terminal thiolate ligands are omitted. [Reproduced with permission of Wolff et al., J. Am. Chem. Soc., 101, 4140 (1979).] (c) MoFe<sub>2</sub>S<sub>4</sub>Cl<sub>4</sub><sup>2-</sup>. [Reproduced with permission from Coucouvanis et al., J. Am. Chem. Soc., 102, 1732 (1980).] (Copyright 1979 and 1980 American Chemical Society.)




Figure 22.19 Schematic representation of the nitrogenase-catalyzed reduction of nitrogen. Fd = ferredoxin, Fld = flavodoxin.

tant proton transfer from water to the dinitrogen, results in the production of the magnesium salt of ADP, free phosphate (P), and ammonia, with regeneration of the proteins in their original states. Energy for the process is provided by the hydrolysis of ATP to ADP plus P. For an example of one conceivable mechanism, consider the model of Fig. 22.17.25 Bonding of N<sub>2</sub> to the molybdenum in a linear, Mo-N≡N, fashion would perturb the Fe<sup>4</sup>-Mo-Fe<sup>4</sup> bonding and result in a complex in which the activated dinitrogen is  $\sigma$ -bonded to the molybdenum and  $\pi$ -bonded to the two Fe<sup>A</sup> atoms. Stepwise injection of electrons via the Fe<sub>4</sub>S<sub>4</sub> cubes and successive protonation of the dinitrogen might give a sequence of intermediates such as the following:

$$M_0-N \equiv N \xrightarrow{2e^-} M_0-N = NH_2 \xrightarrow{2e^-} M_0-NH-NH_3 \xrightarrow{2e^-} M_0+2NH_3$$

It is significant that H<sub>2</sub> inhibits the fixation of nitrogen by nitrogenase.<sup>26</sup> In the presence of  $N_2$ ,  $H_2$ , and  $D_2O$  or  $N_2$ ,  $D_2$ , and  $H_2O$ , the enzyme produces HD. This latter reaction and the H<sub>2</sub> inhibition of N<sub>2</sub> reduction have been interpreted as evidence for the formation of the intermediate coordinated diimide (N<sub>2</sub>H<sub>2</sub>), which reacts with H<sub>2</sub> to form 2H<sub>2</sub> and N<sub>2</sub> (or with D<sub>2</sub> to form 2HD and N<sub>2</sub>).

<sup>25</sup> Teo and Averill, op. cit.

<sup>&</sup>lt;sup>26</sup> See E. I. Stiefel, Prog. Inorg. Chem., 22, 1 (1977).

# cis-DICHLORODIAMMINEPLATINUM(II) ANTICANCER ACTIVITY<sup>27</sup>

In an attempt to determine the effect of oscillating electric fields on bacterial growth, Rosenberg and VanCamp suspended Escherichia coli bacteria in an ammonium chloride solution between two platinum electrodes connected to an audio amplifier. This treatment inhibited cell division (the bacterial population decreased), but cell growth continued, leading to long filaments. After considerable further study, it was discovered that this peculiar effect on the bacteria was due to the electrolytic formation of cis-Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>4</sub> and that the corresponding trans complex has essentially no effect on the bacteria. It was then shown that cis-Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub> has the same sort of effect on E. coli as cis-Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>4</sub> and that trans-Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub>, like the corresponding trans Pt(IV) complex, has no effect. Tests with various animals showed that cis-Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub> is a very effective antitumor agent, causing regression of both slow- and fast-growing cancers. compound, under the name cis-platinum, has been approved for use in humans. The mechanism of the anticancer activity is largely unknown, but certain features are known.28 In the high chloride concentration of extracellular fluids, replacement of the chloride ions of the complex by water molecules is suppressed. However, after passing into a cell, where the chloride concentration is about  $\frac{1}{30}$  of that outside the cell, the following reactions can take place:

Probably the diaquo species reacts with the nitrogens of DNA bases, leading to changes in the DNA structure responsible for the anticancer effect. cis-Platinum binds to two neighboring bases on a single DNA strand (a reaction which is stereochemically impossible for the trans isomer), causing the double helix structure of DNA to unwind.

### CARBONIC ANHYDRASE<sup>29</sup>

In Chap. 7 it was pointed out that the hydration of CO<sub>2</sub> to give carbonic acid is a slow process. This property of CO<sub>2</sub> is not consistent with the fact that many physiological processes require rapid equilibration of CO<sub>2</sub> with HCO<sub>3</sub><sup>-</sup> and

B. Rosenberg, *Interdiscip. Sci. Rev.*, 3, 134 (1978); B. Rosenberg, L. VanCamp, J. E. Trosko, and
 V. H. Mansour, *Nature*, 222, 385 (1969).

R. Rawls, Chem. Eng. News, 35-36 (Jan. 21, 1980); G. L. Cohen, J. A. Ledner, W. R. Bauer,
 H. M. Ushay, C. Caravana, and S. J. Lippard, J. Am. Chem. Soc., 102, 2488 (1980).

<sup>&</sup>lt;sup>29</sup> F. A. Cotton and G. Wilkinson, "Advanced Inorganic Chemistry," 4th ed., pp. 1332–1334, Wiley-Interscience, New York, 1980.

H<sub>2</sub>CO<sub>3</sub> at about pH 7. It is the function of the zinc-containing enzyme called carbonic anhydrase to catalyze this equilibration. The active site of the enzyme contains a zinc ion bonded to three histidine imidazole nitrogen atoms and either a water molecule or a hydroxide ion, as follows:

A water molecule coordinated to a zinc ion has a pK near 7, and thus the role of the zinc ion is to reduce the basicity of the hydroxide ion such that a high effective concentration of hydroxide can exist in an approximately neutral medium. The probable mechanism of the hydration process is shown in the following cyclic scheme.

$$Z_{n}$$
 $CO_{2}$ 
 $Z_{n}$ 
 $CO_{2}$ 
 $CO_$ 

In effect, the enzyme allows the relatively fast reaction,  $CO_2 + OH^- \rightarrow HCO_3^-$ , to be the major pathway for hydration at pH 7, where the hydroxide concentration is so low that the slow reaction of  $CO_2$  with  $H_2O$  would ordinarily predominate.

#### SUPEROXIDE DISMUTASES30

Because oxygen is vital to many biological respiration processes, its redox chemistry has been the subject of many investigations.<sup>31</sup> It is well established that the initial step in the electron-transfer reduction of  $O_2$  produces the superoxide ion,  $O_2$ . It has been postulated that the superoxide ion, or some product derived from it (such as the hydroxyl radical,  $\cdot OH$ ) is toxic to cellular systems. Although there are cogent arguments against this postulate,<sup>32</sup> it is nevertheless true that all organisms that use oxygen, and many that have to survive in an oxygen environment, contain at least one variety of the enzyme (superoxide dismutase) that very efficiently catalyzes the dismutation (disproportionation) of superoxide into hydrogen peroxide and oxygen:

$$2O_2^- + 2H^+ \longrightarrow H_2O_2 + O_2$$

The superoxide dismutase isolated from bovine liver is very effective in suppressing swelling and inflammation of tissue and has been found to be valuable in the treatment of inflammatory osteoarthritis.

There are three varieties of superoxide dismutase: (1) a copper-zinc protein found in cells that have nuclei, (2) a manganese protein found in bacteria, and (3) an iron protein found in bacteria. A crystal structure determination of the copper-zinc protein has shown that the Cu<sup>2+</sup> and Zn<sup>2+</sup> ions are coordinated to the same imidazole ring of a histidine residue, as follows:

Biochemical studies indicate that an arginine residue in the protein, positioned close to the copper atom, plays an important role in the catalytic activity of the enzyme.<sup>33</sup> The following mechanism has been proposed for the catalyzed dismutation of the superoxide ion;<sup>34</sup>

<sup>31</sup> J. Wilshire and D. T. Sawyer, Acc. Chem. Res., 12, 105 (1979).

<sup>32</sup> J. A. Fee, in Bannister and Bannister, op. cit., p. 41.

33 D. P. Malinowski and I. Fridovich, in Bannister and Hill, op. cit., p. 299.
34 A. E. G. Cass and H. A. O. Hill, in Bannister and Hill, op. cit., p. 290.

<sup>&</sup>lt;sup>30</sup> W. H. Bannister and J. V. Bannister, eds., "Biological and Clinical Aspects of Superoxide Dismutase," Proceedings of the International Symposium on Superoxide and Superoxide Dismutases, Malta, 1979; J. V. Bannister and H. A. O. Hill, eds., "Chemical and Biochemical Aspects of Superoxide and Superoxide Dismutase," Proceedings of the International Symposium on Superoxide and Superoxide Dismutases, 2d, Malta, 1979.

First the superoxide ion forms an outer-sphere coordination complex with the hydrated Cu<sup>2+</sup> ion, and a hydrogen-bonded water molecule connects the superoxide ion to the guanidinium group of the arginine. An outer-sphere electron transfer then produces Cu<sup>+</sup> and molecular oxygen. Another superoxide ion is then bound between the hydrated Cu<sup>+</sup> and the arginine. Electron transfer from the copper then produces Cu<sup>2+</sup> and peroxide ion, while simultaneously the copper-bound water molecule and the guanidinium group each donate a proton to the developing peroxide dianion. The hydrogen peroxide then leaves, and

both the Cu<sup>2+</sup>-bound hydroxide ion and the guanidine group are reprotonated by nearby water molecules. The function of the zinc ion is completely unknown.

#### **PROBLEMS**

- 22.1 Draw the structure of porphine. Indicate how the heme structure is related to porphine and how the macrocyclic ligand system in vitamin  $B_{12}$  differs from porphine.
- 22.2 Describe the functions of hemoglobin and myoglobin and describe the changes in the heme groups of hemoglobin on going from the oxy to the deoxy form.
- 22.3 Describe a possible mechanism for the vitamin B<sub>12</sub>-catalyzed dehydration of a diol:

How could you test the mechanism, using tritium as a hydrogen tracer?

- 22.4 Outline the functions of nitrogenase. What is known about the structure of the enzyme in the vicinity of a molybdenum atom?
- 22.5 (a) Show that the hyperbolic curve for myoglobin in Fig. 22.5 is consistent with the equilibrium

$$Mb(aq) + O_2(g) \implies MbO_2(aq)$$

(b) Show that the sigmoidal curve for hemoglobin in Fig. 22.5 can be explained by an equilibrium of the following type, where 1 < n < 4:

$$Hb(aq) + nO_2(g) \Rightarrow Hb(O_2)_n(aq)$$

# UNITS AND CONVERSION FACTORS

The tables in this section give values for some important physical constants (Table A.3) and conversion factors for units of energy (Table A.4). In recent years there has been a trend among scientists toward the use of SI units¹ (i.e., units based on the Systeme Internationale d'Unites). Although there are some advantages to the use of SI units, undue rigidity should be avoided. Indeed, the uncritical adoption of SI units is usually undesirable.² Most modern chemistry journals retain the use of traditional units such as angstroms, atmospheres, molarity (moles per liter), electronvolts, and kilocalories, although there is a marked trend toward the use of joules instead of calories. This text employs the traditional units; thus it conforms with the practice of most working chemists. When necessary, the tables of this appendix can be used to convert from one unit to another.

Nat. Bur. Stand. (U.S.), Spec. Publ. 330 (1981).

<sup>2</sup> A. W. Adamson, *J. Chem. Educ.*, **55**, 634 (1978); D. R. Lide, *Chem. Eng. News*, 4, 54. (May 10, 1982)

Table A.1

Name	Symbol
meter	m
	kg
	S A
A SECTION OF THE PROPERTY OF T	K
candela	cd
	meter kilogram second ampere kelvin

Table A.2

Physical quantity	Name	Symbol
Force Energy Power Electric charge Electric potential Electric capacitance Electric resistance Frequency Magnetic flux	newton joule watt coulomb volt farad ohm hertz	N (kg m s <sup>-2</sup> ) J (N m) W (J s <sup>-1</sup> ) C (A s) V (W A <sup>-1</sup> ) F (A s V <sup>-1</sup> ) Ω (V A <sup>-1</sup> ) Hz (s <sup>-1</sup> )
Magnetic flux density	weber tesla henry	Wb (V s) T (Wb m <sup>-2</sup> ) H (V s A <sup>-1</sup> )

Table A.3 Some useful constants

Constant and symbol	Value, traditional units	Value, SI units
Gas constant, R	82.056 ml atm deg <sup>-1</sup> mol <sup>-1</sup>	8.3143 J K <sup>-1</sup> mol <sup>-1</sup>
Ideal gas volume, std. cond. Avogadro's number, N Faraday constant, F	$62,362 \text{ ml torr deg}^{-1} \text{ mol}^{-1}$ $22,414 \text{ ml atm mol}^{-1}$ $6.02209 \times 10^{23} \text{ mol}^{-1}$	$2.241436 \times 10^{-2} \mathrm{m^3  mol^{-1}}$
	96,487 coulomb g equiv-1 23,061 cal volt-1 equiv-1	9.6487 × 10 <sup>4</sup> C mol <sup>-1</sup>
Boltzmann's constant, k Ice point (0°C) Electron charge, e Electron mass, m	1.3805 × 10 <sup>-16</sup> erg deg <sup>-1</sup> 273.150° K 4.8030 × 10 <sup>-10</sup> abs. esu 9.1091 × 10 <sup>-28</sup> g	$1.3805 \times 10^{-23} \text{ J K}^{-1}$ 273.150  K $1.602 \times 10^{-19} \text{ C}$ $9.1091 \times 10^{-31} \text{ kg}$
Planck's constant, $h$ Velocity of light, $c$ Gravitational constant, $g$ Bohr radius, $a_0$ Proton mass, $M_p$	5.486 × 10 <sup>-4</sup> mu 0.5110 MeV 6.6256 × 10 <sup>-27</sup> erg sec 2.99795 × 10 <sup>10</sup> cm sec <sup>-1</sup> 980.66 cm sec <sup>-2</sup> 0.52918 Å 1.6725 × 10 <sup>-24</sup> kg	$6.6256 \times 10^{-34} \text{ J s}$ $2.99795 \times 10^8 \text{ m s}^{-1}$ $9.8066 \text{ m s}^{-2}$ $0.52918 \times 10^{-10} \text{ m}$ $1.6725 \times 10^{-27} \text{ kg}$

#### TERM SYMBOLS FOR FREE ATOMS AND IONS

The statement that a free atom or ion has a particular valence electron configuration, say  $np^2$ , is an incomplete description of the electronic state of the species. In order to completely describe the state, one must specify the values of the total orbital angular momentum quantum number, L, the total spin angular momentum quantum number, J.

The components, in a reference direction, of L and S can have the following quantized values:

$$M_L = L, L - 1, \dots, -(L - 1), -L$$
  
 $M_S = S, S - 1, \dots, -(S - 1), -S$ 

Here  $M_L$  and  $M_S$  are the vector sums of the  $m_l$  and  $m_s$  values for the individual electrons:

$$M_L = m_{l_1} + m_{l_2} + m_{l_3} + \cdots$$
 $M_S = m_{s_1} + m_{s_2} + m_{s_3} + \cdots$ 

The set of individual quantum states corresponding to a particular value of L and a particular value of S constitutes a "term" and is represented by a term symbol, where the value of L is indicated by one of the capital letters  $S, P, D, F, G, H, \ldots$  (corresponding to  $0, 1, 2, 3, \ldots$ ). The quantum number J is the vector sum of L and S and may have the values

$$J = L + S, L + S - 1, L + S - 2, \dots, |L - S|$$

J can only have positive values or be zero. The components, in a reference direction, of J can have values

$$M_J = J, J-1, \ldots, -(J-1), -J$$

For example, one of the terms of an atom with an  $np^2$  configuration is the  $^1D_2$  (pronounced singlet D two) term. This term can be represented by the following set of individual quantum states, in which the  $m_s$  values are indicated by arrows pointing up or down.

$m_l = +1$	0	-1	$M_L$	$M_{\mathcal{S}}$	$M_J$
	0-6-0	@@000	2 1 0 -1 -2	0 0 0 0 0	2 1 0 -1 -2

The  $np^2$  configuration also yields the terms  ${}^3P_2$ ,  ${}^3P_1$ , and  ${}^3P_0$ , for which we can write the following individual quantum states:

Code	$m_l = +1$	0	Jo on h	$M_L$	$M_S$	$M_J$
$^{3}P_{2}$	00000	00000	00000	1 0 -1 0 -1	1 0 20 1 5 1 0 1 4 -1 -1	2 1 0 -1 -2
${}^{3}P_{1}$ ${}^{3}P_{0}$	900	0000	0000	1 1 -1 0	$     \begin{array}{c}       0 \\       -1 \\       0 \\       0   \end{array} $	0 -1 0

The only other term of the  $np^2$  configuration is the  ${}^1S_0$  term:

$m_l = +1$	0	6, McUra 1 - 1 - od	$M_L$	$M_{S}$	$M_J$
'S <sub>0</sub> ( ①	0	0	0	0	0

Note that we have now written all the possible combinations of  $m_l$  and  $m_s$ . It is important to recognize that most of the individual quantum state assignments are not unique. For example, the configurations  $\bigcirc \bigcirc \bigcirc$  and  $\bigcirc \bigcirc \bigcirc$  could just as well be interchanged, or suitable linear combinations assigned to particular terms.

It should be obvious that, because of limitations imposed by the Pauli principle, not all conceivable combinations of L and S are possible for a given many-electron system. A list of the allowed states for equivalent s, p, and d

Table B.1 Allowed states for equivalent s, p, and d when availed award when are 1

Terms 1	( - L) -						
<sup>1</sup> S <sup>2</sup> P <sup>1</sup> S, <sup>1</sup> D, <sup>3</sup> P <sup>2</sup> P, <sup>2</sup> D, <sup>4</sup> S <sup>1</sup> S			s In ann		e, one of	odneed sir individua	lo is
<sup>1</sup> (SDG), <sup>3</sup> (PF)							
1(SDG), 3(PF), 1(	SDFGI) 3	(PDFGH PFGI), 4(1	H), <sup>5</sup> D DG), <sup>6</sup> S		00		
	<sup>2</sup> S <sup>1</sup> S <sup>2</sup> P <sup>1</sup> S, <sup>1</sup> D, <sup>3</sup> P <sup>2</sup> P, <sup>2</sup> D, <sup>4</sup> S <sup>1</sup> S <sup>2</sup> D <sup>1</sup> (SDG), <sup>3</sup> (PF) <sup>2</sup> D, <sup>2</sup> (PDFGH), <sup>4</sup> <sup>1</sup> (SDG), <sup>3</sup> (PF), <sup>1</sup> (SDG), <sup>3</sup> (PF), <sup>4</sup> (SDG)	<sup>2</sup> S <sup>1</sup> S <sup>2</sup> P <sup>1</sup> S, <sup>1</sup> D, <sup>3</sup> P <sup>2</sup> P, <sup>2</sup> D, <sup>4</sup> S <sup>1</sup> S <sup>2</sup> D <sup>1</sup> (SDG), <sup>3</sup> (PF) <sup>2</sup> D, <sup>2</sup> (PDFGH), <sup>4</sup> (PF) <sup>1</sup> (SDG), <sup>3</sup> (PF), <sup>1</sup> (SDFGD) <sup>3</sup>	<sup>2</sup> S <sup>1</sup> S <sup>2</sup> P <sup>1</sup> S, <sup>1</sup> D, <sup>3</sup> P <sup>2</sup> P, <sup>2</sup> D, <sup>4</sup> S <sup>1</sup> S <sup>2</sup> D <sup>1</sup> (SDG), <sup>3</sup> (PF) <sup>2</sup> D, <sup>2</sup> (PDFGH), <sup>4</sup> (PF) <sup>1</sup> (SDG), <sup>3</sup> (PF), <sup>1</sup> (SDFGI) <sup>3</sup> (PDFGH)	Terms  2S 1S 2P 1S, 1D, 3P 2P, 2D, 4S 1S 2D 1(SDG), 3(PF)	Terms  2S 1S 2P 1S, 1D, 3P 2P, 2D, 4S 1S 2D 1(SDG), 3(PF) 2D, 2(PDFGH), 4(PF) 1(SDG), 3(PF), 1(SDFGH), 3(PDFGH), 5D	Terms  2S 1S 2P 1S, 1D, 3P 2P, 2D, 4S 1S 2D 1(SDG), 3(PF) 1(SDG), 3(PF), 1(SDFGI), 3(PDFGH), 5D	<sup>2</sup> S <sup>1</sup> S <sup>2</sup> P <sup>1</sup> S, <sup>1</sup> D, <sup>3</sup> P <sup>2</sup> P, <sup>2</sup> D, <sup>4</sup> S <sup>1</sup> S <sup>2</sup> D <sup>1</sup> (SDG), <sup>3</sup> (PF) <sup>2</sup> D, <sup>2</sup> (PDFGH), <sup>4</sup> (PF) <sup>1</sup> (SDG), <sup>3</sup> (PF), <sup>1</sup> (SDFGD), <sup>3</sup> (PDFGH), <sup>5</sup> D

electrons is given in Table B.1. Methods for determining the terms corresponding to particular configurations are described in various books. In order to determine which term for a given configuration represents the ground state, we apply write the following individual quantum star

- 1. The most stable state is the one with the largest value of S.
- 2. Of a group of states with the same value of S, that with the largest value of L lies
- 3. Of a group of states with the same values of L and S, corresponding to a shell of electrons less than half full, states with lower J lie lower. When the shell is more than half full, the reverse applies.

In the x-ray photoelectron spectrum of argon (Fig. 1.11), the 2p peak is split into two components corresponding to the  ${}^{2}P_{3/2}$  and  ${}^{2}P_{1/2}$  ions which are formed. These components have relative intensities of 2:1, corresponding to the ratio of the number of individual quantum states for the two states (i.e., the ratio of the 2J + 1 values).

H. B. Gray, "Electrons and Chemical Bonding," pp. 22-27, W. A. Benjamin, New York, 1964; C. J. Ballhausen, "Introduction to Ligand Field Theory," pp. 8-10, McGraw-Hill, New York, 1962; F. A. Cotton and G. Wilkinson, "Advanced Inorganic Chemistry," 3d ed., pp. 80-85, Wiley-Interscience, New York, 1972; J. E. Huheey, "Inorganic Chemistry," pp. 35-38, Harper & Row, New York, 1972; L. Pauling, "The Nature of the Chemical Bonds," 3d ed., pp. 580-588, Cornell University Press, Ithaca, N.Y., 1960. Note that we have now written all the possible combinitions of m, and

### **ELECTRON AFFINITIES**

Table C.1 Electron affinities of atoms†

Element	eV	kcal mol-1	Element	eV	kcal mol-
Aluminum	0.46	10.6	Neon	<0	<0
Antimony	1.05	24.2	Nickel	1.15	26.5
Argon	<0	<0	Niobium	1.13	23
Arsenic	0.80	18.4	Nitrogen	-0.07	-1.6
Barium	<0	<0 1.01	Osmium	1.1	25
Beryllium	<0	<0	Oxygen	1.462	33.72
Bismuth	1.1	25	Palladium	0.6	14
Boron	0.28	6.5	Phosphorus	0.743	17.13
Bromine	3.364	77.58	Platinum	2.128	49.07
Cadmium	<0	<0	Polonium	1.9	44
Calcium	<0	<0	Potassium	0.5012	11.56
Carbon	1.268	29.24	Radon	<0.3012	<0
Cesium	0.4715		Rhenium	0.15	3.5
Chlorine		10.87	Rhenium	1.2	28
Chromium	3.615	83.37	Rubidium	0.4860	11.21
Cobalt	0.66	15.2		1.1	25
Copper	0.7	16	Ruthenium	<0	<0
Fluorine	1.226	28.27	Scandium	2.021	46.61
Gallium	3.399	78.38	Selenium	1.385	31.94
Germanium	0.3	7	Silicon	1.303	30.05
Gold	1.2	28	Silver	0.546	12.59
Hafnium	2.309	53.25	Sodium	<0	<0
Helium	< 0	<0	Strontium	2.077	47.90
lydrogen	<0	<0	Sulfur		14
ndium	0.7542	17.39	Tantalum	0.6	16
odine	0.3	7	Technetium	0.7	45.45
ridium	3.061	70.59	Tellurium	1.971	7
on on	1.6	37	Thallium	0.3	28.8
	0.25	5.8	Tin	1.25	5
rypton	< 0	<0 1042	Titanium	0.2	14
anthanum	0.5	12	Tungsten	0.6	
ead	1.1	25 9.88 2	Vanadium	0.5	
ithium	0.620	14.30	Xenon	<0	<0
lagnesium	<0	<0	Yttrium	~0	~0
anganeco	<0	<0	Zinc	<0	<0
ercury	<0	<0	Zirconium	0.5	12
olybdenum	1.0	23			

Table C.2 Electron affinities of molecules and radicals<sup>a</sup>

Molecule	eV	kcal mo	0 -1		
ZHITIMIH	Diatomics	13			
Br <sub>2</sub>	2.53	58.3			
CN	3.82	88.1			
CS <sup>b</sup>	0.20	4.7			
Cl <sub>2</sub>	2.35	54.2			
$F_2$	3.1	71			
HS	2.32	53.5			
IBr	2.6	60		ectron affini	able C.1 E
	2.55	50.0			
LiCl	0.61	14.1			
NH 0>	0.38	8.8			
15 26.5 ON	0.02		10.6		
NS <sup>b</sup>	1.19	0.5	24.2		
OH H	1.825	27.5			
$O_2$	0.44	42.09			
PH	1.03	10.1			
60	1.13	23.8			
S <sub>2</sub> CLT FATE		26.1			
SeH to put	1.66	38.3			
SiH	2.21	51.0		3.366 %	
OF THE PARTY OF TH	1.28	29.5			
	Triatomics		0.5		
CAT BALLOT DESIGN	- Tracomics John R		29.24		
NSH <sub>2</sub>	1.27	29.3			
H <sub>2</sub>	0.21	4.8			
H <sub>2</sub>	0.74	17.1	13.2		
l <sub>3</sub> c	2.7	62			
$10_2$	2.3	53			
$_{2}H^{d}$	1.19	27.4			
3	2.10	48.4			
H <sub>2</sub>	1.25	28.8			
	1.1	25			
	2.0	46			
H <sub>2</sub> TA TO C	1.12	25.8			
NAME OF TAXABLE PARTY.	ACTIVITIES !	23.8			
	Tetraatomics		The same		
A CONTRACTOR OF THE PARTY OF TH	We trolled				
H <sub>3</sub>	0.08	1.8			
03 8.85 7 4 8.82	2.7	62			
H <sub>3</sub>	≤1.74	≤40.1			
3 Thomas and the state of the s	≥1.7	≥ 39			
I <sub>3</sub> 2.0	≤1.44	≤33.2			
7 00	Humor.	= 33.4	14.3		
			123		
					Manganese

Table C.2 (Continued)

Molecule	eV	kcal mol-1	
Large	er polyatomics		
CH <sub>3</sub> NO <sub>2</sub> CH <sub>3</sub> S CH <sub>3</sub> S C <sub>3</sub> H <sub>5</sub> (allyl) C <sub>5</sub> H <sub>5</sub> (cyclopentadienyl) C <sub>6</sub> H <sub>6</sub> HNO <sub>3</sub> POCl <sub>3</sub> SF <sub>6</sub> SeF <sub>6</sub> TeF <sub>6</sub> WF <sub>6</sub> ReF <sub>6</sub> DSF <sub>6</sub> TeN <sub>6</sub> T	0.4 1.57 1.88 0.55 1.79 -1.14 0.6 1.4 0.5 2.9 3.3 3.5 5	43.4 12.7 41.3 -26.3 14 32 12 67 76 81	ONIZATION P
rF <sub>6</sub> / PtF <sub>6</sub> / altrasioM	8 9.2	184 212	

"B. K. Janousek and J. I. Brauman, in "Gas Phase Ion Chemistry," M. T. Bowers, ed., vol. 2, chap. 10, p. 53, Academic, New York, 1979.

<sup>b</sup> S. M. Burnett, C. S. Feigerle, and W. C. Lineberger, National A. C. S. Meeting, Las Vegas, April 1982, PHYS 170.

<sup>c</sup> R. L. Jackson, M. J. Pellerite, and J. I. Brauman, J. Am. Chem. Soc., 103, 1803 (1981).

<sup>d</sup> V. M. Bierbaum, R. J. Schmitt, C. H. DePuy, R. D. Mead, P. A. Schulz, and W. C. Lineberger, J. Am. Chem. Soc., 103, 6262 (1981).

<sup>e</sup> W. C. Lineberger, Gov. Rep. Announce. Index (U.S.), 79, 92 (1979).

N. Bartlett, E. M. McCarron, B. W. McQuillan, and T. E. Thompson, *Synth. Metals*, 1, 221 (1980).

t Except as noted, data are from H. M. Rownstock, K. Drevi, B. W. Steiner, and J. T. Herroft, J. Chrys. Ref. Drev. 4.

§ R. V. Hodges, F. A. Houle, J. L. Beauchamp, R. A. Moners, and J. G. Verkade, J. Am. Ch. F.

Page Glora, Rel. Dans, 6, suppl. 1 (1977), See Table L7 for atomic ionization potentials

### IONIZATION POTENTIALS

APPENDIX C. ELECTRON APPINITIES 537

Table D.1 Ionization potentials of some molecules and radicals†

Molecule or radical	IP, eV	Molecule or radical	IP, eV	Molecule or radical	IP, eV
H <sub>2</sub>	15.43	Oas Phason	14.01	L bashis would	
ВН	9.77	CO, 2 9 01	13.77	H,S	
BH <sub>2</sub>	~ 9.8	NO	9.26	CS¶	10.47
BH <sub>3</sub>	~ 12.3	N <sub>2</sub> O	12.89	NS NS	
$B_2H_6$	11.39	NO <sub>2</sub>	9.75		
CH	10.64	CH <sub>3</sub> OH	10.84	SO	
CH <sub>2</sub>	10.40	F <sub>2</sub>	15.69	SO <sub>2</sub>	
CH <sub>3</sub>	9.84	HF G.R.V	16.01	SO <sub>3</sub>	~11.0
CH <sub>4</sub>	≤ 12.62	BF <sub>3</sub>	10.01		~ 10.3
$C_2H_2$	11.41	CF <sub>3</sub>	15.56	SF <sub>4</sub> bos slu	
$C_2H_4$	10.51	NF <sub>3</sub>	9.17	SF <sub>6</sub>	15.50
C <sub>2</sub> H <sub>6</sub>	11.52	SiH <sub>4</sub>	13.00	Cl <sub>2</sub> sdsnill L	11.49
$C_6H_6$	9.25	Si <sub>2</sub> H <sub>6</sub>	11.66	HCl	12.74
$N_2$	15.58	P <sub>4</sub> ‡	~ 10.2	BCl <sub>3</sub>	
NH <sub>3</sub>	10.16	PH <sub>3</sub>	9.2	GeH <sub>4</sub>	
CN	14.1	PF <sub>3</sub> §	9.98	Ge <sub>2</sub> H <sub>6</sub>	~ 12.5
HCN	13.59	OPF <sub>3</sub>	11.66	AsH <sub>3</sub>	10.04
CH <sub>3</sub> NH <sub>2</sub>	8.97	CH <sub>3</sub> PH <sub>2</sub> §	12.75	H <sub>2</sub> Se	9.88
CH <sub>3</sub> ) <sub>2</sub> NH	8.24		9.12	Br <sub>2</sub>	10.51
CH <sub>3</sub> ) <sub>3</sub> N	7.81	(CH <sub>3</sub> ) <sub>2</sub> PH§	8.47	HBr	11.67
5H5N	9.27	(CH <sub>3</sub> ) <sub>3</sub> P§	8.11	SbH <sub>3</sub>	9.58
)2	12.07	P(OCH <sub>3</sub> ) <sub>3</sub> §	8.50	H <sub>2</sub> Te	9.14
1,0	12.61	S <sub>2</sub>	9.36	I <sub>2</sub>	9.39
7	12.01	S <sub>8</sub>	9.04	HI	10.39

<sup>†</sup> Except as noted, data are from H. M. Rosenstock, K. Drexl, B. W. Steiner, and J. T. Herron, J. Phys. Chem. Ref. Data, 6, suppl. 1 (1977). See Table 1.7 for atomic ionization potentials.

<sup>‡</sup> C. R. Brundle, N. A. Kuebler, M. B. Robin, and H. Basch, Inorg. Chem., 11, 20 (1972).

<sup>§</sup> R. V. Hodges, F. A. Houle, J. L. Beauchamp, R. A. Montag, and J. G. Verkade, J. Am. Chem. Soc., 102, 932 (1980).

N. Jonathan, A. Morris, M. Okuda, K. J. Ross, and D. J. Smith, Faraday Discuss. Chem. Soc., 54, 48 (1972).

# SELECTED VALUES OF THERMODYNAMIC DATA

The following table lists a few data selected from the U.S. National Bureau of Standards Technical Notes 270-3, 270-4, 270-5, and 270-6, and Interim Report NBSIR 76-1034. For much more complete sets of data, the reader should consult the latter publications, the JANAF Thermochemical Tables [NSRDS-NBS 37 (1971)], and the CODATA compilation in *J. Chem. Thermodyn.*, 10, 903 (1978).

It should be noted that other thermodynamic data are given in various tables in this text, e.g., atomic ionization potentials (Table 1.7), dissociation energies (Tables 3.9 to 3.11),  $\Delta H_f^\circ$  values for gaseous atoms (Table 3.12),  $\Delta H_f^\circ$  values for hydrides (Tables 6.1 and 6.3), proton affinities (Tables 7.1 and 7.2), pK values of acids (Tables 7.3, 7.5, and 7.7), thermodynamic constants for the ionization of aqueous acids (Table 7.12), gas-phase hydration energies (Table 7.8), electron affinities (Appendix C), and molecular ionization potentials (Appendix D).

Table E.1 Selected thermodynamic data at 25°C

-83.66

Species Example	State 20.461-	$\Delta H_f^\circ$ , kcal mol <sup>-1</sup>	$\Delta G_f^\circ$ , kcal mol <sup>-1</sup>	pa 2	S°, cal deg <sup>-1</sup> mol <sup>-1</sup>
Ag Ag <sup>+</sup> Ag <sub>2</sub> O AgO AgCI AgBr AgI	c aq 4 M HClO <sub>4</sub> - c c c c c c c c c	0 25.23 64.2 -7.42 -2.9 -30.37 -23.99 -14.78	0 18.43 64.3 -2.68 3.3 -26.24 -23.16 -15.82	o o o o o o o o o o o o o o o o o o o	10.17 17.37 -21 29.0 14 23.0 25.6 27.6

Table E.1 (Continued)

Species	State	$\Delta H_f^\circ$ , kcal mol <sup>-1</sup>	$\Delta G_f^\circ$ , kcal mol <sup>-1</sup>	S°, cal deg-1 mol-1
Al	c	0	0	6.77
Al³+ I ACI	aq // Y C	-127	VAL 611-8 O	C -76.9 [ ] T
Al <sub>2</sub> O <sub>3</sub>	c	-400.5	-378.2	12.17
Al(OH) <sub>3</sub>	amorph	-305		12.17
Al(OH) <sub>4</sub> -	aq	-356.2	-310.2	28
AIF <sub>3</sub>	C	-359.5	-340.6	15.88
AlCl <sub>3</sub>	С	-168.3	-150.3	26.45
As	c	0	0	
As <sub>4</sub>	g	34.4	22.1	8.4
As <sub>4</sub> O <sub>6</sub>	c	-314.04	-275.46	75
AsH <sub>3</sub>	g	15.88		51.2
HAsO <sub>2</sub>	aq	-109.1	16.47	53.22
H <sub>3</sub> AsO <sub>4</sub>	aq	-215.7	-96.25 -182.1	30.1
AsO <sub>2</sub> -	aq	-102.54	-183.1	44
AsO <sub>4</sub> 3-	aq	-212.27	-83.66	9.9
AsF <sub>3</sub>	g	-220.04	-155.00	-38.9
AsCl <sub>3</sub>	g	-61.80	-216.46	69.07
AsBr <sub>3</sub>	g	-31	-58.77 -38	78.17
Am	c		-38	86.94
Am(OH) <sub>3</sub>		0	0	11.33
AmCl	the U.S. Nation	- 101.5	ab we 75.77 few da	153
AmCl <sub>3</sub>	d 270-6, and in	-8.3		
AmCl <sub>4</sub> -		-28.1		Slandards Techn
Am(CN) <sub>2</sub> -		11.0	56.22	ABSIR 8.66 034
B(8161) 506 1		17	MAL 68.3 20000	the latter 14 ublic
Dielitotami	Thermodyn, M.	lation mol. Chent.	Country of the second second	(1971) 04.1d the
NO SHOULD	ata ure givergin	boim 134.5 omiod	124.0	
0203	de L7), disonia	-304.20	-285.30	36.65
H <sub>3</sub> BO <sub>3</sub>	A aq I F Alder	-256.29	-231.56	9.5 12.90 girl m
B(OH) <sub>4</sub> - BH <sub>4</sub> -	aq	-321.23	-275.65	8 0138.8 24.5
B <sub>2</sub> H <sub>6</sub> Ottaxinoi	aq ans 1.1 and	11.51	27.31	olde 26.4 objobed
	onstants for ghe	0.0	20.7	
7.8), electro	energies (Togle	271.75	-267.77	55.45
S <sub>2</sub> F <sub>4</sub> .(C) xiba:	potentials (AS po	-344.2	-337.1	86 60.71 09008
1613	g	-96.50	-92.91	375,8 situation
Br <sub>3</sub>	g	-49.15	-55.56	69.31
I <sub>3</sub>	g	17.00	4.96	77.47
a	c	nic duta of 25°C	cted thermodynan	83.43
a <sup>2+</sup>	aq	-128.50	0	15.0
oal dep m Or	C Fioni mod	-132.3	-134.02	2.3
102	C	-151.6	-125.5 state	16.83
(OH) <sub>2</sub>	c	-151.6 -225.8	443	
Cl <sub>2</sub>	c [48]	-225.8 $-205.2$	Direct P. W. C. 3	
CO <sub>3</sub>	C E43 10	-203.2 -290.7	-193.7	29.56
20.	On the late of		-271.9	26.8
+ 1919	c	0	0	2.27
2+	-26.24 ps	-91.5	-90.75	-31.0
0	A) 50 - 100	-145.7	-138.7	3.38
O <sub>2</sub> <sup>2-</sup>	aq 58.81-	-189.0	-153.0	
		61.61	100.0	-38

Table E.1 (Continued)

Species of the	State on less	$\Delta H_f^\circ$ , kcal mol <sup>-1</sup>	$\Delta G_f^{\circ}$ , kcal mol <sup>-1</sup>	S*, cal deg-1 mol-1
BeF <sub>2</sub>	c 0.001-	-245.4	-234.1	12.75
BeCl <sub>2</sub>	c A021-	-118.5	-107.3	18.12
Bi	-244.9 o	0.005-		
BiO+	aq 8.704-	429.3	U	13.56
Bi <sub>2</sub> O <sub>3</sub>	c 7.83.7	-137.16	-35.0	200
BiCl <sub>3</sub>	g ()	-63.5	110.0	36.2
BiCl <sub>4</sub> -	25.262 ps	03.3	-61.2	85.74
BiOCI	c 77777 o	-87.7	-115.1 -77.0	20.0
Bi <sub>2</sub> S <sub>3</sub>	-31.372 o	-34.2		28.8
Br <sub>2</sub>	and the second second	TO DEVINE	-33.6 ps	47.9
Br <sub>2</sub>	1 91-11	0	0	36.384
Br	g	7.387	0.751	58.641
HBr	g	26.741	19.701	41.805
Br	g	-8.70	-12.77	47.463
	aq	-29.05	-24.85	19.7
BrO-	aq	-22.5	-8.0	10
BrO <sub>3</sub> -	aq	-20.0	0.4	39.0
BrF <sub>3</sub>	g	-61.09	-54.84	69.89
BrF <sub>5</sub>	g	-102.5	-83.8	76.50
C	graphite	0	0	1.372
C	diamond	0.4533	0.6930	0.568
27 -			160.442	37.760
20 002	g 00.12-	171.291		47.219
CO <sub>2</sub>	8 2.43-	-26.416	-32.780	51.06
CO <sub>2</sub>	g	-94.051	-94.254 02.26	28.1
HCO <sub>3</sub> -	aq 0	-98.90	-92.26	21.8
$CO_3^{2-}$	aq	-165.39	-140.26	-13.6
CH4 00.27	aq	-161.84	-126.17	
2H <sub>6</sub> 4.01	g -96.541-	-17.88	-12.13 ps	44.492 54.85
F <sub>4</sub>	g 0.532-	-20.24	-7.86	
Cl <sub>4</sub>	g 1.28-	-221	-210	62.50
Cl <sub>4</sub>	1 2.511 -	-32.37	-15.60	51.72
Br <sub>4</sub>	g	-24.6	-14.49	74.03
	g 80%-	19	16	85.55
a	C	0	0	9.90
a <sup>2+</sup>		-129.74	-132.30	-12.7
aO	aq	-151.79	-144.37	9.50
a(OH) <sub>2</sub>	c	-235.68	-214.76	19.93
aCl,	C	-190.2	-178.8	25.0
aCO.	c		-269.80	22.2
aCN <sub>2</sub>	c	-288.46		
d TS	c	-83.8		12.37
	c 2811	0.71	0 ps	-17.5
12+ 8 82 -	aq 88.81	-18.14	-18.54 PM	13.1
10.19 Oi	c 0.18-	-61.7	-54.6	13.1
d(OH) <sub>4</sub> 2-	aq P.AE-		-181.3	
iF, and	c 28.65 o	-167.4	-154.8	18.5 27.55
ICI <sub>2</sub> B 25	c 0.24	-93.57	-82.21	
ICO <sub>3</sub>	c 8.51-	-179.4	-160.0	22.1
26		0 181	0	17.2
	-158.2 o	0	MARKET DEPOSIT	

Table E.1 (Continued)

Table E.1 (Continued)			(panning)	(1) kat 910g)	
Species	State on look	$\Delta H_f^\circ$ , kcal mol <sup>-1</sup>	$\Delta G_f^\circ$ , kcal mol <sup>-1</sup>	S°, cal deg <sup>-1</sup> mol <sup>-1</sup>	
Ce3+	aq   4ES -	-166.4	-160.6	-49 Tod	
Ce4+	aq · Tol-	-128.4	-120.4	-72 Do8	
CeO <sub>2</sub>	C	-260.2	-244.9	14.89	
Ce <sub>2</sub> O <sub>3</sub>	c	-429.3	-407.8	36.0	
CeCl <sub>3</sub>	C 0.811-	-251.8	-233.7	36	
Cl <sub>2</sub> M.28	g 210-4	0.00	0	53.288	
Cl	g 1.211-	29.082	25.262	39.457	
HCI 8.85	g 0.1V-	-22.062	-22.777	44.646	
CI-, HCI	aq delle	-39.952	-31.372	13.5	
Cl <sub>2</sub> O	g	19.2	23.4	63.60	
HCIO	g	-22	-18	56.5	
HCIO	aq	-28.9	-19.1	34	
CIO-	aq	-25.6	-8.8	10	
ClO <sub>2</sub> -	aq	-15.9	4.1	24.2	
ClO <sub>3</sub> -	aq	-23.7	-0.8	38 8	
ClO <sub>4</sub> -	aq	-30.91	-2.06	43.5	
CIF	g	-13.02	-13.37 DB	52.05	
CIF <sub>3</sub>	g	-39.0	-29.4	67.28	
Co	c	0	0	7.18	
Co2+	aq	-13.9	-13.0	-27	
Co3+	ag	22	32	-73	
CoO	C NAT CO	-56.87	-51.20	12.66	
CoCl <sub>2</sub>	C U01-3-5	-74.7	-64.5	26.09	
Cr 85					
Cr <sup>2+</sup>	-92.26 o	0.80-	0	5.68	
CrO <sub>3</sub>	aq 30 (M)	-34.3			
CrO <sub>4</sub> <sup>2-</sup>	aq FISI-	-140.9	1240 pa	100	
Cr <sub>2</sub> O <sub>3</sub>		-210.60	-173.96	12.00 HO	
CrCl <sub>2</sub>		-272.4	-252.9	19.4 H.O	
CrCl <sub>3</sub>	-210 <b>3</b>	-94.5	-85.1	27.56	
		-133.0	-116.2	29.4	
Cs		0	0	19.8	
Cs <sup>+</sup>	aq	-62.6	-70.8	31.8	
Cs <sub>2</sub> O	c O	-75.9			
CsO <sub>2</sub>	- c 08.861-	-62.1			
CsN <sub>3</sub>	c TEDAL-	-2.4			
CsHF <sub>2</sub>	c attall-	-219.5			
CsF CsI	c 8.871+	-131.701			
	-269.80 o	-83.7			
Cu	c	-830 8-	0 0	7.92	
Cu+ TEST	aq 0	17.13		9.7	
Cu <sup>2+</sup>	aq 18.54 ps	15.48		-23.8	
CuO	-34.6 o	-37.6	21.0	10.19 050	
Cu <sub>2</sub> O	c €.181-	-40.3	0.10	22.26	
CuCl 6.84	c 8,001-	-32.8	20 65	20.6	
CuCl <sub>2</sub>	-82.21 o	-52.6	10.0	25.83	
CuS 125	c 0.081-	-12.7	-42.0 -12.8	15.9	
CuSO <sub>4</sub>	c	-184.36	-158.2		
	Value of the same		130.2	26	

Table E.1 (Continued)

Table E.1 (Continued)

Species	State Com Land	$\Delta H_f^{\circ}$ , kcal mol <sup>-1</sup>	$\Delta G_f^\circ$ , kcal mol <sup>-1</sup>	S°, cal deg <sup>-1</sup> mol <sup>-1</sup>
F <sub>2</sub>	g 5.9-	-250	0 0	48.44
F 885	g 0.08-	18.88	14.80	37.92
F-	aq	-79.50	-66.64	-3.3
56.42 HH	g 28.32	-64.8	-65.3	41.51
HF AL 22	aq	-76.50	-70.95	21.2
HF <sub>2</sub> - 18.10	aq 1/8.0	-155.34	-138.18	22.1
F <sub>2</sub> O	g 88.901-	-5.2	-1.1	59.1
Fe 82.8	c 0.561-	0	0	6.52
Fe <sup>2+</sup> 48.81		-21.3	-18.85	-32.9
Fe <sup>3+</sup> 2.45	aq	-21.5 -11.6	-1.1	-75.5
Fe <sub>0.947</sub> O	aq	-63.64	-58.59	13.74
Fe <sub>2</sub> O <sub>3</sub>	C		-177.4	20.89
Fe <sub>3</sub> O <sub>4</sub> 19.81	c (285(+)	-197.0 $-267.3$	-177.4 -242.7	35.0
FeCl <sub>2</sub>			-72.26	28.19
FeCl <sub>3</sub>	c	-81.69	-72.26 -79.84	34.0
	254.7	-95.48		
Ge	C	0	0	7.43
Ge d.E.I	g	90.0	80.3	40.10
GeO 0.53	brown	-50.7	-56.7	12
GeO <sub>2</sub> EAOE	c -407.7	-131.7	-118.8	13.21
H <sub>2</sub> GeO <sub>3</sub>	aq	-195.73		
GeH <sub>4</sub> OV a	g	21.7	27.1	51.87
Ge₂H <sub>6</sub>	-70.22 g	38.8		
Ge <sub>3</sub> H <sub>8</sub>	g 8 EE	54.2		
GeF <sub>4</sub>	g	-284.4		
GeCl <sub>4</sub>	g	-118.5	-109.3	83.08
GeBr <sub>4</sub>	g 33.075-	-71.7	-76.0	94.66
Gel <sub>4</sub>	g	-13.6	-25.4	102.5
Ge <sub>3</sub> N <sub>4</sub>	c	-15.1		
H <sub>2</sub>			0	31.208
H	g	0	48.581	27.391
H+	g 7.801 -	52.095	0	0 61191
H-	aq 01.881-	0		OgM
U-	-199,23 B	33.39	52	
26,17	aq ZAJAI-			MgCI
Hg	-279.8 1	0 101 -	0	18.17
Hg <sup>24</sup>	aq 2.011-	40.9	39.30	-7.7 OWNSM
Hg <sub>2</sub> <sup>2+</sup>	aq	41.2	36.70	20.2
HgO	red	-21.71	-13.995	16.80
HHgO <sub>2</sub> -	aq 57.88-		-45.5	MNO THE
HgCl <sub>2</sub>	c 81.111= 0	-53.6	-42.7	34.9 Ont
Hg <sub>2</sub> Cl <sub>2</sub>		-63.39	-50.38	46.0
HgI <sub>2</sub>	INTERNATIONAL CONTRACTOR	-25.2	-24.3	43
16212	C	-29.00	-26.53	55.8
I <sub>2</sub>	0		0	27.757
10.00	C £88.801	0	4.627	62.28
0.07	g cea	14.923	16.798	43.184
50.347 IH	20.69 8	25.535		49.351
I- 66 16	12.26 8	6.33	0.41	26.6
33.5	aq 08-	-13.19	-12.33	20.0

Table E.1 (Continued)

Table E.1 (e.c	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Pagic V. I. (Continued)		
Species	State	$\Delta H_f^{\circ}$ , kcal mol <sup>-1</sup>	$\Delta G_f^{\circ}$ , kcal mol <sup>-1</sup>	S°, cal deg <sup>-1</sup> mol <sup>-1</sup>
10-	aq	-25.7	-9.2	-1.3
103- CO V	aq	-52.9	-30.6	28.3
10,-	aq a	-35.2	-2449 ps	
IF 18.14	g 220-	-22.86	-28.32	56.42
ICI CONTRACTOR	g 70.07-	4.25	-1.30	59.14
IBr	g 2/82/-	9.76	0.89	61.82
IF <sub>5</sub>	g	-196.58	-179.68	78.3
IF <sub>7</sub>	g	-225.6	-195.6	82.8
K	c	0 10	0	15.34
K+	aq	-60.32	-67.70	245
K <sub>2</sub> O	C 02.92	-86.4		
КОН	c	-101.52	3	Fenera C
KF	c rese	-135.58	-128 53	15 01
KI	C ACCE	-78.37	-128.53	15.91
K <sub>2</sub> SO <sub>4</sub>	c system	-343.69		
K <sub>2</sub> CO <sub>3</sub>	c	-275.0	-254.7	27.4
				37.4
La 01.04 La <sup>3+</sup> 01	c £.68	0,00	0	13.6
	aq x	-169.0	-163.4	-52.0
La <sub>2</sub> O <sub>3</sub>	c 8.811-	-428.7	-407.7	30.43
LaCl <sub>3</sub>	С	-256.0		
Li 18.16	c 27.1 c	0.15	0	6.70 Ha
Li+	aq	-66.55	-70.22	3.4 Head
Li <sub>2</sub> O	c	-142.4	-133.8	8.97 H.50
Li <sub>2</sub> O <sub>2</sub>	c	-151.7	135.6	0.97 GeF.
LiN <sub>3</sub>	c 6.001-	2.6		GeCl.
Li <sub>2</sub> CO <sub>3</sub>	c 0.31-	-290.54	-270.66	21.60 nBs0
LiF CAUL	-25.4 o	-147.1	270.00	21.00
LiI	c	-64.6	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Ge <sub>3</sub> N <sub>e</sub>
Mg 805/15	c			
Mg <sup>2+</sup>		0	0 8	7.01
MgO	aq	-111.58	-108.7	-33.0
$Mg(OH)_2$	c	-143.81	-136.10	6.44
MgCl,	C C	-220.97	-199.23	15.10
MgSO <sub>4</sub>		-153.28	-141.45 PA	21.42
$Mg(NO_3)_2$	c	-307.1	-279.8	21.9 (gH
	C 05.08	-188.97	-140.9	39.2
Mn	c 07.08	0	O pu	7.65
Mn <sup>2+</sup>	aq	-52.76	-54.5 ben	-176 OSH
MnO	c	-92.07	-86.74 PM	14.27
$MnO_2$	c	-124.29	-111.18	12.68 DaH
MnO <sub>4</sub> -	aq	-129.4	-106.9	457
MnCl <sub>2</sub>	c	-115.03	-105.29	28 26
V.	9 66,00-	0	105.25	Told I will
12012112	g		0	45.77
62.28 -		112.979	108.883	36.622
0.154 01	ad con at	65.76	83.2	25.8
10, 126.04	5	21.57	20.69	50.347
$O_2^-$	B	7.93 -25.0	12.26	57.33
101	aq	- 15 ()	-8.9	33.5

Table E.1 (Continued)

Species Species	State from lead	$\Delta H_f^{\circ}$ , kcal mol <sup>-1</sup>	$\Delta G_f^\circ$ , kcal mol <sup>-1</sup>	S°, cal deg <sup>-1</sup> mol <sup>-1</sup>	
NO <sub>3</sub> - SCOL 24	-54.634 pa	-49.56	-26.61	35.0	
26.2 O <sub>2</sub> N	g 87.85—	19.61	24.90	52.52	
N <sub>2</sub> O <sub>3</sub>	g 11. ASSES -	20.01	33.32	74.61	
N <sub>2</sub> O <sub>4</sub> SR O	i o	-4.66	23.29	50.0	
N <sub>2</sub> O <sub>4</sub>	g - 2.9 m	2.19	23.38	72.70	
$N_2O_5$	c	-10.3	27.2	42.6	
N <sub>2</sub> O <sub>5</sub> 801.52	24.8 0 B	2.7	27.5	85.0	
NH <sub>3</sub> 98.30	5.85 g	-11.02	-3.94	45.97	
NH <sub>3</sub>	243.5 ps	-19.19	-6.35	26.6	
$N_2H_4$	1	12.10	35.67	28.97	
N <sub>2</sub> H <sub>4</sub> 07 A2	aq gala-	8.20	30.6	33	
N <sub>2</sub> H <sub>4</sub> SS.08	Mary Mary Control of the Control of	22.80	38.07	56.97	
NH <sub>4</sub> +	aq	-31.67	-18.97	27.1	
$N_2H_5^+$	aq	-1.8	19.7	36	
HN <sub>3</sub>		62.16	76.9	34.9	
HNO <sub>2</sub>		-28.5	-13.3	36.5	
NH OH	URV	-27.3	-8,000 pm		
NF <sub>3</sub>	-260.34 s	-29.8	-200	62.29	
$N_2F_4$	g	-1.7	19.4	71.96	
NCL	g	55		- 09	
NOF	-260.17 g f	-15.9	-12.2	59.27	
NOCI	273,10 4 g	12.36	15.78	62.52	
NH₄F 85.28	-214.5 B	-110.89	-83.36	17.20	
NH <sub>4</sub> Cl e.te	0 1 23 0	-75.15	-48.51	22.6	
NH <sub>4</sub> Br	o sall	-64.73	-41.9	27	
NH4I LIE8	0 0 00	The state of the s	-26.9	28	
SMIT	c	-48.14		12.24	
Na Na III. 18	c ag 0.57-11	0 308	0	14.1	
Na <sup>+</sup>	aq	-57.39	-62.59	14.1	
Na <sub>2</sub> O	c ac 4.11-	-99.7			
Na <sub>2</sub> O <sub>2</sub>	c g c.0	-122.30			
NaOH	c	-101.72			
NaF PLE	c	-137.11	0.1	17.22	
NaCl	-5.83 °	-98.27	-91.84	17.33	
NaI	-45.16 PB 2	-68.78	bot bot		
Na <sub>2</sub> SO <sub>4</sub>	-51.95 2 o	-331.52	-303.39	35.73	
Na <sub>2</sub> CO <sub>3</sub>	00.08	-270.4	-250.5	32.5	
Ni Sa	- 108. Useld	0	0	7.14	
Ni <sup>2+</sup>	75.08 6	0 00 28	-10.9	-30.8	
NiO S PT. IA	aq 06.14-	-12.9 -57.3	-50.6	9.08	
Ni(OH) <sub>2</sub>	C		-106.9	21	
Ni(NH) 2+	o =67.87 os so	-126.6	-61.2	94.3	
Ni(NH <sub>3</sub> ) <sub>6</sub> <sup>2+</sup> Ni(CN) <sub>4</sub> <sup>2-</sup>	aq	-150.6	122.8	52	
	aq	87.9		49.003	
O <sub>2</sub>	g	0	0	29 167	
0	g	59.553	55.389	57.08	
$O_3$	g	34.1	39.0		
OH-		-33.67	25 504	-2.57	
22.92 -нО	The second secon	-54.970	-37.594	16.71	
28.30 O <sub>2</sub> H	aq 00.87	-68.315	-56.687	10.71	

Table E.1 (Continued)

Table E.1 (Continueu)			( materi	(Com
Species Species	State Town Work	$\Delta H_f^o$ , kcal mol <sup>-1</sup>	$\Delta G_f^{\circ}$ , kcal mol <sup>-1</sup> state	S°, cal deg <sup>-1</sup> mol <sup>-1</sup>
H <sub>2</sub> O	g 10.61-	-57.796	-54.634	45.10 -,0
$H_2O_2$	24:90 1	-44.88	-28.78	26.2
$H_2O_2$	g SELE	-32.58	-25.24	55.6
P	white	0 00 4-	0	9.82
P 00.57	red	-4.2	-2.9	5.45
P 0.54	g	79.8	2.7.89	0,40
P <sub>2</sub> 0.88	9	34.5	24.8	52.108
P <sub>4</sub>	g	14.08	5.85	66.89
PO <sub>4</sub> 3-	aq	-305.3	-243.5	-53
P4O6	c	-392.0	-67.70	Jan Ha
P4O10	hexagonal	-713.2	-644.8	54.70 H
PH <sub>3</sub>	g (0.88	1.3	3.2	50.22
P <sub>2</sub> H <sub>4</sub>	g 19.81-	5.0	20 - 128_53 - pg	30.22
H <sub>3</sub> PO <sub>3</sub>	c	-230.5	DE	1,H <sub>2</sub> )
H <sub>3</sub> PO <sub>3</sub>	aq 9.07	-230.6	ps	
HPO <sub>3</sub> <sup>2-</sup>	aq & El-	-231.6	-284.7 ps	INO, 171
HPO <sub>4</sub> <sup>2-</sup>	aq	-308.83	-260.34	-8.0 HO,H
H <sub>2</sub> PO <sub>2</sub> -	aq -20.0	-146.7	200.31	VIII.
H <sub>2</sub> PO <sub>3</sub> -	aq A-01	-231.7	3	J.F.
H <sub>2</sub> PO <sub>4</sub> -	aq	-309.82	-260.17	21.6
H <sub>3</sub> PO <sub>4</sub>	aq	-307.92	-273.10	37.8
F <sub>3</sub> 05.71	g 87.57	-219.6		DOI DOI
PCl <sub>3</sub>			-214.5	65.28 a HV
PCl <sub>3</sub>	16,00	-76.4 -68.6	-65.1	51.9
PBr <sub>3</sub>	g 9.14-	-33.3	-64.0	74.49 -8.HV
PF.	g	-381.4	-38.9	83.17 LH
PCI,	g	-89.6	-73.0	07.11
PH <sub>4</sub> Cl	-62:59 o	-34.7	-73.0	87.11
PH₄Br	c	-30.5		0.0
PH₄I	c	-16.7	11.7	26.3
Pb			0.2	29.4
DL 24	c	-137110	0	15.49
PbO	aq 48.19—	-0.4	-5.83	2.5
DI O	red	-52.34	-45.16	15.9
PbO <sub>2</sub> HPbO <sub>2</sub> -	C 96,60E-	-66.3	-51.95	16.4
Pb(OH) <sub>2</sub>	_250.5 ps		-80.90	
PbCl <sub>2</sub>	c		-108.1	12.65 IV
PbI <sub>2</sub>	c	-85.90	-75.08	32.5
	50.6	-41.94	-41.50	41.79
Rb	c 0.801-	0	- 0	18.35 (HOW
Rb+ 0. 8.10	aq	-60.03	-67.97	29.04
RbO <sub>2</sub>	C SECI	-66.6	P4	29.04 (1/12)
Rb <sub>2</sub> O	C	-81		
Rb <sub>2</sub> O <sub>2</sub>	C 098 22	-112.8		
BOH	C O.O.	-99.95		36.622 0
br	C	-133.3	852 8	
bCl	c 492 rs-	-104.05	-97.47	22.92
Ы	c 738.88-	-79.77	-78.60 PA	28.30
			70.00	20.50

Table E.1 (Continued)			$\Delta G_f^{\circ}$ ,		S°,		
Species gob ho	State	AG, keal mol	$\Delta H_f^\circ$ , kcal mol <sup>-1</sup>	kcal mol-1		cal deg-1 n	nol-1
	-	=204.75	-343.12	-314.76		47.19	
Rb <sub>2</sub> SO <sub>4</sub> 00 01	c	-314.7	-271.5	-251.1		43.34	
Rb <sub>2</sub> CO <sub>3</sub>			0 23	0		7.60	di
88.84	rhomb	oic Sic		56.9		40.094	Me
65.14 452	g		66.6 7.9	20.5		-3.5	
S2-	aq	-375.9	30.68			54.51	
S <sub>2</sub>	g		24.45	11.87		102.98	
38	g	-147.5	1.5	-4.7		53.02	
30	g	-103.2	-70.944	-71.748	3	59.30	
302	g	-153.6		-88.19	3	12.5	N
24.2 602	$\beta$ -c	0.81	-108.63 $-94.58$	-88.69		61.34	
303	g		-77.194	-71.871 suid		38.7	
SO <sub>2</sub> SESI	aq		-151.9	-116.3 V		-7	
SO <sub>3</sub> <sup>2-</sup> 22.01	aq	0.03	-131.9 -149.67	-126.15	2	33.4	
40.24 - OSH	aq	63.9	-212.08	-180.69		31.5	
HSO <sub>4</sub> -	aq	-6.5	-217.32	-177.97		4.8	0
SO <sub>4</sub> 2-	aq	-61.4	-4.93	-8.02		49.16	
H <sub>2</sub> S	g	- 124,2	-7.85				
H <sub>2</sub> S <sub>4</sub> 85 -	1	0.6	-8.85				
H <sub>2</sub> S <sub>6</sub> QE 12	1	45,0	-4.7 SIL				,D
SCl <sub>2</sub> 4.78	g		-185.2	-174.8	8	69.77	
SF4 E4.80	g	-79.2	-183.2 -289	-264.2		69.72	
SF <sub>6</sub>	g	0		0	ps	10.92	
Sb 8.7 -	С	-133.71 -	-130.450	53.1		43.06	
Sb O.E.	g	-134.3	62.7	33.8		84	
Sb <sub>4</sub>	g		49.0	35.31		55.61	
SbH <sub>3</sub>	g		34.681	-42.33			
SbO+	aq	<b>-186.7</b>	1.801-	-81.32			
SbO <sub>2</sub> -	aq		5,192-	-97.4		11.1	
HSbO,	aq	0	-116.6	−72.0		80.71	
SDC13	g	37.55	-75.0	-53.5		89.09	
SbBr <sub>3</sub>	g	CC.16	-46.5			8.28	
Sc 0.et	c		-77.1 0	0		-61	
Sc3+			-146.8	-140.2	pa	18.4	
Sc <sub>2</sub> O <sub>3</sub>	aq		-456.22	-434.85	2		
Soci	c		-221.1		2	10 144	
	С	0	-164.9 0	0		10.144	
Se	blac		54.27	44.71		42.22 52.32	
Se 11.8	g	-118.3	7.18.200	3.8	3	32.32	
H <sub>2</sub> Se E0.5.1	g	-212.6	-53.86			49.7	
SeO <sub>2</sub> 0.00	С	0.111	-121.29	-101.87	12		
H <sub>2</sub> SeO <sub>3</sub> A.E.E	aq	-156.2	-143.2	-105.5		12.9	
SeO <sub>4</sub> 2-	aq	-173.7	-7.6				
SeCl <sub>2</sub>	g				2		
SC <sub>2</sub> Cl <sub>2</sub>	g		Marian Distriction of the Control of				3 44
SC <sub>2</sub> Br <sub>2</sub>	g	-106.7	K1107 P	0		4.50	
Si 1.01		-140.3	-155.3 0	98.3		40.12	
Si	g	-214.9	108.9	-30.2		50.55	Hy
SiO	g	110-	-23.8				

Table E.1 (Continued)

Table E.1 (Continued)			Table E.1 (Continued)		
Species Sphilips	State Flore (see	$\Delta H_f^{\circ}$ , kcal mol <sup>-1</sup>	$\Delta G_f^\circ$ , kcal mol <sup>-1</sup>	S°, cal deg <sup>-1</sup> mol <sup>-1</sup>	
SiO <sub>2</sub>	quartz of AlE-	-217.72	-204.75	Rb.50, 00.01	
H <sub>4</sub> SiO <sub>4</sub>	-231.1 ps	-351.0	-314.7	Rb <sub>2</sub> CO <sub>2</sub> 84	
SiH <sub>4</sub>	g	8.2	13.6	48.88	
Si <sub>2</sub> H <sub>6</sub>	g 6.95	19.2	30.4	65.14	
Si <sub>3</sub> H <sub>8</sub> SiF <sub>4</sub>	g 2.05	28.9	-20 pa	-8	
C: E 2-	g 8981	-386.0	-375.9	67.49	
0.01	aq 78.11	-571.0	-525.7	29.2	
C.D	g	-157.0	-147.5	79.02	
C' NI	P71.748	-99.3	-103.2	90.29	
0.0	C 0-88-	-177.7	-153.6	24.2	
	cubic ed.88-	-15.6	-15.0	3.97	
Sn T.88	white White	-77.190	0 12 ps	12.32	
Sn	gray (d)	-0.50	0.03	10.55	
Sn 4.88	- 126.15 g	72.2	63.9 ps	40.24 - OZH	
Sn <sup>2+</sup>	aq HCl	-212.01.5-	-6.5 ps	-4 -OZH	
SnO	c TRATT	-68.3	-61.4 pa	13.5	
SnO <sub>2</sub>	-8.02 o	-138.8	-124.2	12.5 2.H	
Sn <sup>4+</sup>	aq HCl	7.3	0.6	-28 2H	
SnH <sub>4</sub>	g	38.9	45.0	54.39	
SnCl <sub>4</sub>	g	-112.7	-103.3	87.4	
SnBr <sub>4</sub>	g 8,401-	-75.2	-79.2	98.43	
Sr	-2642 o	-289 0		112	
Sr2+ 100	aq 0		-0 4.5	12.5	
SrO ME	c 1.68	-130.450 -141.5	-133.71	-7.8 dZ	
SrO <sub>2</sub>	c see	-141.5 -151.4	-134.3	13.0	
Sr(OH) <sub>2</sub>	35.31 0		38.9 8	Sp. 41 ER	
SrCl <sub>2</sub>	c EE.33 o	-229.2 -198.1	8	HdS	
SrCO <sub>3</sub>	c SE.18-	-291.6	-186.7 pa	27.45	
Ге			-272.5 pg	23.2	
Ге 17.08	000	0	0 11.4 pa	11.88 AMEH	
H <sub>2</sub> Te 00.08	g	47.02	37.55	43.65	
ΓeO <sub>2</sub> 85.8	g	23.8	3	SpB13 68 co.ch	
ΓeO <sub>3</sub> <sup>2-</sup>	c 0	77.1	-64.6	19.0	
ΓeF <sub>6</sub> 4-81	aq 2021 —	-142.6	-45 (6 PB	Sc2+ 0 11	
	g 434.85 g	-31500,024-	-41.05 0	Sc.O 01	
Гі	c	-221.1 0	0 20 20 2		
ΓiO <sup>2+</sup>	aq	-164.9	blackl 201 m	7.32	
rio Oi	c 4 17.44	-124.2	11000000		
TiO <sub>2</sub>	C 8 8 8	-225.8	2126 50	0.51	
CiCl <sub>2</sub>	C	-122.8		12.03 20.9	
iCl <sub>3</sub> 7.04	c 78.101	-172.3	-111.0		
iCl <sub>4</sub> est	g 2.201-	-182.4	-156.2 7.67 ps	33.4	
Red	c	-7.6 0	-173.7 ps	84.8	
0	c		0	6.91	
O <sup>2+</sup>	aq	-103.2	-96.6	9.3	
O <sub>2</sub> + 08.4	aq	-116.3	-106.7	-32.0	
043-101.01	aq Ese	-155.3	→140.3	-10.1	
O <sub>7</sub> 4- 22.02		108.801	-214.9	12.92 13	
	aq 5.0%—36.2	-23.8	-411 78.00		

Table E.1 (Continued)

Species	State	$\Delta H_f^\circ$ , kcal mol $\exists^1$	$\Delta G_f^{\circ}$ , kcal mol <sup>-1</sup>	S°, cal deg-1 mol-1
VCl <sub>2</sub>	c	-108	-97	23.2
VCl <sub>3</sub>	С	-138.8	-122.2	A 5 31.3 ( )
VCl <sub>4</sub>	g	-125.6	-117.6	86.6
Zn	С	0	0	9.95
Zn <sup>2+</sup>	aq	-36.78	-35.14	-26.8
ZnO	С	-83.24	-76.08	10.43
$Zn(OH)_4^{2-}$	aq		-205.23	
ZnF <sub>2</sub>	c	-182.7	-107.5	17.61
ZnCl <sub>2</sub>	С	-99.20	-88.30	26.64
ZnCO <sub>3</sub>	С	-194.26	-174.85	19.7

			ne elements†	lonic radii of th	Lit altig
				Coords-	
			Radius		
		661		pisamun	
		11386	1.12	0	
LEX.				2 2.3	
	pz 4	TOA IV	00.1		
			1.02		
0.57			60.1		
10.0					
			1.28	7 8	
\$2.P			0.79	4 sq   1 m	
1,38			0.94	9 8	
	8		19.00	pe pe A	
TRH					
	0.6				31924
1,87					
			0.635		
		958	1,21		
			1.26		
	4.03 8				
	2				
1.03	115 0				
1.17					
	4 8				
			0.58		
	1. 15 0	7:48i		2 1	
E9:01					

#### **IONIC RADII**

Table F.1 Ionic radii of the elements†

Ion	Coordi- nation number‡	Radius, Å	Ion	Coordination number	98.43	Radius,
Ac3+	6	1.12	At7+	1.3	1111	0.62
Ag <sup>+</sup>	2	0.67	Au+	6		0.62
	4	1.00	Au <sup>3+</sup>	6		1.37
	4 sq	1.02	Au	4 sq		0.68
	5	1.09	Au <sup>5+</sup>	6		0.85
	6	1.15	B3+	6		0.57
	7	1.22	D	3		0.01
	8	1.28		4		
Ag <sup>2+</sup>	4 sq	0.79	D-24	6		0.27
	6	0.94	Ba <sup>2+</sup>	6		1.35
Ag <sup>3+</sup>	4 sq	0.67		7		1.38
	6	0.75		8		1.42
Al3+	4	0.39		9		1.47
	5	0.48		10		1.52
	6	0.535		11		1.57
Am <sup>2+</sup>	7	1.21	-219	12		1.61
	8	1.26	. Be <sup>2+</sup>	3		0.16
	9	1.31		4		0.27
4m³+	6			6		0.45
	8	0.975 1.09	Bi <sup>3+</sup>	5		0.96
m4+	6			6 5 6		1.03
	8	0.85				1.17
S <sup>3+</sup>	6	0.95	Bi <sup>5+</sup>	8		0.76
S <sup>5+</sup>	4	0.58	Bk³+	6		0.96
	6	0.335	Bk <sup>4+</sup>	6		0.83
	O The state of the	0.46		8		0.93

Table F.1 (Continued)

Ion A	Coordi- nation number	Radius,	Ion A	Coordination number	Radius,
Br-	. 6	1.96	16.1	6 HS	0.53
Br3+	4 sq	0.59	Cr2+	6 LS	0.73
Br5+	3 0	0.31	0.08	HS 0	0.80
Br7+		0.25	Cr3+	6 2114	0.615
	6	0.39	Cr4+	48H pe 1	0.41
C4+	3	-0.08	(3)14.0	6 213	0.55
	4	0.15	Cr5+	HS A	0.345
	6	0.16	0.99.0	6 8118	0.49
Ca2+	6	1.00	- D.04.D	4 HS 8	0.57
	7	1.06	Cr6+	4	0.26
	8	1.12	0.58%	6 21	0.44
	9	1.18	Cs <sup>+</sup>	6 2H	1.67
	10	1.23	0.78	8 SH 8	1.74
	12	1.34	0.565	9	1.78
Cd2+	4	0.78	(£25m)	10	1.81
	5	0.87	08.1	11 0	1.85
	6 01	0.95	(1.49.4)	12	1.88
	7 5	1.03	Cu+	2	0.46
	8	1.10	0.620	4	0.60
	12	1.31	1889.0	6	0.77
Ce3+	6	1.01	Cu <sup>2+</sup>	4	0.57
	7	1.07	120.1	4 sq	0.57
	8	1.143	13.00	5	0.65
	9	1.196	0.73	6	0.73
	10	1.25	Cu <sup>3+</sup>	6 LS	0.54
	12	1.34	D+	2	-0.10
Ce4+	6	0.87	Dy <sup>2+</sup>	6	1.07
	8	0.97	\$481.0 -	7	1.13
	10 2/14	1.07	92.0	8	1.19
	12 2112	1.14	Dy <sup>3+</sup>	6	0.912
Cf3+	6 814	0.95	0.76	7	0.97
Cf4+	6	0.821	9.28.0	8	1.027
	8	0.92	0.00.0	9	1.083
CI-	6	1.81	Er3+	6	0.890
Cls+	3 py	0.12	0.68-0	7	0.945
C17+	4 213	0.08	1/400.0	8	1.004
610.0	6 2H	0.27	P.SG.L	9	1.062
Cm3+	6	0.97	Eu <sup>2+</sup>	6	1.17
Cm4+	6	0.85	100.0	97	1.20
(多6.0)	8	0.95	1.0151	8	1.25
Co2+	4 HS	0.58	1,072	9	1.30
	5	0.67	1.124	10	1.35
0.469	6 LS	0.65	Eu³+	6	0.947
	HS	0.745	68.0	17 m4	1.01
0.650	8	0.90	20.0	8	1.066
C03+	6 LS	0.545	p-95.0	9	1.120
18,0	HS	0.61	Ft 0	2	1.285
Co4+	4	0.40	P428.0	3	1.30

Table F.1 (Continued)

	Coordi-	The state of the s		Con-1:	Table F.1
	nation	Radius,	Radius	Coordi-	
lon A	number	Å Mai	Ion	nation number	Radius.
eau .	4 200	1.21			
	6 210	1.31	1.56	6	0.800
F7+	6 -211	0.08	0.59	8 pe.l.	0.92
Fe <sup>2+</sup>	4 HS	0.63	Ir3+0	6 48	0.68
	4 sq HS		Ir4+0	6	0.625
	6 LS	0.64	Ir5+0	6	0.57
	HS	0.780	K+,0-	4 &	1.37)
	8 HS	0.780	0.15	6	1.38
Fe3+	4 HS	0.49	01.0	7	1.46
	5		00.1	8	1.51
	6 LS	0.58	30,1	9	1.55
	***	0.55	SIJ.	10 8	1.59
		0.645	81.1	12	1.64
e4+	8 HS 6	0.78	La <sup>3+</sup>	6 01	1.032
e6+		0.585	1.34	7 51	1.10
r+		0.25	0.78	8	1.160
Ga <sup>3+</sup>		1.80	1.480	9	1.216
14.0	5	0.47	0:95	10	1.27
		0.55	1,03	12	1.36
Gd <sup>3+</sup>		0.620	Li+	4 2	0.590
2.0	7	0.938	16.1	6	0.76
	0	1.00	10.1	8	0.92
	9	1.053	Lu³+	6	0.861
Ge <sup>2+</sup>		1.107	E-1414	8	0.977
ie <sup>4+</sup>		0.73	004.1	9	1.032
		0.390	Mg <sup>2+</sup>	4 01	0.57
<b>!</b>		0.530	463	5 00 21	0.66
		-0.38	9.87	6	0.720
[f 4+		-0.18	6.97	8	0.89
00	4 8	0.58	Mn <sup>2+</sup>	4 HS	0.66
en	6	0.71	ALI	5 HS	0.75
	7	0.76	0.95	6 LS	0.67
g <sup>+</sup>	8	0.83	15820	***	0.830
5	3	0.97	0.92	7 HS	0.90
g <sup>2+</sup>	6	1.19	18.1	Control of the Contro	0.96
5	2	0.69	Mn³+		0.58
	4 8	0.96	80.0		0.58
	6	1.02	0.27		0.645
03+	8	1.14	Mn <sup>4+</sup>		0.39
	6	0.901	880		0.530
	8 8	1.015	Mn <sup>5+</sup>	6 4	0.33
		1.072	Mn <sup>6+</sup>		0.255
	10 01	1.12	Mn <sup>7+</sup>	4 211 4	0.25
	6	2.20	0.65	4	
	3 py	0.44	Mo <sup>3+</sup>	6 210	0.46
J	6	0.95	Mo <sup>4+</sup>	6 SH	
	4	0.42	Mo <sup>5+</sup>	6	0.650
	6	0.53		4 219	0.46
HI.	4			6 SH	0.61

Table F.1 (Continued)

Radins, Ion A	Coordi- nation number	Radius, À nof	Ion A	Coordi- nation number	Radius,
1,27	5 8	0.50	0.80	3	1.34
	6	0.59	0.623	4	1.35
	7	0.73	0.57	6	1.37
N3-	4	1.46	Os <sup>4+</sup>	6	0.630
N3+	6	0.16	Os <sup>5+</sup>	6	0.575
N5+	3	-0.104	Os <sup>6+</sup>	5	0.49
1.24	6	0.13		6	0.545
Na+	4	0.99	Os <sup>7+</sup>	6	0.525
	5	1.00	Os <sup>8+</sup>	4	0.39
	6	1.02	P3+	6	0.44
	7	1.12	P5+	4	0.17
	8	1.18		5	0.29
	9	1.24		6	0.38
1.21	12	1.39	Pa <sup>3+</sup>	6	1.04
Nb3+	6 8	0.72	Pa <sup>4+</sup>	6 01	0.90
Nb4+	6	0.68	981	8	1.01
	8	0.79	Pa5+	6	0.78
Nb5+	4	0.48		8	0.91
0.72	6	0.64	68.0	9	0.95
	7	0.69	Pb <sup>2+</sup>	4 py	0.98
16.0	8	0.74	33 /	6	1.19
Nd <sup>2+</sup>	8	1.29		7	1.23
	9 8	1.35		8	1.29
Nd3+		0.983		9	1.35
	8	1.109	0.665	10	1.40
040.1	0	1.163		11	1.45
		1.27		12	1.49
Vi2+	4	0.55	Pb <sup>4+</sup>		0.65
	A second	0.49		5	0.73
0.645	F			6	0.775
		0.63	0.38	8	0.94
Ni <sup>3+</sup>	(10	0.690	Pd+	2	0.59
	HS	0.56	Pd <sup>2+</sup>	4 sq	0.64
Vi⁴+	6 LS	0.60	ru	6	0.86
No <sup>2+</sup>	6	0.48	Pd³+	6	0.76
Vp2+	6	1.1	Pd <sup>4+</sup>	6	0.615
Vp3+	6	1.10		6	0.97
Np4+	0	1.01	Pm3+,0	8	1.093
	0	0.87		9	1.144
Np5+	8	0.98	08.0		0.94
Vp6+	6	0.75	Po <sup>4+</sup>	0	1.08
Np7+	6 8	0.72	0.870		0.67
)2-	6	0.71	Po <sup>6+</sup>	(	0.99
	2 01	1.35	Pr3+	6	1.126
1.18		1.36		8	1.179
1.21	4	1.38	0.42	9	0.85
	0	1.40	Pr4+00	6	0.83
OHT.	8	1.42	0.400	8	0.90
29.0	2	1.32	Pt2+	4 sq	0.60

Table F.1 (Continued)

Table F.1 (Continued)				able F.1 (Continued)	
Radius, A noI	Coordi- nation number	Radius, Å	Ion A	Coordination	Radius,
1.34	6	0.80	0.50		
Pt4+	6	0.625	98.0	8	1.27
Pt5+	6	0.57	Sm3+ 0	9	1.32
Pu <sup>3+</sup>	6	1.00	Sin	6	0.958
Pu <sup>4+</sup>	6	0.86	8 81.0	7	1.02
	8	0.46	-0.104	8	1.079
Pu <sup>5+</sup>	6	0.74	ELD	9	1.132
Pu <sup>6+</sup>	6	0.71	Sn <sup>4+</sup>	12	1.24
Ra <sup>2+</sup>	8	1.48	311.00	4	0.55
	10	1.70	1.02	5 6.	0.62
Rb+	6	1.52	SLI	6	0.690
0,29	7 8	1.56		70	0.75
	8	1.61		8 8	0.81
	9	1.63	Sr <sup>2+</sup>	6	1.18
	10	1.66	0.72	7 - 1	1.21
	11 8	1.69	88.0	8	1.26
	12	1.72	0.79	9	1.31
	14	1.83	81.0	10 8	1.36
Re4+	6	0.63		12	1.44
Re <sup>5+</sup>	6 494	0.58	Ta <sup>3+</sup>	6	0.72
Re <sup>6+</sup>	6	0.55	Ta <sup>4+</sup>	6	0.68
Re7+	4	0.38	Ta <sup>5+</sup>	6	0.64
	6	0.53		7	0.69
₹h³+	6	0.665	<b>71</b> 20 5	8	0.74
₹h⁴+	6	0.60	Tb <sup>3+</sup>	6	0.923
h5+	6	0.55		7 8	0.98
₹u³+	6	0.68		8 - 6	1.040
Ru4+	6	0.620	771	12 9	1.095
lu5+	6	0.565	Tb⁴+	6	0.76
Lu <sup>7+</sup>	4	0.38	T 444.0	8 2 2	0.88
.u <sup>8+</sup>	4 8	0.36	Tc4+	6	0.645
-4c.0	6	1.84	Tc5+	6	0.60
+ 69.0	6 08 4	0.37	Tc7+	4 13 213	0.37
5+0X.U	4 0	0.12		6 2H	0.56
	6	0.29	Te <sup>2</sup>	6 210	2.21
D <sup>3+</sup>	4 py	0.76	Te <sup>4+</sup>	3	0.52
E80.1	5	0.80	10.1	4	0.66
	6	0.76		6	0.97
) <sup>5+</sup>	6	0.60	Te <sup>6+</sup>	4	0.43
3+	6	0.745	m 3.7 0	6 8	0.56
	8	0.870	Th <sup>4+</sup>	6	0.94
2-0.0	6	1.98	M4730	8	1.04
479.0	6	0.50	1.35	9	1.09
6+	4	0.28		10	1.13
	6	0.42	185.1	. 11 €	1.18
<b>₽</b> 8.0	4	0.26		12	1.21
	6	0.400	Ti <sup>2+</sup>	6	0.86
12+	7 pa to	1.22	Ti <sup>3+</sup>	6	0.670
		1.22	Ti <sup>4+</sup>	4 \$	0.42

Table F.1 (Continued)

Ion	Coordi- nation number	Radius, Å	Ion	Coordination number	Radius, Å
chloride,	5	0.51 TA	V5+	MANUAR	9 0.355
	6	0.605		5	0.46
	8	0.74	DUNDANT SERVICE	6	0.54
TI+	6	1.50	W4+	6	0.66
	8	1.59	W5+	6	0.62
	12	1.70	W6+	4	0.42
Tl3+	4	0.75		5	0.51
	6	0.885		6	0.60
	8	0.98	Xe <sup>8+</sup>	4	0.40
Tm <sup>2+</sup>	6	1.03	d complex si	6	0.48
	8	1.09	Y3+	6	0.900
Tm3+	6	0.880	and the second	7	0.96
	8	0.994		8	1.019
	9	1.052	IN THE CALCULAR	9	1.075
U3+	by 6 by the ma	1.025	Yb2+	6	1.02
U4+	rule 6 plains a	0.89	more of that	7 7 7 60 0	1.08
	7	0.95		8	1.14
	8	1.00	Yb³+	6	0.868
	9	1.05	THE REAL PROPERTY.	7	0.925
	12	1.17	BATHARMO AR	8	0.985
U5+	nic chemity's inc	0.76	sombonness	9	1.042
MIRE alo	mia dirw. ahmu	0.70	Zn2+	lonara treun 10	0.60
U6+ 0022	the difficulties	0.64	concluture sel	Rules of non	0.68
The mobile	2	0.43	pounds with	moo 6avon min	0.740
	mis 40ki komi			la as 8 va ad at tr	0.90
mos sink	n namingonor	0.73	7-4+	4	0.59
i from th	ted and adapted	0.81	paragraphs ha	Survionor au 1	0.66
V2+ 1011	omenclation of	0.86	stional Comm	ed by the artern	0.72
V3+	CONTRACTOR OF THE PARTY OF THE	0.79	acrican assac	y. Current An	0.78
V4+	6 6	0.640	and overd spirm	nis text, a f.8v libe	0.84
AT THIN SEL	he author believ		THE PLANE DEL	coo 9as robers	0.89
	6	0.58	c the cupieu	ALICA MANAGEMENT	
200	8	0.72			- discussion and the

<sup>†</sup> The "traditional" scale of ionic radii, as tabulated by R. D. Shannon, Acta Crystallogr., A32, 751 (1976). "Effective ionic radii," which probably correspond more closely to the physical sizes of ions in solids, can be obtained from the traditional values by adding 0.14 to the cation radii and subtracting 0.14 from the anion radii.

Numericlature of Inorganic Chemistre 2d ed. Butterwork, London, 1971 also see Fure April

sq and py indicate square and pyramidal coordination, and LS and HS indicate low- and high-spin states.

# INORGANIC NOMENCLATURE

As the complexity of the compounds studied by inorganic chemists increases, the difficulty of unambiguously describing these compounds with simple names increases. Rules of nomenclature seldom anticipate the difficulties associated with naming novel compounds with unusual structures. Nevertheless, it is important to be aware of the approved conventions for naming inorganic compounds. The following paragraphs have been excerpted and adapted from the rules issued by the International Commission on the Nomenclature of Inorganic Chemistry. Current American usage differs from these rules in some respects, and, in this text, a few liberties have been taken which the author believes will not cause the reader any confusion.

# FORMULAS AND NAMES OF COMPOUNDS IN GENERAL

In formulas the "electropositive constituent" (cation) should always be placed first, e.g., KCl, CaSO<sub>4</sub>. In the case of binary compounds between nonmetals, in accordance with established practice, that constituent should be placed first which appears earlier in the sequence Rn, Xe, Kr, B, Si, C, Sb, As, P, N, H, Te, Se, S, At, I, Br, Cl, O, F.

Examples: XeF<sub>2</sub>, NH<sub>3</sub>, H<sub>2</sub>S, S<sub>2</sub>Cl<sub>2</sub>, Cl<sub>2</sub>O, OF<sub>2</sub>

<sup>&</sup>quot;Nomenclature of Inorganic Chemistry," 2d ed., Butterworth, London, 1971; also see *Pure Appl. Chem.*, **28**, 67 (1971); adapted and reproduced with permission.

The name of the electropositive constituent is not modified. If the "electronegative constituent" is monatomic or homopolyatomic, its name is modified to end in "-ide." For binary compounds the name of the element standing later in the sequence given above is modified to end in -ide; sodium plumbide, sodium chloride, lithium nitride, arsenic selenide, boron hydride, hydrogen chloride, hydrogen sulfide, silicon carbide, chlorine dioxide, oxygen difluoride, etc.

If the electronegative constituent is heteropolyatomic, it should be designated by the termination "-ate." In certain exceptional cases the terminations "-ide" and "-ite" are used (see below). It is generally possible in a polyatomic group to indicate a "characteristic atom" (as in ClO-) or a "central atom" (as in ICl<sub>4</sub>-). Such a polyatomic group is designated a "complex," and the atoms, radicals, or molecules bound to the characteristic or central atom are termed "ligands." In this case the name of a negatively charged complex should be formed from the name of the characteristic or central element modified to end in -ate.

Binary hydrogen compounds may be named by the principles given above. Volatile hydrides, except those of group VII and of oxygen and nitrogen, may also be named by citing the root name of the element followed by the suffix "-ane." If the molecule contains more than one atom of that element, the number is indicated by the appropriate Greek prefix.

Recognized exceptions are water, ammonia, and hydrazine, owing to long usage. Phosphine, arsine, stibine, and bismuthine are also allowed. However, for all molecular hydrides containing more than one atom of the element, -ane names should be used. I sall the to stall make allies and yet talk combistions

B<sub>2</sub>H<sub>6</sub> diborane PbH<sub>4</sub> plumbane Si<sub>3</sub>H<sub>8</sub> trisilane H<sub>2</sub>S<sub>n</sub> polysulfane

# CIQ e chymothorite of H NAMES FOR IONS AND RADICALS

Monatomic cations should be named as the corresponding element, without change or suffix; gainenges sission apportes bus lation aut 190 should mod Cu<sup>+</sup> the copper(I) ion the copper(II) ion

the copper(II) ion I+ the iodine(I) cation

This principle should also apply to polyatomic cations corresponding to radicals for which special names are given; i.e., these names should be used without change or suffix: the nitrosyl cation (NO<sup>+</sup>), the nitryl cation (NO<sub>2</sub><sup>+</sup>).

Names for polyatomic cations derived by the addition of more protons than required to give a neutral unit to monatomic anions are formed by adding the ending "-onium" to the root of the name of the anion element: phosphonium, arsonium, sulfonium, iodonium. The name "ammonium" for the ion NH<sub>4</sub><sup>+</sup> does not conform to the rule but is retained. Substituted ammonium ions derived from nitrogen bases with names ending in "-amine" receive names formed by

changing -amine to -ammonium, for example, HONH<sub>3</sub>+, the hydroxylammonium ion. When the nitrogen base is known by a name ending otherwise than in -amine, the cation name is formed by adding the ending "-ium" to the name of the base (if necessary omitting a final "e" or other vowel): hydrazinium, anilinium, glycinium, pyridinium.

The names for monatomic anions consist of the name (sometimes abbreviated) of the elements with the termination -ide:

H- hydride ion N<sup>3-</sup> nitride ion (woled see) beautiful bits
F- fluoride ion O<sup>2-</sup> oxide ion (as) moto odernetosta de se estados

Certain polyatomic anions have names ending in -ide: 1 of bound solutions

OH- hydroxide ion  $N_3^-$  azide ion  $N_4^-$  imide ion  $N_4^-$  amide ion  $N_4^-$  amide ion  $N_4^-$  triiodide ion  $N_4^-$  amide ion  $N_4^-$  cyanide ion  $N_4^-$  hydrogen difluoride ion  $N_4^-$  acetylide ion  $N_4^-$  acetylide ion  $N_4^-$  acetylide ion  $N_4^-$ 

It is quite practical to treat oxygen in the same manner as other ligands, but it has long been customary to ignore the name of this element altogether in anions and to indicate its presence and proportion by means of a series of prefixes and used to denote a lower state of oxidation and may be retained in certain trivial names such as the following:

 $NO_2^-$  nitrite  $SO_3^{2-}$  sulfite  $CIO_2^-$  chlorite  $S_2O_6^{2-}$  disulfite  $CIO^-$  hypochlorite  $S_2O_4^{2-}$  dithionite  $IO^-$  hypoiodite

A radical is a group of atoms which occurs repeatedly in a number of different compounds. Certain neutral and cationic radicals containing oxygen or other chalcogens have, irrespective of charge, special names ending in "-yl," and provisional retention of the following is approved:

HO hydroxyl SO sulfinyl (thionyl) carbonyl CO SO<sub>2</sub> sulfonyl (sulfuryl) NO nitrosyl S2O5 disulfuryl NO, nitryl SeO seleninyl PO phosphoryl SeO, selenonyl CIO chlorosyl CrO<sub>2</sub> ClO<sub>2</sub> chloryl chromyl is leading a swin of beninper UO, uranyl worned on melao gaibas ClO<sub>3</sub> perchloryl NpO<sub>2</sub> (similarly for other halogens) (similarly for other actinides) neptunyl motor muimollus muimosts tom nurouen bases with names

Radicals analogous to the above containing other chalcogens in place of oxygen are named by adding the prefixes "thio-," "seleno-," etc. Examples are:

carbonyl chloride COCl<sub>2</sub> thiophosphoryl chloride PSCl<sub>3</sub> SO<sub>2</sub>NH sulfonyl (sulfuryl) imide

### ACIDS

Acids giving rise to -ide anions are named as binary and pseudobinary compounds of hydrogen, e.g., hydrogen chloride, hydrogen sulfide, hydrogen cyanide.

For the oxo acids the -ous or -ic notation to distinguish between different oxidation states is applied in many cases. The -ous names are restricted to acids corresponding to -ite anions.

The prefix "hypo-" is used to denote a lower oxidation state and may be retained in the following cases:

H<sub>2</sub>N<sub>2</sub>O<sub>2</sub> hyponitrous acid HOBr hypobromous acid HOI hypoiodous acid H<sub>4</sub>P<sub>2</sub>O<sub>6</sub> hypophosphoric acid porassium hydrogensulfide HOCl hypochlorous acid

The prefix "per-" has been used to designate a higher oxidation state and is retained for HClO<sub>4</sub>, perchloric acid, and corresponding acids of the other elements in group VII. This use of the prefix per-should not be extended to elements of other groups.

The prefixes "ortho-" and "meta-" have been used to distinguish acids

differing in the "content of water." The following names are approved:

H<sub>3</sub>BO<sub>3</sub> orthoboric acid (HBO<sub>3</sub>)<sub>n</sub> metaboric acid H<sub>4</sub>SiO<sub>4</sub> orthosilicic acid (H<sub>2</sub>SiO<sub>3</sub>)<sub>n</sub> metasilicic acid H<sub>3</sub>PO<sub>4</sub> orthophosphoric acid (HPO)<sub>n</sub> metaphosphoric acid

H<sub>5</sub>IO<sub>6</sub> orthoperiodic acid H<sub>6</sub>TeO<sub>6</sub> orthotelluric acid

The names cf other oxo acids are given in the following list.

H<sub>2</sub>CO<sub>3</sub> carbonic acid HOCN cyanic acid HNCO isocyanic acid HONC fulminic acid HNO<sub>3</sub> nitric acid HNO<sub>2</sub> nitrous acid

H<sub>4</sub>P<sub>2</sub>O<sub>7</sub> diphosphoric or pyrophosphoric acid

H<sub>3</sub>P<sub>3</sub>O<sub>10</sub> triphosphoric acid H<sub>2</sub>SO<sub>4</sub> sulfuric acid

H<sub>2</sub>S<sub>2</sub>O<sub>7</sub> disulfuric acid ligands are listed in alphabetical order regardless of the mumber of 630h

H <sub>2</sub> SO <sub>5</sub> H <sub>2</sub> S <sub>2</sub> O <sub>8</sub> H <sub>2</sub> S <sub>2</sub> O <sub>3</sub> H <sub>2</sub> S <sub>2</sub> O <sub>6</sub> H <sub>2</sub> SO <sub>3</sub> H <sub>2</sub> S <sub>2</sub> O <sub>4</sub> HCIO <sub>4</sub> HCIO <sub>3</sub>	peroxomonosulfuric acid peroxodisulfuric acid thiosulfuric acid dithionic acid sulfurous acid dithionous acid perchloric acid chloric acid
HClO <sub>2</sub>	chlorous acid

# Acids giving rise to -ide amons are manned as banars and page pounds of hydrogen, e.g. by the SALTS CONTAINING ACID HYDROGEN Acids the Magondy discount of the same acids the Magondy Hydrogen acids the Magondy H

Names are formed by adding the word "hydrogen," with a numerical prefix where necessary, to denote the replaceable hydrogen in the salt. The word "hydrogen" is placed immediately in front of the name of the anion:

sodium hydrogencarbonate lithium dihydrogenphosphate potassium hydrogensulfide

# COORDINATION COMPOUNDS

In formulas the usual practice is to place the symbol for the central atom(s) first (except in formulas which are primarily structural), with the ionic and neutral ligands following and the formula for the whole complex enclosed in square brackets. In names the central atom(s) should be placed after the ligands.

The names of coordination entities always have been intended to indicate the charge of the central atom (ion) from which the entity is derived. Since the charge on the coordination entity is the algebraic sum of the charges of the constituents, the necessary information may be supplied by giving either the Stock number (oxidation state of the central ion) or the Ewens-Bassett number (overall charge on the complex ion):

$K_3[Fe(CN)_6]$	potassium hexacyanoferrate (III)
K₄[Fe(CN) <sub>6</sub> ]	potassium hexacyanoferrate (III) tripotassium hexacyanoferrate potassium hexacyanoferrate(II) potassium hexacyanoferrate(4–) tetrapotassium hexacyanoferrate

Structural information may be given in formulas and names by prefixes such as "cis," "fac," "mer," etc. Anions are given the termination -ate. Cations and neutral molecules are given no distinguishing termination. The ligands are listed in alphabetical order regardless of the number of each. The

name of a ligand is treated as a unit. Thus, "diammine" is listed under "a" and "dimethylamine" under "d."

The names of anionic ligands, whether inorganic or organic, end in "o." In general, if the anionic ligand name ends in -ide, -ite, or -ate, the final "e" is replaced by "o," giving "-ido," "-ito," or "-ato," respectively. Enclosing marks are required for inorganic anionic ligands containing numerical prefixes, as (triphosphato), and for "thio," "seleno," and "telluro" analogs of oxo anions containing more than one atom, as (thiosulfato). Examples of organic anionic ligands which are named in this fashion are:

CH,COO acetato (+2)mumitalq(ambiroq)estanta (CH<sub>3</sub>)<sub>2</sub>N<sup>-</sup> dimethylamido

The anions listed below do not follow exactly the above rule, and modified forms have become established; dia consider any property

	Ion To (II) SYE	Ligand
F- Cl- Br- I- O <sup>2</sup> - H- OH- O <sub>2</sub> <sup>2</sup> - CN-	fluoride chloride bromide iodide oxide hydride hydroxide peroxide cyanide	fluoro chloro bromo iodo oxo hydrido (hydro)² hydroxo peroxo cyano

The letters in each of the ligand names which are used to determine the alphabetical listing are given in boldface type in the following examples to illustrate the alphabetical arrangement. For many compounds, the oxidation number of the central atom and/or the charge on the ion are so well known that there is no need to use either a Stock number or an Ewens-Bassett number. However, it is not wrong to use such numbers, and they are included here.

K<sub>2</sub>[OsCl<sub>5</sub>N]

NH<sub>4</sub>[Cr(NCS)<sub>4</sub>(NH<sub>3</sub>)<sub>2</sub>]

potassium pentachloronitridoosmate(2-) potassium pentachloronitridoosmate(VI) [Co(NH<sub>2</sub>)<sub>2</sub>(NH<sub>3</sub>)<sub>4</sub>]OC<sub>2</sub>H<sub>5</sub> diamidotetraamminecobalt(1+) ethoxide [Call on the state of the state [CoN<sub>3</sub>(NH<sub>3</sub>)<sub>5</sub>]SO<sub>4</sub> pentaammineazidocobalt(2+) sulfate pentaammineazidocobalt(III) sulfate ammonium diamminetetrakis(isothiocyanato)chromate(1-)

ammonium diamminetetrakis(isothiocyanato)chromate(III)

<sup>((</sup>CO),Fe(CO),Fe(CO), <sup>2</sup> Both "hydrido" and "hydro" are used for coordinated hydrogen, but the latter term usually is restricted to boron compounds.

Ba[BrF<sub>4</sub>]<sub>2</sub> barium tetrafluorobromate(1-) barium tetrafluorobromate(III) The names of anionic ligands, whether inorganic or organic end in "o

The name of a coordinated molecule is used without change. Neutral ligands are generally set off with enclosing marks.

cis-[PtCl <sub>2</sub> (Et <sub>3</sub> P) <sub>2</sub> ]	cis-dichlorobis(triethylphosphine)platinum a gainlana
[Pt(py) <sub>4</sub> ][PtCl <sub>4</sub> ]	
[Co(en) <sub>3</sub> ] <sub>2</sub> (SO <sub>4</sub> ) <sub>3</sub>	tetrakis(pyridine)platinum(2+) tetrachloroplatinate(2-) tetrakis(pyridine)platinum(II) tetrachloroplatinate(II) tris(ethylenediamine)cobalt(3+) sulfate
K[PtCl <sub>3</sub> (C <sub>2</sub> H <sub>4</sub> )]	tris(ethylenediamine)cobalt(III) sulfate potassium trichloro(ethylene)platinate(1-) potassium trichloro(ethylene)platinate(II) or potassium trichloromonoethyleneplatinate(II)

Water and ammonia as neutral ligands in coordination complexes are called "aqua" (formerly "aquo") and "ammine," respectively. The groups NO and CO, when linked directly to a metal atom, are called "nitrosyl" and "carbonyl," respectively. In computing the oxidation number these ligands are treated as

[Cr(H<sub>2</sub>O)<sub>6</sub>]Cl<sub>3</sub>

Na<sub>2</sub>[Fe(CN)<sub>5</sub>NO]

K<sub>3</sub>[Fe(CN)<sub>5</sub>CO]

hexaaquachromium(3+) chloride hexaaquachromium trichloride sodium pentacyanonitrosylferrate(2-) sodium pentacyanonitrosylferrate(III) potassium carbonylpentacyanoferrate(3-) potassium carbonylpentacyanoferrate(II) is not wrong to use such numbers, and they are included here

NH,[Cr(NCS),(NH,)).]

# Alternative Modes of Linkage of Some Ligands

The different points of attachment of a ligand may be denoted by adding the italicized symbol(s) for the atom or atoms through which attachment occurs at the end of the name of the ligand. Thus the dithiooxalato anion O2[((HI))(100)]

conceivably may be attached through S or O, and these are distinguished as dithiooxalato-S,S' and dithiooxalato-O,O', respectively.

e ato)chamate(ill)

In some cases different names are already in use for alternative modes of attachment, e.g., thiocyanato (-SCN) and isothiocyanato (-NCS), nitro (-NO<sub>2</sub>), and nitrito (-ONO). the metal atoms but also who some nonmetal atoms or groups (ligands) this mately associated with the cluster of the geometrical shape of the cluster is

# designated by transpolotion quadre, surferinging, distant Use of Abbreviations with the line of the control o

In the literature of coordination compounds, abbreviations for ligand names are used extensively, especially in formulas. A list of common abbreviations is given in Table 14.2. min dodecachloro-triummin dod

## Complexes with Unsaturated Molecules or Groups

The name of the ligand group is given with the prefix  $\eta^n$ , where n is the number of bonding atoms of the ligand. This nomenclature has been described in Chap. 14.

# Compounds with Bridging Atoms or Groups

1. A bridging group is indicated by adding the Greek letter  $\mu$  immediately before its name and separating the name from the rest of the complex by hyphens.

2. Two or more bridging groups of the same kind are indicated by "di-\mu-" (or

"bis-µ-"), etc. grange land they villaged tool shadow tool shadow 3. The bridging groups are listed with the other groups in alphabetical order unless the symmetry of the molecule permits simpler names by the use of multiplicative prefixes.

4. Where the same ligand is present as a bridging ligand and as a nonbridging

aligand, it is cited first as a bridging ligand.

Bridging groups between two centers of coordination are of two types: (1) the two centers are attached to the same atom of the bridging group and (2) the two centers are attached to different atoms of the bridging group. For bridging groups of the first type it is often desirable to indicate the bridging atom. This is done by adding the italicized symbol for the atom at the end of the name of the ligand. For bridging groups of the second type, the symbols of all coordinated atoms are added.

 $[(CO)_3Fe(CO)_3Fe(CO)_3]$ 

[(NH<sub>3</sub>)<sub>5</sub>Cr—OH—Cr(NH<sub>3</sub>)<sub>5</sub>]Cl<sub>5</sub>  $\mu$ -hydroxobis[pentaamminechromium(5+)] chloride chloride

μ-hydroxobis[pentaamminechromium(III)]

(solution a legal chloride

tri-µ-carbonyl-bis(tricarbonyliron)  $[B_{r_2}P_t(SMe_2)_2P_tBr_2]$   $bis(\mu$ -dimethylsulfide)-bis[dibromopla-

nonsentature cyclore socializad to [(II)]munit parem name and therefore is not italicited

#### Homoatomic Aggregates

There are instances of a finite group of metal atoms with bonds directly between the metal atoms but also with some nonmetal atoms or groups (ligands) intimately associated with the "cluster." The geometrical shape of the cluster is designated by "triangulo," "quadro," "tetrahedro," "octahedro," etc., and the nature of the bonds to the ligands by the conventions for bridging bonds and simple bonds.

 $Os_3(CO)_{12}$  $Cs_3[Re_3Cl_{12}]$  dodecacarbonyl-*triangulo*-triosmium cesium dodecachloro-*triangulo*-trirhenate(3—) tricesium dodecachloro-*triangulo*-trirhenate

B<sub>4</sub>Cl<sub>4</sub> [Nb<sub>6</sub>Cl<sub>12</sub>]<sup>2+</sup> tetrachloro-*tetrahedro*-tetraboron dodeca-*µ*-chloro-*octahedro*-hexaniobium(2+) ion

# PREFIXES OR AFFIXES USED IN INORGANIC NOMENCLATURE

#### **Multiplying Affixes**

(1) "Mono," "di," "tri," "tetra," "penta," "hexa," "hepta," "octa," "nona" ("ennea"), "deca," "undeca" ("hendeca"), "dodeca," etc., are used by direct joining without hyphens; (2) "bis," "tris," "tetrakis," "pentakis," etc., are used by direct joining without hyphens but usually with enclosing marks around each whole expression to which the prefix applies.

## Structural Affixes

These affixes are italicized and separated from the rest of the name by hyphens.

antiprismo 8 atoms bound into a rectangular antiprism asymmetric a chain structure; often used to designate linear polymeric sub-

stances

cis 2 groups occupying adjacent positions; sometimes used in the sense of fac

closo

a cage or closed structure, especially a boron skeleton that is a polyhedron having all triangular faces

cyclo a ring structure<sup>3</sup>

dodecahedro 8 atoms bound into a dodecahedron with triangular faces

fac 3 groups occupying the corners of the same face of an octahedron

hexahedro 8 atoms bound into a hexahedron (e.g., a cube)

<sup>&</sup>lt;sup>3</sup> Cyclo here is used as a modifier indicating structure and hence is italicized. In organic nomenclature, cyclo is considered to be part of the parent name and therefore is not italicized.

12 atoms bound into a hexagonal prism hexaprismo 12 atoms bound into a triangular icosahedron icosahedro meridional; 3 groups on an octahedron in such a relationship that mer one is cis to the two others which are themselves trans a nestlike structure, especially a boron skeleton that is very close to nido a closed or closo structure octahedro 6 atoms bound into an octahedron pentaprismo 10 atoms bound into a pentagonal prism 4 atoms bound into a quadrangle (e.g., a square) quadro svm symmetric 4 atoms bound into a tetrahedron tetrahedro 2 groups directly across a central atom from each other, i.e., in the trans polar position on a sphere triangulo 3 atoms bound into a triangle 6 atoms bound into a triangular prism triprismo signifies that two or more contiguous atoms of the group are η attached to a metal signifies that the group so designated bridges two centers of coordi-

#### Substitutional Affixes4

An affix such as "ferra," "nickela," "sila," "metalla," etc., can be used to indicate the formal substitution of a "heteroatom" in a hydrocarbon. For example, silabenzene is benzene in which one carbon atom is replaced by a silicon atom,

signifies that one atom of the group is attached to a metal

and  $(OC)_4Fe$  is a ferracyclopropane and is an example of a metallacycle.  $CH_2$ 

tal and (2) a solution surface centered on the nucleus

<sup>&</sup>lt;sup>4</sup> Not approved by the International Commission on the Nomenclature of Inorganic Chemistry.

# ANSWERS TO SELECTED PROBLEMS

#### CHAPTER 1

1.1 Al, 1; S, 2; Sc<sup>3+</sup>, 0; Cr<sup>3+</sup>, 3; Ir<sup>3+</sup>, 4; Dy<sup>3+</sup>, 5. 1.2 Ru<sup>2+</sup>.

1.9 Because I(He) > I(Kr), the first reaction goes as written. Because I(Cl) > I(Si), the second reaction goes as written. Because A(Cl) > A(I), the third reaction goes in the reverse direction.

1.14 The probability of finding the electron at a radius r is proportional to the product of the electron density and the area of a sphere of radius r. Inasmuch as the latter area is zero when r = 0, the probability of finding the electron at a radius r = 0 is zero even though the electron density is greatest at r = 0.

1.15 The nodal surfaces of a 3p orbital are (1) a plane containing the nucleus and perpendicular to the axis of the orbital and (2) a spherical surface centered on the nucleus.

1.16 
$$I = 13.60(9)^2 = 1102 \text{ eV}$$
.

 $= 909 \, eV$ 

1.18 
$$I_{2}(Na) = 13.6 \left[ 8 \left[ \frac{11 - 7(0.35) - 2(0.85)}{2} \right]^{2} - 7 \left[ \frac{11 - 6(0.35) - 2(0.85)}{2} \right]^{2} \right]$$

$$= 42.5 \text{ eV}$$

$$I_{2}(Mg) = 13.6 \left[ \frac{12 - 8(0.85) - 2(1)}{3} \right]^{2} = 15.5 \text{ eV}$$

$$E_{B}(Ne \ 1s) = 13.6 \left[ 2 \left[ \frac{10 - 0.3}{1} \right]^{2} - \left( \frac{10}{1} \right)^{2} + 8 \left[ \frac{10 - 2(0.85) - 7(0.35)}{2} \right]^{2} - 8 \left[ \frac{10 - 0.85 - 7(0.35)}{2} \right]^{2} \right]$$

1.20 Although the first and second ionization potentials of lead are very similar to those of tin, the third and fourth are considerably greater than the corresponding IPs of tin. In the series Ge. Sn. Pb. all four IPs have a minimum at Sn. The IPs of Pb are probably high because of incomplete nuclear shielding by the fourteen 4f electrons.

1.21 For ions of the same charge, the relative strength of binding to an ion-exchange resin, or of complexation in solution, is principally a function of ionic radius. As a consequence of the lanthanide contraction, the elements in the vicinity of holmium have ionic radii very similar to that of

1.22 In(I) and In(III); Sn(II) and Sn(IV); Sb(III) and Sb(V); Te(IV) and Te(VI).

2.1 (a)  $C_i$ ; (b)  $C_1$ ; (c)  $C_{2v}$ ; (d)  $C_{3v}$ ; (e)  $C_{3v}$ ; (f)  $D_{\infty h}$ ; (g)  $T_d$ ; (h)  $D_{3h}$ ; (i)  $D_{2d}$ ; (j)  $C_{4v}$ ; (k)  $C_{2v}$ ; (1)  $C_{2h}$ ; (m)  $D_{2h}$ ; (n)  $D_{2d}$ .

2.3 E, and T2.

 $L_g$  and  $L_{2g}$ . 2.4 (a)  $A_{2u}$ ,  $B_{1g}$ ,  $E_{1g}$ , and  $E_{2u}$ ; (b)  $A_1$  and  $A_2$ ; (c)  $A_2$  and  $A_2$ ; (d)  $A_{1g}$ ,  $E_g$ ,  $A_{1u}$ .

#### CHAPTER 3

charges and ellering electiones themes present the a the gentlet around about a title. weak! have negative towned unages (20 offering electrone partition bases (they the negative the negative the negative to the negative the negative to the negative the negative to the negativ 3.2 Hyperconjugated resonance structures such as O= $S^{2+}F^-$  may be important in SO<sub>2</sub>F<sub>2</sub>, and Factors 1450 - + OH - hipproval was constructed F manufactions, again to up our convention

and semile # M.Z. Windy stock 4.5; Stanle sping - 5 is

therefore the S—O bond order may be comparable to that in SO<sub>2</sub>, that is, 1.5. Lone-pair repulsions may somewhat weaken the bonds in SO<sub>2</sub>.

- 3.5 The properties may be estimated from those for the following isoelectronic species: (a) NO<sub>2</sub>; (b) N<sub>2</sub> and CO; (c) H<sub>3</sub>C—CH<sub>3</sub>; H<sub>2</sub>N—NH<sub>2</sub>; and HO—OH; (d) CO<sub>2</sub>; (e) CH<sub>3</sub>; (f) SiO<sub>2</sub>; (g) SO<sub>2</sub>; (h) N<sub>2</sub>O<sub>4</sub>.
- 3.7 Tin is tetracovalent ( $sp^3$  hybridization) in tin metal and in  $SnX_4$  molecules. The lower IS values for the latter molecules correspond to higher atomic charges and lower s-orbital occupations. In  $SnX_2$  compounds, the tin atoms have lone-pair electrons with relatively high s-orbital character. Thus, although the tin atoms in these compounds have positive atomic charges, the IS values are even higher than they are in metallic tin.
- 3.8 The electronegativity of fluorine is greater than that of oxygen, and the Mn atoms in MnF<sub>2</sub> are more positive than those in MnO<sub>2</sub>.
- 3.9  $q_N = -0.474$ ,  $q_H = 0.158$ ,  $q_C = 1.209$ ,  $q_F = -0.302$ .
- 3.12 SO<sub>2</sub>, NF<sub>3</sub>, SF<sub>4</sub>, SF<sub>2</sub>, N<sub>2</sub>F<sub>4</sub>, SiH<sub>3</sub>Cl, O<sub>3</sub>, BrF<sub>5</sub>, S<sub>2</sub>Cl<sub>2</sub>.
- 3.14  $\Delta H_f^{\circ}(N_3H_5) = 58.5 \text{ kcal mol}^{-1}; \Delta H_f^{\circ}[(\text{GeH}_3)_2\text{Se}] = 39 \text{ kcal mol}^{-1}.$
- 3.16 One estimates an N—F bond length of 1.28 Å. The actual distance in NF<sub>3</sub> is greater because of repulsion between the lone pairs of the N and F atoms.
- 3.18 Of the various possible resonance structures one can write for  $S_4N_3^+$ , the one shown as an answer to Prob. 2.1(h) is the most satisfactory from the point of view of electrostatic interactions among the formal charges. Hence the S—N bonds indicated as double bonds in that structure are expected to be (and are) the shortest [*Inorg. Chem.*, 19, 2396 (1980)].
- 3.20 If I mol of diamond is vaporized,  $2N \pmod{4N}$  C—C bonds are broken. Hence the sublimation energy of diamond is about twice the C—C bond energy.
- 3.22  $E_B(C \mid s) = 309 \text{ eV}$ ;  $E_B(C^+ \mid s) = 324 \text{ eV}$ .
- 3.24 Lone-pair-lone-pair repulsion is much greater for first-row elements than for heavier elements.

#### CHAPTER 4

- 4.2 For linear  $H_3^+$ , one calculates the following energy levels (in order of increasing energy):  $\alpha + \sqrt{2}\beta$ ,  $\alpha$ ,  $\alpha \sqrt{2}\beta$ . The two electrons occupy the lowest level, and thus the total energy is  $2\alpha + 2\sqrt{2}\beta$ . For triangular  $H_3^+$ , the energy levels are  $\alpha + 2\beta$ ,  $\alpha \beta$ , and  $\alpha \beta$ . With two electrons occupying the lowest level, the total energy is  $2\alpha + 4\beta$ . Thus we calculate that the triangular form is more stable by  $4\beta 2\sqrt{2}\beta$ .
- **4.3** (a) p = 5.615; S = 0.113;  $\beta = 1.75 \times 0.113 \times 17.2 = 3.40$  eV;  $\Delta E = 1.414 \times 3.40 = 4.8$  eV. (b) p = 5.059; S = 0.158;  $\beta = 1.75 \times 0.158 \times 16.3 = 4.51$  eV;  $\Delta E = \Delta \alpha/2 + \frac{1}{2}\sqrt{(\Delta \alpha)^2 + 8\beta^2} = 7.3$  eV.
- **4.5** The bond orders and numbers of unpaired electrons are NeO+, 1.5, 1;  $O_2$ +, 2.5, 1; CN+, 2, 0; BN, 2, 0; SiF+, 3, 0; NO-, 2, 2; PCI, 2, 2;  $I_2$ +, 1.5, 1; NEH+, 1, 0.
- 4.7 The  $P_4^{2+}$  ion might be expected to have a square structure, with a total of five bonds (one delocalized  $P-P\pi$  bond and four  $P-P\sigma$  bonds).
- 4.9 Bi<sub>4</sub><sup>2-</sup> square planar; Te<sub>4</sub><sup>2-</sup> zigzag chain; S<sub>4</sub>N<sub>4</sub><sup>2+</sup> planar ring.
- **4.11** Delocalized  $\pi$  bonding is favored when the atoms involved all have comparable effective electronegativities. In the described compounds, the O and S atoms would have positive formal charges (and effective electronegativities greater than the neutral atom values), and the N and P atoms would have negative formal charges (and effective electronegativities lower than the neutral atom values). In the case of S—N compounds, the effective electronegativities end up with similar magnitudes; in the case of N—O, P—O, and P—S compounds, the effective electronegativity differences are quite large, and alternative structures are favored.

4.13 In the case of N, the 2s-2p separation is relatively small and therefore the  $2s\sigma$  and  $2p\sigma$  orbitals of N<sub>2</sub> interact strongly. In the case of F, the increased effective nuclear charge lowers the energy of the 2s orbital much more than that of the 2p orbital, resulting in a greater 2s-2p separation and weaker 2so-2po interaction in F2 than in N2.

# CHAPTER 5 none of the continue of the contract of the contract loss of a house of a house of a house of a house of the continue of the contract loss of a house of a house of the contract loss of the contrac

$$H + p - H_2 \xrightarrow{k} o - H_2 + H$$

H + p-H<sub>2</sub>  $\xrightarrow{k}$  o-H<sub>2</sub> + H 5.2 The rate of the reaction F + H<sub>2</sub>  $\rightarrow$  HF + H is comparable to that of the reaction in H+F<sub>2</sub>→HF+F (both reactions are exothermic), and therefore the H-atom concentration is comparable to the F-atom concentration. For this reason one must include the reactions  $H+F \rightarrow HF$  and  $H+H \rightarrow H_2$  in the mechanism.

5.4 2NO 
$$\rightarrow$$
 N<sub>2</sub> + O<sub>2</sub>  
 $H_2 + N_2 \rightarrow N_2H_2$  and solved a between MALE SO<sub>2</sub> + F<sub>2</sub>  $\rightarrow$  SO<sub>2</sub>F<sub>2</sub>.

- $SO_2 + F_2 \rightarrow SO_2F_2$ 5.5 The least-motion reaction of singlet CH<sub>2</sub> with H<sub>2</sub> is symmetry-forbidden. However, if the H<sub>2</sub> approaches the  $CH_2$  over the empty  $p_s$  orbital, the reaction is allowed. [See J. Am. Chem. Soc., 99,
- 5.7 Both nuclear-fission and branching-chain reactions are exothermic. The neutrons formed in nuclear fission are analogous to the chain-carrying radical species. More neutrons are produced in fission than are consumed, just as is the case with radicals in a branching-chain reaction. The escape of neutrons from the fissioning material is analogous to the chain-terminating steps at the reaction vessel wall. The "critical mass" of nuclear fission is analogous to the first explosion limit.

# CHAPTER 6

6.1 (a) 
$$CaH_2 + CO_3^{2-} + 2H_2O \rightarrow CaCO_3 + 2H_2 + 2OH^-$$

(a) 
$$CaH_2 + CO_3^{2-} + 2H_2O \rightarrow CaCO_3 + 2H_2 + 2OH$$
  
(c)  $3LiAlH_4 + 4(C_2H_5)_2O \cdot BF_3 \rightarrow 2B_2H_6 + 3LiAlF_4 + 4(C_2H_5)_2O$ 

(e) 
$$AsH_3 + GeH_3^- \rightarrow AsH_2^- + GeH_4$$

6.3 
$$NaNH_2 + GeH_4 \xrightarrow{liq. NH_3} GeH_3^- + Na^+ + NH_3$$
  
 $GeH_3^- + CH_3I \rightarrow CH_3GeH_3 + I^-$   
 $CH_3GeH_3 + HBr \rightarrow CH_3GeH_2Br + H_2$ 

### CHAPTER 7

7.1 If the exchange reaction does not proceed by a mechanism involving the rate-determining step  $PH_3 + OD^- \xrightarrow{k_1} PH_2^- + HOD$ 

$$PH_3 + OD^- \xrightarrow{k_1} PH_2^- + HOD$$

then the rate of the actual rate-determining step must be greater than that of the above reaction.

Hence  $k_1 \le 0.4 \ M^{-1} \ s^{-1}$  and  $pK_{PH_3} \ge 27$ . 7.3 NH<sub>3</sub> < CH<sub>3</sub>GeH<sub>3</sub> < AsH<sub>3</sub> < C<sub>2</sub>H<sub>5</sub>OH < H<sub>4</sub>SiO<sub>4</sub> < HSeO<sub>4</sub><sup>-</sup> < HSO<sub>4</sub><sup>-</sup> < HSO<sub>3</sub>F < HClO<sub>4</sub>.

8.8 1.60 2.66 3.60; 4.60 aretoria laborarios e

7.5 Slowest:  $NH_3 + OH^- \rightarrow H_2O + NH_2^-$ Fastest:  $HSO_4^- + OH^- \rightarrow H_2O + SO_4^{2-}$ 

- 7.7 The sublimation of 1 mol of ice involves the cleavage of 2 mol of hydrogen bonds. Therefore the energy per hydrogen bond is 11.9/2 or 6.0 kcal mol-1, paragraph, the personal all educations are the
- 7.9 The stoichiometry of borax corresponds to half-neutralized boric acid, so the solution will consist largely of H<sub>3</sub>BO<sub>3</sub> and B(OH)<sub>4</sub>-.
- 7.10 The  $\pi$  bonding between the boron atom and the fluorine atoms of BF<sub>3</sub> is stronger than the analogous  $\pi$  bonding in BCl<sub>3</sub>. (The  $p\pi$ - $p\pi$  overlap for two first-row atoms is greater than that for a first-row and a second-row atom.) Hence it is more difficult to convert the boron atom of BF3 to sp3 of bonding by coordination of a Lewis base because of the greater loss of  $\pi$ -bonding energy.
- 7.11 (b)  $\text{Li}_3\text{N} + 3\text{NH}_4^+ \rightarrow 3\text{Li}^+ + 4\text{NH}_3$

(d) 
$$H_3BO_3 + H_2SO_4 \rightarrow 3H_3O^+ + B(HSO_4)_4^- + 2HSO_4^-$$

7.12 Hphth<sup>-</sup> + OH<sup>-</sup> 
$$\xrightarrow{\text{H}_2\text{O}}$$
 phth<sup>2-</sup> + H<sub>2</sub>O

7.14 The OH- is strongly hydrogen-bonded to the dissolved water molecules, thus enhancing the solubility of the KOH 

7.16 (b) and (c).

7.18 In the absence of steric effects, (CH<sub>3</sub>)<sub>3</sub>N would be expected to be the strongest base. However, in (CH<sub>3</sub>)<sub>3</sub>BN(CH<sub>3</sub>)<sub>3</sub>, the repulsions between methyl groups on adjacent atoms are so great as to make the energy of interaction of B(CH<sub>3</sub>)<sub>3</sub> with (CH<sub>3</sub>)<sub>3</sub>N effectively weaker than that of B(CH<sub>3</sub>)<sub>3</sub> with (CH<sub>3</sub>)<sub>2</sub>NH. 7.19 BH<sub>3</sub>, a relatively soft acid, prefers to coordinate to the "soft" phosphorus site. BF<sub>3</sub>, a hard acid,

prefers the "hard" nitrogen site.

7.20 Cationic species are often good electron acceptors (Lewis acids); in fact they may even be electron-deficient. Hence they can exist only in the absence of good Lewis bases, i.e., in acidic media. The opposite is true for anionic species; they are often good electron donors and can exist only in the absence of good Lewis acids. st newtones from the historing material is arealogous to at The "critical mass" of nuclear fission is analogous to the first

CHAPTER 6

#### CHAPTER 8

- 8.1 (a)  $2K1 + 10_3^- + 6H^+ + 6CI^- \rightarrow 3ICI_2^- + 6H_2O + 2K^+$ 
  - (c)  $3Cl_2O + 6OH^- \rightarrow 4Cl^- + 2ClO_3^- + 3H_2O$
  - (e)  $4\text{MnO}_4^- + 3\text{H}_2\text{PO}_2^- + 7\text{H}^+ \rightarrow 4\text{MnO}_2 + 3\text{H}_3\text{PO}_4 + 2\text{H}_2\text{O}$
  - (g)  $S + SO_3^{2-} \rightarrow S_2O_3^{2-}$
  - (i)  $4K_2FeO_4 + 20H^+ \rightarrow 4Fe^{3+} + 3O_2 + 10H_2O + 8K^+$ m)  $2NO_2 + 2OH^- \rightarrow NO_3^- + NO_2^- + H_2O$ (m)  $2NO_2 + 2OH^- \rightarrow NO_3^- + NO_2^- + H_2O$
  - (n)  $4H_3PO_3 \rightarrow PH_3 + 3H_3PO_4$
  - (o)  $As + 3Ag^+ + 3H_2O \rightarrow 3Ag + H_3AsO_3 + 3H^+$
  - (t)  $TI(OH)_3 + 4I^- + 3H^+ \rightarrow I_3^- + TII + 3H_2O$
  - (u)  $3O_3 + Ru^{2+} + H_2O \rightarrow 3O_2 + RuO_4 + 2H^+$
- 8.4  $E^{\circ} = -1.73 \text{ V}$ .
- 8.6 Prepare a sample of H<sub>2</sub>SO<sub>5</sub> in which the —OOH oxygens are labeled randomly with a certain concentration of <sup>18</sup>O. Mix this with an equal amount of ordinary H<sub>2</sub>SO<sub>5</sub> and carry out the decomposition. If more cases sition. If mass-spectrometric examination of the O<sub>2</sub> shows that one-half of the molecules have the <sup>18</sup>O<sub>3</sub> and carry out the december of the labeled. content of the labeled —OOH groups and that one-half of the molecules are isotopically normal, the first mechanism is indicated. If practically all the O<sub>2</sub> molecules contain at least one <sup>16</sup>O atom and if the concentration of  $^{18}$ O is one-half of that in the labeled — OOH groups, then the second mechanism is indicated

**8.8** 1 (c); 2 (b); 3 (a); 4 (d).

9.1 HI → \H, + \H.

9.3 Anode:  $e^-_{am} \rightarrow e^-$ Cathode:  $e^- \rightarrow e^-$ 

9.5 (a)  $CH_3GeH_3 + e^{-}_{am} \rightarrow \frac{1}{2}H_2 + CH_3GeH_2^{-}$ 

(b)  $I_2 + 2e^-_{am} \rightarrow 2I^-$ 


(c)  $(C_2H_5)_2S + 2e^-_{am} + NH_3 \rightarrow C_2H_5S^- + C_2H_6 + NH_2^-$ 

9.7 The electronic transition of the V band presumably involves ejection of a valence electron from M into the solvent. Therefore in the case of a metal with a low electron affinity, such as Cs, the transition should occur at a low energy, and in the case of a metal with a higher electron affinity, such as Na, the transition should occur at a higher energy.

# CHAPTER 10 - I bloom O'ald white normals reveal him have accurate and add

Structure (a) is actually observed. In each of the other structures, one boron atom is rather loosely connected to the others by a single bond.

10.3 b = h = n, and q = -2. Hence  $\alpha = n + 3$  and  $\beta = n - 2$ . If we assume that there are  $n \to -1$ bonds, then the number of B—B bonds is 3 and the number of B—B bonds is n-2. 10.5 whe grad the revo (nontenuation of a partition of a state of the rest of the state of the s



10.8  $B_5H_{12}$ : 4023, 3114, 2205;  $B_6H_{10}$ : 4220, 3311, 2402;  $B_6H_{12}$ : 6030, 5121, 4212, 3303.

10.9 Trigonal prism of As atoms.

10.10 The nmr spectrum is explained by a pentagonal pyramidal structure (nido) for  $(CCH_3)_6^{2+}$ . The  $(CH_1)_{\pm 1}$ . (CH)<sub>5</sub><sup>+</sup> ion would be expected to have a square pyramidal structure.

11.1			$\Delta H^{\circ}$ , kcal
$NH_4+(g)+C$	$1^-(g) \rightarrow$	NH <sub>4</sub> Cl(s)	-158.7
NH <sub>4</sub>	$Cl(s) \rightarrow$	$\frac{1}{2}$ N <sub>2</sub> (g) + 2H <sub>2</sub> (g) + $\frac{1}{2}$ Cl <sub>2</sub> (g)	75.2
1/2	$l_2(g) \rightarrow$	Cl(g)	29.1
	$e^{-(g)} \rightarrow$		-83.4
N(g) + 3			-280.3
	$N_2(g) \rightarrow$		113
	$H_2(g) \rightarrow$		208.4
	$H(g) \rightarrow$	$H^+(g) + e^-(g)$	313.6
NH,	<sup>+</sup> (g) →	$NH_3(g) + H^+(g)$	217
11.4 Possible coor	dination .	ther energy (8)	ald as to be supply

- 11.4 Possible coordination numbers of M and X are 3 and 1, 6 and 2, 9 and 3, etc., respectively.
- 11.5 The minimum value of  $r_{\rm M}/r_{\rm X}$  is 0.5275.
- 11.7 The greater lattice energy of Mg<sup>2+</sup>O<sup>2-</sup>, compared with that of Mg<sup>+</sup>O<sup>-</sup>, more than compensates for the higher ionization potential and lower electron affinity. Mg+O-would be expected to be paramagnetic, whereas MgO is diamagnetic.
- 11.9 The S<sup>2-</sup> and Se<sup>2-</sup> ions are so much larger than the metal ions that anion-anion contact occurs in the crystals, and the metal ions "rattle" in the anion lattices. For  $S^{2-}$ ,  $r = \frac{1}{2}\sqrt{2}(2.60) = 1.84 \,\text{Å}$ .
- 11.11 The layers stack so as to maximize the electrostatic attraction between the oppositely charged boron and nitrogen atoms.
- 11.13 Fractional space occupancy 0.3401 for diamond, 0.5236 for simple cubic. The diamond structure is ideal for covalently bonded compounds in which the average number of valence electrons per atom is four. The simple cubic structure (CN 6) is unstable with respect to a close-packed
- 11.15 The Be atom is so small that an NaCl-structure BeO would involve strong oxygen-oxygen repulsions. These are avoided in the actual wurtzite-type structure of BeO.

# Structure (a) is actually observed. In each of the other structures, one boron atom is rather tooker) CHAPTER 12

- bonds, then the number of B B bonds is 3 and the number of B B B 12.1 Increase in the pressure of Zr favors the bcc structure ( $d^3s^1$  configuration) over the hcp structure  $(d^2s^1p^1 \text{ configuration})$ . Increase in the pressure of Fe favors the ccp structure  $(d^5s^1p^2 \text{ configuration})$ over the bcc structure ( $d^7s^1$  configuration).
- 12.3 The electrical conductivity of a solid-solution alloy passes through a minimum on varying the composition from one pure metal to the other. This result is probably caused by the relative disorder
- 12.5 Ag, ccp; Ag<sub>3</sub>Al, bcc; Ag<sub>9</sub>Al<sub>4</sub>, γ-brass structure; Ag<sub>5</sub>Al<sub>3</sub>, hcp; Al, ccp.
- 12.7 (a) Yes; (b) no, Re melts too high; (c) no, Pt (a d-electron-rich metal) and Ta (a d-electron-poor metal) would react to form a very stable alloy.
- 12.9 Eu and Yb have cores like those of Gd and Lu, respectively. Hence Eu and Yb crystals involve two bonding electrons per atom, whereas the other lanthanide metals involve three bonding electrons per atom. Thus the "abnormal" densities of Eu and Yb are related to the extraordinary stability of the half- and completely filled 4f electronic shell.

(CH),\* ion would be expected to have a square pyramidal structure.

- 12.10 GeF<sub>5</sub><sup>-</sup> and/or GeF<sub>6</sub><sup>2-</sup> ions.
- 12.11 4.92 Å.) not (ohin) structure to be a pentagonal parameter and to the first structure of the first structure is explained by a pentagonal parameter and the first structure is explained by a pentagonal parameter an

13.1 11,300 Å.

13.3 (a) p; (b) p; (c) n; (d) p; (e) n.

13.5 (c)  $\ll$  (b) < (a) < (d).

13.7 Increase in pressure causes a decrease in internuclear distance and a decrease in band gap. (See Fig. 12.11.) Hence the transition energy decreases and the wavelength increases with increasing pressure. Gallium phosphide, being more ionic (less covalent) than GaAs, has a greater band gap and therefore emits at a shorter wavelength.

## CHAPTER 14

14.2 The 2-coordinate silver atoms are Ag(I), and the 4-coordinate silver atoms are Ag(III). These types of coordination are characteristic of  $d^{10}$  and  $d^{8}$  ions, respectively.

14.4 (a) A total of three isomers, including a pair of optical isomers. (b) A total of five isomers, including a pair of optical isomers. (c) Three isomers.

14.5 Co(en)<sub>3</sub>3+, trigonal distortion; trans-Co(NH<sub>3</sub>)<sub>4</sub>Cl<sub>2</sub>+, tetragonal distortion.

14.7 (a) For  $MX_4Y_2$  and  $MX_3Y_3$ , four isomers each, including a pair of optical isomers. (b) Six isomers, including two pairs of optical isomers. (c) Ten isomers, including three pairs of optical isomers.

14.8 Low-temperature  $^{13}$ C or proton nmr spectra would be expected to show either four or five resonances, depending on the structure. The relative intensities of the peaks, corresponding to the atom abundance ratios, would also be diagnostic. Infrared spectroscopy would help identify, in the C-H stretch region,  $\eta^5$ -C<sub>5</sub>H<sub>5</sub> and  $\eta^5$ -C<sub>7</sub>H<sub>7</sub> groups.

14.10 In the tbp structure, the bidentate ligands can both connect an apical with an equatorial site (optical isomers), or one can connect an apical with an equatorial site while the other connects two equatorial sites. In the sp structure, the bidentate ligands can both connect two basal sites, or one can connect two basal sites while the other connects the apical site with a basal site (optical isomers).

# CHAPTER 15 10000 orth drive selection of the day of the day of the Action of the day of

15.2 In spite of the negative charge of Cl<sup>-</sup>,  $\Delta_o$  for Cl<sup>-</sup> is less than  $\Delta_o$  for NH<sub>3</sub> because of the repulsive interaction between the  $p\pi$  electrons of Cl<sup>-</sup> and the  $d\pi$  electrons of Cr<sup>3+</sup> (Fig. 15.11).  $\Delta_o$  for CN<sup>-</sup> is very high because of back bonding, i.e., the shift of electron density from the  $d\pi$  orbitals of Cr<sup>3+</sup> to the antibonding  $\pi^*$  orbitals of CN<sup>-</sup>. The latter interaction stabilizes the  $d\pi$  orbitals and increases  $\Delta_o$  (Fig. 15.12).

15.4 Fe—C bond order 1.5; C—N bond order 2.5. Formal charges of Fe, C and N: -1, 0, and -0.5, respectively.

15.6 The low-spin configuration, corresponding to less electron density directly between the metal and the ligands, would be favored at high pressures.

15.8 Complexes of  $d^5$  iridium (a third-row transition element) are low-spin because of the high  $\Delta_o$  in such complexes. The  $t_{2g}$  orbitals (which contain the odd electron) overlap with  $3p\pi$  orbitals of the chlorine atoms, thus forming a delocalized set of MOs containing the electron spin density.

15.11 The energy level diagram of Fig. 15.13 corresponds to positively charged metal atoms with negative ligands, not to neutral unligated metal atoms. For the latter, the valence s and p orbitals are lower than the d orbitals and can be used in bonding.

16.2

16.5 Diamagnetic NiCl<sub>4</sub><sup>2-</sup> would be square planar; such a structure is unstable with respect to the tetrahedral form, probably because of repulsions between the chlorines. Ti(CO)4<sup>4+</sup> is unstable because there are no  $d\pi$  electrons to engage in back bonding. Cd(CO)<sub>3</sub> would be expected to be unstable because the d electrons are held so tightly (high nuclear charge of Cd) that they cannot engage in back bonding to the CO groups. AuF<sub>5</sub><sup>2-</sup> is unstable with respect to AuF<sub>4</sub><sup>-</sup> because fluoride ions cannot engage in back bonding and cannot remove the negative charge which builds up on the Au atom when five ligands are coordinated to it.

16.8 The data are consistent with a coordinated NO+ and a high-spin  $d^7$  Fe(I) atom, with three

16.11 (a) 13; (b) 12; (c) 14.

16.15 (C<sub>4</sub>BH<sub>5</sub>)Fe(CO)<sub>3</sub>, with a pentagonal pyramid C<sub>4</sub>BFe cluster. The number of cluster electrons is 16, corresponding to a nido structure. The part of the language to the bounds are no local section.

## CHAPTER 17

17.1 The Mn(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> ion is a weak-field, high-spin  $d^5$  complex with the spectroscopic symbol  ${}^6A_1$ . There is only one combination of quantum numbers corresponding to five unpaired d electrons. Inasmuch as transitions involving a change in multiplicity are forbidden, there are no allowed transitions. The pale color of Mn(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup> is due to weak forbidden transitions, and to allow

17.3 CrF<sub>6</sub><sup>3-</sup>, green; Cu(NH<sub>3</sub>)<sub>4</sub><sup>2+</sup>, blue; FeO<sub>4</sub><sup>2-</sup>, blue-red (purple or magenta); Co(en)<sub>3</sub><sup>2+</sup>, orange. 17.4 CoF<sub>6</sub><sup>3-</sup>: 16,400 cm<sup>-1</sup> ( ${}^{5}T_{2g} \rightarrow {}^{5}E_{g}$ ). NiCl<sub>4</sub><sup>2-</sup>: 2400 cm<sup>-1</sup> [ ${}^{3}T_{1}(F) \rightarrow {}^{3}T_{2}$ ]; 5400 cm<sup>-1</sup>  $[{}^{3}T_{1}(F) \rightarrow {}^{3}A_{2}]: 17,300 \text{ cm}^{-1} [{}^{3}T_{1}(F) \rightarrow {}^{3}T_{1}(P)]. \text{ Fe}(H_{2}O)_{6}^{2+}: 8200 \text{ cm}^{-1} ({}^{5}T_{2g} \rightarrow {}^{5}E_{g}).$ 

17.5 VCl<sub>4</sub>, 1;  $CrO_4^{2-}$ , 0;  $FeO_4^{2-}$ , 3;  $Fe(H_2O)_6^{2+}$ , 1;  $Cr(H_2O)_6^{3+}$ , 3;  $Ni(NH_3)_6^{2+}$ , 3;  $Fe(CN)_6^{4-}$ , several;  $Co(H_2O)_6^{2+}$ , 3;  $Mn(H_2O)_6^{2+}$ , 0;  $MnO_4^{2-}$ , 1;  $Zn(OH)_4^{2-}$ , 0.

17.7 An  $O_h d^3$  complex has a nondegenerate quartet ground state and three triply degenerate quartet

## CHAPTER 18

18.2  $CoCl_4^{2-}$  would be expected to have a greater  $\Delta$  and hence a lower  $\mu$ . (See Eq. 18.2 and Table 18.4.) 18.11 The energy level disgram of Fig. 15.1 lower than the of orbitals and can be used in bonding.

18.4 The NiF<sub>6</sub><sup>2-</sup> ion in K<sub>2</sub>NiF<sub>6</sub> is a low-spin d<sup>6</sup> octahedral complex of Ni(IV). The compound Ni(NH<sub>1</sub>)<sub>2</sub>Cl<sub>2</sub> is probably not a 4-coordinate Ni(II) complex but rather an octahedrally coordinated Ni(II) compound, with bridging Cl- ions. Ni(PEt<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub> is a square planar complex, and Ni(Ph<sub>3</sub>AsO)<sub>2</sub>Cl<sub>2</sub> is tetrahedral.

18.6 Flattening of the tetrahedron splits the  $t_2$  energy levels into an upper level of energy  $2\delta$  and two lower levels each of energy  $-\delta$ . In a flattened  $d^8$  complex, the ligand-field stabilization energy is  $3\delta - 2\delta = \delta$ ; in a flattened  $d^9$  complex, the stabilization energy is  $4\delta - 2\delta = 2\delta$ . Elongation of the tetrahedron splits the  $t_2$  levels into two upper levels each of energy  $\delta$  and a lower level of energy  $-2\delta$ . In an elongated  $d^8$  complex, the stabilization energy is  $4\delta - 2\delta = 2\delta$ ; in a flattened  $d^9$  complex, the stabilization energy is  $4\delta - 3\delta = \delta$ .

18.9 The ligand-field stabilization energy of a  $d^7$  tetrahedral complex is greater than that of a  $d^8$ tetrahedral complex, and the LFSE of a  $d^8$  octahedral complex is greater than that of a  $d^7$  octahedral complex.

18.14 Infrared measurement of C-O stretching frequency, XPS measurement of C 1s or O 1s binding energy, <sup>13</sup>C nmr chemical shift, electron or x-ray diffraction measurement of C—O or M—C bond distance, etc.

18.15 Fe(CO)<sub>2</sub>(NO)<sub>2</sub> tetrahedral; Fe(CO)<sub>4</sub>H<sub>2</sub> cis-octahedral; Mn(CO)<sub>4</sub>NO trigonal bipyramidal with NO equatorial; Fe(CO)<sub>4</sub>CN<sup>-</sup> trigonal bipyramidal with CN axial; Fe(CO)<sub>4</sub>C<sub>2</sub>H<sub>4</sub> trigonal bipyramidal with ethylene carbons in equatorial plane.

18.17 In neither TiO nor VO does the metal atom have any  $e_s^*$  electrons that can engage in superexchange interaction.

# CHAPTER 19 La moissanail semandades set enteres transfer and sent enteres and sent enteres

 $19.1 \text{ Cr}(H_2O)_6^{3+} < Al(H_2O)_6^{3+} < Fe(H_2O)_6^{3+} < Y(H_2O)_6^{3+} < Sr(H_2O)_6^{2+} < K(H_2O)_6^{4-}.$ 

19.3 A is the cis complex; B is the trans complex. In the cis complex, the ammonia molecules are labilized by the trans chloride ions; replacement of an ammonia molecule by thiourea causes the trans chloride to be labilized. Hence all positions become occupied by thiourea. In the trans complex, the chloride ions labilize each other; only these ligands are displaced by thiourea molecules.

19.5 The NH<sub>2</sub>- ions catalyze the displacement of the last coordinated chloride ion by ammonia.

$$\begin{array}{ccc} Cr(NH_3)_5Cl^{2+} + NH_2^- & \rightleftharpoons & Cr(NH_3)_4(NH_2)Cl^+ + NH_3 \\ \\ Cr(NH_3)_4(NH_2)Cl^+ & \to & Cr(NH_3)_4(NH_2)^{2+} + Cl^- \\ \\ Cr(NH_3)_4(NH_2)^{2+} + 2NH_3 & \to & Cr(NH_3)_6^{3+} + NH_2^- \end{array}$$

19.7 If the reaction rate is reduced by the addition of Fe<sup>2+</sup> to the system, the formation of Sn(III) in a reversible primary step would be strongly indicated:

$$Sn(II) + Fe^{3+} \rightleftharpoons Sn(III) + Fe^{2+}$$
  
 $Sn(III) + Fe^{3+} \rightarrow Sn(IV) + Fe^{2+}$ 

19.9 The data suggest the following reaction paths:

If we let K equal the acid ionization constant of  $V(H_2O)_6^{3+}$ , then  $k = k_1 + k_2 K/(H^+)$ . 19.11 A second-order associative reaction of Ni(CO)<sub>4</sub> with L implies a very unstable intermediate or activated. On the other hand, activated complex with five ligands and 20 valence electrons on the nickel atom. On the other hand,

such an intermediate in the Co(CO)<sub>3</sub>NO + L reaction would not be unstable because the NO group can accept a pair of electrons from the Co atom, thus forming a bent NO group and maintaining an 18-electron count.

19.12 The two axial water molecules in  $Cu(H_2O)_6^{2+}$  are held much more weakly than the four equatorial ones as a consequence of Jahn-Teller distortion.

#### CHAPTER 20

20.4 The activation energies of hydrogen oxidative additions are much lower than the H<sub>2</sub> dissociation energy because the general mechanism involves the exothermic formation of M—H bonds simultaneously with the endothermic H—H cleavage.

20.6 (a) NiL<sub>4</sub> 
$$\xrightarrow{H^*}$$
 HNiL<sub>4</sub>  $\xrightarrow{C,H_4}$  L<sub>4</sub>Ni—CH<sub>2</sub>CH<sub>3</sub>  $\xrightarrow{H}$   $\xrightarrow{C_3H_4}$  L<sub>4</sub>Ni—CH<sub>2</sub>CH<sub>2</sub>CH<sub>3</sub>  $\xrightarrow{H}$   $\xrightarrow{H}$   $\xrightarrow{H}$  H H H H CH<sub>3</sub>CH<sub>2</sub>CH=CH<sub>3</sub>  $\xrightarrow{C}$   $\xrightarrow{$ 

**20.8** (a)  $(\eta^5 - C_5 H_5)$ Fe(CO)<sub>2</sub>(COCH<sub>3</sub>); (b) IrL<sub>2</sub>(CO)(CH<sub>2</sub>Cl); (c) [(CO)<sub>3</sub>Co]<sub>2</sub>(CR)<sub>2</sub>, tetrahedral cluster compound.

20.10 By using  $D_2O$  as a solvent, mass-spectrometric analysis of the product acetaldehyde would indicate whether any of the solvent hydrogen ends up in the acetaldehyde. Such a result seems unlikely, because it would require the effective loss of a proton from a C-H bond.

21.1 The data suggest that  $CO_2$  is adsorbed dissociatively, to give adsorbed CO molecules and adsorbed oxygen atoms.

21.2 1.78, 1.54, and 1.09 × 1015 atoms cm<sup>-2</sup>.

21.4 Platinum is not an electropositive metal; it does not form a stable nitride. Therefore it would not be expected to form a stable intermediate with  $N_2$ , as iron does.

#### CHAPTER 22

22.3 The following is just one possible mechanism:

If the CH<sub>2</sub> group of the diol were labeled with tritium, most of the tritium would end up in the water. and some of it would end up in the Co—CH<sub>2</sub>— group of the coenzyme.

22.5 (a) From the equilibrium constant expression for the reaction

$$K = \frac{[MbO_2]}{[Mb][O_2]}$$

one can readily derive the expression for the percentage saturation,


$$100 \frac{[\text{MbO}_2]}{[\text{Mb}] + [\text{MbO}_2]} = \frac{100 \times K[\text{O}_2]}{1 + K[\text{O}_2]}$$

By considering the form of the equation under the limiting conditions of very low and very high [O<sub>2</sub>], it can be seen that the curve is always concave downward.

(b) In this case, a similar derivation gives

$$100 \frac{[Mb(O_2)_n]}{[Mb] + [Mb(O_2)_n]} = \frac{100 \times K[O_2]^n}{1 + K[O_2]^n}$$

and it can be shown that this equation is concave upward at low  $[O_2]$  and concave downward at high  $[O_2]$ .



#### FORMULA INDEX

ADP, 523 ATP, 521-523 AgBr, 328 AgCd, 296 AgCd, 296 AgCl, 333 AgO, 209 Ag,S, 328 Ag<sub>1</sub>Hg<sub>4</sub>, 296 Al, 293, 319 Al3+, 205 AlEt, 496 AIF, 280 Al(OH), 273 (AlSiO<sub>4</sub>),\*-, 273 Al<sub>2</sub>Br<sub>4</sub>, 278 Al<sub>2</sub>SiO<sub>4</sub>F<sub>2</sub>, 284 Ar, 16, 534 As, 271, 302, 317 AsH , 166 Au(CN), 333 Au(CO)2, 359 AuCl, 334 Au<sub>2</sub>Cl<sub>4</sub>, 344-345 B, 318-319 B(CH<sub>1</sub>)<sub>1</sub>, 135, 209 BCl<sub>3</sub>, 154 BFCIBr, 28 BF<sub>3</sub>, 25-26, 53, 250 BHCl<sub>2</sub>, 154 BH<sub>2</sub>Cl, 154 BH<sub>3</sub>, 154, 253 BH<sub>3</sub>CN<sup>-</sup>, 47 BH<sub>3</sub>CO, 44, 47–48, 135 BH<sub>3</sub>N(CH<sub>3</sub>)<sub>3</sub>, 252 BH, 119, 161, 165-166, 255 B(OH)<sub>3</sub>, 188-189, 197-198 B(OH),-, 198 BO2, 47

B<sub>2</sub>, 106

B2Cl4, 154-155

B<sub>2</sub>H<sub>6</sub>, 154, 161, 166, 168,

249-251, 253-256

B2H7, 252 B,O, 250 B<sub>3</sub>C<sub>3</sub>H<sub>7</sub>, 258 B<sub>3</sub>H<sub>3</sub>Fe<sub>2</sub>(CO)<sub>6</sub>, 259-261 B<sub>3</sub>H<sub>8</sub>-, 252 B<sub>3</sub>N<sub>3</sub>(CH<sub>3</sub>)<sub>6</sub>Cr(CO)<sub>3</sub>, 49 B<sub>3</sub>N<sub>3</sub>H<sub>3</sub>Cl<sub>3</sub>, 38 B, N, H, 49 B<sub>3</sub>O<sub>3</sub>(OH)<sub>4</sub>-, 198 B4H10, 166, 249-251, 256, 258 B<sub>4</sub>H<sub>8</sub>Fe(CO)<sub>3</sub>, 259-261, 259-261 B<sub>5</sub>H<sub>11</sub>, 166, 249-250, 258 B<sub>5</sub>H<sub>12</sub>-, 252, 258 B, H, 249-250, 256, 258, 259-260 B<sub>6</sub>H<sub>10</sub>, 249-250, 258 B<sub>6</sub>H<sub>10</sub>(PMe<sub>1</sub>)<sub>2</sub>, 258 B<sub>6</sub>H<sub>6</sub><sup>2-</sup>, 251-252, 256-257 B<sub>2</sub>C<sub>2</sub>H<sub>13</sub>, 258 B<sub>9</sub>C<sub>2</sub>H<sub>11</sub><sup>2-</sup>, 259 B<sub>9</sub>C<sub>2</sub>H<sub>12</sub>-, 259 B<sub>9</sub>X<sub>9</sub>-, 258 B<sub>10</sub>C<sub>2</sub>H<sub>12</sub>, 259, 262 B<sub>10</sub>H<sub>10</sub><sup>2-</sup>, 252 B<sub>10</sub>H<sub>14</sub>, 249-250, 253 B<sub>10</sub>H<sub>12</sub>(Et<sub>2</sub>S)<sub>2</sub>, 253 B<sub>10</sub>C<sub>2</sub>H<sub>12</sub>, 253 B<sub>12</sub>H<sub>12</sub><sup>2-</sup>, 251-252 B<sub>n</sub>H<sub>n</sub><sup>2-</sup>, 162, 257-258 B, X,, 258 B<sub>n</sub>X<sub>n</sub><sup>2-</sup>, 258 BaTiO<sub>3</sub>, 321 BeCl<sub>2</sub>, 79 BeH<sub>2</sub>, 126 Be<sub>2</sub>, 106 Be<sub>2</sub>SiO<sub>4</sub>, 284 Be<sub>4</sub>O(O<sub>2</sub>CCH<sub>3</sub>)<sub>6</sub>, 344-345 bipy, 399-400 Br, 148-150 Br<sup>-</sup>, 222 BrCN, 47-48 BrF<sub>2</sub><sup>+</sup>, 204 BrF<sub>3</sub>, 204

BrF, . 88, 204 BrF. 88 BrO, 49 BrO, 49 Br2, 148-150

C, 271-272, 277-278, 312-313, 499-500 C(CH<sub>3</sub>)<sub>3</sub>\*, 203 C(C,H,),\*, 380 CF<sub>2</sub>, 80-81 CF, 368-369 CH(C,H,), 185 CHCl<sub>3</sub>, 209 CHF<sub>1</sub>, 173 CH<sub>2</sub>, 81, 126, 159 CH,CO, 48 CH, NH, 77 CH2N2, 47-48, 495 CH, 368 CH, CCH, 47 CH-CHO, 479-480 CH,CN, 47, 489-490, 501-502 (CH,CO)CH, 347 CH, COOH, 479-481 CH,COOOH, 480 CH<sub>3</sub>CO<sub>3</sub>, 480 CH,I, 481 CH<sub>3</sub>NC, 489-490 CH,NO, 173 CH<sub>2</sub>OH, 173, 480-481 CH<sub>3</sub>SH, 173 CH1X, 66 (CH<sub>1</sub>),NO, 54 CH<sub>4</sub>, 29, 119-121, 159, 175 CH,+, 175 CLi2, 81 CN-, 358-359, 368, 409 CNO-, 43 CN,2-, 47 CO, 107-111, 368, 478-481, 490-495, 501-504, 513

CO(NH<sub>2</sub>)<sub>2</sub>, 201

CO2, 47-48, 79, 196-197, 509, CIF, 140-143 511, 524-525 Cr(CO)6, 48, 344, 377-378, 482 CIF, 83, 87 CO,2-, 197, 368 Cr(C6H6)2, 379 CIO2, 230 CS, 47 CrCl<sub>3</sub>, 271-272, 334, 344 CIO2+, 230-231 C<sub>2</sub>(CN)<sub>4</sub>, 442 CrF2, 431 ClO<sub>3</sub>-, 230 C2H2, 253 CrH, 168 ClO, 41, 119 C2H2O, 47 Cr(H<sub>2</sub>O)<sub>5</sub>C<sub>6</sub>H<sub>7</sub>N<sub>2</sub>O<sup>4+</sup>, 463 Cr(H<sub>2</sub>O)<sub>5</sub>X<sup>2+</sup>, 462–463 Cl<sub>2</sub>, 150-151, 155 C, H, 154, 351, 440-442, Cl<sub>2</sub>O<sub>2</sub>, 230 474-475, 479-480, 495 [Cr(H<sub>2</sub>O)<sub>6</sub>]SO<sub>4</sub>, 424 Co, 303-305 C.H.OH, 173 Cr(H2O)62+, 462-463 Co(B<sub>0</sub>C<sub>2</sub>H<sub>11</sub>)<sub>2</sub>-, 259-260 (C2H3)2O, 205 Cr(H2O)63+, 463 Co(CCH3)4B3H6OC2H5(C5H5), (C,H,),S, 205 CrN, 308 393-394 C2H4, 27, 154 Cr(NO)4, 48 Co(CN), H, O2-, 452 C2N2, 489 CrO2, 429 Co(CN)<sub>5</sub>R<sup>3-</sup>, 472 Co(CN)<sub>5</sub>X<sup>3-</sup>, 452, 472 C2Ph2, 400 Cr(V), 468 C,S,R,2-, 351 Cr(VI), 468 Co(CN)52-, 452 C<sub>30</sub>H<sub>22</sub>N<sub>4</sub>, 505-507 Cr2(OAc)4.2H2O, 347 Co(CN),3-, 472 C24HSO4-2H2SO4, 313 Cr2O1, 320 Co(CO), NO, 48 C, H, 47 Cr3C2, 308 Co(CO), , 209 C, H, , 351 Cr(bipy)3"+, 400 Co(CO)4H, 478 C, H, 103 [Cr(dipy),]Br,-4H,O, 424 Co(C<sub>4</sub>H<sub>7</sub>N<sub>2</sub>O<sub>2</sub>)2R(B), 516-517 C, H, OH, 173 [Cr(en)<sub>3</sub>][Ni(CN)<sub>5</sub>]-1.5H<sub>2</sub>O, 335 Co(C<sub>6</sub>H<sub>7</sub>NO)<sub>5</sub><sup>2+</sup>, 335 C.H. 130-131 Cs-, 246-247 CoCl<sub>4</sub><sup>2-</sup>, 414-415, 427-428 C,H,N-, 352 CsCl, 278-279 CoCl<sub>5</sub>Cs<sub>3</sub>, 336 C.H. 474-476 CsCuCl<sub>1</sub>, 334 CoFe(CMe)<sub>4</sub>(BH)<sub>8</sub>C<sub>5</sub>H<sub>5</sub>, 390 C,N,H,+, 443-444 Cu, 295-297, 300-301 [CoH(CN)<sub>5</sub>]K<sub>3</sub>, 165 C,H,-, 351 Cu+, 480 CoH(CO)4, 183 C,H,N, 123, 168 Cu(CN)2K, 269 [Co(H<sub>2</sub>O)<sub>6</sub>](SO<sub>4</sub>)<sub>2</sub>(NH<sub>4</sub>)<sub>2</sub>, 424 C, H12, 103 CuCl<sub>2</sub>, 431 Co(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, 414, 460-461 C.H.CH, 184-185 CuCl<sub>4</sub><sup>2-</sup>, 433, 448 CoL<sub>4</sub>X<sub>2</sub>, 415-416 C<sub>8</sub>H<sub>3</sub>CH<sub>3</sub>, 184–185 CuF2, 431 CoL, 415 C.H.OH, 205 Cu(H2O)62+, 433 Co(NH<sub>3</sub>)<sub>5</sub>C<sub>6</sub>N<sub>2</sub>OH<sub>6</sub><sup>3+</sup>, 463 C<sub>s</sub>H<sub>s</sub>, 49, 209 CuI, 320 Co(NH<sub>3</sub>),Cl<sup>2+</sup>, 448 C.Li, 313 Cu(NH<sub>3</sub>)<sub>2</sub>+, 333 Co(NH<sub>3</sub>)<sub>5</sub>NO<sub>2</sub><sup>2+</sup>, 357–358 Co(NH<sub>3</sub>)<sub>5</sub>OH<sup>2+</sup>, 452–453 C, Na. 313 Cu(NH<sub>3</sub>)<sub>4</sub>(H<sub>2</sub>O)<sub>2</sub><sup>2+</sup>, 448 CuS, 199 C,H,+, 352-353 Co(NH<sub>3</sub>)<sub>5</sub>ONO<sup>2+</sup>, 357-358 C,H, 379 CuZn, 296 Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup>, 417, 452-453, C, AsF, 313 CuZn<sub>3</sub>, 296 C, H, 476 462-463 Cu<sub>2</sub>O, 320 Co(NH<sub>3</sub>)<sub>5</sub>py<sup>3+</sup>, 463 CaH16, 476 Cu, Al, 296 Co(NH<sub>3</sub>)<sub>6</sub><sup>2+</sup>, 343 Co(NH<sub>3</sub>)<sub>6</sub><sup>3+</sup>, 343, 447-448 CaHa2-, 131 Cu<sub>3</sub>Sn, 296 C<sub>1</sub>M, 313 Cu31Sn8, 296 [Co(NO)<sub>2</sub>I]<sub>2</sub>, 396 C12GeF5 6, 313 Cu<sub>5</sub>Sn, 296 [Co(NO<sub>2</sub>)<sub>6</sub>]K<sub>2</sub>Pb, 424 C, H2n+2, 493 Cu<sub>5</sub>Zn<sub>8</sub>, 296 C.H., 129-131 Co(PPh2Me)2Cl2NO, 439 Cu<sub>9</sub>Al<sub>4</sub>, 296 Ca, 299-300 Co2(CO)8, 478 Co2C4B6H10(C5H5)2, 393 CaAl<sub>2</sub>Si<sub>2</sub>O<sub>8</sub>, 273 CaCO<sub>3</sub>, 279-280 Co<sub>3</sub>O<sub>4</sub>, 437 e am, 241-246 CaC2, 279-280, 288-289 Co<sub>4</sub>B<sub>4</sub>H<sub>4</sub>(C<sub>5</sub>H<sub>5</sub>)<sub>4</sub>, 393 e aq, 236-241 Co4(CO)12, 344-345 en, 445 CaF<sub>2</sub>, 274-275 Eu<sup>2+</sup>, 241 Co<sub>6</sub>H(CO)<sub>15</sub>-, 345-346 CaGa2, 288 Co<sub>8</sub>(CO)<sub>18</sub>C<sup>2-</sup>, 387 CaH2, 161 Co(diars)<sub>2</sub>(NCS)NO+, 396-397 Ca(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, 448 Co(diars)<sub>2</sub>NO<sup>2+</sup>, 397 CaMg(SiO<sub>3</sub>)<sub>2</sub>, 271 F-, 160-161, 188 CaSi<sub>2</sub>, 288 Co(en), F2+, 416 FBrO<sub>2</sub>, 231 FCH, OH, 91 Ca2Mg3(OH)2(Si4O11)2, 271 Co(en)<sub>2</sub>(NO<sub>2</sub>)<sub>2</sub>+, 357 Co(phen)<sub>3</sub><sup>2+</sup>, 460–461 Co(phen)<sub>3</sub><sup>3+</sup>, 460–461 FCN, 47, 49 CdCl<sub>2</sub>, 271-272 CdCl<sub>5</sub>3-, 335 FCIO<sub>2</sub>, 231 CdO, 320 Cr(CO)<sub>5</sub>CMeOMe, 482 FIO<sub>2</sub>, 231 Cr(CO)<sub>5</sub>I<sup>-</sup>, 344 F<sub>2</sub>, 49, 70-71 CI-, 368 Cr(CO), PMe3, 344 F<sub>3</sub>C<sub>3</sub>N<sub>3</sub>, 49

Fd, 521-523

Fe, 220, 303-305, 495, 497-498 (Fe(CN)<sub>4</sub>)K<sub>4</sub>, 424 Fe(CN)<sub>3</sub><sup>3</sup>, 359, 458 Fe(CN),4-, 359, 370, 458 Fe(CO)<sub>2</sub>(NO)<sub>2</sub>, 48 Fe(CO),C2B3H3, 386 Fe(CO), C, H, 131 Fe(CO),(CHF2CF2)2, 442 Fe(CO), CN-, 439 Fe(CO),COR-, 473 Fe(CO),py, 439 Fe(CO), 259, 336, 471, 473 Fe(CO), H+, 471 FeC,H,(CO),H, 166 FeC<sub>3</sub>H<sub>3</sub>(C<sub>3</sub>H<sub>4</sub>SiCl<sub>3</sub>), 499 Fe(C,H,)2, 351-352, 379 Fe(C<sub>3</sub>H<sub>3</sub>)<sub>2</sub>+, 381 FeF<sub>3</sub>, 419-420 FeH<sub>2</sub>(CO)<sub>4</sub>, 338 [Fe(H<sub>2</sub>O)<sub>6</sub>](SO<sub>4</sub>)<sub>2</sub>(NH<sub>4</sub>)<sub>2</sub>, 424 Fe(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, 459 Fe(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, 459 FeH, 4, 165 Fe(NO)<sub>2</sub>(CO)<sub>2</sub>, 396 Fe(OH)2, 220 FeO<sub>4</sub>K<sub>2</sub>, 209 ECH , 220, 100 FeS, 320 Fe(SANE)2C1, 267-268 Fe(TIM)L<sub>2</sub><sup>2+</sup>, 418 Fe<sup>2+</sup>, 220, 221, 331, 468 Fe<sub>3</sub>(CO)<sub>6</sub>(HOCC(CH<sub>3</sub>)C(CH-3)COH), 386-387 Fe<sub>3</sub>(CO)<sub>3</sub><sup>2-</sup>, 501 Fe<sub>3</sub>(CO)<sub>9</sub>, 379 Fe<sub>2</sub>(C<sub>10</sub>H<sub>8</sub>)<sub>2</sub>+, 467-468 Fe<sub>2</sub>N, 308 Fe<sub>2</sub>Ni(CO)<sub>6</sub>(C<sub>2</sub>Ph<sub>2</sub>)C<sub>5</sub>H<sub>5</sub>, 403 Fe<sub>2</sub>(OH)<sub>2</sub><sup>4+</sup>, 344 Fe<sub>2</sub>O<sub>3</sub>, 320 Fe<sup>3+</sup> 221 Fe3+, 221 Fe<sub>3</sub>(CH<sub>3</sub>CHN)(CO)<sub>9</sub><sup>-</sup>, 501 Fe<sub>3</sub>(CH<sub>3</sub>CHN)(CO)<sub>9</sub>H, 501-502 Fe<sub>3</sub>(CH<sub>3</sub>CH<sub>2</sub>N)H<sub>2</sub>, 501-502 Fe<sub>3</sub>(CH<sub>3</sub>CNH)(CO)<sub>9</sub>-, 501 Fe<sub>3</sub>(CO)<sub>8</sub>(C<sub>2</sub>Ph<sub>2</sub>)<sub>2</sub>, 386 Fe<sub>3</sub>(CO)<sub>9</sub>C<sub>2</sub>Ph<sub>2</sub>, 403 Fe,H(CO),, 501 Fe<sub>3</sub>O<sub>4</sub>, 429, 437 Fe<sub>4</sub>C(CO)<sub>12</sub><sup>2-</sup>, 502 Fe<sub>4</sub>(CO)<sub>12</sub>CCO<sub>2</sub>CH<sub>3</sub>, 502-503 Fe<sub>4</sub>(CO)<sub>13</sub>H<sup>-</sup>, 389 Fe<sub>4</sub>[Fe(CN)<sub>6</sub>]<sub>3</sub>·xH<sub>2</sub>O, 359 Fe<sub>4</sub>H(CH)(CO)<sub>12</sub>, 502 Fe<sub>4</sub>N(CO)<sub>12</sub>, 388 Fe<sub>4</sub>S<sub>4</sub>(SCH<sub>2</sub>Ph)<sub>4</sub><sup>2-</sup>, 517-519 Fe<sub>5</sub>C(CO)<sub>14</sub><sup>2-</sup>, 502

Fe<sub>5</sub>(CO)<sub>15</sub>C, 385 Fe<sub>6</sub>C(CO)<sub>16</sub><sup>2-</sup>, 502-503 Fe(phen)<sub>2</sub>(NCS)<sub>2</sub>, 425-426 Fe(phen),2+, 418 Fe[(pz)<sub>3</sub>BH]<sub>2</sub>, 425 Fld, 521-523 Ga(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, 448 Gd<sup>2+</sup>, 241 Gd<sup>3+</sup>, 241 Ge, 319 GeH<sub>3</sub>-, 245 GeH<sub>3</sub>Br, 168 GeH<sub>3</sub>Na, 168 GeH<sub>3</sub>PH<sub>2</sub>, 167 GeH<sub>4</sub>, 168, 185, 245 Gel<sub>2</sub>, 319 Gel4, 319 GeR<sub>3</sub>-, 245 Ge<sub>2</sub>R<sub>6</sub>, 245 Ge<sub>9</sub><sup>2-</sup>, 261-262 Ge<sub>9</sub><sup>4-</sup>, 261-262 H, 148-151, 155-158, 237-241 H-160-161 H+, 219-220, 237-240 HBr, 148-150, 177 HCO<sub>3</sub>-, 196-197, 524-525 HCl, 27, 57-59, 187, 318 HClO<sub>4</sub>, 179 HClO<sub>4</sub>·H<sub>2</sub>O, 190 HCl·H<sub>2</sub>O, 190 HF, 170, 186-188, 191, 201, 203 HF, , 188 HI, 151-154 HNCO, 47 HNO<sub>3</sub>·3H<sub>2</sub>O, 191 HNO<sub>3</sub>, 201 HOCl, 77, 232 HN<sub>1</sub>, 48 HOCI, 77, 232 HO<sub>2</sub>, 157–158 us= 198–199 HS-, 198-199 HSO<sub>3</sub>-, 197, 233-234 HSO<sub>3</sub>CF<sub>3</sub>, 183 HSO<sub>3</sub>F, 203-204 HSO<sub>4</sub><sup>-</sup>, 181, 196 H<sub>2</sub><sup>+</sup>, 96, 100–101 H<sub>2</sub>, 54, 112-113, 147-159, 175, 219-220, 474, 478-479, 493-498 H<sub>2</sub>CO<sub>3</sub>, 196-197, 525 H<sub>2</sub>O, 26, 35, 66, 82, 124, 126, 155-157, 173, 184-187, 236-237, 278, 499-500

H,O+, 236

H<sub>2</sub>O<sub>2</sub>, 91, 157-158, 221,

H<sub>2</sub>PO<sub>2</sub><sup>-</sup>, 222

237-239, 526-527

LiH+, 96

H<sub>2</sub>PO<sub>4</sub>-, 182, 196 H<sub>2</sub>S, 60, 173, 198-199 H<sub>2</sub>SO<sub>3</sub>, 197 H<sub>2</sub>SO<sub>4</sub>, 179, 201-203, 250 H<sub>2</sub>S<sub>2</sub>, 60, 91 H,S,O, 201 H<sub>3</sub>+, 145, 175 H<sub>3</sub>AsO<sub>3</sub>, 217-219 H<sub>3</sub>AsO<sub>4</sub>, 217-219 H<sub>1</sub>O<sub>2</sub>, 191 H,PO, 179 H<sub>3</sub>PO<sub>4</sub>, 250 H<sub>5</sub>IO<sub>6</sub>, 223 Нь, 507-513 Hf, 295 Hf(BH<sub>4</sub>)<sub>4</sub>, 339-340 Hg<sup>2+</sup>, 205 HgCl+, 343 HgCl<sub>2</sub>, 79, 333, 343 HgCl<sub>3</sub><sup>-</sup>, 343 HgCl<sub>4</sub><sup>2-</sup>, 343 Hgl<sub>2</sub>, 271-272 Hg<sub>3</sub>AsF<sub>6</sub>, 309-310 COLCLES 1, 151-154 1-, 217-219, 222-223, 230, 233 IF<sub>7</sub>, 89 IO<sub>3</sub> -, 233-234 12, 151-154, 204, 205, 233 1, -, 45, 55, 115-118, 217-219, 223 - 7 (02) 10 24 10 Ir, 295 IrBr<sub>6</sub><sup>2-</sup>, 417 Ir(CO)(PPhMe<sub>2</sub>)<sub>2</sub>Cl, 471 Ir(CO)(PPhMe2)2(H)2Cl, 471 IrCl<sub>2</sub>(NO)(PPh<sub>3</sub>)<sub>2</sub>, 398 IrCl<sub>6</sub><sup>2-</sup>, 458 IrCl,3-, 458 Ir(PPh<sub>3</sub>)<sub>2</sub>(CO)(NO)Cl<sup>+</sup>, 396 Ir(PPh<sub>3</sub>)<sub>3</sub>Cl, 472 K, 242-243 K-, 246-247 KCl. 320 KF, 103, 204 KH, 161 KH<sub>2</sub>PO<sub>4</sub>, 188-190 KOH, 185-186, 201 LaH<sub>2</sub>, 162 La, Ba<sub>1</sub>-, TiO<sub>3</sub>, 321 Li, 242, 297-298 LiAlH<sub>4</sub>, 162, 165-166, 250 LiAl(SiO<sub>3</sub>)<sub>2</sub>, 271 LiAs, 289 LiCH<sub>3</sub>, 482 LiGa, 288 LiH, 64-65, 161-162, 320

***	
Li <sub>2</sub> +, 96	1. 108 H
Li <sub>2</sub> , 112-113, 297	
Li <sub>2</sub> O, 321	
Li <sub>6</sub> , 297-298	
$L_{1x}Mn_{1-x}O, 321$	
Li <sub>x</sub> Ni <sub>1-x</sub> O, 321	
Li, TiS <sub>2</sub> , 314	
Mb, 507-509	
Mg, 292	
MgSiO <sub>3</sub> , 269	
[Mn(CN).1K .2H O 45	No. The
[Mn(CN) <sub>6</sub> ]K <sub>4</sub> ·3H <sub>2</sub> O, 42 Mn(CO) NO 420	4
Mn(CO) <sub>4</sub> NO, 439 Mn(CO) <sub>5</sub> +, 183 Mn(CO) = 245, 279	
Mn(CO) <sub>5</sub> +, 183 Mn(CO) <sub>5</sub> -, 245, 378	
Mn(CO) CE 442 442	
Mn(CO) <sub>5</sub> CF <sub>3</sub> , 442-443	
Mn(CO) <sub>5</sub> CH <sub>3</sub> , 378	
Mn(CO) <sub>5</sub> Cl, 419	
MnC <sub>3</sub> H <sub>5</sub> (CO) <sub>4</sub> , 351-352	2 17 3
MnC <sub>7</sub> H <sub>7</sub> (CO) <sub>3</sub> , 353	VIII.II
MIIIC717(CO)6, 353	
MnCl <sub>6</sub> <sup>4-</sup> , 370	15,1,01
MnF <sub>2</sub> , 419–420	121-1
WINF 3, 431	100 11
MnH(CO) <sub>5</sub> , 183-184	75.
$[Mn(H_2O)_6](SO_4)_2K_2$ , 42	4
WIII(NO),C() 48 443	Street, street, 50-2
MIIO, 321, 429-431	351
111102, 223	WEST THAT
MnO <sub>4</sub> , 222–223, 244	MODEL I
WIHO4 , 244	TANK STATE OF
Mn <sub>2</sub> (CO) <sub>10</sub> , 245, 371–372	2, 378, N
417	The state of the s
Mn <sub>3</sub> O <sub>4</sub> , 437	MARIN N
1010, 495	4179 27
Mo(CO)(NO)(C,H.)C,H	s <sup>+</sup> , 473 N
MO(CO)2C7H7 H, B(3.5-	THE WAY
dimethylpyrazolyl).1	381 N
MO(CO)3C7H7, 380	5 5 12
Mo(CO) <sub>3</sub> C <sub>7</sub> H <sub>8</sub> , 380	all the work
Mo(CO) <sub>5</sub> P <sub>4</sub> S <sub>3</sub> , 267-268	
Mo(CO) <sub>6</sub> , 379	
MoC <sub>2</sub> H <sub>2</sub> (CO) <sub>2</sub> + 353	Parkey and the same
MoC <sub>7</sub> H <sub>7</sub> (C <sub>5</sub> H <sub>5</sub> )(CO) <sub>2</sub> , 353	
More, S. (1.2 522	N
MOO C1 2- 420	N
MoS <sub>2</sub> , 271–272	NI NI
	Carlotte Committee of the Committee of t
Mo, Fe, So(SFt) 3- 521 52	NI NI
Mo <sub>2</sub> Fe <sub>6</sub> S <sub>9</sub> (SEt) <sub>8</sub> <sup>3-</sup> , 521-52 Mo <sub>2</sub> Fe <sub>7</sub> S <sub>8</sub> (SEt) <sub>12</sub> <sup>3-</sup> , 522	Ne Ne
Mo <sub>2</sub> (HPO <sub>4</sub> ) <sub>4</sub> <sup>2-</sup> , 372	
	Ni.
Mo <sub>4</sub> O <sub>6</sub> Na, 309	Ni.
30.8 , 371	Ni(

N, 497–498 NCS <sup>-</sup> , 47
NCS- 47
NEt,+, 245 654 (23 M) (0080143
NF <sub>3</sub> , 65-66, 134
NH 407 400
NH, 497-498
[NII(CH <sub>3</sub> ) <sub>3</sub> ]OH. 184
NH <sub>2</sub> -, 199-201, 245
NH <sub>2</sub> , 497–498
NH <sub>2</sub> CN, 48
NH <sub>2</sub> NO <sub>2</sub> , 77
NH <sub>2</sub> OH, 54
NH <sub>3</sub> , 29, 35-36, 41, 65-66, 123,
186–187, 194–195, A Har
199–201, 209, 215–216, 160
241-246, 368, 497-498,
518-523
NH <sub>3</sub> BH <sub>3</sub> , 41
NH <sub>4</sub> <sup>+</sup> , 119, 194–196, 199–201,
245-246
NO, 46, 48, 155, 215-216
NO <sup>+</sup> , 231, 368
NOCI 10 11-
NOCI, 42, 155
NOF <sub>3</sub> , 44, 133–134
NO <sub>2</sub> <sup>+</sup> , 47–48, 231
NO <sub>2</sub> , 215
1102, 00, 145, 230, 232
43/-/3X JAA ADD
NO <sub>2</sub> <sup>2-</sup> , 237, 244 NO <sub>3</sub> <sup>-</sup> , 43
NO, -, 43
N <sub>2</sub> , 123, 497–498, 518–523
N <sub>2</sub> H <sub>2</sub> , 523
N H 54 OF STATE OF THE
N <sub>2</sub> H <sub>4</sub> , 54, 91, 215–216
$N_2H_6^{2+}$ , 54 $N_2O$ , 47, 77, 215, 245 $N_2O_2^{2-}$ , 28
N <sub>2</sub> O, 47, 77, 215, 245
$N_2O_2^{2-}$ , 28
N <sub>3</sub> , 47
114, 242-243, 297
Na , 246–248
VaCI 274 296 222
NaCl, 274, 286, 320
101, 1/0
1- 11/0/6 , 448
142 W U <sub>1</sub> , 308
a3IVIBAAI(()H).(Si O ) aar
b(NC, H10), 335
bOF, 3- 89
b.(CO)-(C H) 200
b <sub>3</sub> (CO) <sub>7</sub> (C <sub>5</sub> H <sub>5</sub> ) <sub>3</sub> , 389
0~12, 371-393
1 2 1 2 2
060112 , 392
-, 103
305-303. 4111 480 400 405
11, 270
Al <sub>2</sub> O <sub>4</sub> , 437
As, 275-276
(CN) <sub>3</sub> NO <sup>2-</sup> , 396
O

```
Ni(CN)<sub>4</sub><sup>2-</sup>, 29-30, 244
  Ni(CN)<sub>4</sub><sup>4-</sup>, 244
Ni(CN)<sub>5</sub><sup>3-</sup>, 335
  Ni(CO)<sub>4</sub>, 48, 438
  Ni(C<sub>2</sub>H<sub>4</sub>)<sub>3</sub>, 440–442
  NiCr<sub>2</sub>O<sub>4</sub>, 433
 Ni(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, 368, 408–409,
        411-414
 Ni(NH<sub>3</sub>)<sub>x</sub><sup>2+</sup>, 342–343
 NiO, 320-321
 NiO<sub>2</sub>Na, 431
 Ni(PPh<sub>3</sub>)<sub>3</sub>, 475
 Ni(S<sub>2</sub>C<sub>2</sub>Ph<sub>2</sub>)<sub>2</sub>-, 400-401
Ni(S<sub>2</sub>C<sub>2</sub>Ph<sub>2</sub>)<sub>2</sub>, 400–401
Ni(S_2C_2Ph_2)_2^{2-}, 400–401
NiX<sub>4</sub><sup>2-</sup>, 436
Ni(en)<sub>3</sub><sup>2+</sup>, 411–414
Ni<sub>4</sub>B<sub>4</sub>H<sub>4</sub>(C<sub>5</sub>H<sub>5</sub>)<sub>4</sub>, 393
Ni<sub>5</sub>(CO)<sub>12</sub><sup>2-</sup>, 389
Ni<sub>5</sub>Zn<sub>21</sub>, 296
Np(BH<sub>4</sub>)<sub>4</sub>, 339-340
```

O, 155

O<sup>2-</sup>, 368 OCN-, 43 OCS, 47-48, 57 OCI-, 230 OF<sub>2</sub>, 82 OH, 155, 236-239 OH-, 184-186, 192-194 OH<sub>3</sub><sup>+</sup>, 41, 190–194, 196, 201 ONF<sub>3</sub>, 44, 133-134 OPF<sub>3</sub>, 134 O<sub>2</sub>+, 106 O<sub>2</sub><sup>-</sup>, 106, 221, 237, 244, 526-527 O<sub>2</sub>, 46, 106, 108-110, 155-158, 220, 237–239, 244, 343, 499-500, 507-513, 526-527 O<sub>2</sub>F<sub>2</sub>, 54-55, 91 O<sub>2</sub><sup>2-</sup>, 106 O<sub>3</sub>, 42, 80, 117-118, 145 Os, 295 Os(CO)<sub>4</sub>H<sub>2</sub>, 472 Os(CO)<sub>5</sub>, 472 OsHCl(CO)(PPh<sub>1</sub>)<sub>1</sub>, 166 OsHCl<sub>2</sub>[ $P(C_4H_9)_2C_6H_5$ ]<sub>3</sub>, 165 OsH<sub>2</sub>(CH<sub>2</sub>)(CO)<sub>10</sub>, 503-504 OsH<sub>3</sub>(CH)(CO)<sub>9</sub>, 503-504 [Os(NH<sub>3</sub>)<sub>4</sub>Cl]<sub>2</sub>N<sub>2</sub><sup>3+</sup>, 466–467  $[Os(NH_3)_5]_2N_2^{5+}, 466$ OsO<sub>2</sub>(CN)<sub>4</sub><sup>2-</sup>, 438 Os<sub>3</sub>(CO)<sub>10</sub>C<sub>2</sub>Ph<sub>2</sub>, 403 Os<sub>3</sub>(CO)<sub>12</sub>, 383 Os<sub>3</sub>H(CH<sub>3</sub>)(CO)<sub>10</sub>, 503-504 Os<sub>4</sub>(CO)<sub>13</sub>H<sup>-</sup>, 389 Os<sub>5</sub>(CO)<sub>16</sub>, 383 Os<sub>6</sub>(CO)<sub>18</sub>, 384

P. 319, 326  $P(C_6H_5)_3$ , 183 P(C,H,), 335 PCl<sub>4</sub><sup>+</sup>, 119 PF<sub>3</sub>, 134, 368-369 PF<sub>1</sub>(CH<sub>1</sub>)<sub>2</sub>, 83-85 PF<sub>4</sub>CH<sub>3</sub>, 83-85 PF<sub>5</sub>, 55, 83-84 PH<sub>3</sub>, 137-140, 166, 177-178, 185, 222 POF<sub>3</sub>, 134 PO[N(CH<sub>3</sub>)<sub>2</sub>]<sub>3</sub>, 246 P2H4, 5, 91 P4, 132, 222 PaH<sub>3</sub>, 162 Pd, 490-491 PdCl<sub>2</sub>, 269-270, 480 PdH<sub>0.6</sub>, 162 Pt, 295, 310-311, 324-325, 489  $Pt(CMe)_2(BH)_6(PMe_3)_2$ , 387  $Pt(CN)_4K_2 \cdot 3H_2O, 310$ Pt(C<sub>2</sub>H<sub>4</sub>)Cl<sub>3</sub><sup>-</sup>, 351-352  $[PtCl_3(C_2H_4)]K \cdot H_2O, 440$ PtCl<sub>4</sub><sup>2-</sup>, 25-26, 37-38, 454 [PtCl<sub>6</sub>]K<sub>2</sub>, 355 PtF<sub>6</sub>, 209, 216  $PtHCl[P(C_2H_5)_3]_2, 165$  $PtL_2(CH_2CMe_2CH_2)$ , 477 PtL<sub>2</sub>(CH<sub>2</sub>CMe<sub>3</sub>)<sub>2</sub>, 477 PtL2Cl2, 456 [Pt(NH<sub>3</sub>)Cl<sub>5</sub>]K, 355 PtNH<sub>3</sub>NO<sub>2</sub>Cl<sub>2</sub>-, 455  $Pt(NH_3)^{2+}, 454$ Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub>, 356, 454, 524 Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>4</sub>, 355, 524  $Pt(NH_3)_2(H_2O)Cl^+, 524$  $Pt(NH_3)_2(H_2O)_2^{2+}, 524$ [Pt(NH<sub>3</sub>)<sub>3</sub>Cl<sub>3</sub>]Cl, 355 [Pt(NH<sub>3</sub>)<sub>4</sub>Cl<sub>2</sub>]Cl<sub>2</sub>, 355 [Pt(NH<sub>3</sub>)<sub>5</sub>Cl]Cl<sub>3</sub>, 355 [Pt(NH<sub>3</sub>)<sub>6</sub>]Cl<sub>4</sub>, 355 Pt[P(CH<sub>3</sub>)<sub>3</sub>]<sub>4</sub>, 209 Pt(PR<sub>3</sub>)<sub>2</sub>, 381-382 Pt(PR<sub>3</sub>)<sub>2</sub>(H)Cl, 166 Pt(PR<sub>3</sub>)<sub>3</sub>, 381 Pt(PR<sub>3</sub>)<sub>4</sub>, 381 Pt(SnCl<sub>3</sub>)<sub>5</sub><sup>3-</sup>, 211 Pt(dien)X+, 458  $Pt(py)_2Cl_2(C_3H_5R), 477$ Pu(BH<sub>4</sub>)<sub>4</sub>, 339–340

Re, 295 ReH<sub>9</sub>K<sub>2</sub>, 165 ReH<sub>9</sub><sup>2+</sup>, 340 ReO<sub>2</sub>py<sub>4</sub><sup>+</sup>, 438 Re<sub>2</sub>(C<sub>1</sub>H<sub>3</sub>)<sub>4</sub>, 372 Re<sub>2</sub>Cl<sub>4</sub>(PR<sub>3</sub>)<sub>4</sub>, 372 Re<sub>2</sub>Cl<sub>8</sub><sup>2-</sup>, 372 Re<sub>3</sub>Cl<sub>12</sub><sup>3-</sup>, 380–381 Re<sub>4</sub>(CO)<sub>16</sub><sup>2-</sup>, 384–385 Rh, 491-493 Rh(CO)<sub>2</sub>I<sub>2</sub>-, 481 RhCl(PPh<sub>3</sub>)<sub>2</sub>, 474 RhCl(PPh<sub>3</sub>)<sub>2</sub>(H)R, 474 RhCl(PPh<sub>3</sub>)<sub>2</sub>(H)<sub>2</sub>, 474 RhCl(PPh<sub>3</sub>)<sub>2</sub>(H)<sub>2</sub>(olefin), 474 RhCl(PPh<sub>3</sub>)<sub>3</sub>, 473-474 RhFe3(CO)11C5H5, 384 Rh<sub>13</sub>(CO)<sub>24</sub>H<sub>3</sub><sup>2-</sup>, 387 Rh<sub>17</sub>(S)<sub>2</sub>(CO)<sub>32</sub><sup>3-</sup>, 395 Rh<sub>2</sub>(O<sub>2</sub>CR)<sub>4</sub>, 372 Rh<sub>22</sub>(CO)<sub>35</sub>H<sub>x</sub><sup>5-</sup>, 394-395 Rh<sub>22</sub>(CO)<sub>37</sub><sup>4-</sup>, 394-395 Rh<sub>6</sub>(CO)<sub>15</sub>C<sup>2-</sup>, 389 Rh<sub>6</sub>(CO)<sub>16</sub>, 344-345 Ru<sup>2+</sup>, 439 RuCl<sub>3</sub>·3H<sub>2</sub>O<sub>3</sub> 343 RuCl<sub>6</sub><sup>2-</sup>, 417  $Ru(NH_3)_4(C_6N_2OH_6)_2^{n+}, 439$ Ru(NH<sub>3</sub>)<sub>4</sub>H<sub>2</sub>OLCo(NH<sub>3</sub>)<sub>5</sub><sup>4+</sup>,  $Ru(NH_3)_4SO_4LCo(NH_3)_5^{2+}$ 463  $Ru(NH_3)_5C_4N_2H_5^{3+}$ , 444  $Ru(NH_3)_5C_4N_2H_5^{4+}$ , 444 Ru(NH<sub>3</sub>)<sub>5</sub>Cl<sup>2+</sup>, 343  $Ru(NH_3)_5H_2O^{2+}$ , 343  $Ru(NH_3)_5N_2^{2+}$ , 343 [Ru(NH<sub>3</sub>)<sub>5</sub>]<sub>2</sub>C<sub>2</sub>N<sub>2</sub><sup>5+</sup>, 466 [Ru(NH<sub>3</sub>)<sub>5</sub>]<sub>2</sub>N<sub>2</sub><sup>5+</sup>, 467  $Ru(NH_3)_6^{2+}$ , 343 Ru<sub>4</sub>Cl(CO)<sub>13</sub>-, 387-388 Ru<sub>6</sub>(CO)<sub>17</sub>C, 385 [Ru(bipy)2Cl]2C4H4N23+, 465-466

S. 269-270 S2-, 198-199 SCN-, 358 SF4, 83, 87 SF<sub>4</sub>CH<sub>2</sub>, 88-89 SF<sub>6</sub>, 45, 88 (SN), 311-312 SO<sub>2</sub>, 53, 197, 232-233 SO<sub>3</sub>, 201  $SO_3^-, 232$ SO<sub>3</sub><sup>2-</sup>, 197 SO<sub>4</sub><sup>2-</sup>, 45, 231, 232 S<sub>16</sub><sup>2+</sup>, 204 S2F2, 91 S<sub>2</sub>N<sub>2</sub>, 77, 132, 311 S<sub>2</sub>O, 76-77 S2O52-, 197 S2O6F6, 204  $S_2O_6^{2-}, 232$ S,N,CI+, 43-44, 133 S<sub>3</sub>N<sub>3</sub>-, 132 S<sub>3</sub>N<sub>3</sub>Cl<sub>3</sub>, 132 S42+, 204

S<sub>4</sub>N<sub>3</sub>+, 132

S<sub>4</sub>N<sub>4</sub>, 38, 92, 132, 266 S4N4F4, 92-93 S4N4H4, 132 S,N,+, 132 S,NH, 132 S<sub>8</sub>, 28-29, 60, 92 S,2+, 92, 204 SbBr<sub>6</sub><sup>3-</sup>, 90  $Sb(C_2O_4)_3^{3-}, 89-90$ Sb(C<sub>6</sub>H<sub>5</sub>)<sub>5</sub>, 335 Sb(C<sub>6</sub>H<sub>6</sub>)5, 87 SbF<sub>5</sub>, 191, 201, 203-204 ScH<sub>2</sub>, 162 Sc, Cl8, 309 Se, 269, 327 SeO<sub>4</sub><sup>2-</sup>, 49 Se, N4, 266 Se<sub>8</sub><sup>2+</sup>, 204 Si, 316-320, 325-327, 499 SiF<sub>4</sub>, 25-27, 45, 53-54, 280 SiHCl, 318 SiH<sub>2</sub>CH<sub>2</sub>, 127 SiH, Br, 167 SiH, K, 167 (SiH<sub>3</sub>)<sub>3</sub>N, 128-129 SiH4, 166 SiO<sub>2</sub>, 128, 278, 318 SiR, X, 209 SiS<sub>2</sub>, 269, 284 Si<sub>2</sub>(C<sub>6</sub>H<sub>2</sub>(CH<sub>3</sub>)<sub>3</sub>)<sub>4</sub>, 128 SmH<sub>2</sub>, 162 Sn, 331 SnCl2, 211 SnCl<sub>2</sub>N(CH<sub>3</sub>)<sub>3</sub>, 211 SnCl<sub>2</sub>N(CH<sub>3</sub>)<sub>3</sub>BF<sub>3</sub>, 211 SnCl, , 211 Sr(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, 448 SrTiO<sub>3</sub>, 324

TaF,2-, 89 Te, 327 Te<sub>4</sub><sup>2+</sup>, 204 Te<sub>6</sub><sup>2+</sup>, 204 Te64+, 261-262 TeBr<sub>6</sub><sup>2-</sup>, 90 TeCl<sub>6</sub><sup>2-</sup>, 90 ThH<sub>2</sub>, 162  $Th(i-PrN(O)C(O)t-Bu)_4$ , 339 Ti, 295 Ti(C<sub>5</sub>H<sub>5</sub>)<sub>2</sub>(CH<sub>2</sub>CR<sub>2</sub>CH<sub>2</sub>), 477 Ti(C5H5)4, 353-354 TiCl, 496 TiCl<sub>4</sub>, 496 Ti(H<sub>2</sub>O)<sub>6</sub><sup>3+</sup>, 368, 432 TiN, 308 TiO, 320 TiO2, 276 TiO2-xFx, 324 TiS<sub>2</sub>, 313-314 TI(II), 468

#### 584 FORMULA INDEX

TI<sup>3+</sup>, 468 TICI, 282 TI<sub>2</sub>AIF<sub>3</sub>, 336

U(C<sub>8</sub>H<sub>8</sub>)<sub>2</sub>, 131 UH<sub>3</sub>, 162 UO<sub>2</sub>F<sub>5</sub><sup>3-</sup>, 89

V<sup>2+</sup>, 331 V<sup>3+</sup>, 331 V(CO)<sub>2</sub>C<sub>2</sub>H<sub>2</sub>, 443 V(CO)<sub>6</sub>, 381 VH, 162 VO<sup>2+</sup>, 331 VO<sub>2</sub>+, 331 VO<sub>2</sub>F<sub>4</sub><sup>3-</sup>, 438 V<sub>2</sub>O<sub>7</sub><sup>4-</sup>, 344

W, 295, 494–495 W(CO)<sub>5</sub>CR<sub>2</sub>, 476–477 W(O)(PEt<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub>(CHCMe<sub>3</sub>), 476–477 WO<sub>3</sub>, 308 WO<sub>3-1</sub>F<sub>4</sub>, 324 W<sub>3</sub>(NEt<sub>2</sub>)<sub>4</sub>Cl<sub>2</sub>, 372

Xe, 70-71 XeF<sub>2</sub>, 70-71 XeF<sub>4</sub>, 70-71, 88 XeF<sub>6</sub>, 70-71 XeOF<sub>4</sub>, 70-71

Zn, 296-297, 331 Zn<sup>2+</sup>, 241 ZnFe<sub>2</sub>O<sub>4</sub>, 437 [Zn(H<sub>2</sub>O)<sub>6</sub>]SiF<sub>6</sub>, 433 ZnO, 320 ZnS, 276-277 Zr, 295 Zr(BH<sub>4</sub>)<sub>4</sub>, 339-340 ZrC, 295 ZrF, <sup>3-</sup>, 89 ZrPt<sub>1</sub>, 295

Absorption spectrum: On an aband base abios of alkali metals in THF, 246-247 of ammoniated electron, 241-242 of hydrated electron, 238 Acceptor level in p-type semiconductor, 318 Acceptors, electron pair, in acid-base theory, 205 Acetaldehyde, intermediate in oxidation of ethylene to acetic acid. 479-481 Acetate ion, bridging, 347 Acetic acid: formation from ethylene, 479-480 formation from methanol, 480-481 Acetonitrile, 47 adsorption on Ni, 489 reaction with Fe clusters, 501-502 Acetoxy radical, intermediate in oxidation of acetaldehyde, 480 Acetylacetone, 347 Acetylene in carborane synthesis, 253 Acetylenes, hydrogenation using Wilkinson's catalyst, 474 Acid-base reactions, 171-213 Acid-base theory: Brönsted, 199 Lewis, 205-211 "solvent," 204 Acid catalysis of oxyanion reductions, 230-231 quois tegodiso beisalbicoo at Acid hydrates, oxonium ion in, 190-191 Acidity: aqueous acids, correlation with rate of reac-

tion with  $e_{aq}^{-}$ , 240

of binary hydrides, 177-179

of aqueous hydrogen atom, 240 aqueous protonic acids, 177-184

comparison of aqueous with gas-phase, 182

effects of substituents on gas-phase, 171-174

gas-phase, 171-176

of gas-phase BH+, 173

in liquid ammonia, 178 of toluene and water in gas phase and aque-

ous solution, 184-185 Acidity function, 202–203

in aprotic solvents, 204 aqueous protonic, 177-184 of the Consense of the land of the Land conjugate, 199 correlation of heat of ionization with electron affinity of radical, 175 entropy of ionization, 195-196 hard and soft, 205-209 kinetics of reaction with metal-ammonia solutions, 246 nomenclature, 559-560 in protonic solvents, 199-204 some special cases, 196-199 table of pK values, 177, 179, 180, 183 thermodynamic data for ionization, 195-196 very strong, as reaction media, 203-204 Actinides, 13-14 Activated complex: in H<sub>2</sub> + I<sub>2</sub> reaction, 153 in ligand substitution, and LFSE, 449-451 Activation energy, 147-151, 156 of ligand substitution, and LFSE, 449-451 Pt (II) complex substitution reactions, Activation volumes of ligand exchange reac-

Acyl cations in strongly acidic media, 203-204

Acyl complexes by oxidative addition to metal

oxidative, in homogeneous catalysis,

Adsorbed species, tools for characterization,

effects of surface site, 484-490

as function of surface coverage, 490-493

sis, 478–480

Affixes in inorganic nomenclature, 564-565 Aldehydes, formation by homogeneous cataly-

To notice complexation of

carbonyl, 473

Adenosine, complex with vitamin B<sub>120</sub>,

Addition:

484-487

Adsorption:

in homogeneous catalysis, 470-471

Acids: 107 warming the bary releases a referred

Alkali metals, 14 Anion size, effect on hydration energy, 185 anionic, 246-248 Anion structures and isoelectronic principle, compounds with graphite, 313 288-289 solutions in nonaqueous solvents, 241-248 Anion vacancies in defect semiconductors, 320 Alkaline earth dihalide molecules, bond Answers to problems, 566-578 angles, 94 Antibonding molecular orbitals, 100 Alkaline earths, 14 Anticancer activity of cis-Alkenes (see Olefins) dichlorodiammineplatinum(II), 524 Alkyl group, effect of size on acidity of gas-Antiferromagnetism, 332, 428-431 phase protonic acid, 173 Antimony pentafluoride: Allene, 47 acidity in BrF, 204 Allosteric theory of heme-heme interaction, acidity in H,SO4, 201 solutions as super-acid media, 203-204 Allowed transitions in electronic spectra, Antimony pentaphenyl, 87 404-406 Appearance potential spectroscopy, 487 Alloys: Aprotic solvents: bonding energies and structures, 291-297 acids and bases in, 204 reaction with H2, 164-165 physical properties of, 206-207 Allred-Rochow electronegativities, 72-73 Aquation of Pt(NH<sub>3</sub>)<sub>2</sub>Cl<sub>2</sub>, 524 Allyl alcohol, isomerization to propionalde-Aqueous electrons, 236-241 hyde, 478 Aqueous redox chemistry, 214-235 Allyl complexes of manganese, 351-352 Arachno boranes, 252, 258 Allyl ligand, nucleophilic attack at, 473 Arachno metal clusters, 383-385, 387-389 Aluminosilicates, crystal structure, 273 Arfvedsonite, 271 Aluminum, semiconductor dopant, 319 Arginine residue in superoxide dismutase, Aluminum bromide, 278 526-527 Aluminum bromide structure, 278 Argon: Aluminum hydroxide, crystal structure, ionization potentials, 16 272-273 x-ray photoelectron spectrum, 16 Aluminum triethyl, reaction with TiCl, to Aromatic hydrocarbons, Hückel treatment, form Ziegler-Natta catalyst, 496 129-131 Ambidentate ligands, 357 Aromatic systems, pi bonding to transition Amide ion, synthesis in NH, 245 metals, 351-354 Amide radical on Fe surface in Haber process, Aromaticity, 130 Arsenic: Amines, kinetics of proton exchange with crystal structure, 271 annudana ni panishana ammonium ions, 194-195 semiconductor dopant, 317, 319 Ammonia: acidities of substituted, 178-179 Arsenic acid, 217-219 Arsenic cluster compound, 262 complexes of platinum, 355-356 Arsenic pentafluoride, intercalation in dipole moment, 65-66 formation from N2 by nitrogenase, 518-523 graphite, 313 Arsenious acid, 217-219 hydrogen bonding in, 186-187 irreducible representation of  $p_x$  and  $p_y$  nitro-Arsine, synthesis, 166 gen orbitals in, 35 Atomic charges: 100 House to the May 100 hours kinetics of proton exchange with NH,+, in coordinated carbonyl groups, 443 correlation with ligand replacement rate, 194-195 Lewis octet structure of, 41 liquid: ionization of, and acid-base reactions from extended Hückel study of PH3, 139-140 in, 199-200 pK values in, 178 of Ni atoms in dithiene complexes, 401 solutions of metals, 241-246 from XPS, 69-71 Atomic core, 13 evi-val asbirbyd yanid lo oxidation by NO, 215-216 stepwise complexation of Ni2+, 342-343 Atomic orbitals, 3, 10-13 per la goringmos synthesis from N<sub>2</sub> and H<sub>2</sub>, 497-498 energies, 3-10 sq no empuritedura lo amalla Ammoniated electrons, 241-246 linear combinations of, 96-102 shapes, 3-9 ET THE seangeage reactions, 244-246 symmetry, 9 201 almontus blapil at Amorphous semiconductors, 326-327 Amphiboles, 269-270 Atomization energies: Angular wave functions, 3-4 of metals, 291-293 of molecules, 57

reaction with OH-, 48

Bite of trischelate complex, 350 Atoms: Street barren and see geometric barren Body-centered cubic structure, 266-267, 274 in chain reactions, 148-151, 155-158 of metals, 293-297 electron affinities, 535 electron configurations, 10-13 Boiling points: aprotic solvents, 206-207 size, 21-22 correlation with ligand replacement rate, boranes, 250 molecular hydrides, and hydrogen bonding, term symbols for, 532-534 protonic solvents, 200 total binding energy, 20-21 ATP, reaction with vitamin B<sub>12s</sub>, 514 Bond angles: in alkaline-earth dihalide molecules, 94 Aufbau of atoms, 10 in MF, and OMF, molecules, 134 Auger electron spectroscopy, 486 of some hydrides, 81
Bond cleavage: Axial vs. equatorial coordination in d8 trigonal bipyramidal complexes, 439-440 ir metal-ammonia solution reactions, Axial ligands in dinuclear complexes, effect on 244-246 metal-metal bonding, 372 in oxidative addition, 471-472 Axis of symmetry, 25 Bond dissociation energy, 55 Azide ion, 47 Bond distance, 50-55 correlation with bond order, 53 correlation with force constant, 63 Back bonding, 368-370, 438-444 correlation with hybridization, 123 in CO adsorbed on metals, 491-492 in nitrogen-oxygen compounds, 53 effect on reactivity, 443-444 N-O, in nitrosyl complexes, 398-399 and trans effect, 455-456 Band bending at semiconductor junctions, Bond energies, 59-62 effect on coordination number, 340-341 322+324 no use toobs murrosque termini Band gaps of semiconductors, 319-320 table of, 60 Band theory of metals, 297-306 Bond integral, 99 Barium titanate, 321 moore level vations OM Bond length(s): correlation with bonding charge, 115 Base hydrolysis of Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup> ions, 452-453 correlation with dissociation energy, 55 Base strengths of NH<sub>3</sub>, pyridine, and N<sub>2</sub>, 123 in MF, and OMF, molecules, 134 in aprotic solvents, 204 Bond order, 102 correlation with bond distance, 53 conjugate, 199 of diatomic molecules, 107 correlation of proton affinity with ioniza-Bond polarity, 64-76
Bond rotations, 91-92 tion potential, 176 hard and soft, 205-209 Bond strength, 55-63 in protonic solvents, 199-203 of coordinated carbonyl group, 443 very strong solutions, as reaction media, 203 Bond-stretching force constants, 62-63 onding: in boranes, 253-259 of gas-phase B, 173 Bonding: inconstancy of trends, 205 Batteries, rechargeable, use of TiS, in, 314 boron compounds, criteria for, 254 classification of, 264-265 Bending frequencies for linear triatomic spein coordination compounds, 361-374 from magnetic data, 423-428 Berry mechanism of pseudorotation, 84, 336 covalent, 40-95 delocalized, 42-45 Bidentate ligands, 346-351 Biferrocenylene, 467-468 in metallic hydrides, 162-163 Bifluoride ion, hydrogen bonding in, 188 Bonding charge in C-C bonds, correlation Bimolecular reaction of H<sub>2</sub> and I<sub>2</sub>, 151–153 with C-C bond length, 115 Binuclear complexes, metal-metal bonding, Bonding energies of metals, 291-294 Bonding MOs, 100 Bioinorganic chemistry, 505-528 Biological systems, 505–528
Bipyridyl complexes, 399–400 Borane (BH<sub>3</sub>), 253 Borane ammine, Lewis octet structure of, 41 Stongs OM gracode lu de Bis(benzene)chromium and 18-electron rule, Borane anions: bonding in B<sub>n</sub>H<sub>n</sub><sup>2-</sup>, 257 synthesis, 251-252 Borane carbonyl, 44, 47, 135 nature of aqueous solutions, 197

reaction with IO<sub>3</sub>, 233-234

Boranes, 249-263 physical properties, 250 structure and bonding, 253-259 synthesis of, 166, 249-253 from lower hydrides by electric discharge, by pyrolysis of B<sub>2</sub>H<sub>6</sub>, 250-251 Borate ion, structure of, in aqueous solution, 198 Borazine: poor analog of benzene, 49 reaction with HCl, 49 Boric acid, ionization in aqueous solution, 198 Boric acid crystals, hydrogen bonding in, 188-189 Boric oxide in B<sub>2</sub>H<sub>6</sub> synthesis, 250 Borohydride (see Hydroborate) Boron, semiconductor dopant, 318-319 Boron halide clusters, 258-259 Boron hydrides (see Boranes) Boron trifluoride: in B<sub>2</sub>H<sub>6</sub> synthesis, 250 bond distance, 53 Boron trimethyl, 135 Branch and Calvin equation for estimating pKvalues, 181-182 Branching-chain reaction, 155-157 Brass structures, 296-297 Brewer and Engel rules, 293-297 Bridging bidentate ligands, 347 Bridging carbonyl groups, 344-345 in CO adsorbed on metals, 491-494 Bridging CO group, unsymmetric, 389 Bridging hydrogens in boranes, 253 Bridging ligands, function in electron transfer, 462-468 Bridging monodentate ligands, 344-346 Bromate, oxidation by fluorine to perbromate, Bromide, oxidation by O2, 222 Bromine, reaction with H<sub>2</sub>, 148-150 Bromine pentafluoride, structure and bonding, 88 Brönsted-Bjerrum equation, 237-238 Brönsted concept of acids and bases, 199

Bronzes, tungsten, 308–309
Buildup of atoms, 10
Butterfly clusters, 384–385, 387–389, 502–503

Cadmium chloride, crystal structure, 271–272
Calcite structure, 279–280
Calcium, band theory applied to, 299–300
Calcium carbide structure, 279–280, 289
Calcium gallide structure, 288
Calcium silicide structure, 288
Calculations in MO theory, 135–145
Cancer drug cis-platinum, 524
Capped metal clusters, 383–384, 387, 395
Capped octahedral geometry, 338
Capped porphyrin, 511–512

Capped trigonal prismatic geometry, 338 months Carbenes: and and all the mean of the later of geometry, 80-81 transition-metal complexes, 482 in olefin metathesis, 475-477 Walsh diagram treatment, 126 (See also Methylene) Carbides, metallic: preparation, 307-308 properties, 307 Carbon atom in metal cluster, 385, 387, 389, 502-503 All Amazon magazon policio 1004 A Carbon-carbon single bond length as function of hybridization, 50-52 hims gold lan Carbon dioxide, 47 reactions with OH- and uv light, 48 slowness of reaction with H2O and OH, 196-197, 524-525 Carbon disulfide, 47 Carbon-hydrogen bond breaking in Os, clusters, 503-504 Manager Was Springer and Carbon monoxide: And the state of the O'D at adsorption as function of surface coverage, 490-493 AZA ZZA DO 110 ZOBIL DO dissociation on metal surfaces, 494-495 infrared spectrum adsorbed on Pd, 490 LEED spectra of, adsorbed on metals, 491-493 Mos los Marsan in senon band MO energy level diagram, 107 poisonous character of, 513 reaction of: with CH3OH to form acetic acid, 480-481 with H<sub>2</sub> in Fischer-Tropsch synthesis, 493-496 with H<sub>2</sub> in hydroformylation, 478-479 with H<sub>2</sub>O to form CO<sub>2</sub> and H<sub>2</sub>, 479 wave function contours, 108, 110 XPS spectrum of, adsorbed on W, 494 Carbonic acid, 196-197, 524-525 Carbonic anhydrase, 524-525 Carbonium ions in strongly acidic media, 203 Carbonyl group: ambidentate character in gold complex, 359 back bonding to: in Ni(CO)4, 438 in transition-metal carbonyls, 443-444 bridging, 344-345 effect on acidity of transition-metal hydrides, 183 unsymmetric bridging in cluster, 389 Carbonyl hydrides, pK values, 183 Carbonyl sulfide, 47 dissociation energies, 57 reaction with uv light, 48 Carbonyls, transition-metal, 48 Carboranes: isomerization, 262 synthesis, 253 Caro's acid, 234 Catalysis:

acid, of oxyanion reductions, 230-231

Cis-trans isomerism of transition-metal com-

Catalysis (Cont.): heterogeneous, 484-504 homogeneous, 470–483 involving transition-metal compounds, 332-333 nonexplana a marila nword of metal-ammonia reaction, 245 by metal clusters, 501-504 types of reactions involved, 470-473 Catenation in nonmetal hydrides, 167 Cation vacancies in defect semiconductors, Center of symmetry, 25 Cesium, solutions in THF, 246-247 Cesium chloride structure, 278-279 Chain-branching reaction, 155-157 Chain reactions, 148-151, 155-158 in olefin metathesis, 475-477 Chains in crystal structures, 269-271 Chalcogenide glasses, photoconductivity of, Chalcogens, 14 Character tables, 30–34 Characters of irreducible representations, 30 Charge-transfer spectra of complexes, 417-418 Charge transfer transitions in transition-metal compounds, 331 Charges, formal, 41 Chelate complexes, 346-351 Chelate effect, 346-347 Chemical shift (nmr) as function of electronegativity, 67 Chlorate, reaction with halide ion, 230 Chloride ion: complexes of Pt, 355–356 stepwise complexation of Hg<sup>2+</sup>, 343 Chlorine, reaction with H<sub>2</sub>, 150-151 Chlorine atom, bridging in metal cluster, 387-388 Chlorine fluoride, CNDO/2 treatment, 140-144 Chlorine trifluoride structure, 87-88 Chlorine-35 nqr coupling constants, 68 Chromium hexacarbonyl: and 18-electron rule, 377-378 reaction with LiCH<sub>3</sub>, 482 Chromium pentacarbonyl complexes, synthesis, 344 Chromium(II), oxidation by Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup>, 462-463 Chromium(II) acetate, 347 Chromium(II) complexes, one-electron oxidative addition to, 472

Chromium (III) chloride, crystal structure,

Chromium (IV) oxide, ferromagnetism, 429

Chromium (V) in Cr(VI) + Fe2+ reaction,

Cis and trans complexes, electronic spectral

Cis-platinum, anticancer drug, 524

differences, 415-416

plexes, 355-356 Clock reaction, 233-234 Close-packed structures, 266-267 Closo boranes, 252, 258 Closo metal clusters, 383, 385-388, 390 Clostridium pasteurianum, 518 Cluster compounds (see Polyhedral clusters) Cluster electrons, 382 CNDO (complete neglect of differential overlap) and CNDO/2 methods, 140-144 Cobalt: bis(dimethylglyoximato) complexes as vitamin B<sub>12</sub> models, 516-517 in vitamin B<sub>12</sub> and derivatives, 514-517 Cobalt carbonyl in homogeneous catalysis, 478-479 Cobalt catalyst in oxidation of acetaldehyde to acetic acid, 480 Cobalt porphyrin, adsorbed on graphite cathode, 499-500 Cobalt(II) complexes: bonding and structure from magnetic data, 427-428 one-electron oxidative addition to, 472 Cobalt(III) complexes, synthesis, 343 Cobaltacarborane, 259-260 Coefficients of AOs: in CIF by CNDO/2 method, 142 in PH<sub>1</sub>, 139 Coenzyme of vitamin B<sub>12</sub>, 514-516 Coercive force of ferromagnet, 305-306 Coinage metals, 14 property and average Colors: of transition-metal compounds, 331 of visible spectrum, 414 Combinations of ligand sigma orbitals in octahedral complexes, 365-367 Complex formation, aqueous solution, 342-343 Complexation constants (see Equilibrium constants) Complexes, nomenclature, 560-565 Complexes of transition metals, 332 bonding in, 361-374 kinetics and mechanisms of reactions, 447-469 Condensation reactions in macrocyclic ligand formation, 481-482 Conductance, aqueous H+ and OH- mechanism, 192-193 Conduction band in semiconductors, 316-320, 322-325 Conformational isomerism, 91-93 Conjugate acids and bases, 199 Constants, table of, 530 Contraction in size: in lanthanide series, 22 in transition-metal series, 21

Controlled-valence semiconductors, 321

Conversion factors, 529-531 Covalent radius of hydrogen, 54 Coordination compounds: Covalent single-bond distances, table of, 51 bonding in, 361-374 Crossover systems (high-spin-low-spin), electronic spectra, 404-420 424-426 ferro-, ferri-, and antiferromagnetism, Crown ethers in complexation of cations in 428-431 alkali-metal solutions, 247-248 Jahn-Teller distortions, 431-433 Cryptands, 247-248 kinetics and mechanisms of reactions, Crystal axes, 484-485 447-469 Crystal-field theory, 361-365 ligand-field stabilization energy, 433-437 Crystal planes, 484-485 ligand-metal pi bonding, 437-444 nomenclature, 560-565 paramagnetism, 421-428 metals and alloys, 293-297 of transition metals, 332 saline hydrides, 161 Coordination geometry of transition-metal Crystals (see Solids) compounds, 333-341 Cubane-like clusters in Fe-S proteins, 517-523 Coordination number(s): Cubic close-packed structure: correlation with electronegativity difference, adsorption on, 488-493 of metals, 293-297 de manaly shangoolido correlation with radius ratios, 280-283 Cubic close packing, 266-267, 274-276 effect on ionic radius, 282-283, 550-555 Cubic coordination, 338-339 4, 6, 8, and 12, prevalence of, 340-341 Curie temperature, 304, 332, 428-429 in transition-metal compounds: Cyanamide, reaction with water, 48 CN 2, 333 Cyanamide ion, 47 Company of the Ballong and Cyanamide ion, 47 Company of the Cyanam CN 3, 334 Cyanate ion, Lewis octet structure of, 43 CN 4, 334 Cyanide ion: CN 5, 334-336 ambidentate character, 358-359 CN 6, 336-338 back bonding to, 409 CN 7, 338 Bodford & Octob of the and Cyanoborohydride ion, 47 CN 8, 338-339 Cyanogen: (coattant) as (min) mide lesimate) CN 9, 339-340 as bridging ligand in mixed-valence com-CN 12, 339-340 plex, 466 abdust days no loss a samoli prevalent CNs, 340-341 chemisorption on Pt, 489 Coordinative unsaturation in homogeneous Cyanogen bromide, 47 catalysis, 470-471 reaction with OH-, 48 Copper, photoelectron spectrum of, 299-301 Cyanogen fluoride, 47 Copper-zinc phase diagram, 296-297 poor analog of carbon dioxide, 49 Copper-zinc superoxide dismutase, 526 Cyclobutadiene, 130–131 Core binding energy, 69 correlation with electronegativity, 76 stabilization by transition metals, 131 of metal dithienes, 401 Cyclobutane formation by ethylene dimerizanitrosyl complexes, 398-399 tion, 474-475 of transition-metal carbonyls, 443-444 Cycloheptatrienyl complexes, 352-353 xenon fluorides, 71 Cycloheptatrienyl group, pi-acceptor charac-Core of atom, 13 Correlation diagram: Cyclometallation, 472, 477 for MOs, 125 Cyclooctasulfur, atomization energy, 60 for octahedral d<sup>2</sup> complex, 406 Coulomb integral(s), 98, 136-137 Cyclooctatetraenide ion, complex with uranium (IV), 131 Coulombic interaction with proton in gas-Cyclooctene, involvement in olefin metathesis phase acids, 172 study, 476 Markelumeo (11) mumora Counter-ion, effect on ionic radius, 283-284 Cyclopentadienyl complex: of iron, 351-352 (11) muimetal? Covalent bonding, 40-95, 264, 280 of titanium, 353-354 in Lewis acid-base reactions, 209 in salts, 288 Cyclopropane conversion to cyclohexane, 103 Covalent radii: Cysteine groups in iron-sulfur proteins, 517 single-bond, 52 single-, double-, and triple-bond, for car-

bon, nitrogen, and oxygen, 53

d electron configuration, metal complex, effect on substitution rate, 448-451

Deuterium-hydrogen exchange between PH<sub>3</sub> delectrons, variable number in transitionand D2O, 177-178 metal compounds, 330-332 Developer of photographic latent image, 328 d functions, 7-8 Diagonal planes, 26 d orbitals: Diamagnetism, 331, 421-422 and color of transition-metal compounds, Diamond-like structures, 288 - Inbixo box Diamond structures, 277-278 energy splitting of: Diarsine, 342 in octahedral field, 361-363 down on toals Diatomic molecules: in square planar field, 364-365 molecular orbitals, 105-107 in tetragonally elongated octahedral field, s and p orbital interactions, 106 Diazomethane, 47 in tetrahedral field, 363-364 noo loom tool 3 reaction on metal surfaces, 495 five equivalent, 9 reaction with uv light, 48 of hydrogen atom, 6-9 participation of: Diborane: bonding in, 255-256 in bonding of non-transition-element comformation from H<sub>2</sub> + B<sub>2</sub>Cl<sub>4</sub>, 154-155 pounds, 45 reaction with BH<sub>4</sub>-, 161-162 in bonding of trisilylamine, 128-129 reaction with water, 168 in I<sub>3</sub> bonding, 116-118 structure and bonding, 253-256 in metallic bonding, 293-297 synthesis, 250 in transition-metal CN 2 complexes, 333 thermal decomposition to higher boranes, of transition-metal complex, overlap with 250-251 ligand orbitals, 365-370 Diboron tetrachloride, 154-155 d<sup>8</sup> complexes: Dichlorodiammineplatinum (II) anticancer factors favoring tetrahedral and square activity, 524 planar structures, 436 Dielectric constants: in homogeneous catalysis, 470-471 aprotic solvents, 206-207 structures, 431-432 protonic solvents, 200 trigonal bipyramidal, favored sites for pi Differentiation of acid and base strength in acceptors, 439-440 nonaqueous solvents, 202 valence electron count, 376-377 d-d transitions (see Ligand-field spectra) Diimide, 523 Diiron nonacarbonyl and 18-electron rule, Dangling bonds in amorphous silicon, 326-327 Diketones, chelation, 347 Defect semiconductors, 320 Dimanganese decacarbonyl: Degeneracy and Jahn-Teller distortion, 431 bonding, 372 Dehydration of solid in desiccator, 216 and 18-electron rule, 378 Delocalization: Admon Bras Had to spectrum and photolysis to Mn(CO)5, 419 of electron onto ligand in electron exchange Dimerization of olefins by homogeneous catalreaction, 461 ysis, 474-475 of negative charge in anions, 172-173 Diopside, 269 in symmetric mixed-valence complexes, Dioxygen cation, 106 Dioxygen difluoride, bonding, 54-55 465-468, 518 Delocalized pi bonding, 42-45 Dipole moments, 65-66 Delta molecular orbitals, 104 of LiH, 66 Deltahedron, 252, 257 of NH<sub>3</sub> and NF<sub>3</sub>, 65-66 Density: Electron density plot (or H.O.) Disilane, synthesis, 167 Dismutation (see Disproportionation) metallic carbides and nitrides, 307 saline hydrides, 161 Disproportionation: Density matrix of CIF by CNDO/2 method, of hypophosphite, 222 143 of N2O, 215 Density of states diagram(s): of NO2, 215 for insulator, 301-302 of olefins (see Metathesis of olefins) reduction potential criterion for, 221 for metals, 297-304 for semiconductors, 317-318 Dissociation: Deprotonation: of Br<sub>2</sub>, 148-149 of Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup> in base hydrolysis, 453 of Cl2, 155 in homogeneous catalysis, 470-471 of extremely weak acids with KOH,

of I<sub>2</sub>, 153

185-186

Derivatization of silicon photoelectrode, 499

Dissociation energies, 55-59 and activation energies, 147, 149-151 Eighteen-electron rule (Cont.): correlation with bond length, 55 exceptions to, 381-382 of diatomic molecules, 107 Fe(C<sub>5</sub>H<sub>5</sub>)+, 381 of hydrides, 168-170 Pt(PR<sub>3</sub>)<sub>3</sub> and Pt(PR<sub>3</sub>)<sub>2</sub>, 381-382 of protonic acids, 175 Common and browning tables of, 56-58 and oxidation-state ambiguity, 396-401 Distoord suggestes, 277 Dissociation pressures, hydrogen-metal sys-Electric arc furnace in Si preparation, 318 tems, 164-165 administration vimousical Electric discharge: All blad lambadano Distortion: in synthesis of higher boranes, 251 Jahn-Teller, 431-433 in synthesis of nonmetal hydrides, 167 of octahedron, 337-338 Electric field gradient at nucleus (ngr), 68 Disulfane, atomization energy, 60 Electrical conductance: blott leabodenes ni Disulfite ion, 197 of metal-ammonia solutions, 242-243 Disulfuric acid, solutions in H<sub>2</sub>SO<sub>4</sub>, 201 of metallic compounds, 310-314 Dithiene complexes, 400-401 of metals, 298-303 Dithicketone complexes, 400-401 protonic solvents, 200 Dithiolate complexes, 400-401 of semiconductor, 316-318 a shapped Dithiolate ligands in trigonal prismatic comof solutions of Pt(IV)-NH3-Cl complexes, plexes, 350-351 Dithionate as product of SO<sub>2</sub> oxidation, Electrode surface modification, 498-500 Electrolysis: DNA, reaction with Pt(NH<sub>3</sub>)<sub>2</sub>(H<sub>2</sub>O)<sub>2</sub><sup>2+</sup>, 524 of molten LiH, 161 and fallem-gordenant lo Dodecahedron geometry, 338-339 of NaBr-NH, solution, 241-242 Domains in ferromagnets, 304-306 of water using photoelectrolytic cell, Donor level in n-type semiconductor, 317 lactors favoring terramedra Donors, electron pair, in acid-base theory, 205 Electron affinity(ies), 20, 535-537 Double layer crystal structure, 273 hydride radical, 169-170 Double quartet theory, 46 of hydrogen, 168 Double zeta basis set, 145 hydrogen atom, 169 hydrogen language Doubly-bridged porphyrin, 511-513 of radicals, 175 Ohb Pra grongeone Drago E and C parameters for heats of Lewis Electron binding energy, 15 acid-base reactions, 210-211 Electron carrying proteins, 507 annulanced by Dynamic Jahn-Teller effect, 433 Electron configurations: me ni space and and of atoms and ions, 10-13 E and C parameters for predicting heats of of diatomic molecules, 107 page 1990 Lewis acid-base reactions, 210-211 of the elements, table, 11 has your page 10 Eclipsed configuration in dinuclear complexes, of free atoms and ions, 532-534 stability of half- and completely-filled shells, Effective atomic number rule (see Eighteenof electron onto ligand in electro Electron density: Effective nuclear charge, 12, 17, 136 atomic, 4-9 Effective pH in nonaqueous solvents, 202 Effective quantum number, 20 in LiH molecule, 64-65 of molecule(s), 97, 101 Eight-coordinate complexes, 338-339 Eighteen-electron rule, 375-403 in molecules, 100 manufactured to be the sol Electron density contour maps, 7-8, 108-114 application of: to CH<sub>3</sub>Mn(CO)<sub>5</sub>, 378 Electron density difference plots, 112-114 to Cr(C<sub>6</sub>H<sub>6</sub>)<sub>2</sub>, 379 Electron density plot for H<sub>2</sub>O molecule, 82 to Cr(CO)6, 377-378 Electron-electron interaction and electronic to Fe<sub>2</sub>(CO)<sub>9</sub>, 379 spectra, 405-411 to Fe(C<sub>5</sub>H<sub>5</sub>)<sub>2</sub>, 379 Electron-electron repulsion, 126-127, 410 to Mn<sub>2</sub>(CO)<sub>10</sub>, 378 Electron-exchange reactions, 459 to Mn(CO)5-, 378 excited state in, 460-461 and the state of where C to Mo(η<sup>6</sup>-C<sub>7</sub>H<sub>8</sub>)(CO)<sub>3</sub>, 380 Electron loss spectroscopy, 487 to  $Mo(\eta^7 - C_7 H_7)(CO)_3^+$ , 380 of adsorbed CO, 492 to Mo[H<sub>2</sub>B(pyrazolyl)<sub>2</sub>](CO)<sub>2</sub>C<sub>7</sub>H<sub>7</sub>, 381 Electron pair donors and acceptors in Lewis to Re<sub>3</sub>Cl<sub>12</sub><sup>3-</sup>, 380 acid-base theory, 205 to low-nuclearity complexes, 377-382 Electron paramagnetic resonance (see epr) to metal-cluster compounds, 382-396 Electron repulsion, valence shell (see Valence shell electron repulsion)

Derivatization of stucon prioroelectrode, app

Electron-rich compounds, 45 Electrons: ammoniated, 241-246 Electron shielding, 12-13, 17-21 in anion vacancies, 320 Electron spin resonance (see epr) capture by trapping centers in silver halides, Electron-to-atom ratio and metallic structure. of Mo-Fe cofactor of situa 293-297 327-329 hydrated, 236-241 Electron transfer reactions: solvated, 236-248 through extended bridges, 463-468 Electronvolts in adding half-reactions, octahedral complexes, 458-468 of Br. and Br. 149 Electronegativities, 71-76 219-222. Allred-Rochow, 72-73 Electrophile, 205 Electrostatic factor in Lewis acid-base reac-Mulliken, 71-73 orbital character, 73-74 tions, 209-210 Electrostatic ligand-field theory, 361-365 Pauling, 61 Elimination, reductive, in homogeneous catalyperiodic table trends, 61 sis, 471-472 relation to bond energies, 61-62 Endothermic reactions, 150 revised Pauling, 71-72 Energetic similarities: Sanderson, 72-73 in 5-coordination, 334-336 uses in chemistry, 75-76 in 8-coordination, 339 Electronegativity: Energies of MOs: correlation of: to make paid the HM to 3 at for C1F by CNDO/2 method, 141 with core binding energy, 76 for PH3, 138 and adologo of nothing with H-X stretching frequency, 75 Energy level diagram: (APD) (1997) with hybridization of orbital, 123 for carbon monoxide, 107 effect on pK of acid, 181-182 for cyclic C<sub>n</sub>H<sub>n</sub> molecules, 131 orbital, parameters, 74 for delocalized mixed-valence complex, 465 of substituent in gas-phase protonic acid, for dinuclear complexes with metal-metal Electronegativity difference, correlation with bonding, 371 for homonuclear diatomic molecules, 106 coordination number, 283 Electronic populations in PH<sub>3</sub>, 139 for I<sub>3</sub>-, 116-117 for localized symmetric electron-exchange Electronic spectra: system, 459 CoCl<sub>4</sub><sup>2-</sup>, 414-415 og lo napoga una anitoutil Co(en)<sub>2</sub>F<sub>2</sub>+, 416 of methane, 120 molecular, 101-102 Co(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, 414 for NH, synthesis, 498 CoL6 and cis- and trans-CoL4X2, 415-416 for Ni (C<sub>2</sub>H<sub>4</sub>)<sub>3</sub>, 441 Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup>, 417 Exchange integral, 99 coordination compounds, 404-420 for O<sub>3</sub>, 118 for octahedral complex: with only sigma calculations, 411-416 bonding, 367 charge-transfer, 417-418 with sigma and pi bonding, 369 ligand-field, 404-416 for p-n junction, 322 metal-metal bonded systems, 418-419 for reaction involving radicals, 150 photoelectron spectra, 419-420 for semiconductor electrodes, 323-324 selection rules, 404-406 Fe(II) complexes, 417-418 Energy levels: for 3-center bond, 254 IrBr<sub>6</sub><sup>2</sup>, 417 Energy units, 530-531 hydrogen atom, 10 Mn<sub>2</sub>(CO)<sub>10</sub>, 419 Ni(en)<sub>3</sub><sup>2+</sup>, 411 Engel and Brewer rules, 293-297 Ni(H<sub>2</sub>O)<sub>6</sub><sup>2+</sup>, 408–409, 411–414 RuCl<sub>6</sub><sup>2-</sup>, 417 Enstatite, 269 Entering ligand, effect of Pt(II) complex substi-Perent Coble of Sign Sign transition metal coordination compounds tution, 456-458 Enthalpies (see Heats of formation) (see coordination compounds, above) Entropies, table of, 539-549 (See also Infrared spectroscopy) Electronic transitions: and the chelate effect, 347 in mixed-valence complexes, 465-468 Entropy: in NO<sub>2</sub>-, 145 estimation of, 215 of ionization of aqueous acids, 195-196 in O<sub>3</sub>, 145 in transition-metal compounds, 331 residual, in ice, 187 of vaporization, protonic solvents, 200 transition-metal coordination compounds,

404-420

Enzymes, 507 nitrogenase, 518-523 epr (electron paramagnetic resonance): of Cu(H2O)62+, 433 of Mo-Fe cofactor of nitrogenase, 521 Equatorial vs. axial coordination in de trigonal bipyramidal complexes, 439-440 Equilibrium: of Br<sub>2</sub> and Br, 149 of I<sub>2</sub> and I, 151–152 Equilibrium constants: and chelate effect, 346-347 effect of standard state, 346-347 ethylenediamine-M2+ complexes, 445 Hg2+-Cl- complexes, 343 Ni<sup>2+</sup>-NH<sub>3</sub> complexes, 342-343 ESCA (see X-ray photoelectron spectroscopy) Ethane, formation from H<sub>2</sub> + C<sub>2</sub>H<sub>4</sub>, 154 Ethylene: comparison of pi-acceptor character with C2 (CN)4, 442 dimerization to cyclobutane, 474-475 formation from CH2N2 on metal surfaces, oxidation to acetic acid, 479-481 Ethylene complex: of nickel (0), 440-442 of platinum, 351-352, 440 Ethylenediamine, 342 equilibrium constants of M2+ complexes, EXAFS (extended absorption fine structure), 519-520 Exchange energy: in atoms, 12 in ferromagnetic metals, 304 Exchange integral, 99 Excited state in electron-exchange reaction, 460-461 Exclusion principle, 10 Exothermic reactions, 149-150, 155 Expanded metals in liquid ammonia, 243 Explosion limits, 157-158 Explosions, 155-158 Extended absorption fine structure (EXAFS), 519-520 Extended basis sets, 145 Extended Hückel theory, 135-140 application to phosphine molecule, 137-140 Emerine heard, effect of Profit F centers, 320 f electrons, 13 Face-centered cubic packing, 266-267

Facial chelation, 346

ceptibilities, 421

Facial coordination, 356
Families of periodic table, 15

Fermi energy of metals, 304

Faraday method for determining magnetic sus-

Ferric ion, hydrolysis of, 344 Ferrimagnetism, 428-429 Ferrocene, 351–352 and 18-electron rule, 379 Ferrocyanide, photooxidation of, 499 Ferrolectric-paraelectric transition in KH2PO4, Ferroelectric properties of KH2PO4, 188-190 Ferromagnetism, 331-332, 428-429 of metals, 303-306 Ferrous ion, reduction of VO,+, 331 Fischer-Tropsch analog, 502-503 Fischer-Tropsch process, 493-496 Five-coordinate complexes, 334-336 Five-coordinate intermediate: in Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup> base hydrolysis, 453 in square planar complex substitution, 453-456 Supper Lamidagon & X-H ritiw Fixation of nitrogen, 518-523 about 1114 Fluoride ion: basicity in BrF<sub>3</sub>, 204 comparison with hydride ion, 160-161 oxide semiconductor dopant, 324 reaction with bromate to form perbromate, reaction with Pt, 216 Fluorine nmr spectra of pentavalent phosphorus compounds, 84–85
Fluorite structure, 274–275 Fluoroform, gas-phase acidity, 173 Force constants, 62-63 of C-F bonds in CF, groups, 442 of C-O bonds in metal carbonyls, 443-444 of Mo-O bonds, correlation with bond length, 63 table of, 62 ampraya behaved latern-latern Formal charge, 41-42 influence on acidity of hydroxy acid, 179-182 Formulas, rules for, 556-557 Four-coordinate complexes, 334 Fractional bonds, 45 Free energies of formation, 214-216 general table of, 539-549 Galleries in interstitial layered compounds, Gases, kinetics and mechanisms of reactions, 147-159 in mixed-valence cou Gate voltage in MOS transistors, 325-326 Geometry: of carbenes, 80-81 of transition-metal compounds, 333-341

Gerade wave functions, 9, 36

Fermi level in semiconductors, 322

Ferraboranes, 259-261

Ferredoxin analog, 517-519

Ferredoxins, 517

Germane: Heat(s) (Cont.): deprotonation with KOH, 185-186 of ionization, for gas-phase protonic acids, reactions with HBr and NaNH2, 168 171-176 Germanium, purification by thermal transof Lewis acid-base reactions, prediction of, port, 319 from parameters, 210-211 Germanium cluster anions, 261-262 Heme, 507 Germanium iodides in thermal transport of Hemoglobin, 507-513 Ge. 319 blocking of O<sub>2</sub> sites by CO, 513 Germanium tetrafluoride, reaction with gra-CO complex, 513 phite and fluorine, 313 model compounds for, 511-513 Glasses, 289 R and T states, 509-511 Globin, 507-508 configuration of heme group in, 510-511 Glutamate mutase, function with vitamin B<sub>12</sub> Heteroaromatic systems, pi bonding to transicoenzyme, 515-516 tion metals, 352 Gouy balance method for determining mag-Heterogeneous catalysis, 484-504 netic susceptibilities, 421 Heteronuclear bond: Graphite: MOs, 101-102 crystal structure of, 271-272 polarity, 64-76 intercalates, 312-313 Heteronuclear bond energy, relation to elecsemimetallic character of, 312 tronegativities, 61 Graphite bisulfates, 313 Hexaamminecobalt (III) ion, rates of reaction, Grimm-Sommerfeld compounds, 288 447-448 Group orbitals, 114-119 Hexagonal close-packed structure of metals, in octahedral complexes, 365-367 293-297 Group-theoretical symbols for orbitals: Hexagonal close packing, 266-267, 274-275 in octahedral field, 362-363, 365-369 Hexahalostannates studied by Mössbauer specin square planar field, 364 me mouse possible troscopy, 68-69 in tetrahedral field, 363-364 Hexamethyl borazine complexes with transi-Group theory, 27–39 tion metals, 49 Groups of Periodic table, 15 High- and low-spin complexes, 372-373 Gurney-Mott photographic latent image thecrossover systems, 424-426 ory, 328 distinguishing by magnetic moments, 424 heat of interconversion, 425 H\_function, 203 ionic radii, 435-436 H<sub>o</sub> function, 202–203 High-resolution electron loss spectroscopy, Haber process, 497-498 487 Hafnium, bcc and hcp structures, 295 Histidine group(s): Half-reactions, 216-229 in carbonic anhydrase, 525 adding and subtracting, 219, 222 in superoxide dismutase, 526 Halide ions, complexation of Al3+ and Hg2+, Holes: in close-packed structures, 274-278 Halides, criteria for molecularity and salinity, in valence band, 316-318 in valence shell of complex, 405 Halogen pi donation in boron halide clusters, HOMO (highest occupied molecular orbit), 258-259 153-154 Halogens, 14 Homogeneous catalysis, 470-483 reactions with hydrogen, 147-155 Homonuclear bond, MOs, 100-101 Hamiltonian operator, 97 Horizontal planes, 26 Hard and soft acids and bases, 205-209 Hückel 4n + 2 rule, 130-132Harmonic oscillator, approximation for Hückel criterion of aromaticity, 130

Hückel theory, 129-133

Hybrid orbitals, 121-124

Hume-Rothery compounds, 295-297

of C orbitals in CF, groups, 443

correlation with bond strength, 121-123

extended, 135-140

Hybrid sp orbitals, 79 Hybridization, 121-124

Hund's rule, 12, 106

Hartree-Fock calculations, 10 Heat capacity plot for KH<sub>2</sub>PO<sub>4</sub>, 190 Heat(s): of atomization, of metals, 291-293 of formation: boranes, 250 general table of, 539-549 saline hydrides, 161 salts, periodic table trends, 288

bonds, 62-63

Hybridization (Cont.): Hydrogen atom: effect on bond distance, 52 angular wave functions, 4 of metal d orbitals, 370 in aqueous solutions, 237-241 in methane, 121 covalent radius, 54 of s and p orbitals, 79 dissociation from hydride molecule, 168-170 Hydrated electrons, 236-241 electron affinity, 168 Hydration of CO2 by carbonic anhydrase, energy levels, 10 524-525 ionization potential, 169, 175-176 Hydration energies: in metal cluster, 345-346 of anions, effect of size, 185 orbital energies, 3-9 of transition-metal cations, effect of LFSE, orbital shapes, 3-9 quantum numbers, 1-3 Hydrazine: radial wave function, 3-7 bonding, 54 in reaction of H<sub>2</sub> with O<sub>2</sub>, 155-158 synthesis, 215-216 in reactions of H<sub>2</sub> with halogens, 148-151 Hydrazinium ion, bonding, 54 Hydrogen bonding, 184–194 in ammonia, 186–187 Hydrazoic acid, reaction with uv light, 48 Hydride ion, 160-163, 168-170 in aqueous hydroxide ion, 184-185 Hydrides, 160-170 in boric acid, 188-189 boiling points and hydrogen bonding, 187 in hemoglobin, 509-510 bond angles, 81 in hydrogen fluoride, 186-188 bonding in AH<sub>2</sub> molecules, 125-127 in polypeptide chains, 188 classification of, 160 in trimethylammonium hydroxide, 184 hydridic character of, 168-170 in water and ice, 186-188 metallic, 162-165 Hydrogen bridges in boranes, 253 of nonmetals, 166-167 Hydrogen bromide: acidities, 177-178 dissociation energy, 149 protonic character of, 168-170 formation in  $H_2 + Br_2$  reaction, 148–150 saline, 160-162 reaction with GeH<sub>4</sub>, 168 of transition metals, acidity, 183-184 Hydrogen chloride: Hydridic character of hydrides, 168-170 dissociation energy, 57-58 Hydroborate: bonding in, 255 hydrogen bonding in, 187 reactions of, 161-162 reaction with Si, 318 Hydrogen fluoride, 170 in synthesis: of boranes, 249-252 anhydrous, ionization and acid-base reacof hydrides, 166 systhesis of, 161 tions in, 201 hydrogen bonding in, 186-188 Hydrocarbons: polymerization in gas phase, 187-188 aromatic, 129-131 reaction with fluoride ion, 188 Fischer-Tropsch synthesis, 493-496 Hydroformylation by homogeneous catalysis, Hydrogen halides, estimation of pK values, 177 478-479 Hydrogen ion: Hydrogen: aqueous conductance mechanism, 192-193 compounds of, 160-170 effect of concentration on reduction potendissolution in metal, 163-164 tials, 219-221 effect on doping of amorphous Si, 326-327 kinetics of aqueous migration, 193 kinetics of reaction with OH-, 193 exchange with deuterium between PH3 and reaction with  $e^{-}_{aq}$ , 237–240 D<sub>2</sub>O, 177-178 formation from H<sub>2</sub>O and CO, 479 (see also Oxonium ion) kinetics and mechanisms of reactions, Hydrogen ion hydration (see Oxonium ion) 147-159 Hydrogen molecule, electron density differprotonated, 175 ence plot, 113 reaction of: with CO in Fischer-Tropsch syn-Hydrogen peroxide: thesis, 493-496 from disproportionation of O<sub>2</sub>-, 526 with halogens, 147-155 in  $H_2 + O_2$  reaction, 157-158 with iron-titanium alloy, 164 in oxidations by O2, 221-222 with N2 to form NH3, 497-498 reaction with  $e^{-}_{aq}$ , 237–239 with oxygen, 155-158 Hydrogen sulfide: stepwise absorption by metal, 163-164 atomization energy, 60 storage with metallic hydrides, 163-165 second ionization constant in aqueous solu-

tion, 198-199

Inner-sphere electron transfer reactions of Hydrogenation: octahedral complexes, 462-463 of CH, CN, Fe cluster models for catalyst, Inorganic nomenclature, 556-565 501-502 Insertion reactions in homogeneous catalysis, of ethylene, 154 472-473 of olefins by honiogeneous catalysis, Insulated-gate field-effect transistor, 325-326 473-474 Insulator, conversion to metal by pressure, Hydrolysis, base, of Co(NH<sub>3</sub>)<sub>5</sub>X<sup>2+</sup> ions, 452-453 Integrated circuits, MOS transistors in, 325 Hydronitrite ion, synthesis in NH<sub>3</sub>, 244 Intermediates in redox reactions, 221-222, 468 Hydronium ion (see Oxonium ion) Intermetallic compounds (see Alloys) Hydroxide ion: Intermolecular forces, 265 aqueous conductance mechanism, 192-193 Intermolecular insertion in homogeneous catalhydration of in aqueous solution, 184-185 ysis, 472-473 kinetics of aqueous migration, 193 Interstitial layered compounds, 312-314 structure of hydrates, 191–192 ydroxy acids, 179–182 Interstitial metal atoms in defect semiconduc-Hydroxy acids, 179-182 Hydroxyl radical: tors, 320 Intervalence electronic transition, 465-466 in  $H_2 + O_2$  reaction, 155-156 Intramolecular insertion in homogeneous catalin irradiated H<sub>2</sub>O, 236-239 ysis, 472-473 and superoxide dismutase, 526 Intramolecular oxidative addition, 472 Hydroxylamine, bonding, 54 Intrinsic conductivity of semiconductors, 317 Hydroxylic solvents, weakening of hydroxide Inverse spinels, 436-437 ion basicity in, 185-186 Iodate, reduction by HSO<sub>1</sub>-, 233-234 Hyperconjugation, 44, 133-135 Iodide, 217-219 in BH<sub>3</sub>CO, 44, 135 oxidation by O2, 222 in boron trimethyl, 135 oxidation by permanganate, 222-223 in CH<sub>3</sub>O<sup>-</sup>, 173 in O<sub>2</sub>F<sub>2</sub>, 55 Iodine: reaction with H2, 151-154 in ONF<sub>3</sub>, 44, 133-134 in thermal transport purification of Ge, 319 Hypervalency, 45 Iodine clock reaction, 233-234 Hypho boranes, 252, 258 Ion-exchange column separation of nuclear fis-Hypochlorous acid, reaction with NO2-, 232 sion products, 23 Hypophosphite: Ion neutralization spectroscopy, 486 disproportionation, 222 Ion scattering spectroscopy, 486 reduction of water by, 222 Ionic bonding, 265, 280 Hysteresis in magnetization curve, 305 in Lewis acid-base reactions, 209 Ionic character of bonds, 54 Ionic charges, effect on crystal structure, Ice: 283-284 Ionic polarizability: crystal structure of, 186-188 effect on ionic radius of counter-ion, hydrogen bonding in, 186-188 283-284 Ice structure, 278 effect on lattice energy, 287-288 Icosahedral geometry, 339-340 table, 287 Identity operation, 25 Imide radical on Fe surface in Haber process, Ionic radii: Pauling, 281 "traditional" values of Shannon, 550-555 497-498 Improper rotational and, 27 of transition metals: effect of LFSE, INDO (intermediate neglect of differential 434-436 overlap) method, 144 high- and low-spin, 345-436 ionic strength, effect on rate constant, 237-238 Induced reaction, 468 Infrared absorption: Ionization constants, protonic solvents, 200 of adsorbed CO, 490 Ionization potential(s): in transition-metal hydride complexes, 166 of atoms, 15-21 Infrared reflection-absorption, 487 table, 18-19 Infrared spectroscopy: of hydride radical, 168 and hydrogen bonding, 192 of hydrogen atom, 169 of mixed-valence compounds, 465-466 of methane, 120-121

of molecules and radicals, 538

thiocyanate linkage isomers, 358

Inner-sphere complex, 452

lons:	Kernel of atom, 13
conductance in H <sub>2</sub> O, 192	Ketene, 47
electron configurations, 10-13	reactions with OH- and uv light, 48
nomenclature, 557-559	Kinetics:
term symbols for, 532-534	estimation of pK value from, 177-178
ridium, solubility in tungsten, 294-295	of gas-phase reactions, 147-159
ron, catalyst in Haber process, 497-498	of hydrated electron reactions, 237-241
ron atom, coordination modes in R and T	of olefin metathesis, 476
hemoglobin, 510-511	of proton-transfer reactions, 193-195
ron cluster compounds:	of reactions of transition-metal complexes
models for nitrile hydrogenation catalysts,	447–469
501-502	of redox reactions, 230-234
reaction with CH <sub>3</sub> CN, 501-502	Kinks on surfaces, 488
ron-molybdenum protein of nitrogenase,	
518-523	Lability of octahedral complexes, 447-451
ron pentacarbonyl:	correlation(s):
nmr spectrum and ligand scrambling, 336	with d electron configuration, 448-451
reaction with B <sub>5</sub> H <sub>9</sub> , 259-261	with atomic size and charge, 448
ron-porphyrin systems, 507–513 ron-sulfur proteins, 517–523	and LFSE, 449-451
ron superoxide dismutase, 526	Labilization of trans ligand, 454-456
ron-titanium alloy, reaction with H <sub>2</sub> , 164	Landolt clock reaction, 233-234
ron(II)-phenanthroline and related com-	Lanthanide contraction, 22
plexes, spectra, 417–418	Lanthanides, 13-14
rradiation of water, 236-237	separation with ion-exchange column, 23
rreducible representations, 30-36	Latent image in photographic emulsions,
characters of, 30	327-329 and a sydiam acrod m
of oxygen $p_x$ orbital of water molecule, 35	Lattice energy, 285–288
of $p_x$ and $p_y$ orbitals of nitrogen of ammo-	comparison of experimental and calculated
nia, 35	286-287
socyanic acid, 47	evaluation of experimental, 286
soelectronic principle, 46-49	thermodynamic factors affecting trends, 28
application to crystal structure prediction,	of transition-metal compounds, effect of LFSE, 434-435
288-289	Layers in crystal structures, 271–273
soelectronic species with 22 electrons, 4	LCAO (linear combination of atomic orbitals
somer shifts in Mössbauer spectroscopy,	theory, 96–102
68-69	Lead(IV), oxidizing power compared to
somerism:	tin(IV), 23
conformational, 91–93	Leaving ligand, effect on Pt(II) complex subs
of transition-metal complexes, 354-360	tution, 456–458
cis-trans, 355–356	Lewis acid-base theory, 205-211
linkage, 357–359	application to metals, 295
optical, 357 somerization:	Lewis bases, attack on linear triatomic spe-
	cies, 48
of 1,2-B <sub>10</sub> C <sub>2</sub> H <sub>12</sub> , 253, 262, 359–360 of CH <sub>3</sub> NC on Ni, 489–490	Lewis octet structures:
of olefins by homogeneous catalysis,	of ammonia, 41
477–478	of BH <sub>3</sub> NH <sub>3</sub> , 41
sonicotinamide as bridge in electron transfer,	of cyanate ion, 43
463-464	of nitrate ion, 43
sotopic labeling:	of nitrosyl chloride, 42
in exchange between H <sub>2</sub> O and SO <sub>4</sub> <sup>2-</sup> , 231	of oxonium ion, 41
in oxyanion reductions, 230, 232	of ozone, 42
	of perchlorate ion, 41
adeite, 271	of S <sub>3</sub> N <sub>2</sub> Cl <sup>+</sup> , ion, 43–44
ahn-Teller distortions, 431-433	of triodide, 45
dynamic, 433	Lewis octet theory, 40-46, 77
spectral evidence, 432	extension to transition-metal compounds,
Jahn-Teller theorem, 431	375
	Ligand-field spectra, 404-416

Ligand-field splitting of photoelectron spectra of MnF, and FeF, 419-420

Ligand-field splitting parameter, quantification, 409-410

Ligand-field stabilization energy (LFSE),

activation energy of substitution, 449-451 calculation, 436

Ligand-field theory, 361-365

Ligand-to-metal charge transfer spectra, 417 Ligands:

ambidentate, 357

entering and leaving, in Pt(II) complex reactions, 456-458

nomenclature, 560-565

in transition-metal complexes, 341-354 monodentate, 341-346 pi-bonded, 351-354 polydentate, 346-351

rates of replacement, 447-451 Linear combination of atomic orbitals (LCAO) theory, 96-102

Linear H<sub>3</sub>+, 145

Linear transition-metal two-coordinate complexes, 333

Linkage isomerism of transition-metal complexes, 357-359

Linnett double quartet theory, 46

Lipscomb's topological styx numbers, 255 Liquid ammonia:

expanded metals in, 243

ionization of, and acid-base reactions in, 199-201

Lithium:

bonding in molecules and metal, 297-298 intercalation in TiS2, 314

solutions in NH<sub>3</sub>, 242 Lithium aluminum hydride:

in B<sub>2</sub>H<sub>6</sub> synthesis, 250 in hydride synthesis, 166

synthesis of, 162

Lithium arsenide structure, 289 Lithium gallide structure, 288

Lithium hydride, 161-162

Lithium hydride molecule:

dipole moment, 66

electron density distribution, 64-65 Lithium ions, substitution for M2+ in NiO and MnO, 321

Lithium molecule, electron density difference plot, 113

Lithium oxide, reaction with NiO to form controlled-valence semiconductor, 321

London dispersion forces, 265

Lone-pair electron density distribution, 66 Lone-pair hybridization in NH3, pyridine, and N<sub>2</sub>, 123

Lone-pair-lone-pair repulsion, 54 in S<sub>4</sub>N<sub>4</sub>F<sub>4</sub>, 92-93

Lone pairs of water molecule, 82-83 Low- and high-spin complexes (see High- and Low-spin complexes)

Low-energy electron diffraction, 487 of adsorbed CO, 491-493

LUMO (lowest unoccupied molecular orbit), 153-154

Macrocyclic ligands, 481-482 Madelung constants, 285-286 Madelung's rule, 10-12

Magnesium, energetics of metallic bonding,

Magnesium boride structure, 288 Magnesium hydride, 165 Magnetic domains, 304-306

Magnetic moments: chromium bipyridyl complexes, 400 coordination compounds, 421-424 coupling in ferromagnets, etc., 428-431

Magnetic quantum number, 2

Magnetic susceptibility: of coordination compounds, 421-423 effect of temperature, 422-423, 425-426, 428-429

of K-NH<sub>3</sub> solutions, 243

Magnetism of transition-metal compounds, 331-332

Magnetite, ferrimagnetism of, 429, 437 Main-group cluster compounds, 260-262 Main-group elements, 13-14

Manganate(VI) ion, synthesis in NH<sub>3</sub>, 244 Manganese pentacarbonyl anion and 18electron rule, 378

Manganese pentacarbonyl hydride, reaction with HO<sub>3</sub>SCF<sub>3</sub>, 183-184

Manganese pentacarbonyl methyl and 18electron rule, 378

Manganese superoxide dismutase, 526 Manganese(II) oxide, antiferromagnetism, 429-431

Marcus equation, 461-462 Mass action effect on metal ion complexation,

Mechanisms:

of gas-phase reactions, 147-159 of oxyanion redox reactions, 230-234 PH<sub>3</sub>-D<sub>2</sub>O exchange reaction, 177-178 of reactions of octahedral complexes, 451-453

of reactions of transition-metal complexes, 447-469

Melting points: aprotic solvents, 206-207 boranes, 250 Cu-Zn phases, 296 metallic carbides and nitrides, 307 metals, 291-292

Methyl ethylene phosphate hydrolysis, 85

Melting points (Cont.): Methyl group: protonic solvents, 200 effect on gas-phase acidity, 173 of second-row fluorides, trends in, 280 on metal surface in Fischer-Tropsch synthe-Mercuric ion, stepwise coordination of Cl-, 343 sis, 493-495 Meridional chelation, 346 Methyl halide model to account for dipole Meridional coordination, 356 moment, 66 Metaborate ion, 47 Methyl isocyanide: Metal-ammonia solutions, 241-246 chemisorption on Ni, 489-490 catalyzed decomposition of, 245 isomerization to CH<sub>3</sub>CN, 489-490 kinetics in, 246 Methyl mercaptan, gas-phase acidity, 173 Metal anions in nonaqueous solutions, Methyl pentacarbonyl manganese, 378 246-248 Methylene, reaction with H2 to form CH4, Metal cluster compounds (see Polyhedral 159 clusters) Micas, 273 Metal-metal bonding, 347 Micrococcus aerogenes, 517 binuclear complexes, 370-372 Migration of double bonds, 477-478 electronic spectra, 418-419 Migratory insertion in homogeneous catalysis, photochemical cleavage, 419 472-473 Metal oxide semiconductor (MOS) transistors, Miller indices, 484-485 MINDO (modified intermediate neglect of dif-Metal-to-ligand charge transfer spectra, ferential overlap) method, 144 417-418 Mirror images and optical isomerism, 357 Metallacycle formation, 472 Mirror plane, 25 Metallacyclobutanes in olefin metathesis mech-Mitchell photographic latent image theory, anism, 475-477 Metallic bonding, 265 Mixed oxidation states in semiconductors, energetics of, in Mg, 292 320-321 Metallic compounds, 306-314 Mixed-valence compounds, 465-468, 517-518 one-dimensional, 308-312 MNDO (modified neglect of differential overtwo-dimensional, 312-314 lap) method, 144 Metallic glasses, 289 Model heme compounds, 511-513 Metallic hydrides, 162-165 Model nitrogenase compounds, 520-522 Metallobiomolecules, 505-507 Model vitamin B<sub>12</sub> compounds, 516-517 Metalloboranes, 259-261 Metallocarboranes, 259-260 Molecular beam surface scattering, 487 Molecular models to account for dipole Metalloporphyrins, 505-517 moments, 65-66 Metals, 291-315 Molecular orbital theory, 96-146 banc. ry, 297-306 of metal-metal bonding, 370-372 bonding energies and structures, 291-297 electrical and magnetic properties, 297-306 of octahedral complexes, 365-370 physical properties, 291-292 pi bonding, 368-370 sigma bonding, 365-368 solubility in liquid NH3, 241 Metathesis of olefins by homogeneous catalyof polyhedral clusters, 257-258 superiority over ligand field theory, 409 sis, 475-477 Molecular orbitals: Tal 181 abboth multichain reaction, 475-477 antibonding, 100 possible concerted process, 475 bonding, 100 Methane: calculations, 135-145 acidities of substituted, 173, 178-179 energy level diagram, 120 criteria for stability, 103-104 ionization potentials, 120-121 of diatomic molecules, 105-107 photoelectron spectrum of, 120 highest occupied, 153-154 protonated, 175 lowest occupied, 153-154 sigma bonding in, 119-121 in metallic bonding, 297, 299 Methanol: in Ni (C<sub>2</sub>H<sub>4</sub>)<sub>3</sub>, 441 carbonylation to acetic acid, 480-481 in three-center bonding, 254 gas-phase acidity, 173 three-dimensional representations for O2, Methyl acetylene, 47 Methyl ester of propylphostonic acid, hydrol-Molecular topology, 76-77 ysis, 85-86 Molecules:

electron affinities of, 536-537

ionization potentials of, 538

Molybdenum-iron protein of nitrogenase, 518-523 Molybdenum-oxygen bonds, 63 Molybdenum sulfide, crystal structure, Moments, magnetic (see Magnetic moments) Monodentate ligands, 341-346 Mooser and Pearson plot, 283 MOS (metal oxide semiconductor) transistors, 325-326 Mössbauer spectroscopy, 68-69 Mulliken electronegativities, 71-73 Mulliken population analysis, 139-140 Multiplicity change in spectral transition, Multiplicity maximization in atoms, 12 Myoglobin, 507-513 Names for inorganic compounds, 556-565 NDDO (neglect of diatomic differential overlap) nethod, 144 Néel temperature, 332, 428-430 Nephelauxetic effect, 410 Nernst equation, 219 Neutralization reactions: in BrF<sub>3</sub>, 204 kinetics of, 193–194 Neutron diffraction of MnO, 429-430 adsorption of CH<sub>3</sub>CN on, 489 chemisorption of CH<sub>3</sub>CN on, 489-490 ethylene complex of, 440-442 reaction with S and diphenylacetylene to form dithiene complex, 400 Nickel arsenide structure, 275–276 Nickel carbonyl, structure and backbonding Nickel dithienes, bonding in and Ni atom charges in, 400-401 Nickel ion: in complexes with macrocyclic ligands, stepwise coordination of ammonia, 342-343 Nickel oxide, reaction with Li<sub>2</sub>O, 321 Nickel(II) complexes, factors favoring tetrahedral and square planar, 436 Nido boranes, 252, 258 Nido metal clusters, 383–387 Nine-coordinate complexes, 339–340 Niobium nitride, 307 Nitrate ion, Lewis octet structure of, 43 Nitration of aromatic hydrocarbons, 231 Nitric oxide: bonding in, 46 effect on H<sub>2</sub> + Cl<sub>2</sub> reaction, 155 Oxidation of NH<sub>3</sub>, 215-216

Nitrides, metallic: preparation of, 308

properties of, 307

Nitrile hydrogenation, Fe cluster models for catalyst, 501-502 1 ashinbed onlared as Nitrite ion: back bonding to, 409 electronic transition in, 145 modes of coordination to Co(III), 357-358 reaction with  $e^{-}_{aq}$ , 237–238 reaction with HOCl, 232 Nitrito cobalt complex, 357-358 Nitrito-nitro isomerization, 357-358 Nitro cobalt complex, 357-358 Nitrogen: bonding to molybdenum in nitrogenase, dissociation of Fe catalyst in Haber process, motes; stoour being ration? 497-498 fixation of, 518-523 reaction with H2 to form NH3, 497-498 reduction to ammonia by nitrogenase, 518-523 Nitrogen atoms of Fe surface in Haber process, 497-498 Nitrogen-oxygen bond distances, 53 Nitrogen oxytrifluoride, 133-134 Nitrogen-ruthenium complex, synthesis, 343 Nitrogen trifluoride dipole moment, 65-66 Nitrogenase, 518-523 Nitromethane, gas-phase acidity, 173 Nitrosation of secondary amine, 231 Nitrosyl chloride, Lewis octet structure of, 42 Nitrosyl complexes: preparation of, 396 structure, bonding, and properties of, legalar organizations afterpol 396-399 Nitrosyl group: coordination geometry, 396-399 pi-acceptor character, 443 Nitrosyl ion in HNO2-H2SO4-H2O mixtures, 231 Nitrosyls, transition-metal, 48 Nitrous oxide, 47 Nitryl ion, 47 in HNO<sub>3</sub>-H<sub>2</sub>SO<sub>4</sub>-H<sub>2</sub>O mixtures, 201, 231 reaction with OH-, 48 nmr method for determining magnetic susceptibilities, 421 nmr spectra, 67 PF<sub>5</sub>, CH<sub>3</sub>PF<sub>4</sub>, and (CH<sub>3</sub>)<sub>2</sub>PF<sub>3</sub>, 84-85 of transition-metal hydride complexes, 166 Noble gases, 14 No-bond resonance, 44-45 Nodal plane of p electron, 5–7 Nodal surfaces, 5-7, 104-105 Nodes, atomic orbitals, 3-9 Nomenclature, 556-565 Nonaqueous solvents, 199-207 Nonmetal cluster compounds, 260-262 Nonmetal hydrides, 166-167 Nonmetals, cations, in strongly acidic media,

204

Nonstoichiometry: in metallic hydrides, 162 in semiconductors, 320 Nontransition elements, 13-14 Normal spinels, 436-437 Normalization, 99-100 ngr spectroscopy, 67-68 n-type semiconductivity, 317-326 Nuclear fission as example of branching chain reaction, 159 Nuclear fission products, ion exchange separa-Nuclear magnetic resonance, 67 of OH,+, 191 of Ti(C<sub>5</sub>H<sub>5</sub>)<sub>4</sub>, 353-354 Nuclear quadrupole resonance, 67-68 Nucleophile, 205 Octaethylporphyrin, 505 Octahedral complexes, 336-338 electronic spectra, 404-420 electrostatic ligand-field theory, 361-362 high delta values and back-bonding ligands, 376-377 high delta values and no back-bonding ligands, 376-377 kinetic classification, 449 lability, 447-451 ligand-field stabilization, 433-437 low delta values, 375-376 magnetic moments, 423, 427 mechanisms, 451-453 mechanisms of redox reactions, 458-468 molecular orbital theory, 365-370 substitution reactions of, kinetics, 447-453 Octahedral d8 vs. tetrahedral d8 complexes, 431-432 Octahedral-field splitting, 362-363 Octahedral holes in close-packed structures, Octahydrotriborate ion, 161 Octet theory, 40-46 Oil crisis and the Fischer-Tropsch process, 495-496 Olefins: dimerization and metathesis, 474-477 hydroformylation, 478-479 hydrogenation by homogeneous catalysis, 473-474 isomerization, 477-478 pi bonding to transition metals, 351-352, 370, 440-442 Ziegler-Natta polymerization, 496-497 One-dimensional metallic compounds, 308-312 One-equivalent oxidizing agents, 232-233 Optical isomerism of transition-metal complexes, 357 Orbital angular momentum: coordination compounds, 425-428

quantum number, 2

Orbital electron populations by extended Hückel method, 139-140 Orbital electronegativity parameters, 74 Orbital magnetic moment, 423 Orbital symmetry effects on kinetics, 152-155 Orgel diagrams, 407-408 Ortho hydrogen, formation from para hydrogen, 158 Orthogonality of orbitals, 104 Osmium, solubility in tungsten, 294-295 Osmium clusters, equilibria between CH, CH<sub>2</sub>, and CH<sub>3</sub>, 503-504 Outer-sphere complex, 451-452 Outer-sphere electron transfer reactions of octahedral complexes, 458-462 Overlap integral(s), 99, 100, 103 correlation with hybridization, 122 of HOMO and LUMO in reactions, 153-154 in PH<sub>3</sub>, 137 Oxidation potentials (see Reduction potentials) Oxidation-reduction reactions (see Redox Oxidation state ambiguity in metal complexes, 396-401 Oxidation states: unusual in intermediates of redox reactions, variety of, in transition-metal compounds, 330-331 Oxidative addition in homogeneous catalysis, 471-472 intramolecular, 472 one-electron, 472 Oxide ion: from dissociation of CO on metal surface, function in antiferromagnetic coupling of MnO, 429-431 pi-donor character in MO2X4 complexes, 437-438 Oxidizing agents: one- and two-electron, 232-233 stability of, in aqueous solution, 220 Oxonium ion: in acid hydrates, 190-191 aqueous conductance mechanism, 192-193 hydration of, 191 Lewis octet structure of, 41 nmr of, in liquid SO<sub>2</sub> solution, 191 in strongly acidic media, 203-204 Oxyanion reductions: effect of charge of central atom on rate, effect of size of central atom on rate, Oxyanions, mechanisms of redox reactions, Oxygen: binding curves for Hb and Mb, 508

Perchloric acid, pK, 179-180 Periodic table, 13-15 Oxygen (Cont.): cooperative binding by hemoglobin, families, 15 508-511 groups, 15 trends in acidities of binary hydrides, molecular, 106 bonding in, 46 177-178 electron density contour maps, 108-110 trends in electronegativity, 61 trends in heats of formation of salts, 288 reaction with Co(II), 343 trends in hydridic and protonic character, reaction with  $e_{aq}^-$ , 237–239 reaction with H2, 155-158 168-170 Permanganate, oxidation by iodide, 222-223 reduction at Pt and derivatized graphite cathodes, 499-500 Perovskite structure, 321 transport and storage in biochemistry, Peroxide ion, 106 507-513 Peroxysulfuric acid, 234 Oxygen atom: pH: effect on reduction potentials, 219-221 in metal cluster, 344-345 transfer in redox reactions, 230-232 effective, in nonaqueous solvents, 202 Oxygen-binding proteins, 507 pH ranges, effective, 201-202 Ozone: Phase diagram of Cu-Zn system, 296 electronic transition in, 145 Phenanthroline-iron(II) complex spectrum, Lewis octet structure of, 42 418 Phenyl group, C-H bond oxidative addition, MOs, 117-118 p orbitals: Phosphate ions, hydrogen bonding linking in 472 of hydrogen atom, 5-9 KH<sub>2</sub>PO<sub>4</sub>, 188-190 in metallic bonding, 293-297 Phosphinates, hydrolysis, 87 of transition-metal complex, overlap with Phosphine: ligand orbitals, 366-367 deprotonation with KOH, 185-186 Palladium, adsorption of CO on, 490-491 extended Hückel study, 137-140 Palladium catalyst in oxidation of ethylene to pK estimation from kinetic data, 177-178 acetic acid, 480 Palladium hydride, 162 synthesis, 166 Phosphoric acid in B2H6 synthesis, 250 Palladium(II) chloride, 269-270 Phosphoric acid esters, hydrolysis, 85-87 Para hydrogen, conversion to ortho hydrogen, Phosphorous acid, pK, 179-180 158 Phosphorus, semiconductor dopant, 319, Paramagnetism, 331-332, 428-429 of B2 and O2, 106 326-327 Phosphorus (P<sub>4</sub>), structures, 132 of coordination compounds, 421-428 Phosphorus pentafluoride: Parameters: bond lengths, 55 for estimating ligand field splitting and geometry and bonding, 83-84 Racah parameter, 410 Photoanodes, 498-499 for predicting heats of Lewis acid-base reac-Photochemical cleavage of metal-metal bonds, tions, 210-211 Pauli exclusion principle, 10 419 Photochemical generation of I atoms, 152 Pauling electronegativities, 61 Photoconductivity in xerography, TV, and Pauling ionic radii, 281 photography, 327-328 Pauling structural rules, 283-284 Photoelectrolytic cell, 323-325 Pearson's hard and soft acids and bases, Photoelectron spectroscopy, 15-16, 486 205-209 Pentaamminecobalt(III) ions: x-ray, 69-71, 486 Photoelectron spectrum: base hydrolysis, 452-453 of Cu, 299-301 reduction by Cr2+, 462-463 of FeF2, 419-420 Pentaborane-9, bonding in, 256 Pentacyanocobaltate(III) ion reactions, 452 of methane, 120 of MnF<sub>2</sub>, 419-420 Pentagonal bipyramid activated complex in Photographic latent image, 327-329 ligand substitution, and LFSE, 449-451 Pentagonal bipyramidal geometry, 338 interaction with p-n junction, 322-323 Photons: Pentaphenylantimony, 87 interaction with semiconductor electrode, Peracetic acid, intermediate in oxidation of 323-325 acetaldehyde, 480 Photovoltaic cell, 322-323 Perbromate ion, synthesis of, 49

Perchlorate ion, Lewis octet structure of, 41

Physical quantities, 529-531

Pi-acceptor ligands, 368-370, 438-444 and trans effect, 455-456 Polarity: preferred sites in d8 trigonal bipyramidal of covalent bonds, 64-76 of Si-H and C-H bonds, 75 complexes, 439 Pi bonding: Polarization: beyond first row of periodic table, 127-129 of atoms in LiH, 64-65 in bridging ligand in electron transfer, 464 effect of, on strength of protonic acid, in transition-metal complexes, 368-370, 437-444 of hydrogen bonds in KH<sub>2</sub>PO<sub>4</sub>, 189-190 in trisilylamine, 129 in Lewis acid-base reactions, 209 Pi-bonding ligands in synthesis of transition-Polyborate ions in aqueous solution, 198 metal hydride complexes, 165-166 Polydentate ligands, 346-351 Pi complexes, 351-354 abbreviations, 348-349 heteroaromatic, 352 Polyhedra, borane anions, 252 Pi-donor ligands, 368-370, 437-438 Polyhedral clusters: 2n + 2 rule, 258, 383 Pi molecular orbitals, 104-105 Picket-fence porphyrin, 511-512 applications in synthesis, 392 Pitzer's rule for entropy of ionization of acids, C<sub>5</sub>H<sub>5</sub>CoFe(CMe)<sub>4</sub>(BH)<sub>8</sub>, 390 [(CH<sub>3</sub>)<sub>3</sub>P]<sub>2</sub>Pt(CMe)<sub>2</sub>(BH)<sub>6</sub>, 387 pK values: exceptions, 393-396 of aqueous acids, 177-183 Fe<sub>2</sub>(CO)<sub>6</sub>(HOCC(CH<sub>3</sub>)C(CH<sub>3</sub>)COH), of aqueous hydrogen atom, 240 386-387 estimation with Branch and Calvin equa-Fe<sub>3</sub>(CO)<sub>8</sub>(C<sub>2</sub>Ph<sub>2</sub>)<sub>2</sub>, 386-387 tion, 181-182 Fe<sub>4</sub>N(CO)<sub>12</sub>-, 388 estimation from formal charges, 179-182 Fe<sub>5</sub>(CO)<sub>15</sub>C, 385 of free and coordinated pyrazinium ion, Fe(CO)<sub>3</sub>C<sub>2</sub>B<sub>3</sub>H<sub>5</sub>, 386 HFe<sub>4</sub>(CO)<sub>13</sub>-, 389 of HS-, 198-199 HOs<sub>4</sub>(CO)<sub>13</sub>-, 389 inductive effect, 444 Mo<sub>6</sub>C<sub>18</sub><sup>4+</sup>, 391 of metal ammine complexes, 453 Nb<sub>3</sub>(CO)<sub>7</sub>(C<sub>5</sub>H<sub>5</sub>)<sub>3</sub>, 389 of mixed valence complexes, 466-467 Nb<sub>6</sub>Cl<sub>12</sub><sup>2+</sup>, 392–393 Plane of symmetry, 25 Ni<sub>5</sub>(CO)<sub>12</sub><sup>2-</sup>, 389 Platinacyclobutanes, 477 Os<sub>3</sub>(CO)<sub>12</sub>, 383 Platinum: Os<sub>5</sub>(CO)<sub>16</sub>, 383 anticancer drug, 524 Os<sub>6</sub>(CO)<sub>18</sub>, 384 chemisorption of C<sub>2</sub>N<sub>2</sub> on, 489 complexes of ammonia and chloride, Re<sub>4</sub>(CO)<sub>16</sub><sup>2-</sup>, 384–385 Rh<sub>13</sub>(CO)<sub>24</sub>H<sub>3</sub><sup>2-</sup>, 387-388 Rh<sub>6</sub>(CO)<sub>15</sub>C<sup>2-</sup>, 389 355-356 ethylene complex of, 351-352, 440 one-dimensional metallic compounds of, RhFe<sub>3</sub>(C<sub>5</sub>H<sub>5</sub>) (CO)<sub>11</sub>, 384 Ru<sub>4</sub>Cl (CO)<sub>13</sub>-, 387-388 Ru<sub>6</sub>(CO)<sub>17</sub>C, 385 reaction with F2, 216 B<sub>n</sub>H<sub>n</sub><sup>2-</sup> ion bonding, 257 reaction with ZrC, 295 catalysis by, 501-504 solubility in tungsten, 294-295 on suspended semiconductor particles, in main-group, 260-262 MO theory of, 257-258 photoelectrolysis, 324-325 Platinum hexafluoride, synthesis, 216 as models of heterogeneous catalysts, Platinum metals, 14, 22 501-504 Platinum(II) complex isomers, preparations transition-metal boranes and carboranes, 259-261 using trans effect, 454-455 Platinum(II) complexes, rate law for substitutransition-metal compounds, 382-396 Polymerization of olefins, Ziegler-Natta, tion reactions, 454 496-497 p-n junction, 322, 325-326 Polynuclear complexes, 344-346 PNDO (partial neglect of differential overlap) Polypeptide chains, hydrogen bonding in, p-type semiconductivity, 318-322, 325-326 Polysulfur nitride, 311-312 Point group of molecule, procedure for deter-Polyvanadates, 344 Porphine, 505-507 Point groups, 27-30 Porphyrins, 505-513 character tables of, 31-34 Potassium: examples of, 29 solutions in NH<sub>3</sub>, 242-243 solutions in THF, 246-247

Potassium dihydrogen phosphate, hydrogen bonding and ferroelectric properties, 188-190

Potassium hydroxide, use in deprotonation of weak acids, 185-186

Potentials, reduction (see Reduction potentials)

Prefixes in inorganic nomenclature, 564-565 Prepared-for-bonding state of metals, 292-

Pressure, effect on explosive reactions,

Pressure-composition isotherms, H2-FeTi system, 164

Principal quantum number, 2 Problems, answers to, 566-578

Promotion to "prepared-for-bonding" state,

Propylene, Ziegler-Natta polymerization, 496-497

Protein chains, hydrogen bonding in, 188 Proteins, 507

Proton affinities:

of anions, 171-173 table of, 172

correlation with ionization potentials, 176 of hydroxide and benzyl anions, 184 of neutral bases, 173-176 table of, 174

Proton magnetic resonance of transition-metal hydride complexes, 166

Proton-transfer reactions, kinetics, 193-195 Protonation of metal complex, 471 Protonic acids:

aqueous acidity, 177-184

heats of ionization in gas phase, 171-176 Protonic character of hydrides, 168-170

Protonic solvents:

acids and bases in, 199-204 reaction with LiAlH<sub>4</sub>, 162

reaction with saline hydrides, 161 Prussian blue, 359

Pseudorotation of trigonal bipyramidal mole-

Pyrazine as bridging ligand in mixed-valence compounds, 465-467

Pyrazinium ion, effect of coordination to Ru(II) on pK, 443-444

Pyridine, reaction with HCl, 168

Pyrolysis in synthesis of nonmetal hydrides, 166

Pyroxenes, 269-270

Pyrrolide anion complex of iron, 352

Quadruple bonding in dinuclear metal complexes, 372

Quantum numbers: allowed values for hydrogen atom, 2-3 for free atoms and ions, 532-534 of hydrogen atom, 1-3

Quenching:

of explosion, 157

of orbital magnetic moment, 423-428

R and T states of hemoglobin, 509-511 Racah parameter, B, quantification, 409-411 Radial wave functions, 3-7

Radicals:

in chain reactions, 148-151, 155-158

electron affinities, 536-537 formed by irradiation of water, 236-237 ionization potentials, 538 nomenclature, 557-559

Radii, ionic:

Pauling, 281

"traditional" values of Shannon, 550-555

Radius ratio(s): effect on structure, 280-283 for oxides and halides, table of, 282

Raman spectra:

of aqueous H<sub>3</sub>BO<sub>3</sub>, 198 of aqueous SO2 and HSO3, 197

Rare earths (see Lanthanides)

Rate constants:

of aqueous hydrogen atom reactions, 239-241

effect of ionic strength on, 237-238 of electron-exchange reactions, 460-461 correlation with Keg, 461-462

of hydrated electron reactions, 237-241 of proton transfer reactions, 193-195

of reactions involving CO2, H2O, and OH,

Rate law, 148-149, 151

Pt(II) complex substitution reactions, 454 Rates:

lack of correlation with free energies, 215 oxyanion reductions, trends in, 231-232 proton transfer reactions, 193-195

of transition-metal complex isomerizations, 359-360

Reaction coordinates for Pt(II) complex substitution reactions, 457

Reaction quotient, Q, 219

Reactions:

acid-base, 171-213

kinetics and mechanisms of gas-phase, 147-159

of metal-ammonia solutions, 244-246

Rectifier, semiconductor, 325

Redox couples, interaction with semiconductor electrodes, 323-325

Redox reactions, 214-235

of complexes: correlation of rate and equilib-

rium constants, 461-462 inner-sphere, 462-463

mechanisms, 458-468

outer-sphere, 458-462 intermediates in, 221-222, 468

predicting products with reduction potential

diagrams, 222-223

Redox reactions (Cont.): thermodynamic aspects, 214-229 Rhodium catalyst in carbonylation of CH31, unusual oxidation states in intermediates, Rotation of groups around bonds, 91-92 of vanadium, 330-331 Rotational axis, 25 Reduced Madelung constant, 285-286 Rubredoxins, 517 Reducible representation, 36-38 Ruthenium-nitrogen complex, synthesis, 343 of N-H bonds in ammonia, 36-37 Ruthenium(II), back bonding, 439, 444 of p orbitals of chlorines in PtCl<sub>4</sub><sup>2-</sup>, 37-38 Rutile structure, 275-276 Reducing agents: stability of, in aqueous solution, 220 in synthesis of transition-metal hydride coms character of hybrid orbital, correlation with plexes, 165-166 overlap integral, 122 Reduction potentials, 216-229 s character of orbital, correlation with orbital diagrams, 221-229 electronegativity, 123 table, 224-229 s electron density at nucleus from Mössbauer use in predicting products of reactions, spectroscopy, 68-69 s orbitals: of e aq and aqueous H atom, 240 of hydrogen atom, 2-6 effect of pH, 219-221 in metallic bonding, 293-297 tables, 218, 224-229 of transition-metal complexes, overlap with of vanadium, 331 Reductive cleavage reactions in metal-ammonia ligand orbitals, 365-366 Saline hydrides, 160-162 solutions, 244-245 Salt bridges in hemoglobin, 509-510 Reductive elimination in homogeneous cataly-Sanderson electronegativities, 72-73 Schiff-base complex, 482 Relaxation energy: Schrödinger equation, 1-2, 97 in acid ionizations, 182 for hydrogen atom, 10 in ionization of gas-phase protonic acid, Scrambling of fluorines in PF<sub>5</sub>, 84 Scrambling of rings in Ti(C5H5)4, 354 in Lewis acid-base reactions, 209-210 Screening constant, 17-20 Representations: Secondary ion mass spectroscopy, 486 irreducible, 30-36 Secular determinant, 98 reducible, 36-38 Secular equations, 98 Representative elements, 13-15 Selection rules in electronic spectra, 404-406 Repulsion: Selenium, metallic, 269 between bonding pairs of electrons, 90 Selenium-arsenic compounds, photoconductivbetween lone pairs, 54 electron-electron, 126-127 ity, 327 Selenium nitride, 266 in H<sub>2</sub>O, 124 Self-consistent-field MO methods, 140-145 interligand: effect on coordination number, Semi-bridging CO group in cluster, 389 Semiconductors, 316-329 in K[PtCl<sub>3</sub>(C<sub>2</sub>H<sub>4</sub>)] · H<sub>2</sub>O, 440 amorphous, 326-327 in trischelate complexes, 350 Resistivities, 316 applications, 321-325 of metallic carbides and nitrides, 307 band gaps, 319-320 conductivity, 316-318 of metals, 303 Resonance, 42-45 controlled-valence, 321 defect type, 320 no-bond, 44-45 Resonance hybrids, 43-44 purification and doping, 317-319 Seven-coordinate complexes, 338 metallic bonding, 292 Sevenfold coordination, ways of achieving, 89 pentaborane-9, 256 Shared edges and faces, instability in crystal of polysulfur nitride, 312 Resonance integral(s), 99, 137 structures, 284 Shielding: in PH<sub>3</sub>, 138 Resonance structures, 77 of electrons by electrons, 17-21 of nuclear charge by electrons, 12-13 of B<sub>6</sub>H<sub>6</sub><sup>2-</sup>, 257 SI units, 529-530 of Ni(CO)4, 438 Sigma molecular orbitals, 104-105 Rhenium, solubility in tungsten, 294-295 Rhodium, adsorption of CO on, 491-493 Silacyclobutanes, 127 Silane, synthesis, 166

Silica (cristobalite) structure, 278

Solvents (Cont.): Silicon: protonic: acids and bases in, 199-204 purification of, 318-319 physical properties of, 200 in semiconductors, 316-320, 325-327 Solvolysis: Silicon-carbon double bonding, 127-128 in anhydrous sulfuric acid, 201 Silicon-chlorine bond distances, 50 in synthesis of nonmetal hydrides, 166 Silicon dioxide molecule, nonexistence, sp hybridization, 79, 333 sp2 hybrid orbitals, 115 Silicon hydrides, reactivity compared with sp<sup>3</sup> hybridization, 81-83 hydrocarbons, 75 Spectra (see Electronic spectra) Silicon photoanode, covered with ferrocene Spectrochemical series, 409 groups, 499 Spectroscopic notation, 405 Silicon-silicon double bonding, 128 Silicon sulfide, 269 Spin: Silicon tetrafluoride: of electrons in atoms, 12 of Fe2+ and Fe3+ ions in Fe3O4, 437 bond distance, 53-54 of Mn<sup>2+</sup> ions in MnO, 430 d orbitals in bonding, 45 of weak- and strong-field complexes, Silver bromide, photoconductivity of, 328 Silver cluster latent image, 328-329 372-373 Silver halides, latent image in photography, Spin magnetic moment, 423 Spin multiplet in photoelectron spectrum of 327-329 Silver sulfide latent image specks, 328 FeF<sub>2</sub>, 419-420 Spin multiplicities of complexes, 405 Silyl derivatives, interconversion, 209 Spin-only formula for magnetic moment, Six-coordinate complexes, 336-338 Sixteen-electron complexes in homogeneous Spin-orbit coupling parameters, 427 catalysis, 470-471 Slater atomic orbital functions, 135–136 Spin quantum number, 2 Slater's rules, 17 Spinels: Sodium: magnetic, 437 normal and inverse, 436-437 solutions in NH<sub>3</sub>, 242-243 Splitting of d orbital energies: solutions in THF, 246-247 Sodium amide, reaction with GeH<sub>4</sub>, 168 in octahedral field, 362-363, 434 Sodium chloride structure, 274-275 in square planar field, 364-365 in tetragonally distorted octahedral field, Sodium hydride, 161, 170 Sodium hydroborate (see Hydroborate) in tetrahedral field, 363-364 Soft and hard acids and bases, 205-209 Splitting of electronic levels of complexes, Solar energy conversion using semiconductors, 322-325 405-416 Solid state, 264-290 Spodumene, 271 Square antiprism geometry, 338-339 Solids: Square planar complexes, 334 application of isoelectronic principle, electrostatic ligand-field theory, 364-365 288-289 stability relative to tetrahedral, 436 classification of, 265-266 substitution reactions, 453-458 containing finite complexes, 266-268 Square pyramidal activated complex in ligand containing infinite one-dimensional comsubstitution, and LFSE, 449-451 plexes, 269-271 Square pyramidal complexes, 334-336 containing infinite three-dimensional com-Staggered configuration in dinuclear complexes, 274-280 plexes, 372 containing infinite two-dimensional com-Standard potentials (see Reduction potentials) plexes, 271-273 Standard states and equilibrium constants, lattice energy, 285-288 packing of nonspherical or dipolar mole-346-347 States of free atoms and ions, 532-534 cules, 267-268 Solubility products and reduction potentials, Steady state: in acid-e-am reactions in liquid ammonia, 220-221 Solvated electrons, 236-248 246 in reaction mechanism, 148-149 Solvents: Step site on surface, 488-489 Stepwise absorption by metal of hydrogen, for alkali metals, 241-248 aprotic: acids and bases in, 204 163-164 Stepwise complexation, 342-343

physical properties of, 206-207

nonaqueous, 199-207

Stereochemical ambiguity in 5-coordination, 334-335 Stereochemical control of valence, 398 Stereochemical nonrigidity, 336, 353-354 Stereochemistry of O2 coordination in hemoglobin, 510-511 Stereoregularity in Ziegler-Natta polymerization, 496-497 STO-3G/Gaussian-70 method, 144 Stoichiometries of the oxidation of SO2, 232-233 Stretching frequencies: of C=C bond in metal dithienes, 401 of CO adsorbed on Pd and Rh, 490-492 correlation with electronegativity, 75 for linear triatomic species, 47 of M-H bond in transition-metal hydride complexes, 166 in mixed-valence complexes, 466 of N-O bond in metal nitrosyls, 398-399 of O-H bonds and hydrogen bonding, 192 Strong- and weak-field complexes, 372-373 distinguishing by magnetic moments, 424 Strontium titanate, in photoelectrolysis, Structural reorganization, 359-360 in electron transfer reactions, 459-460 Styx numbers for boranes, 255 Substituents: effects on acidity of binary hydrides, 178-179 effects on acidity of gas-phase acids, 171-174 Substitution reactions: aqueous +2 ions, rates, 451 octahedral complexes, kinetics, 447-453 square planar complexes, kinetics, 453-458 Sulfate ion: d orbitals in bonding, 45 as product of SO<sub>2</sub> oxidation, 232-233 Sulfide ion, oxidation to polysulfide, 198 Sulfides, solubility products, 199 Sulfur: atomization energy, 60 fibrous, 269-270 Sulfur atoms in metal cluster, 395 Sulfur dioxide: aqueous solutions, 197 bond distance, 53 oxidation by I- and 2-equivalent oxidizing agents, 232-233 Sulfur hexafluoride, structure and bonding, 88 Sulfur nitride, 266 Sulfur nitride polymer, metallic character, 311-312 Sulfur-nitrogen species, Hückel theory treatment, 132-133

Sulfur tetrafluoride structure, 87-88

B<sub>2</sub>H<sub>6</sub> synthesis, 250

uric acid:

llfur trioxide, solutions in H<sub>2</sub>SO<sub>4</sub>, 201

Sulfuric acid (Cont.): ionization of, and acid-base reactions in, NO2+ and NO+ reactions in, 231 pK, 179-180 Sulfurous acid, 197 Superconductivity: metals, 300-301 (SN), 312 Superconductivity transition temperatures of carbides and nitrides, 307 Superexchange, 429-431 Superoxide dismutases, 526-528 Superoxide ion, 106 destruction by superoxide dismutase, 526-528 intermediate in oxidations by O2, 221 synthesis in NH<sub>3</sub>, 244 Surface coverage in adsorption on metals, 490-493 Surfaces: of electrodes, modifications, 498-500 Miller indices, 484-485 stepped, 488-489 tools for characterization, 484-487 Susceptibility, magnetic (see Magnetic susceptibility) Symbols (term): for atoms and ions, 532-534 for electronic states of complexes, 405-409 Symmetry, 24-39 of atomic orbitals, 9 and electronic spectral selection rules, 404-405 elements, 25-29 and kinetics, 152-155 operations, 25-27 and orthogonality, 103-104 and polyatomic molecules, 114-121 species, 30 Symmetry rules in kinetics, 152-155 lar momentum, 426-427

Synergic bonding, 370 Systeme Internationale units, 529-530 T and R states of hemoglobin, 509-511 T ground states and unquenched orbital angu-Tanabe and Sugano plots, 411-413 Taube's rule for ligand substitution rate of octahedral complex, 448-451 Television, 327 Tellurium-arsenic compounds, photoconductivity, 327 Tellurium cluster compound, 261-262 Temperature coefficient: of conductivity of metals, 299

of conductivity of semiconductors, 316

Terephthalic acid as bridge in electron

Template syntheses, 481-482

transfer, 464-465

Term symbols: for atoms and ions, 532-534 for electronic states of complexes, 405-Termolecular rate constant, 152 Terraces on surfaces, 488 Tetraamminecopper(II) ion, rates of reaction, Tetraammineplatinum(II) ion, reaction illustrating trans effect, 454 Tetraborane: bonding in, 256 synthesis by B<sub>2</sub>H<sub>6</sub> pyrolysis, 250-251 Tetrachloroplatinate(II) ion, reactions illustrating trans effect, 454-455 Tetracyanoethylene, back bonding to, 442 Tetracyanoplatinate metallic compounds, 310-311 Tetradentate ligands, chelation, 346 Tetragonal distortion of octahedron, 337 electrostatic ligand-field theory, 364-365 Tetrahedral complexes, 334 always weak-field, 373 electronic spectra, 404-405, 407-409, 414-415 electrostatic ligand-field theory, 363-364 elongation and flattening, 432-433 magnetic moments, 427 Tetrahedral d8 vs. octahedral d8 complexes, 431-432 Tetrahedral-field splitting, 363-364, 373 Tetrahedral holes in close-packed structures, Tetrahedral molecules, sigma bonding in, Tetrahydrofuran solutions of alkali metals, 246-247 Tetramesityldisilene, 128 Tetraphenylporphyrin, 505 Thallium(II) in Tl<sup>3+</sup> + Fe<sup>2+</sup> reaction, 468 Thermal desorption spectroscopy, 487 Thermal transport purification of semiconductors, 319 Thermochemical bond energies, 60 Thermodynamic aspects of redox chemistry, 214-229 Thermodynamic data, table, 539-549 Thermodynamics, limitations of, 215-216 Thiocyanate ion, 47 ambidentate character, 358 Third body in bimolecular reaction, 157 Three-center bonding, 253-257 in gas-phase protonated species, 175 topological equations for, 255 Three-coordinate complexes, 334 TIM-iron(II) complexes, 418 Tin, reduction of VO<sub>2</sub><sup>+</sup> and VO<sup>2+</sup>, 331 Tin complexes, Mössbauer spectroscopic study, Tin(II) chloride, reaction as Lewis acid and

Lewis base, 211

Tin(IV), oxidizing power compared to lead(IV), 23 Titanacyclobutanes, 477 Titanium, bcc and hcp structures, 295 Titanium cyclopentadienyl, 353-354 Titanium dioxide (rutile) structure, 275-276 Titanium disulfide, structure and use as electrode material, 313-314 Titanium-iron alloy, reaction with H2, 164 Titanium tetrachloride, reaction with A1Et, to form Ziegler-Natta catalyst, 496 Titanium trichloride in Ziegler-Natta olefin polymerization, 496 Topological equations for 3-center bonding, Topology of molecules, 76-77 Total coordination number 2, 78-79 Total coordination number 3, 80-81 Total coordination number 4, 81-83 Total coordination number 5, 83-88 Total coordination number 6, 88-89 Total coordination number 7, 89-90 Total coordination number of atom, 78 Trans effect, 454-456 Trans effect series of ligands, 454 Transistors, 325 Transition elements, 13-15 Transition-metal compounds: coordination compounds in (see Electronic spectra, coordination compounds) coordination numbers in (see Coordination numbers, in transition-metal compounds) Transition-metal hydrides, acidity, 183-184 Transition metals: ferromagnetism, 303-306 hydride complexes, 165-166 introduction to chemistry of, 330-360 metalloboranes and metallocarboranes, 259-261 stabilization of cyclobutadiene, 131 Trapping centers in photographic emulsions, 328 Tremolite, 271 Trialkylsilyl derivatives, interconversion, Triangular H<sub>3</sub><sup>+</sup>, 145 Tricapped trigonal prism geometry, 339-340 Trichlorosilane in Si purification, 318 Trichlorosilylferrocene, 499 Tridentate ligands, chelation, 346 Trifluoromethyl group, back bonding to, Trigonal bipyramidal complexes, 334-336 Trigonal bipyramidal geometry, 83 Trigonal bipyramidal intermediate in reactions of square planar complex, 453-456 Trigonal distortion of octahedron, 337 Trigonal prismatic geometry, 337 in trischelate complexes, 347-351

Triiodide, 217-219 bond length, 55 MOs, 115-117

Trimethylamine oxide, bonding, 54 Trimethylammonium hydroxide, hydrogen bonding in, 184

Triphenylmethane, deprotonation with KOH, 185-186

Triple bonding in dinuclear metal complexes,

Triplet states of d2 complex, 406-407 Trischelates, twist angle, 347-351 Tris(ethylene)nickel (0), 440-442

Trisilylamine, structure and bonding, 128-129 Tropylium ion, oxidation of Fe<sub>6</sub>C(CO)<sub>16</sub><sup>2-</sup>, 502 Tungsten, solubility of metals in, 294-295

Tungsten bronzes, 308-309

Turnbull's blue, 359

Twelve-coordinate complexes, 339-340 Twist angle in trischelate complexes, 347-351

Two-coordinate complexes, 333 Two-dimensional metallic compounds,

312-314 Two-equivalent oxidizing agents, 232-233

Ultraviolet photoelectron spectroscopy (see Photoelectron spectroscopy)

Ultraviolet-visible spectroscopy in study of heme models, 513

Ungerade wave functions, 9, 36 Units of measure, 529-531

Unsaturation, coordinative, in homogeneous catalysis, 470-471

Unusual oxidation states in mechanisms of redox reactions, 468

Uranium complex with cyclooctatetraenide ion, 131

Uranocene, 131

Vacancies in crystal lattices, 320 Valence electrons of atom, 13 Valence force field, 63

Valence shell electron repulsion, 77-90

effect on lattice energy, 286 molecular geometry predictions, 78 reliability of predictions, 90

in water molecule, 124

Valence state ionization potentials, 136 Vanadium, redox chemistry of, 330-331

van der Waals bonding, 265 Vertical planes, 26

Vibrational frequencies for linear triatomic species, 47

Viscosity:

aprotic solvents, 206-207 glasses, 289 protonic solvents, 200

Visible region of spectrum, 414

Vitamin B<sub>12</sub>, 514-517 coenzyme, 514-516

reduction to vitamin B<sub>12s</sub>, 514

Volumes of activation of ligand exchange reactions, 452

Wacker process for oxidation of ethylene to acetic acid, 479-480 Wade's rules, 258, 382-383

Walls of vessel, effect on reaction rate, 157-158

Walsh diagrams, 124-127 Water:

formation in H<sub>2</sub> + O<sub>2</sub> reaction, 155-158 hydrogen bonding in, 186-188 ionization by irradiation, 236-237 photoelectrolysis, 324-325

Water exchange reaction of aqueous complex,

Water gas shift reaction, 479 Water molecule:

acidity of derivatives, 178-179 irreducible representation of lone pair in, 35 lone pairs, 82-83

model to account for dipole moment, 66 orbital hybridization in, 124 valence shell electron repulsion treatment,

Walsh diagram treatment, 126 Wave function of atom, 2 Weak- and strong-field complexes, 372-373 Werner coordination theory, 354-355 Wilkinson's catalyst, 473-474 Wurtzite structure, 275-277

X-alpha methods, 144 Xenon fluorides, atomic charges from core binding energies, 69-71

Xerography, 327

XPS (see x-ray photoelectron spectroscopy) X-ray absorption spectroscopy, 519-520 X-ray diffraction:

electron density difference plot from, 114 of MnO, 429

X-ray photoelectron spectroscopy (ESCA; XPS), 69-71, 486

of argon, 16

of CO adsorbed on W, 494

of mixed-valence complex, 467 of xenon compounds, 70-71

Zeise's salt, 440

Zeta parameter in Slater functions, 135-136 Ziegler-Natta olefin polymerization, 496-497 Zinc, reduction of VO<sub>2</sub>+, VO<sup>2+</sup>, and V<sup>3+</sup>, 331 Zinc-blende structure, 275-277 Zinc-copper phase diagram, 296-297 Zinc ion in carbonic anhydrase, 525 Zinc sulfide structures, 275-277 Zirconium, bcc and hcp structures, 295 Zirconium carbide, reaction with Pt, 295

Zoned refining in Si purification, 318-319

## PERIODIC TABLE OF THE ELEMENTS

Halogens Noble eas

Halogens Noble esses	4003	He	VIIB 2	18,998 20.183	F Ne		35,453 39,948	Cl Ar	81	79.904 83.80	Br Kr	36	904	I Ko			-	At Rn	85 86			
H	Chalcogens	•	VIB	14,007 15,999 1	0	60	32.064 3	S	11 91	78.96	3	24	1 0977	1	21		(017)	Po	84 . 8			
			VB		Z	7	30.974	Ь		192	-	22	70 101 07 11	10	300			Bi	83			
			IVB	-	O	9	28.086	S	14	72.59		33	110 60		Su	30	7 207.1	Pb	82			
			IIIB	10.811	B	10	26.982	Al	TTD 13 14 15	60 72		2 2	30 31 32	70-4-11	Ag Cd In	46	200.59 204.37 207.19	E	18			
							tale	dals	TID					04711	3	48	200.59	Hg	80			
-							Cainage metale	liage ille	<b>*</b> £	1D	03,340	3	29	_	_	47	196'961	Pt Au	79	1		
							Con	0		16.02	26.71	Ž.		106.4			195.09	_	78		etals	
									III A	40.040	55.847 58.933	3	27	_	Rh	44 45 46	192.2	Ir	17		Platinum metals	
						n metals					55.847	Fe		101.07	Ru	44	190.2	os	76		Pla	
						Transition metals				VIIA	54.938	Mn	2.5	(66)	Tc	43	186.2	Re	_			
101							-			VIA	51.996	ت	24	95.94	Mo	42	183.85	W	1	(263)		1000
I THE TOTAL OF THE PARTY OF THE										VA		>		95.906	NP	41	178.49 180.948	Ta			Ha	2000
										IVA	47.90	Ti	22 23	91.22	Zr	40	178.49	H	72 73		Rf	150.4
ths										IIIA	44.956	Sc	21	8.905	Y	39	138.91	I.a	25	(227)	Ac	100
Alkaline earths			,	IIA	9,012	Be	1	24,312	Mg	12	40.08	Ca	20	7.62	Sr	38	137.34	Ba	98	(226)	Ra	200
Alka	IA	1.008	Н		6:63	Li	-	22.990	Na		39.102	K	61	85.47	Rb	33	132 905	Ce	55	(223)	F	-

Alkali metals

Lu	71	(257)	Lr	103
Yb	70	(253)	No	102
Tm	69	(256)	Md	101
Er	89	(253)	Fm	100
	19	(254	E	8
Dy	99	(249)	Cf	86
176	. 59	(247)	Bk	16
PS	64		Cm	96
	63	(243)	Am	9.8
Sm			Pu	94
			Np	93
	99	238.03	2	92
	65	(231)	Pa	161
Ce	38	232.038	T	90
Lanthanide series			Actinide series	The same of the sa
	Pr Nd Pm Sm Eu Gd Tb	Pr Nd Pm Sm Eu Gd Tb Dy Ho Er Tm Yb (59) 69 67 68 67 68 69 70	Pr         Nd         Pm         Sm         Eu         Gd         Tb         Dy         Ho         Er         Tm         Yb           59         60         61         62         63         64         65         66         67         68         69         70           8         (231)         23803         (233)         (243)         (243)         (243)         (243)         (243)         (243)         (253)         (253)         (256)         (253)	Pr         Nd         Pm         Sm         Eu         Gd         Tb         Dy         Ho         Er         Tm         Yb           99         60         61         62         63         64         65         66         67         68         69         70           8         (234)         (243)         (243)         (247)         (249)         (254)         (253)         (256)         (253)           Pa         U         Np         Pu         Am         Cm         Bk         Cf         Es         Fm         Md         No



## OTHER MCGRAW-HILL INTERNATIONAL EDITIONS IN RELATED FIELDS

Austin: SHREVE'S CHEMICAL PROCESS INDUSTRIES, 5/E

Braun: INTRODUCTION TO CHEMICAL ANALYSIS
Breck: CHEMISTRY FOR SCIENCE AND ENGINEERING
Burgoyne: A SHORT COURSE IN ORGANIC CHEMISTRY

Ewing: INSTRUMENTAL METHODS OF CHEMICAL ANALYSIS, 5/E Gilreath: FUNDAMENTAL CONCEPTS OF INORGANIC CHEMISTRY

Griffin: MODERN ORGANIC CHEMISTRY

Monson-Shelton: FUNDAMENTALS OF ORGANIC CHEMISTRY

Pine-Hendrickson: ORGANIC CHEMISTRY, 4/E.

Sawyer-McCarty: CHEMISTRY FOR ENVIRONMENTAL

ENGINEERING, 3/E

Sienko-Plane: CHEMISTRY, 5/E

Sienko-Plane: CHEMISTRY: Principles And Applications, 3/E

Sienko-Plane: EXPERIMENTAL CHEMISTRY, 6/E

Smith: PRINCIPLES OF BIOCHEMISTRY: General Aspects, 7/E

Smith: PRINCIPLES OF BIOCHEMISTRY: Mammaline Biochemistry, 7/E

Zlatkis-Breitmaier: A CONCISE INTRODUCTION TO ORGANIC CHEMISTRY

